


2011 California Access Compliance Reference Manual

2010 California Building Standards Code
with
California Errata and Amendments
Effective: January 01, 2011



Statutes, Regulations, Policies, Interpretations of Regulation (IRs), Official Comments (Checklists), & Code Appeals

Updated November 18, 2011



Division of the
State Architect

CALIFORNIA DEPARTMENT OF GENERAL SERVICES

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Introduction

The Division of the State Architect (DSA) has compiled California's Statutes, Title 24 Regulations, DSA Policies, DSA Interpretations of Regulations, DSA Checklists, and DSA Code Appeals related to accessibility for persons with disabilities. The general intent of this document is to help clarify the obligations, and specifically for accessibility in projects under the plan review jurisdiction of DSA, including State of California public elementary and secondary schools (grades K–12), community colleges, and state funded buildings and facilities. Following is a brief description of the contents of the six sections which comprise DSA's California Access Compliance Reference Manual:

Section 1 – Statutes: California Law consists of 29 codes covering various subject areas, the State Constitution and Statutes. Some of the statutes listed in this manual reflect the laws currently in effect specifically related to the DSA on the subject of access compliance.

Section 2 – Regulations: The California Code of Regulations (CCR) is the official compilation and publication of the regulations adopted, amended or repealed by state agencies. The CCR consists of 28 titles; Title 24, the California Building Standards Code, serves as the basis for the design and construction of buildings in California. The regulations included in this document are excerpted from Title 24 and include building regulations, adopted by DSA, which govern accessibility for persons with disabilities.

Section 3 – Policies: The policies indicated in this manual address those aspects of DSA's plan and construction review program that are not clearly addressed by code. These policies are applicable to projects within the jurisdiction of DSA.

Section 4 – Interpretations of Regulations (IRs): The Interpretations of Regulations shown in this section are intended for use by DSA staff and as a resource for design professionals to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. The IRs typically indicate acceptable methods of achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

Section 5 – Official Comments (Checklists): This section contains a collection of 25 subject-specific checklists covering a variety of accessibility topics which may be applicable to construction projects typically submitted to DSA. We have attempted to include relevant citations of accessibility requirements from the CBC and the ADA Standards for Accessible Design. The checklists are intended for use by DSA staff and as a resource for design professionals to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA.

Section 6 – Code Appeals: When accessibility code interpretation or code application disagreements occur in DSA's regional offices, a Code Appeal Process (CAP) is available. CAP (formerly RIP) is a formal method to resolve project-specific disputes by the issuance of official interpretations by DSA. This section contains selected DSA code appeal determinations.

DSA hopes you find this reference material to be a valuable resource.

DSA Access Compliance Statutes

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL STATUTES

Introduction

Section 1 – Statutes: California Law consists of 29 codes covering various subject areas, the State Constitution and Statutes. Some of the statutes listed in this manual reflect the laws currently in effect specifically related to the DSA on the subject of access compliance.

Contents

(click title to move to California Code)

[Business and Professions Code](#)

[Civil Code](#)

[Education Code](#)

[Government Code](#)

[Health and Safety Code](#)

[Insurance Code](#)

[Public Resources Code](#)

[Vehicle Code](#)

Business and Professions Code

(click the Statute number to view Statute)

Division 1. Department of Consumer Affairs

Chapter 1. The Department [§125.6](#)

§125.6 Refusal to perform licensed activity; aiding or inciting refusal of performance by another licensee; discrimination or restriction in performance; race, color, sex, religion, ancestry, disability, marital status, or national origin

Civil Code

Division 1. Persons

Part 2. Personal Rights [§51–53](#)

§51 Unruh Civil Rights Act; equal rights; business establishments; violation

§51.1 Mandatory service on State Solicitor General of each party's brief or petition and brief in causes of action based on violation of civil rights statutes

§51.5 Discrimination, boycott, blacklist, etc.; business establishments; equal rights

§51.7 Freedom from violence or intimidation

§51.8 Discrimination; franchises

§52 Denial of civil rights or discrimination; damages; civil action by people or person aggrieved; intervention; unlawful practice complaint

§52.1 Civil actions for protection of rights; damages, injunctive and other equitable relief; violations of orders

§52.2 Court of competent jurisdiction; defined; actions

§53 Restrictions upon transfer or use of realty because of sex, race, color, religion, ancestry, national origin, or disability

Division 1. Persons**Part 2.5. Blind and Other Physically Disabled Persons [§54–§55.2](#)**

§54	Right to streets, highways, and other public places; disability
§54.1	Access to public conveyances, places of public accommodation, amusement or resort, and housing accommodations
§54.2	Guide, signal or service dogs; right to accompany individuals with a disability and trainers; damages
§54.3	Violations; liability
§54.4	Blind or visually impaired pedestrian; failure to carry cane or use guide dog
§54.5	White cane safety day; proclamation
§54.6	Visually Impaired
§54.7	Zoos or wild animal parks; facilities for guide, service or signal dogs accompanying individuals with a disability
§54.8	Hearing impaired persons; assistive listening systems in civil or criminal proceedings; notice of need; availability; use in proceedings
§55	Violations; injunction; action by person actually or potentially aggrieved
§55.1	Violations; injunctions; district or city attorney, attorney general
§55.2	Mandatory service on State Solicitor General of each party's brief or petition and brief in causes of action based on violation of civil rights statutes

Division 2. Property**Part 4. Acquisition of Property****Title 6. Common Interest Developments****Chapter 3. Ownership Rights and Interests [§1360–§1361](#)**

§1360	Modification of unit by owner; facilitation of access for handicapped; approval by project association
§1361	Common Areas

Education Code**Title 1. General Education Provisions****Division 1. General Education Code Provisions****Part 10.5. School Facilities****Chapter 3. Construction of School Buildings****Article 3. Approvals [§17280–§17317](#)**

§17280	Supervision of design, construction and fire damage repair by Department of General Services
§17280.5	Advisory committee convened by Seismic Safety Commission; study and report on developing regulatory process with respect to buildings not originally constructed in compliance with Field Act; retrofitting buildings; equivalent pupil safety performance standard
§17281	Short Title
§17282	Damage caused by natural disasters; repairs, alterations, or reconstruction; expedited review and approval process; time limitations
§17283	"School Building"
§17284	Nonconforming school building; extension of use
§17284.5	Non conforming existing private buildings; use as school buildings; extension of waivers
§17285	Leased nonconforming buildings
§17286	"School building"; exemption for certain facilities
§17287	"School building"; exclusion of buildings used for outdoor science, conservation, and forestry classes

- §17288 Special educational services on university campuses; exemption from school building requirements; notice
- §17289 Exemptions for facilities used for independent study; requirements; duration of exemption
- §17290 Repealed by Stats.1997, c. 320 (S.B.708), § 1, eff. Aug. 18, 1997, operative Sept. 30, 1997
- §17291 Owned relocatable facilities; waiver of provisions; extension; applicability
- §17292 Use of owned or leased relocatable building as school building; conditions
- §17292.5 Expelled pupils program; operation of program; lease agreements for facilities
- §17293 Pregnant and parenting teen program; operation of new or expanded program; leases agreements for school facilities
- §17293.5 Repealed by Stats.2000, c. 65 (A.B.1830), § 1, eff. July 3, 2000, operative Jan. 1, 2002
- §17294 "Construction or alteration"
- §17295 Required approval of plans by Department of General Services
- §17296 School-based integrated children's services program facility; exemption
- §17297 Required safety approval by Department of General Services before letting any contract
- §17298 Fabrication, construction or alteration of relocatable school buildings with previous approval
- §17299 Requirements of specifications, structural design computations and cost estimates with plans submitted for approval
- §17300 Filing fees for submission of plans for approval; rates; installments
- §17301 Public school planning, design, and construction review revolving fund; fees; audits
- §17302 Preparers of plans, specifications, and estimates; qualifications; observation of construction
- §17303 Plan review; complete application; methods to reduce time lapse; notice
- §17304 Printing of plans; approval letter
- §17305 Qualified plan review firms; contracts
- §17306 Review of application; referral of documents to review firm
- §17307 Compliance with the provisions of this article and approval of the Department of General Services
- §17307.5 Construction work on public schools; issuance of stop work orders; liability
- §17308 Legislative findings, employee training; interpretational materials
- §17309 Reports required of architects, engineers, and inspectors; information required
- §17310 Rules and regulations; building standards
- §17311 Inspections by Department of General Services and appointed inspector
- §17312 Violations and false statements
- §17313 Structural inspection by Department of General Services upon special request; payment of expenses
- §17314 Approval of public school building for occupancy by Department of General Services deemed to meet local building requirements for use as a private school
- §17315 Certificate of compliance; verified reports
- §17316 Contracts with structural engineers or architects; required provision making plans, specifications, and estimates the property of the school district
- §17317 Seismic safety inventory of public school buildings; report
- §17318 Repealed by Stats.1996, c. 277 (S.B. 1562), § 1, operative Jan. 1, 1998
- §17319 Repealed by Stats.1996, c. 277 (S.B. 1562), § 1, operative Jan. 1, 1998

Article 6. Fitness for Occupancy [§17365–§17374](#)

§17365	Legislative findings and declaration
§17366	Legislative intent
§17367	Building examinations; required actions of governing board upon report of unsafe condition
§17368	“School building”
§17369	Buildings excluded from definition of “school building”
§17370	Liability of governing board members
§17371	Limitation on liability of governing board
§17372	Grounds for permitting use of unsafe buildings
§17373	Application for funds for repair, reconstruction or replacement; repayment
§17374	Permitted expenditures for completing corrective measures

Education Code

Title 3. Postsecondary Education

Division 5. General Provisions**Part 40. Donahoe Higher Education Act****Chapter 14. Disabled Student Services****Article 3. State-funded Services [§67310](#)**

§67310	Legislative findings, declarations and intent; equal access to public postsecondary education; other resources; accountability and evaluations
--------	--

Division 7. Community Colleges**Part 49. Community Colleges, Education Facilities****Chapter 1. School Sites****Article 7. Approval [§81130–§81149](#)**

§81130	Supervision of construction and certain repairs
§81130.3	Short Title
§81130.5	Offsite buildings; school building; construction or alteration
§81130.6	Damage caused by natural disasters; repairs, alterations, or reconstruction; expedited review and approval process; time limitations
§81131	Repealed by Stats.1990, c. 1372 (S.B.1854), § 546
§81131.4	Repealed by Stats.1981, c. 470, p. 1767, § 218
§81131.5 to	
§81132	Repealed by Stats.1990, c. 1372 (S.B.1854), §§ 547 to 549
§81133	Approval or rejection; examination; safety; complete plans; cost estimate; filing fee; contract validity; compliance with article
§81133.5	Construction work on community colleges; issuance of stop work orders; liability
§81134	Methods to ensure complete application
§81135	Contracts with qualified plan review firms
§81136	Referral of documents to qualified plan review firm
§81137	Repealed by Stats.1990, c. 1372 (S.B.1854), § 554
§81138	Preparers of plans, specifications, and estimates; qualifications; observatory of construction
§81140	Repealed by Stats.1990, c. 1372 (S.B.1854), § 555
§81141	Reports required of architects, engineers, and inspectors; information required
§81142	Rules and regulations; building standards
§81143	Inspections by Department of General Services and appointed inspector
§81144	Violations and fraudulent false statements
§81146	Approval of public school building for occupancy by Department of General Services deemed to meet local building requirements for use as a private school
§81147	Certificates of compliance verified reports
§81149	Purchase of offsite building or facility for school; conditions

Evidence Code

Division 6. Witnesses

Chapter 4. Interpreters and Translators [§750–§755.5](#)

- §754 Deaf or hearing impaired persons; interpreters; qualifications; guidelines; compensation; questioning; use of statements
- §754.5 Privileged statements; deaf or hearing impaired persons; use of interpreter

Government Code

Title 1. General

Division 5. Public Work and Public Purchases

Chapter 7. Access to Public Buildings by Physically Handicapped Persons [§4450–§4461](#)

- §4450 Purpose; standards for access to buildings; regulations
- §4450.5 State architect's regulations, identification of parking spaces for handicapped
- §4451 Buildings and facilities to which chapter applicable; standards and specifications; exceptions
- §4452 Minimum standards; deviation from specifications
- §4453 Responsibility for enforcement of chapter
- §4453.5 Inspection of state and school district buildings by physically disabled volunteers; reports; correction plan; applicability of section
- §4454 Approval of plans and specifications; filing fees; consultation
- §4455 Duties of department of rehabilitation
- §4455.5 Elevators; Braille symbols
- §4456 Alteration of existing buildings or facilities
- §4457 Portable buildings of school district
- §4458 Violations; injunctions; district or city attorney, attorney general
- §4459 Accessibility requirements; use of fees
- §4459.5 State Architect; program for voluntary certification of persons who meet criteria as certified access specialists; determination of criteria
- §4459.6 Ad hoc advisory committee; development of requirements for certification as access specialists; representatives
- §4459.7 Published list of certified access specialists; disclaimer of liability; audits of work
- §4459.8 Certification effective for three years; suspension of certification or denial of certification renewal; payment of fees; costs of reassessing qualifications of renewal applicants
- §4460 Detectable warning products and directional surfaces; approval
- §4461 Mandatory service on State Solicitor General of each party's brief or petition and brief in causes of action based on violation of civil rights statutes

Division 5. Public Work and Public Purchases

Chapter 9. Rapid Transit [§4500](#)

- §4500 Contracts for rapid transit equipment or structures; ready access for individuals with disabilities

Division 7. Miscellaneous**Chapter 15. Facilities for Handicapped Persons [§7250–§7252](#)**

§7250	Application
§7251	Toilet facilities; signs
§7252	Level or ramped entrances; signs

Government Code
Title 2. Government of the State of California

Division 3. Executive Department**Part 1. State Departments and Agencies****Chapter 1. State Agencies****Article 9.5. Discrimination [§11135–§11139.8](#)**

§11135	Programs or activities funded by state; discrimination on basis of race, national origin, ethnic group identification, religion, age, sex, color, or disability; federal act; definitions; legislative findings and declarations
§11136	Notice to contractor, grantee or local agency by state agency; probable cause to believe violation of statute or regulation; hearing
§11137	Action to curtail state funding upon determination of violation
§11138	Rules and regulations
§11139	Prohibitions and sanctions; construction and enforcement of article
§11139.5	Standards and guidelines; establishment; assistance

Division 3. Executive Department**Part 2.8. Department of Fair Employment and Housing****Chapter 6. Discrimination Prohibited****Article 2. Housing Discrimination [§12955–§12956.1](#)**

§12955	Unlawful practices
§12955.1	Discrimination; disabled persons; design and construction of multifamily dwellings; building standards; adoption of regulations
§12955.2	Familial status
§12955.3	Disability
§12955.4	Religious organizations; preference to persons of same religion; restrictions
§12955.5	Discriminatory housing practices; collecting information
§12955.6	Construction with other laws
§12955.7	Coercion, intimidation, threats, or interference with rights
§12955.8	Unlawful practices; proof; business establishment
§12955.9	Housing for older persons; application
§12956	Retention of records upon notice of complaint
§12956.1	Restrictive covenants based on race, sex, or other discriminatory grounds; notice; exception; determination that covenant is void; criminal penalty; recordation of modified documents

Division 5. Personnel**Part 2. State Civil Service****Chapter 5. Appointments****Article 9. Hiring of Disabled Persons [§19230–§19237](#)**

§19230	Legislative declaration; state policy
§19231	Individual with a disability
§19232	Affirmative action programs; goals and timetables; state agencies
§19233	State personnel board; responsibilities

§19234	Review of hiring activities; disproportionate exclusion; correction of under representation
§19236	Plans to overcome under representation; responsibilities of state personnel board
§19237	Report

Government Code Title 5. Local Agencies

Division 2. Cities, Counties and Other Agencies

Part 1. Powers and Duties Common to Cities, Counties, and Other Agencies

Chapter 9. Meetings [§54950–§54963](#)

§54950	Declaration, intent; sovereignty
§54950.5	Short title
§54951	Local agency
§54951.1 &	
§54951.7	Repealed by Stats.1993, c. 1138 (S.B.1140), §§ 2.3, 2.5, operative April 1, 1994
§54952	Legislative body, definition
§54952.1	Member of a legislative body of a local agency; conduct
§54952.2.	Meeting; prohibited devices for obtaining collective concurrence; exclusions from chapter
§54952.3 &	
§54952.5	Repealed by Stats.1993, c. 1138 (S.B.1140), §§ 5, 6 operative April 1, 1994
§54952.6	Action taken
§54952.7	Copies of chapter to members of legislative body of local agencies
§54953	Meetings to be open and public; attendance
§54953.1	Testimony of members before grand jury
§54953.2	Legislative body meetings to meet protections and prohibitions of the Americans with Disabilities Act
§54953.3	Conditions to attendance
§54953.5	Right to record proceedings; conditions; tape or film records made by or under direction of local agencies
§54953.6	Prohibitions or restrictions on broadcasts of proceedings of legislative body; reasonable findings
§54953.7	Allowance of greater access to meetings than minimal standards in this chapter
§54954	Time and place of regular meetings; special meetings; emergencies
§54954.1	Mailed notice to persons who filed written request; time; duration and renewal of requests; fee
§54954.2	Agenda; posting; action on other matters
§54954.3	Opportunity for public to address legislative body; adoption of regulations; public criticism of policies
§54954.4	Reimbursements to local agencies and school districts for costs
§54954.5	Closed session item descriptions
§54954.6	New or increased taxes or assessments; public meetings and public hearings; joint notice requirements
§54955	Adjournment; adjourned meetings
§54955.1	Continuance
§54956	Special meetings; call; notice
§54956.5	Emergency meetings in emergency situations
§54956.6	Fees
§54956.7	Closed sessions, license applications; rehabilitated criminals
§54956.8	Real property transactions; closed meeting with negotiator
§54956.86	Charges or complaints from members of local agency health plans; closed hearings; members' rights
§54957	Closes sessions; personnel matters; exclusion of witnesses
§54957.1	Closed sessions; public report of action taken
§54957.2	Minute book record of closed sessions; inspection

- §54957.5 Agendas and other writings distributed for discussion or consideration at public meetings; public records; inspection; closed sessions
- §54957.6 Closed sessions; salaries, salary schedules or fringe benefits
- §54957.7 Disclosure of items to be discussed in closed sessions
- §54957.8 Closed sessions; legislative body of a multijurisdictional drug law enforcement agency
- §54957.9 Disorderly conduct of general public during meeting; clearing of room
- §54958 Application of chapter
- §54959 Penalty for unlawful meeting
- §54960 Actions to stop or prevent violations of meeting provisions; applicability of meeting provisions; validity of rules or actions on recording closed sessions
- §54960.1 Unlawful action by legislative body; action for mandamus or injunction; prerequisites
- §54960.5 Costs and attorney fees
- §54961 Meetings prohibited in facilities; grounds; identify of victims of tortuous sexual conduct or child abuse
- §54962 Closed session by legislative body prohibited

Division 3. Executive Department

Part 1. State Departments and Agencies

Chapter 1. State Agencies

Article 9. Meetings [§11120–§11132](#)

- §11120 Public policy; legislative finding and declaration; citation of article
- §11121 State body defined
- §11121.2 Repealed by Stats.2001, c. 243 (A.B.192), § 3
- §11121.5 Repealed by Stats.1984, c. 1158, § 3
- §11121.7 Repealed by Stats.2001, c. 243 (A.B.192), § 4
- §11121.8 Repealed by Stats.2001, c. 243 (A.B.192), § 5
- §11121.9 Provision of copy of article to members of state body
- §11121.95 Appointees or elected officials not yet in office; conformity of conduct to articulate requirements
- §11122 Action taken
- §11122.5 Meeting defined: Collective concurrence prohibited; exceptions
- §11123 Meetings; attendance; teleconference option
- §11123.1 State body meetings to meet protections and prohibitions of the Americans with Disabilities Act
- §11124 Conditions to attendance
- §11124.1 Tape or film recording of proceedings; inspection of state's recording; broadcast restrictions
- §11125 Notice of meeting
- §11125.1 Agendas and other writings distributed for discussion or consideration at public meetings; public records; Franchise Tax Board; inspection; availability on the Internet; closed sessions
- §11125.2 Appointment, employment or dismissal of public employees; closed sessions; public report
- §11125.3 Action on items of business not appearing on agenda; notice
- §11125.4 Special meetings; authorized purposes; notice; required finding of hardship or need to protect public interest
- §11125.5 Emergency meetings
- §11125.6 Fish & Game Commission; emergency meetings; appeals of fishery closures or restrictions
- §11125.7 Agenda item discussion before state body; opportunity for public address; regulation by state body; freedom of expression; application of provisions
- §11125.8 Hearings to consider crimes against minors or crimes of sexual assault or domestic violence; identification of applicant; disclosure of nature of hearing
- §11125.9 Regional water quality control boards; compliance with notification guidelines
- §11126 Closed sessions
- §11126.1 Record of topics discussed and decisions made at closed sessions; availability
- §11126.3 Disclosure of nature of items to be discussed in closed session; scope of session; notice of meeting; announcement of pending litigation; unnecessary disclosures; disclosures at open session following closed session

§11126.5	Disorderly conduct of general public during meeting; clearing of room
§11126.7	Fees
§11127	Application of article
§11128	Time of closed session
§11128.5	Adjournment; declaration; notice; hour for reconvened meeting
§11129	Continuance; posting notice
§11130	Actions to prevent violations or determine applicability of article; validity of rules discouraging expression; taping of closed sessions; discovery procedures for tapes
§11130.3	Judicial determination action by state body in violation of §§11123 or 11125 null and void; action by interested person; grounds
§11130.5	Court costs and attorney fees
§11130.7	Violations; misdemeanor
§11131	Use of facility allowing discrimination; state agency
§11131.5	Identity of victims or alleged victims of crimes; tortuous sexual conduct, or child abuse; public disclosure
§11132	Closed session by state body prohibited

Health and Safety Code

Division 12. Fires and Fire Protection

Part 1. General Provisions

Chapter 1. Liability in Relation to Fires [§13000–§13011](#)

§13011	Double doors
--------	--------------

Division 13. Housing

Part 1. Employee Housing Act

Chapter 1. General Provisions and Definitions [§17000–§17011](#)

§17000	Short title
§17000.1 to	
§17000.4	Repealed by Stats.1961, c. 1844, p. 3919, § 7
§17001	Compliance with building standards and regulations; local standards
§17002	Use of material, appliance, etc., not prescribed by this part; approval of alternate; ordinances
§17003	Commission
§17003.5	Reference to commission of housing and community development deemed to be department of housing and community development; exercise of powers and duties
§17004	Department
§17005	Employee; exclusions
§17005.5	Employee community housing
§17006	Resident-employment housing
§17007	Enforcement agency
§17008	Employee housing
§17008.7	Repealed by Stats.1998, c. 371 (S.B.302), § 1
§17009	Labor supply employee housing
§17009.5	Person
§17010	Temporary employee housing; seasonal employee housing; permanent employee housing; permanent single-family employee housing
§17011	Sleeping place

Division 13. Housing**Part 1. Employee Housing Act****Chapter 2. Application and Scope** [§17020–§17024](#)

§17020	Supremacy over local ordinances or regulations; continuation of existing rules and regulations; duration of building standards
§17021	Reservation to local jurisdiction for local use zones, fire zones, property lines, water supply and sewage disposal; exception for construction or improvement to agricultural employee housing; compliance with California Environmental Quality Act; recovery of costs incurred for review of application or permit denial
§17021.5	Single-family structure with residential land use designation; treatment of employee housing; definition
§17021.6	Agricultural land use designation; treatment of employee housing; definition
§17021.7	Mobile homes and recreational vehicles used to house agricultural employees; maintenance requirement
§17022	Occupational safety and health standards; enforcement
§17022.5	Model or prototype plans for employee housing
§17023	Application of rules and regulations; duration of building standards
§17024	Housing for faculty or employees of schools, colleges, or universities

Division 13. Housing**Part 1. Employee Housing Act****Chapter 3. Permits and Fees** [§17030–§17039](#)

§17030	Permit required; exemptions; enforcement for railroad corporations
§17030.5	Permanent housing; duration of permit; findings
§17031	Permanent housing; exemption from annual permit requirement; procedure; conditions; findings; revocation
§17031.3	Permit for employee community housing; exemptions
§17031.4	Local enforcement agency; information to department
§17031.5	Employee Housing; termination or modification of tenancy; tenants' rights
§17031.6	Eviction proceedings; defenses; payment of reasonable monthly rental value to court in cases of delay or continuance
§17031.7	Retaliatory employment action
§17031.8	Local enforcement agency; submission of information; annual report
§17032	Applications; time; contents; amended permits
§17033	Railroad Corporations; permits to operate employee housing
§17034	Violations
§17035	Roster
§17036	Regulations; fees
§17037	Compliance with requirements; failure to obtain permit; penalty fees
§17037.5	Certificate of non-operation; submittal to enforcement agency; requirements
§17038	Compliance; appointment of responsible person; emergency telephone number
§17039	Compliance; maintenance and sanitation; application of violation provisions

Division 13. Housing**Part 1. Employee Housing Act****Chapter 4. Rules and Regulations** [§17040–§17043](#)

§17040	Duties of department; enforcement of building standards; adoption and submission of building standards
§17041	Consistency with accepted standards and practices; fee schedule; waiver or reduction of fees
§17042	Building standards; restrictions on department
§17043 to §17045	Repealed by Stats.1951, c. 1127, p. 2894, § 28

Division 13. Housing**Part 1. Employee Housing Act****Chapter 5. Enforcement [§17050–§17056](#)**

- §17050 Local enforcement; assumption of enforcement by department; powers of enforcement agency
- §17051 Service of process or notice
- §17052 Annual inspections; exceptions
- §17053 Complaint and information file; public record; availability to local enforcement agencies; district attorneys, and attorney general
- §17054 Attorney general; investigations; powers; prosecutions
- §17055 Administrative complaint; civil action
- §17056 Prosecution of serious violators; implementation of part; bilingual civil service employees; report

Division 13. Housing**Part 1. Employee Housing Act****Chapter 6. Violations [§17060–§17062.5](#)**

- §17060 Nuisance; health or safety hazards; jurisdiction; service of summons; lis pendens; recordation
- §17060.2 Orders or notices of violations; vacating of accommodations; relocation ordinances; attorney's fees and costs; deferral of orders of abatement
- §17060.5 Transfer to third party; continuance of action or proceeding; subjection of new owner to order for correction

Division 13. Housing**Part 5. Regulation of Buildings Used for Human Habitation****General Provisions [§17910–§17913](#)**

- §17910 Short title
- §17911 Application of part
- §17912 Application of rules, regulations and building standards to existing buildings
- §17913 Uniform codes; notice of publication, approval and adoption; publication of information bulletins regarding enforcement; distribution of information

Division 13. Housing**Part 1.5. Regulation of Buildings Used for Human Habitation****Chapter 2. Rules and Regulations [§17920–§17927](#)**

- §17920 Definitions
- §17920.3 Substandard building; conditions
- §17920.5 Local appeals board
- §17920.6 Housing appeals board
- §17920.7 Repealed by Stats.1990, c. 1083 (S.B.1830), § 6; Stats.1990, c. 1111 (A.B.2666), § 6
- §17920.8 Exit identification near floor
- §17920.9 Building standards; fire safety and fire resistant regulations; foam building systems; approved testing agency
- §17920.10 Lead hazards; violations; definitions
- §17921 Building standards; rules and regulations
- §17921.1 Hotplates
- §17921.3 Water closets, urinals, and associated flushometer valves; requirements, local enforcement
- §17921.5 Repealed by Stats.1984, c. 888, § 1
- §17921.7 ABS Plumbing pipe; manufacturing; use of approved resins and compounds; documentation; approval standards
- §17921.9 CPVC plastic piping; alternative material; safe work practices

§17922	Administrative code rules and regulations; uniform housing code requirements; local requirements
§17922.1	Modification or change of regulation requirements; findings
§17922.2	Hazardous building ordinances and programs; building standards; local conditions; exceptions; study
§17922.3	Residential structure; movement into or within jurisdiction of local agency or the department; application of Section 17958.9
§17922.5	Application for, and issuance of, building permit; prerequisites
§17922.6	Noise insulation standards and requirements
§17922.7	Noise insulation standards; changes, modifications or additions by cities, counties and public entities
§17922.8	Advisory committee
§17922.9	Low and moderate income housing; FHA mortgage restriction on garage and house size; exemption from local requirements
§17923	Alternate materials and methods of construction; approval; tests to prove compliance
§17924	Promulgation of rules and regulations; adoption and submission of building standards
§17925	Opposition to building standards, rules or regulations; hearing; determination; filing
§17927	Garage door springs

Division 13. Housing

Part 1.5. Regulation of Buildings Used for Human Habitation

Chapter 3. Appeals [§17930–§17932](#)

§17930	Hearing
§17931	Rules pertaining to hearing appeals
§17932	Finality of decision
§17933	Repealed by Stats.1968, c. 1018, p. 1970, § 5
§17934	Blank
§17935	Renumbered § 17931 and amended by Stats.1968, c. 1018, p. 1970, § 6
§17936	Blank
§17937 &	
§17938	Renumbered §§ 17930, 17932 and amended by Stats.1968, c. 1018, p. 1970, §§ 7, 8
§17939	Repealed by Stats.1968, c. 1018, p. 1970, § 9
§17940	Repealed by Stats.1968, c. 1473, p. 2950, § 58
§17941	Repealed by Stats.1968, c. 1018, p. 1970, § 11

Division 13. Housing

Part 1. Regulation of Buildings Used for Human Habitation

Chapter 4. Application and Scope [§17950–§17959.6](#)

§17950	Apartment house, hotel and dwelling provisions
§17951	Local fees; alternate materials and construction methods; approval; evidence
§17952	Enforcement; notice to city or county of violation; hearing; assessment of fees
§17953	Preliminary soil report; ordinance requiring; waiver
§17954	Soil investigation by lot; necessity; preparation; recommendations
§17955	Approval; building permit conditions; appeal
§17956	Liability of public agency or employee
§17957	Alternate procedure
§17958	Adoption of regulations or ordinances imposing requirements in Section 17922 by governing body of cities and counties
§17958.1	Efficiency units
§17958.2	Limited density owner-built rural dwellings; regulations; findings prior to operative effect; local variances
§17958.3	Maintenance of copy of building standards and other state regulations relating to buildings
§17958.4	Window security bars; safety release mechanisms; state and local requirements; disclosure; application of ordinances
§17958.5	Local variances; annual report

- §17958.7 Local variances; findings; filing; rejection of modification
- §17958.8 Alterations and repairs; original materials and methods
- §17958.9 Apartment houses and dwellings; movement; retention of existing materials and methods of construction
- §17958.11 Alternative building regulations; joint living and work quarters; geographic areas
- §17959 Consideration of proposed universal design guidelines for home construction or home modifications; enhancement of full life cycle use of housing without regard to physical abilities or disabilities of home's occupants or guests as part of state's guidelines or ordinances
- §17959.4 Hardship cases; deferral of order of abatement
- §17959.5 Variances

Division 13. Housing

Part 1.5. Regulation of Buildings Used for Human Habitation

Chapter 5. Administration and Enforcement

Article 1. Enforcement Agencies [§17960–§17967](#)

- §17960 City or county building departments
- §17960.1 Plan-checking; contract with or employment of private entity
- §17960.5 Residential building standards; application to approved projects
- §17961 City or county housing or building department, health department, or environmental agency; enforcement duties
- §17961.5 Renumbered §17962 and amended by Stats.1979, c. 1152, p. 4272, § 85
- §17962 Fire protection provisions; enforcement
- §17964 Designation of department or officer
- §17965 Department of housing and community development
- §17966 Contracts for assistance
- §17967 Records and reports of local enforcement agencies; examination; copies

Division 13. Housing

Part 1.5. Regulation of Buildings Used for Human Habitation

Chapter 5. Administration and Enforcement

Article 2. Inspection [§17970–§17972](#)

- §17970 Authority to enter and inspect premises
- §17971 Authority of owner to enter premises to carry out instructions or perform work
- §17972 Limitations on authority to enter

Division 13. Housing

Part 1.5. Regulation of Buildings Used for Human Habitation

Chapter 5. Administration and Enforcement

Article 3. Actions and Proceedings [§17980–§17992](#)

- §17980 Buildings in violation; notice to abate nuisance; instituting actions or proceedings; substandard buildings; repair or demolition; preferences; notice of violations; costs
- §17980.1 Buildings hazardous to life in event of earthquake; retrofitting; conditions; noncompliance; notice; receiver; application; appointment; fees
- §17980.2 Lien for costs; fee; contents; recording; expenses
- §17980.3 Receiver; powers and duties; fees and commissions; discharge
- §17980.4 Action for recovery of expenses incurred by enforcement agency; remedies; criminal and civil liability of owner
- §17980.5 Special fund for implementation of §17980.1 to §17980.4
- §17980.6 Violations; order or notice to repair, failure to correct; remedies of §17980.7 applicable
- §17980.7 Failure of owner to comply within a reasonable time with terms of order or notice pursuant to §17980.6

- §17980.8 Administrative determination of unsafe or substandard condition; abatement or other exercise of authority; owner exclusive remedy; judicial review standard; application of section
- §17980.9 City of Los Angeles or City of San Diego; inspection of vacant single-family dwellings; action to correct violations or abate nuisances; tax notice; reimbursement of costs
- §17981 Temporary relief pending final judgment
- §17982 Order to remove violation or abate nuisance
- §17983 Powers of court
- §17984 Liability for costs
- §17985 Notice of pending action; costs; effect; notice of final disposition; recording
- §17986 Recordation of notice
- §17987 Vacation of notice
- §17988 Service of summons
- §17989 Service of notices and orders; time for service
- §17990 Pleading in response to summons; time to file

Division 13. Housing

Part 2.5. State Building Standards

Chapter 1. General Provisions and Definitions

Article 1. Title [§18901–§18902](#)

- §18901 Short title
- §18902 State Buildings Standards Code; Title 24 of California Administrative Codes; references
- §18903 &
- §18904 Repealed by Stats.1979, c. 1152, p. 4292, § 162

Division 13. Housing

Part 2.5. State Building Standards

Chapter 1. General Provisions and Definitions

Article 2. Definitions [§18905–§18919](#)

- §18905 Construction
- §18905.1 &
- §18905.2 Renumbered §§ 18910, 18911 and amended by Stats.1965, c. 1828, p. 4218, §§ 9, 10
- §18905.5 Adopting agency
- §18906 Adoption or adopt
- §18906.3 &
- §18906.4 Renumbered §§ 18912, 18913 and amended by Stats.1965, c. 1828, p. 4219, §§ 13, 14
- §18907 Approval
- §18908 Building; structure
- §18909 Building standard
- §18910 Code
- §18911 Codification; codify
- §18912 Commission
- §18913 Emergency Standard
- §18914 Executive Director
- §18915 Local Agency
- §18916 Model code
- §18917 Occupancy
- §18917.2 Propose
- §18917.3 Publication; publish
- §18917.5 Secretary
- §18918 State Agency
- §18919 Regulation

Division 13. Housing**Part 2.5. State Building Standards****Chapter 2. Organization****Article 1. The California Building Standards Commission** [§18920–§18924](#) [§18925](#) [§18926–§18929.1](#)

§18920	Existence; composition
§18921	Appointed members
§18922	Chair; vice chair
§18923	Term of Office
§18924	Compensation; travel expenses
§18925	Executive Director
§18926	Coordinating Council; existence; membership; duties
§18927	Advisory panels; qualifications of persons appointed; compensation
§18928	Model code, national standard or specification; adoption of and reference to most recent addition; date of publication; committee
§18928.1	Building standards; incorporation of model codes, applicable national specifications or published standards; publication agreement
§18929	Adoption of administrative regulations applying to implementation or enforcement of building standards; publication; certain Housing and Community Development Department regulations excepted
§18929.1	Adoption of regulations for annual code adoption cycle; procedures, contents

Division 13. Housing**Part 2.5. State Building Standards****Chapter 3. Powers of the Commission** [§18930–§18934.8](#)

§18930	Approval or adoption of building standards; analysis and criteria; review considerations; factual determinations
§18931	Duties
§18931.5	Review and publication costs; payment of proportionate share
§18932	Contents and format of code
§18933	Amendment or repeal of building standards
§18934	Public participation; guidelines
§18934.5	Standards for state buildings; adoption, approval, codification and publication
§18934.6	Uniform Code for Building Conservation of the International Conference of Building Officials; publication of standards; exception
§18934.7	Uniform Code for Building Conservation of the International Conference of Building Officials; publication of standards; exception
§18934.8	Amendments to California Building Code; emergency amendments

Division 13. Housing**Part 2.5. State Building Standards****Chapter 4. The California Building Standards Code** [§18935–§18944.7](#)

§18935	Proposed building standards; notice and hearings; initial statement of reasons; review and publication; approval; changes
§18936	Notices of Meetings
§18937	Emergency Standards
§18938	Filing and codification; publication; effective date; application of section
§18938.5	Application of standards; local ordinances; and model codes
§18940	Codification of standards
§18941	Standards; administration and enforcement; performance basis
§18941.5	Amendments, additions, deletions to standards; effective date; publication date; more restrictive standards
§18941.6	Hazardous building ordinances and programs; building standards; local conditions; exceptions; study

- §18941.7 Repealed by Stats.1997, c. 645 (A.B.1071), § 14, operative Jan. 1, 2003
- §18941.8 March Air Force Base; graduated compliance with regulations or standards; adoption of ordinance; conditions
- §18941.9 Graduated compliance; adoption of ordinances; application; conditions
- §18942 Publication; supplements; emergency standards; availability and possession of code
- §18942.1 Filing of regulations or orders of repeal; transmittal
- §18943 Effect of standards in individual titles
- §18944 References to code in agency regulations
- §18944.5 Agencies bound by code
- §18944.7 State historical building code; alternative regulations and standards; maintenance as separate and distinct part or portion

Division 13. Housing

Part 2.5. State Building Standards

Chapter 5. Appeals and Enforcement [§18945–§18949](#) [§18949.1–§18949.6](#) [§18949.25–§18949.31](#)

- §18945 Right to appeal
- §18946 Hearing; reference; decision
- §18947 Appeal to occupational safety and health appeals board
- §18948 Responsibility for enforcement and administration
- §18949 Fee Schedule
- §18949.1 State Architect, transfer of responsibilities to commission
- §18949.2 State Fire Marshal; formal rule making process; transfer of duties to commission; fire and life safety standards; development; review, modification
- §18949.3 Office of Statewide Health Planning and Development; transfer of duties to commission
- §18949.4 State Energy Resources Conservation and Development Commission; submission of standards for review and approval; time schedule
- §18949.5 Department of Housing and Community Development; transfer of duties to commission
- §18949.6 Procedure for adoption of standards and administrative regulations
- §18949.25 Construction inspector
- §18949.26 Plans examiner
- §18949.27 Building Official
- §18949.28 Experience and certification requirements; exemptions
- §18949.29 Continuing Education
- §18949.30 Application of Chapter
- §18949.31 Local agencies; costs and fees

Division 13. Housing

Part 2.7. State Historical Building Code [§18950–§18961](#)

- §18950 Short title
- §18951 Purpose
- §18952 Application
- §18953 Intent
- §18954 Repairs, alterations, and additions; application of building standards and building regulations; physically handicapped accessibility standards
- §18955 Qualified historical building or structure
- §18956 Application of Government Code, Public Resources Code, and other statutes and regulations
- §18957 Authorized building and fire officials; performance of duties
- §18958 Additional agencies authorized to adopt rules and regulations
- §18959 Administration and enforcement
- §18959.5 Alternative building standards, rules and regulations; historical buildings code board
- §18960 State historical building code board
- §18961 Review, enforcement and administration of variances, appeals procedure; agency to consider alternative provisions of this part and obtain review

Division 13. Housing**Part 5.3. Access to Places of Public Amusement and Resort
by Physically Handicapped Persons [§19952–§19954.5](#)**

- §19952 Seating or accommodations in various locations within facility; removable seats; application; construction
- §19953 Injunctions; attorney's fees
- §19954 Injunctions; persons who may bring action
- §19954.5 Mandatory service on State Solicitor General of Each party's brief or petition and brief in causes of action based on violation of civil rights statutes

Division 13. Housing**Part 5.5. Access to Public Accommodations by Physically Handicapped Persons [§19955–§19959.5](#)**

- §19955 Purpose
- §19955.3 Definitions
- §19955.5 Access to passenger vehicle service stations, shopping centers, physicians' and surgeons' offices, and office buildings constructed with private funds; prospective application of section
- §19956 Conformity with Government Code provisions; exceptions
- §19956.5 Public curb or sidewalk constructed with private funds
- §19957 Exceptions from literal requirements of standards and specifications in hardship, etc., cases
- §19957.5 Local appeals board; jurisdiction; members; duties
- §19958 Enforcement; building department defined
- §19958.5 Violations; injunctions; district or city attorney; county counsel; Attorney General
- §19958.6 Civil penalties for violations of regulations implementing sections promulgated by State Architect; circumstances considered by court in determining amount of penalties; suspended penalties
- §19959 Alteration of existing public accommodations
- §19959.5 Mandatory service on State Solicitor General of each party's brief or petition and brief in causes of action based on violation of civil rights statutes

Division 13. Housing**Part 6. Factory-built Housing****Chapter 1. General Provisions and Definitions [§19960–§19961](#)**

- §19960 Short title
- §19961 Legislative Findings

Division 13. Housing**Part 6. Factory-built Housing****Chapter 2. Definitions [§19965–§19977](#)**

- §19965 Construction of part
- §19966 Approved
- §19967 Building Component
- §19967.1 Building system
- §19967.2 Building standard
- §19969 Department
- §19969.3 Design Approval Agency
- §19970 Dwelling unit
- §19971 Factory-built housing
- §19972 First user
- §19974 Installation
- §19975 Local enforcement agency
- §19975.1 Local inspection agency
- §19976 Manufacture

- §19976.05 Quality assurance agency
- §19976.1 Residential Building
- §19977 Site

Division 13. Housing**Part 6. Factory-built Housing****Chapter 3. Regulation [§19980–§19985](#)**

- §19980 Factory-built housing; insignia of approval
- §19981 Presumption of compliance of approved factory-built housing with local ordinances and regulations; prohibition against modification without approval
- §19982 Schedule of fees; disposition and appropriation of fees; reductions in schedule
- §19983 Delegating enforcement authority to local government agencies; approving design approval agencies
- §19984 Law governing adoption of building standards and rules and regulations
- §19985 Approval of factory-built housing manufactured in accordance with standards of another state

Division 13. Housing**Part 6. Factory-built Housing****Chapter 4. Application and Scope [§19990–§19993](#)**

- §19990 Adoption of rules and regulations and building standards
- §19990.6 Foam building systems; laws, standards and regulations
- §19991 Enforcement by department
- §19991.1 In-plant inspections by local agencies; certification; fees
- §19991.2 In-plant inspections by department
- §19991.3 Design approval agencies; regulations for qualification and disqualification
- §19991.4 Qualification and disqualification of quality assurance agencies to perform inspections
- §19992 Installation of factory-built housing; enforcement and inspection by local agencies; fees
- §19993 Zoning, load and pressure requirements reserved to local jurisdictions; factory-built housing

Division 13. Housing**Part 6. Factory-built Housing****Chapter 5. Appeals [§19995–§19996](#)**

- §19995 Hearing by department
- §19996 Rules and regulations

Division 13. Housing**Part 6. Factory-built Housing****Chapter 6. Penalties [§19997](#)**

- §19997 Violation; misdemeanor

Insurance Code

Division 2. Classes of Insurance

Part 2. Life and Disability Insurance

Chapter 1. The Contract

Article 2.5. Discriminatory Practices [§10140–§10145.4](#)

§10144	Physically or mentally impaired person; coverage and rates
§10144.1	Disability insurer; claimant with terminal illness; experimental medical procedure or plan of treatment; coverage denial; notification requirements; review rights
§10144.2	Victims of domestic violence; health care service plans; enrollment, coverage or rate discrimination; underwriting coverage on basis of medical condition
§10145	Blindness or partial blindness

Public Resources Code

Division 5. Parks and Monuments

Chapter 2.6. Public Playground Equipment [§5410–§5411](#)

§5410	Legislative findings and declarations
§5411	Purchase of equipment usable by physically handicapped persons

Vehicle Code

Division 3. Registration of Vehicles and Certificates of Title

Chapter 1. Original and Renewal of Registration; Issuance of Certificates of Title

Article 8. Special Plates [§5000–§5024](#)

§5007	Disabled person or disabled veterans; special identification license plates; return to department on death or expiration
-------	--

Division 11. Rules of the Road

Chapter 2. Traffic Signs, Signals, and Markings

Article 3. Offenses Relating to Traffic Devices [§21458](#)

§21458	Curb markings
--------	---------------

Division 11. Rules of the Road

Chapter 9. Stopping, Standing, and Parking [§22500–§22526](#)

§22500	Prohibited stopping, standing, or parking
§22507	Local regulation; preferential parking
§22507.8	Disabled persons' and veterans' parking spaces; unauthorized parking or obstructing; off street parking facilities
§22507.9	Special enforcement units, handicapped parking enforcement; compensation and benefits; application of section
§22511	Zero-emission vehicle (ZEV) parking stalls or spaces; off-street parking facility posting and signage requirements; decals; local ordinances
§22511.5	Disabled persons or disabled veterans; parking privileges
§22511.55	Issuance and renewal of disabled parking placard; conditions; printing requirements
§22511.56	Presentation of identification and evidence of issuance; failure to present; reputable presumption of misuse; penalty; confiscation of placard
§22511.57	Disabled person placards lost or stolen; owner of placard deceased; vehicle parking restrictions and prohibitions
§22511.58	Physician's certificate information; release to specified local agencies; local review board

§22511.59	Temporary distinguishing placard
§22511.6	Cancellation or revocation of distinguishing placards
§22511.7	Designation of parking for disabled persons and veterans
§22511.8	Off street parking; designation of parking for disabled persons and veterans; removal of unauthorized vehicles
§22511.85	Public offstreet parking facilities; loading and unloading disabled persons; sufficient space
§22511.9	Replacement signs relating to parking privileges for disabled persons; contents
§22511.10	Disabled persons; Legislative findings
§22511.11	Office of State Architect; regulations; location of disabled person parking stalls or spaces
§22522	Parking near sidewalk access ramps

DSA Access Compliance Regulations

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL REGULATIONS

Introduction

Section 2 – Regulations: The California Code of Regulations (CCR) is the official compilation and publication of the regulations adopted, amended or repealed by state agencies. The CCR consists of 28 titles; Title 24, the California Building Standards Code, serves as the basis for the design and construction of buildings in California. The regulations included in this document are excerpted from Title 24 and include building regulations, adopted by DSA, which govern accessibility for persons with disabilities.

TABLE OF CONTENTS

PART 1 – 2010 CALIFORNIA ADMINISTRATIVE CODE

Effective Date: January 1, 2011

CHAPTER 5

ACCESS TO PUBLIC BUILDINGS BY PERSONS WITH DISABILITIES

ARTICLE 1 – COMPLIANCE PROCEDURES

5-101 Purpose 10
5-102 General 10
5-103 Application 10
5-104 Fees 11
5-105 Project Cost 12
5-106 Revision of Plans and Specifications 12
5-107 Billing for Further Fees 12
5-108 Refunds 13
5-109 Review of Plans and Specifications 13
5-110 Written Approval 13
5-111 General Requirements 13

ARTICLE 2 – DIVISION OF THE STATE ARCHITECT – ACCESS COMPLIANCE PROCESSING PRODUCT APPROVALS JANUARY 1, 2001

5-201 Processing Independent Entity Evaluation Approvals (IEEA) 14
5-202 IEEA Application Procedure 14
5-203 IEEA Acceptance Procedure 14
5-204 Accounting of IEEA 14
5-205 Contacts for Questions 14

ARTICLE 3 – ACCEPTANCE OF DETECTABLE WARNING AND DIRECTIONAL SURFACE PRODUCTS FOR MANUFACTURERS AND DESIGN PROFESSIONALS JANUARY 1, 2001

5-301 Division of the State Architect, Access Compliance, Acceptance of Product 15

ARTICLE 4 – APPLICATION FOR INDEPENDENT ENTITY EVALUATION APPROVAL (IEEA)

5-401 Application for IEEA 16

PART 1 – HISTORY NOTE APPENDIX 17

PART 2 – 2010 CALIFORNIA BUILDING CODE

Effective Date: January 1, 2011

CHAPTER 1 – SCOPE AND ADMINISTRATION

Matrix Adoption Table 18

DIVISION I CALIFORNIA ADMINISTRATION

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION	PAGE NUMBERS	
1.1 General	18	
1.9 Division of the State Architect.....	22	
<u>DIVISION II SCOPE AND ADMINISTRATION</u>		
111 Certificate of Occupancy	24	
<u>CHAPTER 2 – DEFINITIONS</u>		
Matrix Adoption Table	25	
202 Definitions	28	
<u>CHAPTER 3 – USE AND OCCUPANCY CLASSIFICATION</u>		
Matrix Adoption Table	36	
302 Classification.....	36	
310 Residential Group R.....	37	
<u>CHAPTER 4 – SPECIAL DETAILED REQUIREMENTS ON USE AND OCCUPANCY</u>		
Matrix Adoption Table	38	
406 Motor-Vehicle-Related Occupancies	38	
410 Stages and Platforms	38	
412 Aircraft-Related Occupancies	38	
420 Groups R-1, R-2, R-2.1, R-3, R-4	39	
<u>CHAPTER 9 – FIRE PROTECTION SYSTEMS</u>		
Matrix Adoption Table	40	
907 Fire Alarm and Detection Systems	40	
<u>CHAPTER 10 – MEANS OF EGRESS</u>		
Matrix Adoption Table	43	
1002 Definitions	44	
1003 General Means of Egress	44	
1007 Accessible Means of Egress.....	45	
1008 Doors, Gates and Turnstiles	49	
1009 Stairways	50	
1010 Ramps	50	
1011 Exit Signs.....	51	
1012 Handrails.....	51	
1013 Guards	51	
1017 Aisles	53	
1022 Exit Enclosures	53	
<u>CHAPTER 11 – RESERVED</u>		54
<u>CHAPTER 11A – HOUSING ACCESSIBILITY</u>		
Matrix Adoption Table	55	
<u>DIVISION I – APPLICATION, GENERAL PROVISIONS AND DEFINITIONS</u>		
1101A Application	55	
1102A Building Accessibility	56	

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION	PAGE NUMBERS
1103A Design and Construction	58
1104A Covered Multifamily Dwellings	58
1105A Garages, Carports and Parking Facilities	58
1106A Site and Building Characteristics	58
1107A Definitions	59
<u>DIVISION II – EXTERIOR FACILITIES</u>	
1108A General Requirements for Accessible Parking and Exterior Routes of Travel	64
1109A Parking Facilities	64
1110A Exterior Routes of Travel.....	67
1111A Changes In Level on Accessible Routes	68
1112A Curb Ramps on Accessible Routes.....	69
1113A Walks and Sidewalks on an Accessible Route	70
1114A Exterior Ramps and Landings on Accessible Routes	71
1115A Exterior Stairways.....	73
1116A Hazards on Accessible Routes	74
<u>DIVISION III – BUILDING FEATURES</u>	
1117A General Requirements for Accessible Entrances, Exits, Interior Routes of Travel And Facility Accessibility.....	76
1118A Egress and Areas of Refuge	77
1119A Interior Routes of Travel.....	77
1120A Interior Accessible Routes.....	77
1121A Changes in Level on Accessible Routes	78
1122A Interior Ramps and Landings on Accessible Routes.....	78
1123A Interior Stairways.....	80
1124A Elevators and Platform (Wheelchair) Lifts.....	81
1125A Hazards on Accessible Routes	84
1126A Doors	85
1127A Common Use Facilities	87
<u>DIVISION IV – DWELLING UNIT FEATURES</u>	
1128A Covered Dwelling Units	97
1129A Reserved	97
1130A Accessible Route Within Covered Multifamily Dwelling Units	97
1131A Changes in Level on Accessible Routes	97
1132A Doors	98
1133A Kitchens.....	100
1134A Bathing and Toilet Facilities.....	101
1135A Laundry Rooms	106
1136A Electrical Receptacle, Switch and Control Heights.....	106
<u>DIVISION V – FEATURES COMMON TO EXTERIOR AND INTERIOR OF BUILDINGS</u>	
1137A Other Features and Facilities	108
1138A Reserved	108
1139A Accessible Drinking Fountains	108
1140A Accessible Telephones	109
1141A Accessible Swimming Pools.....	110
1142A Electrical Receptacle, Switch and Control Heights.....	111
1143A Signage	112
1144A through 1149A Reserved.....	113

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION

PAGE NUMBERS

DIVISION VI – SITE IMPRACTICALITY TESTS

1150A Site Impracticality Tests	114
Test No. 1 – Individual Building Test	114
Test No. 2 – Site Analysis Test	115
Test No. 3 – Unusual Characteristics Test	115

DIVISION VII – FIGURES (link to separate document for 11A Figures)

CHAPTER 11B – ACCESSIBILITY TO PUBLIC BUILDINGS, PUBLIC ACCOMMODATIONS, COMMERCIAL BUILDINGS AND PUBLICLY FUNDED HOUSING

Matrix Adoption Table	117
-----------------------------	-----

DIVISION I – NEW BUILDINGS

1101B Scope	117
1102B Definitions	118
1103B Building Accessibility	123
1104B Accessibility for Group A Occupancies	124
1105B Accessibility for Group B Occupancies	129
1106B Accessibility for Group E Occupancies	131
1107B Factories and Warehouses	132
1108B Accessibility for Group H Occupancies	133
1109B Accessibility for Group I Occupancies	133
1110B Accessibility for Group M Occupancies	135
1111B Accessibility for Group R Occupancies	137
1112B Reserved	140
1113B Reserved	140
1114B Facility Accessibility	141
1115B Bathing and Toilet Facilities (Sanitary Facilities)	142
1116B Elevators and Platform (Wheelchair) Lifts	151
1117B Other Building Components	156
1118B Space Allowance and Reach Ranges	168
1119B Special Standards of Accessibility for Buildings with Historical Significance	169
1120B Floors and Levels	169
1121B Transportation Facilities	169
1122B Fixed or Built-in Seating, Tables and Counters	175
1123B Access to Employee Areas	176
1124B Ground and Floor Surfaces	176
1125B Storage	176
1126B Vending Machines and Other Equipment	177

DIVISION II – SITE ACCESSIBILITY

1127B Exterior Routes of Travel	178
1128B Pedestrian Grade Separations (Overpasses and Underpasses)	180
1129B Accessible Parking Required	180
1130B Parking Structures	183
1131B Passenger Drop-off and Loading Zones	183
1132B Outdoor Occupancies	184

DIVISION III – ACCESSIBILITY FOR ENTRANCES, EXITS AND PATHS OF TRAVEL

1133B General Accessibility for Entrances, Exits and Paths of Travel	186
--	-----

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION	PAGE NUMBERS
<u>DIVISION IV – ACCESSIBILITY FOR EXISTING BUILDINGS</u>	
1134B Accessibility for Existing Buildings.....	198
1135B Historic Preservation – Special Standards of Accessibility for Buildings with Historical Significance	201
<u>FIGURES 11B – 1A THROUGH 11B – 40D</u> (link to separate document for 11B Figures)	
<u>CHAPTER 11C – STANDARDS FOR CARD READERS AT GASOLINE FUEL-DISPENSING FACILITIES</u>	
Matrix Adoption Table	202
1101C Card-Reader Devices at Fuel-Dispensing Equipment	202
1102C Application.....	203
1103C Number of Accessible Card-Reading Devices Required	203
1104C Required Features	203
<u>FIGURES 11C – 1 AND 11C – 2</u> (link to separate document for 11C Figures)	
<u>CHAPTER 16 – STRUCTURAL DESIGN</u>	
Matrix Adoption Table	204
1607 Live Loads	204
<u>CHAPTER 16A – STRUCTURAL DESIGN</u>	
Matrix Adoption Table	205
1607A Live Loads	205
<u>CHAPTER 27 – ELECTRICAL</u>	
Matrix Adoption Table	206
2702 Emergency and Standby Power Systems.....	206
<u>CHAPTER 30 – ELEVATORS AND CONVEYING SYSTEMS</u>	
Matrix Adoption Table	207
3001 General	207
<u>CHAPTER 31 – SPECIAL CONSTRUCTION</u>	
Matrix Adoption Table	208
3104 Pedestrian Walkways and Tunnels.....	208
<u>CHAPTER 31B – PUBLIC SWIMMING POOLS</u>	
Matrix Adoption Table	209
3113B Pool Decks	209
<u>CHAPTER 33 – SAFEGUARDS DURING CONSTRUCTION</u>	
Matrix Adoption Table	210
3306 Protection of Pedestrians.....	210

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION.....	PAGE NUMBERS
<u>CHAPTER 34 – EXISTING STRUCTURES</u>	
Matrix Adoption Table	211
3401 General	211
3409 Historic Buildings	211
<u>CHAPTER 35 – REFERENCED STANDARDS</u>	
Matrix Adoption Table	212
<u>PART 2 – HISTORY NOTE APPENDIX</u>	215

PART 3 – 2010 CALIFORNIA ELECTRICAL CODE

Effective Date: January 1, 2011

<u>CALIFORNIA ARTICLE 89 – GENERAL CODE PROVISIONS</u>	
Matrix Adoption Table	216
89.109.1 Division of the State Architect – Access Compliance	216
<u>CHAPTER 4 – EQUIPMENT FOR GENERAL USE</u>	
Matrix Adoption Table	216
<u>ARTICLE 404 – SWITCHES</u>	217
<u>ARTICLE 406 – RECEPTACLES, CORD CONNECTORS, AND ATTACHMENT PLUGS (CAPS)</u>	
Matrix Adoption Table	217
<u>CHAPTER 7 – SPECIAL CONDITIONS</u>	
<u>ARTICLE 760 – FIRE ALARM SYSTEMS</u>	
Matrix Adoption Table	217
<u>PART 3 – HISTORY NOTE APPENDIX</u>	218

PART 5 – 2010 CALIFORNIA PLUMBING CODE

Effective Date: January 1, 2011

<u>CHAPTER 1 – ADMINISTRATION</u>	
Matrix Adoption Table	219
<u>DIVISION I – CALIFORNIA ADMINISTRATION</u>	
1.9.0 Division of the State Architect	219
<u>CHAPTER 4 – PLUMBING FIXTURES AND FIXTURE FITTINGS</u>	
Matrix Adoption Table	219
412.0 Minimum Number of Required Fixtures	220

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION

PAGE NUMBERS

<u>PART 5 – HISTORY NOTE APPENDIX</u>	221
--	-----

PART 8 – 2010 CALIFORNIA HISTORICAL BUILDING CODE

Effective Date: January 1, 2011

CHAPTER 8-1 – ADMINISTRATION

8-101 Title, Purpose and Intent	222
8-102 Application	222
8-103 Organization and Enforcement	223
8-104 Review and Appeals	223
8-105 Construction Methods and Materials	224
8-106 SHBSB Rulings	224

CHAPTER 8-2 – DEFINITIONS

8-201 Definitions	225
-------------------------	-----

CHAPTER 8-3 – USE AND OCCUPANCY

8-301 Purpose and Scope	228
8-302 General	228
8-303 Residential Occupancies	229

CHAPTER 8-4 – FIRE PROTECTION

8-401 Purpose, Intent and Scope	230
8-402 Fire-resistive Construction	230
8-403 Interior Finish Materials	230
8-404 Wood Lath and Plaster	231
8-405 Occupancy Separation	231
8-406 Maximum Floor Area	231
8-407 Vertical Shafts	231
8-408 Roof Covering	231
8-409 Fire Alarm Systems	231
8-410 Automatic Sprinkler Systems	232
8-411 Other Technologies	232
8-412 High-rise Buildings	232

CHAPTER 8-5 – MEANS OF EGRESS

8-501 Purpose, Intent and Scope	233
8-502 General	233
8-503 Escape or Rescue Windows and Doors	234
8-504 Railings and Guardrails	234

CHAPTER 8-6 – ACCESSIBILITY

8-601 Purpose, Intent and Scope	235
8-602 Basic Provisions	235
8-603 Alternatives	235
8-604 Equivalent Facilitation	236

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION

PAGE NUMBERS

CHAPTER 8-7 – STRUCTURAL REGULATIONS

8-701 Purpose, Intent and Scope	238
8-702 General	238
8-703 Structural Survey	238
8-704 Nonhistorical Additions and Nonhistorical Alterations	238
8-705 Structural Regulations	239
8-706 Lateral Load Regulations	239

CHAPTER 8-8 – ARCHAIC MATERIALS AND METHODS OF CONSTRUCTION

8-801 Purpose, Intent and Scope	241
8-802 General Engineering Approaches	241
8-803 Nonstructural Archaic Materials	241
8-804 Allowable Conditions for Specific Materials	241
8-805 Masonry	242
8-806 Adobe	242
8-807 Wood	243
8-808 Concrete	243
8-809 Steel and Iron	244
8-810 Hollow Clay Tile	244
8-811 Veneers	244
8-812 Glass and Glazing	244

CHAPTER 8-9 – MECHANICAL, PLUMBING AND ELECTRICAL REQUIREMENTS

8-901 Purpose, Intent and Scope	248
8-902 Mechanical	248
8-903 Plumbing	249
8-904 Electrical	251

CHAPTER 8-10 – QUALIFIED HISTORICAL DISTRICTS, SITES AND OPEN SPACES

8-1001 Purpose and Scope	253
8-1002 Application	253
8-1003 Site Relationships	253

APPENDIX A

Chapter 8-1	254
Chapter 8-6	254

PART 8 – HISTORY NOTE APPENDIX

257

PART 12 – 2010 CALIFORNIA REFERENCED STANDARDS CODE

Effective Date: January 1, 2011

CHAPTERS 12–11A AND 12–11B – BUILDING AND FACILITY ACCESS SPECIFICATIONS

12-11A.201 and 12-11B.201 Detectable Warnings	258
---	-----

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION	PAGE NUMBERS
PRODUCT APPROVAL FOR DETECTABLE WARNING PRODUCTS AND DIRECTIONAL SURFACES	
12-11A.202 and 12-11B.202 Scope.....	258
12-11A.203 and 12-11B.203 Detectable Warning Products.....	258
12-11A.204 and 12-11B.204 Directional Surfaces	258
12-11A.205 and 12-11B.205 Independent Entity.....	258
12-11A.206 and 12-11B.206 Two-year Approval.....	258
12-11A.207 and 12-11B.207 Fee.....	259
12-11A.208 and 12-11B.208 Disability Access Account.....	259
12-11A.209 and 12-11B.209 Detectable Warning Products and Directional Surfaces	259
12-11A.210 and 12-11B.210 Significant Degradation.....	259
12-11A.211 and 12-11B.211 Selection of Independent Entity	259
<u>PART 12 – HISTORY NOTE APPENDIX</u>	260

2010 CALIFORNIA ADMINISTRATIVE CODE

California Code of Regulations - Title 24, Part 1

Effective Date: January 1, 2011

CHAPTER 5

ACCESS TO PUBLIC BUILDINGS BY PERSONS WITH DISABILITIES

ARTICLE 1

COMPLIANCE PROCEDURES

5-101. Purpose. These regulations implement Sections 4450 et seq. of the Government Code to ensure that where state funds are utilized for the construction or alteration of any public building or facility or where the funds of counties, municipalities, or other political subdivisions are utilized for the construction or alteration of elementary, secondary or community college buildings and facilities that the plans and specifications for such buildings and facilities are reviewed by the Division of the State Architect (DSA) and certified to be in compliance with California law requiring access for persons with disabilities prior to a contract being awarded.

Authority: Government Code Sections 4450, 4453 and 4454.

Reference: Government Code Section 4454.

HISTORY:

1. New Group 2 (§§ 81 through 86) filed 3-5-71 as an emergency; effective on filing. Certificate of Compliance included (Register 71, No. 10). For history of former Group 2 see Register 66, No. 38.
2. Amendment filed 11-24-78; designated effective 1-1-79 (Register 78, No. 47).

5-102. General. For the purpose of assuring compliance with minimum requirements for accessibility by persons with disabilities, the governmental agency controlling the appropriation from which the project is funded shall submit an application, together with plans and full, complete and accurate specifications and filing fee, to the State Architect. The DSA will process the documents. Written approval shall be obtained prior to award of a construction contract.

Authority: Government Code Section 4453.

Reference: Government Code Section 4454.

HISTORY:

1. Amendment filed 11-24-78; designated effective 1-1-79 (Register 78, No. 47).

5-103. Application. For each project to be reviewed and certified, a separate application (Form DSA-1) shall be submitted to the DSA. The application shall be accompanied by a complete set of project plans and specifications and an appropriate filing fee (see Section 5-104). The above documents shall be submitted to one of the following regional offices:

DIVISION OF THE STATE ARCHITECT
OAKLAND REGIONAL OFFICE
1515 Clay Street, Suite 1201
Oakland, CA 94612

DIVISION OF THE STATE ARCHITECT
SAN DIEGO REGIONAL OFFICE
10920 Vía Frontera, Suite 300
San Diego, CA 92127

DIVISION OF THE STATE ARCHITECT
SACRAMENTO REGIONAL OFFICE
1102 Q Street, Suite 5200
Sacramento, CA 95811

DIVISION OF THE STATE ARCHITECT
LOS ANGELES REGIONAL OFFICE
700 N. Alameda St., Suite 5-500
Los Angeles, CA 90012

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

The application shall be considered received when all the required documents and fees have been received by the office and the application number assigned.

The documents submitted for review and used for certification shall be retained by the DSA.

Authority: Government Code Section 4454.

Reference: Government Code Section 4454.

HISTORY:

1. Amendment filed 11-24-78; designated effective 1-1-79 (Register 78, No. 47). For prior history, see Register 76, No. 25.
2. Renumbering and amendment of former Section 83 to Section 83.1 filed 8-30-84; effective upon filing pursuant to Government Code Section 11346.2(d) (Register 84, No. 35).
3. Erratum to reflect locations of offices.

5-104. Fees.

(a) The filing fee for projects under applications received on or after July 1, 2009 shall be four tenths of one percent (0.4%) of the first \$500,000.00 of the estimated project cost plus two tenths of one percent (0.2%) of the project cost greater than \$500,000.00 up to and including \$2,000,000.00 plus two one-hundredths of one percent (0.02%) of the excess of the estimated project cost over \$2,000,000.00, except that the minimum fee in any case shall be \$400.00.

Example of filing fee to accompany application:

Estimated project cost = \$250,000.00		
.004 × \$250,000.00	=	\$1,000.00
Estimated project cost = \$1,500,000.00		
.004 × \$ 500,000.00	=	\$2,000.00
.002 × \$1,000,000.00	=	<u>2,000.00</u>
		\$4,000.00
Estimated project cost = \$5,000,000.00		
.004 × \$ 500,000.00	=	\$2,000.00
.002 × \$1,500,000.00	=	3,000.00
.0002 × \$3,000,000.00	=	<u>600.00</u>
		\$5,600.00

(b) The fee schedule in effect at the time of filing shall apply throughout the duration of such application.

(c) When the actual project cost exceeds the estimated cost a further fee for such projects shall become due and shall be equal to the difference between the filing fee paid and the amount computed under the schedule above using the actual cost of the project. The actual project cost shall be determined as directed in Section 5-105 and billed according to Section 5-107.

(d) If the applicant requests the cancellation or withdrawal of the application and return of the plans and specifications and filing fee, this shall be granted unless the review has begun. No portion of the filing fee can be returned after the review has started.

(e) Beginning in July 2009, with a review in 2011 and within every four years thereafter, the State Architect shall review the fee schedule and make a written determination whether the fees are sufficient to fund the programs.

- (i) If the State Architect determines that a lesser amount is sufficient to maintain the programs, the fees may be reduced for a period up to four years.
- (ii) If the State Architect determines that a greater amount is necessary to maintain the programs utilizing these funds, the State Architect shall propose a fee schedule increase.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Authority: Government Code Section 4453.

Reference: Government Code Section 4454.

HISTORY:

1. New section filed 8-30-84; effective upon filing pursuant to Government Code Section 11346.2(d) (Register 84, No. 35).
2. (OSA/AC-A 1/89) Editorial transfer from CCR, Title 21 to Title 24 11-1-89.
3. (OSA/AC-A 2/89) Amend CCR, Title 24, Part 1, Sec. 5-104 (a) (b), effective 1-1-90. Approved by Building Standards Commission 10-30-89.
4. (OSA/AC EF 1/92) Emergency order by the Office of the State Architect/Access Compliance to amend Section 5-104 (a), Part 1, Title 24, California Code of Regulations. Filed as an emergency order with the secretary of state February 25, 1992; effective March 1, 1992. Approved as an emergency by the California Building Standards Commission on February 24, 1992.
5. (OSA/AC EF 1/92) Emergency order by the Office of the State Architect/Access Compliance to amend Section 5-104 (a), Part I, Title 24, California Code of Regulations; approved by the California Building Standards Commission on February 24, 1992; filed as an emergency order with the secretary of state February 25, 1992, and effective March 1, 1992, has lapsed. No action was taken by the OSA/AC to make these regulations permanent; therefore, the initial regulations are back in effect as of June 29, 1992.

5-105. Project cost. For purposes of determining the fees, both the estimated and actual project cost shall be the cost for the total outlay contemplated for all work included in the certified plans and specifications. The term “project” shall be defined as all buildings and other structures, together with the development of the site, but in the event the plans and specifications submitted with the application do not provide for the construction of, addition or alteration to a building or structure, then it shall be for the site development proposed in the application.

The actual project cost shall include all items, which are normally considered to be contractors’ operation costs. Addenda or change order items which increase the contract amount shall be included in the final actual project cost computation.

All fees and/or reimbursable charges paid the construction managers shall be included in the actual project cost. When the contract for the work includes items not otherwise subject to the approval of the office and not included in the approved plans and specifications the actual cost shall include this work unless such costs are segregated by separate bid items or by separately priced items of change orders, or by a certified copy of the subcontractor’s bid. Such segregation shall not be made by contract price breakdown or estimates.

Authority: Government Code Section 4454.

Reference: Government Code Section 4454.

HISTORY:

1. New section filed 8-30-84; effective upon filing pursuant to Government Code Section 11346.2 (d) (Register 84, No. 35).

5-106. Revision of plans and specifications. No additional fee is charged upon submission of revisions to the approved plans and specifications, provided that the entire matter is actually one transaction having to do with the same project and the revisions do not require substantial review for accessibility. If the original plans are abandoned and the plans and specifications submitted in lieu thereof are in fact for a new project rather than an identical project, or where a modified set of plans is for an essentially different concept, it is necessary that a new application be filed and a fee paid. This is regardless of the fact that the project may have the same name, be of the same general size, and be situated at the same location as the project for which the original application was made.

Authority: Government Code Section 4454.

Reference: Government Code Section 4454.

HISTORY:

1. New section filed 8-30-84; effective upon filing pursuant to Government Code Section 11346.2(d) (Register 84, No. 35).

5-107. Billing for further fees. For public school projects the DSA shall determine whether or not further fees are due and shall bill the district for such further fees.

For projects other than public schools, the applicant or owner shall submit to the office a report verifying the actual project cost within 90 days after the completion of the project. This actual project cost shall be the basis for the further fee computation. The accuracy and timely submission of this actual project cost report shall be the responsibility of the owner or his designated agent. The owner shall be billed for further fees upon completion of the project or portion thereof if fee is due.

Authority: Government Code Section 4454.

Reference: Government Code Section 4454.

HISTORY:

1. New section filed 8-30-84; effective upon filing pursuant to Government Code Section 11346.2 (d) (Register 84, No. 35).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

5-108. Refunds. Claims for refunds of five dollars or less due to errors in cost reporting or fee computation shall be made within one year from the date of payment.

Authority: Government Code Section 4454.

Reference: Government Code Section 4454.

HISTORY:

1. New section filed 8-30-84; effective upon filing pursuant to Government Code Section 11346.2(d) (Register 84, No. 35).

5-109. Review of plans and specifications. The DSA will review the submitted documents to ensure that the requirements cited in Article 1 are fully met.

Authority: Government Code Section 4453.

Reference: Government Code Section 4454.

HISTORY:

1. Amendment filed 11-24-78; designated effective 1-1-79 (Register 78, No. 47).

5-110. Written approval.

(a) Approval obtained. Upon completion of review, DSA will return to the awarding authority a written approval, if the documents comply with the requirements. This approval of the application constitutes the “written approval” required by Section 4454 of the Government Code. No changes or revisions shall be made following written approval, which affect access compliance items unless such changes or revisions are submitted to the DSA for approval.

(b) Approval denied. If the documents fail to meet the requirements of these regulations, DSA will return to the awarding authority the plans with corrections noted thereon together with instructions for resubmittal of the plans and specifications. The corrected plans are the property of the Division of the State Architect and shall be returned within six months or the application will be void. No valid construction contract may be awarded before written approval is obtained.

(c) Unauthorized deviations. In the event that there is an unauthorized deviation from the requirements of these regulations with respect to the standards specified, the same shall be rectified by full compliance there with within ninety (90) days after discovery of such deviation.

(d) Notification. Where the State Architect is the enforcement authority and any project is proposed to be approved and such approval action would deny accessibility either required by Sections 4450 and 4458, inclusive, of the Government Code to persons with disabilities, or by reason of an equivalent facilitation exception granted pursuant to Section 4451 of the Government Code, the State Architect shall notify affected persons with disabilities or organizations and others who have made written requests to be informed as to such proposals under consideration.

Authority: Government Code Sections 4450 and 4460 and Health and Safety Code Section 18949.

Reference: Government Code Sections 4460.

HISTORY:

1. Amendment filed 11-24-78; designated effective 1-1-79 (Register 78, No. 47).
2. New subsection (d) filed 3-6-81 as an emergency; effective upon filing (Register 81, No. 10). A Certificate of Compliance must be transmitted to OAL within 120 days or emergency language will be repealed on 7-4-81.
3. Order of Repeal of 3-6-81 emergency order filed 3-13-81 by OAL pursuant to Government Code Section 11349.6 (Register 81, No. 11).
4. New subsection (d) filed 7-28-82; effective thirtieth day (Register 82, No. 31).
5. Amendment of subsection (a) filed 7-17-85; effective thirtieth day thereafter (Register 85, No. 29).

5-111. General requirements. General requirements and building standards are located in Title 24, Part 2.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

ARTICLE 2 DIVISION OF THE STATE ARCHITECT – ACCESS COMPLIANCE PROCESSING PRODUCT APPROVALS JANUARY 1, 2001

Detectable warning products and directional surfaces installed after January 1, 2001 shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect, Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing, evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

5-201. Processing independent entity evaluation approvals (IEEA). Independent Entity Evaluation Approvals shall be registered in the Division of the State Architect (DSA) headquarters office.

To maintain a central file for all IEEA and to operate within the current DSA program, certain administration and all accounting shall be performed at the DSA headquarters office under the direction of the Principal Architect.

5-202. IEEA Application procedure.

1. Upon receipt of an IEEA application, send the application fee and a copy of the application to the DSA headquarters office, attention: Access Compliance.
2. A paper file will be created for each IEEA, which will initially include a copy of the application and the application fee. Headquarters personnel will then file the product, manufacturer and registration information, creating an IEEA number.
3. The application fee will be given to the headquarters cashier for deposit.

5-203. IEEA Acceptance procedure.

1. Prior to issuing IEEA acceptance, it is required that all fees be paid. If fees are due, please contact the manufacturer for payment and forward the payment to the DSA headquarters office, along with the request for the additional payment.
2. The fee, if any, will be given to the headquarters, cashier for filing and deposit.
3. The acceptance letter will be retained at DSA head quarters, Access Compliance. A copy of the status approval letter will be returned to the applicant.
4. Headquarters' personnel will register, prepare and distribute all necessary copies of the acceptance letter. The original file shall be maintained at headquarters.

5-204. Accounting of IEEA. Income for IEEA will be earned in the month in which they are banked. This money will be applied to Disability Access Account for deposit.

5-205. Contacts for questions.

1. IEEA Contact, DSA headquarters, attention: Access Compliance, IEEA Program.
2. Headquarters Administration Contact — DSA headquarters, attention: Access Compliance, IEEA Program.
3. Headquarters Accounting Contact, DSA headquarters, Accounting.

Authority: Government Code Sections 4450, 4460 and Health & Safety Code Section 18949.1.

Reference: Government Code Section 4460.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

ARTICLE 3 ACCEPTANCE OF DETECTABLE WARNING AND DIRECTIONAL SURFACE PRODUCTS FOR MANUFACTURERS AND DESIGN PROFESSIONALS JANUARY 1, 2001

Detectable warning products and directional surfaces installed after January 1, 2001 shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect, Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing, evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

5-301. Division of the State Architect, Access Compliance, acceptance of product. The procedure for the DSA-AC acceptance of manufactured products is detailed in this article.

All products require prior evaluation by a recognized evaluation agency that has a program specifically intended for such purposes. DSA-AC shall review the evaluation report for compliance with related and appropriate national standards and Title 24 requirements.

5-301.1. Product submittal. Products must meet the requirements of Section 5-301.

5-301.2. Division of the State Architect, Access Compliance, products exempt from evaluation by a recognized agency. No products can be approved for use that do not require evaluation by a recognized evaluation agency.

5-301.3. Products evaluated by recognized state and city agencies. No products can be approved by any state and city agencies for use that do not require evaluation by a recognized evaluation agency.

5-301.4. Products evaluated by a recognized evaluation agency. Products must have, as a minimum, an approved report published by a nationally recognized evaluation agency. Without an evaluation report, the applicant will be required to obtain such a report or will be denied acceptance on DSA-AC projects. The report and its evaluation criteria may be reviewed for compliance with national standards.

5-301.5. Development of DSA acceptance criteria. Development of new DSA-AC acceptance criteria shall be based on acceptance criteria from a recognized evaluation agency.

5-301.6. Marking. Each detectable warning and directional surface products shall be provided with:

1. Label indicating the DSA label number,
2. Manufacturer's product number, and
3. Product approval expiration date.

Authority: Government Code Sections 4450 and 4460 and Health & Safety Code Section 18949.1.

Reference: Government Code Section 4460.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**ARTICLE 4
APPLICATION FOR INDEPENDENT ENTITY EVALUATION APPROVAL (IEEA)**

5-401. Application for IEEA. The following form must be filed in duplicate:

**APPLICATION FOR IEEA FORM
(Filed in Duplicate)**

1. Product Name: _____

2. Description of Product: _____ Expiration Date: _____

3. Intended Product Use: _____

4. Company Name: _____

5. Company Address: _____

6. Contact Person: _____

Title: _____

Contact Person's Phone Number: _____

Contact Person's Fax Number: _____

7. Name of Applicant: _____

8. Signature of Applicant: _____ Date: _____

9. Application Fee Submitted: _____

Please make checks payable to Division of the State Architect, Access Compliance

New Submittal:	\$1,500.00
Revised Submittal:	\$ 500.00

Fees shown are for initial application. Additional time expended during product review in excess of the initial fee will be billed on an hourly basis.

10. Return application, check and submittal to:

Division of the State Architect – Access Compliance
1102 Q Street, Suite 5100
Sacramento, CA 95811

HISTORY NOTE APPENDIX FOR CHAPTER 5

Administrative Regulations for the Division of the State Architect, Access Compliance (Title 24, Part 1, California Code of Regulations)

The format of the history notes has been changed to be consistent with the other parts of the *California Building Standards Code*. The history notes for prior changes remain within the text of this code.

1. **(DSA-AC 2/01)** Adoption of detectable warning products and standards, Chapter 5, Articles 2, 3 and 4. Approved by the California Building Standards Commission on November 28, 2001. Filed with the Secretary of State on March 1, 2002, effective April 2, 2002.
2. **(DSA-AC 05/04)** Changes without regulatory effect to addresses in Section 5-103 and an acronym in Section 5-202. Filed with Secretary of State on June 28, 2006 and effective 30th day after filing with Secretary of State.
3. **(DSA-AC 03/06)** Repeal of duplicate provisions and editorial and formatting amendments to administrative standards for implementing facility access in conformance with California Law and federally recognized accessibility standards. Effective January 1, 2008.
4. **(DSA-AC 04/09)** Revisions to Section 5-104, Fees, by State and Consumer Services Agency on behalf of the Division of State Architect-Access Compliance. Effective February 13, 2010.

2010 CALIFORNIA BUILDING CODE
California Code of Regulations - Title 24, Part 2
Based on the 2009 International Building Code
 Effective Date: January 1, 2011

CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 1 – SCOPE AND ADMINISTRATION

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1-AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
1.1						X														
1.9.1						X														
111.2						X														

DIVISION 1
CALIFORNIA ADMINISTRATION

SECTION 1.1
GENERAL

1.1.1. Title. *These regulations shall be known as the California Building Code, may be cited as such and will be referred to herein as “this code.” The California Building Code is Part 2 of twelve parts of the official compilation and publication of the adoption amendment and repeal of building regulations to the California Code of Regulations, Title 24, also referred to as the California Building Standards Code. This part incorporates by adoption the 2009 International Building Code of the International Code Council with necessary California amendments.*

1.1.2. Purpose. *The purpose of this code is to establish the minimum requirements to safeguard the public health, safety and general welfare through structural strength, means of egress facilities, stability, access to persons with disabilities, sanitation, adequate lighting and ventilation, and energy conservation; safety to life and property from fire and other hazards attributed to the built environment; and to provide safety to fire fighters and emergency responders during emergency operations.*

1.1.3. Scope. *The provisions of this code shall apply to the construction, alteration, movement, enlargement, replacement, repair, equipment, use and occupancy, location, maintenance, removal and demolition of every building or structure or any appurtenances connected or attached to such buildings or structures throughout the State of California.*

1.1.3.1. Nonstate-regulated buildings, structures, and applications. *Except as modified by local ordinance pursuant to Section 1.1.8, the following standards in the California Code of Regulations, Title 24, Parts 2, 2.5, 3, 4, 5, 6, 9, 10 and 11 shall apply to all occupancies and applications not regulated by a state agency.*

1.1.3.2. State-regulated buildings, structures, and applications. *The model code, state amendments to the model code, and/or state amendments where there are no relevant model code provisions, shall apply to the following buildings, structures, and applications regulated by state agencies as referenced in the Matrix Adoption Tables and as specified in Sections 1.2 through 1.14, except where modified by local ordinance*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

pursuant to Section 1.1.8. When adopted by a state agency, the provisions of this code shall be enforced by the appropriate enforcing agency, but only to the extent of authority granted to such agency by the state legislature.

Note: See Preface to distinguish the model code provisions from the California provisions.

1. *State-owned buildings, including buildings constructed by the Trustees of the California State University, and to the extent permitted by California laws, buildings designed and constructed, by the Regents of the University of California, and regulated by the Building Standards Commission. See Section 1.2 for additional scope provisions.*
2. *Local detention facilities regulated by the Corrections Standards Authority. See Section 1.3 for additional scope provisions.*
3. *Barbering, cosmetology or electrolysis establishments, acupuncture offices, pharmacies, veterinary facilities and structural pest control locations regulated by the Department of Consumer Affairs. See Section 1.4 for additional scope provisions.*
4. *Energy efficiency standards regulated by the California Energy Commission. See Section 1.5 for additional scope provisions.*
5. *Dairies and places of meat inspection regulated by the Department of Food and Agriculture. See Section 1.6 for additional scope provisions.*
6. *Organized camps, laboratory animal quarters, public swimming pools, radiation protection, commissaries serving mobile food preparation vehicles, and wild animal quarantine facilities regulated by the Department of Public Health. See Section 1.7 for additional scope provisions.*
7. *Hotels, motels, lodging houses, apartment houses, dwellings, dormitories, condominiums, shelters for homeless persons, congregate residences, employee housing, factory-built housing, and other types of dwellings containing sleeping accommodations with or without common toilets or cooking facilities. See Section 1.8.2.1.1 for additional scope provisions.*
8. *Accommodations for persons with disabilities in buildings containing newly constructed covered multifamily dwellings, new common use spaces serving existing covered multifamily dwellings, additions to existing buildings where the addition alone meets the definition of "COVERED MULTIFAMILY DWELLINGS" and common-use spaces serving covered multifamily dwellings which are regulated by Department of Housing and Community Development. See Section 1.8.2.1.2 for additional scope provisions.*
9. *Permanent buildings and permanent accessory buildings or structures constructed within mobile home parks and special occupancy parks regulated by the Department of Housing and Community Development. See Section 1.8.2.1.3 for additional scope provisions.*
10. *Accommodations for persons with disabilities regulated by the Division of the State Architect. See Section 1.9.1 for additional scope provisions.*
11. *Public elementary and secondary schools, community college buildings, and state-owned or state-leased essential service buildings regulated by the Division of the State Architect. See Section 1.9.2 for additional scope provisions.*
12. *Qualified historical buildings and structures and their associated sites regulated by the State Historical Building Safety Board with the Division of the State Architect. See Section 1.9.3 for additional scope provisions.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

- 13.** *General acute care hospitals, acute psychiatric hospitals, skilled nursing and/or intermediate care facilities, clinics licensed by the Department of Public Health and correctional treatment centers regulated by the Office of Statewide Health Planning and Development. See Section 1.10 for additional scope provisions.*
- 14.** *Applications regulated by the Office of State Fire Marshal include but are not limited to the following in accordance with Section 1.11.*

 - 14.1** *Buildings or structures used or intended for use as an:*

 - 1.** *Asylum, jail*
 - 2.** *Mental hospital, hospital, home for the elderly, children’s nursery, children’s home or institution, school or any similar occupancy of any capacity*
 - 3.** *Theater, dancehall, skating rink, auditorium, assembly hall, meeting hall, nightclub, fair building, or similar place of assemblage where 50 or more persons may gather together in a building, room or structure for the purpose of amusement, entertainment, instruction, deliberation, worship, drinking or dining, awaiting transportation, or education*
 - 4.** *Small family day care homes, large family day-care homes, residential facilities and residential facilities for the elderly, residential care facilities*
 - 5.** *State institutions or other state-owned or state-occupied buildings*
 - 6.** *High rise structures*
 - 7.** *Motion picture production studios*
 - 8.** *Organized camps*
 - 9.** *Residential structures*
 - 14.2** *Tents, awnings or other fabric enclosures used in connection with any occupancy*
 - 14.3** *Fire alarm devices, equipment and systems in connection with any occupancy*
 - 14.4** *Hazardous materials, flammable and combustible liquids*
 - 14.5** *Public school automatic fire detection, alarm and sprinkler systems*
 - 14.6** *Wildland-urban interface fire areas*
- 15.** *Public libraries constructed and renovated using funds from the California Library Construction and Renovation Bond Act of 1988 and regulated by the State Librarian. See Section 1.12 for additional scope provisions.*
- 16.** *Graywater systems regulated by the Department of Water Resources. See Section 1.13 for additional scope provisions.*
- 17.** *For applications listed in Section 1.9.1 regulated by the Division of the State Architect – Access Compliance, outdoor environments and uses shall be classified according to accessibility uses described in Chapter 11A, 11B and 11C.*
- 18.** *Marine Oil Terminals regulated by the California State Lands Commission. See Section 1.14 for additional scope provisions.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1.1.4. Appendices. Provisions contained in the appendices of this code shall not apply unless specifically adopted by a state agency or adopted by a local enforcing agency in compliance with Health and Safety Code Section 18901 et. seq. for Building Standards Law, Health and Safety Code Section 17950 for State Housing Law and Health and Safety Code Section 13869.7 for Fire Protection Districts. See Section 1.1.8 of this code.

1.1.5. Referenced codes. The codes, standards and publications adopted and set forth in this code, including other codes, standards and publications referred to therein are, by title and date of publication, hereby adopted as standard reference documents of this code. When this code does not specifically cover any subject related to building design and construction, recognized architectural or engineering practices shall be employed. The National Fire Codes, standards, and the Fire Protection Handbook of the National Fire Protection Association are permitted to be used as authoritative guides in determining recognized fire prevention engineering practices.

1.1.6. Nonbuilding standards, orders and regulations. Requirements contained in the International Building Code, or in any other referenced standard, code or document, which are not building standards as defined in Health and Safety Code Section 18909, shall not be construed as part of the provisions of this code. For nonbuilding standards, orders, and regulations, see other titles of the California Code of Regulations.

1.1.7. Order of precedence and use.

1.1.7.1. Differences. In the event of any differences between these building standards and the standard reference documents, the text of these building standards shall govern.

1.1.7.2. Specific provisions. Where a specific provision varies from a general provision, the specific provision shall apply.

1.1.7.3. Conflicts. When the requirements of this code conflict with the requirements of any other part of the California Building Standards Code, Title 24, the most restrictive requirements shall prevail.

1.1.8. City, county, or city and county amendments, additions or deletions. The provisions of this code do not limit the authority of city, county, or city and county governments to establish more restrictive and reasonably necessary differences to the provisions contained in this code pursuant to complying with Section 1.1.8.1. The effective date of amendments, additions, or deletions to this code by a city, county, or a city and county filed pursuant to Section 1.1.8.1 shall be the date filed. However, in no case shall the amendments, additions or deletions to this code be effective any sooner than the effective date of this code.

Local modifications shall comply with Health and Safety Code Section 18941.5 for Building Standards Law, Health and Safety Code Section 17958 for State Housing Law or Health and Safety Code Section 13869.7 for Fire Protection Districts.

1.1.8.1. Findings and filings.

1. The city, county, or city and county shall make express findings for each amendment, addition or deletion based upon climatic, topographical, or geological conditions.

Exception: Hazardous building ordinances and programs mitigating unreinforced masonry buildings.

2. The city, county, or city and county shall file the amendments, additions, or deletions expressly marked and identified as to the applicable findings. Cities, counties, cities and counties, and fire departments shall file the amendments, additions or deletions, and the findings with the California Building Standards Commission at 2525 Natomas Park Drive, Suite 130, Sacramento, CA 95833.
3. Findings prepared by fire protection districts shall be ratified by the local city, county, or city and county and filed with the California Department of Housing and Community Development, Division of Codes and Standards, P.O. Box 1407, Sacramento, CA 95812-1407 or 1800 3rd Street, Room 260, Sacramento, CA 95811.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1.1.9. Effective date of this code. Only those standards approved by the California Building Standards Commission that are effective at the time an application for building permit is submitted shall apply to the plans and specifications for, and to the construction performed under, that permit. For the effective dates of the provisions contained in this code, see the History Note page of this code.

1.1.10. Availability of codes. At least one complete copy each of Titles 8, 19, 20, 24, and 25 with all revisions shall be maintained in the office of the building official responsible for the administration and enforcement of this code. Each state department concerned and each city, county or city and county shall have an up-to-date copy of the code available for public inspection, See Health and Safety Code Section 18942 (d)(1) and (2).

1.1.11. Format. This part fundamentally adopts the International Building Code by reference on a chapter-by-chapter basis. Such adoption is reflected in the Matrix Adoption Table of each chapter of this part. When the Matrix Adoption Tables make no reference to a specific chapter of the International Building Code such chapter of the International Building Code is not adopted as a portion of this code.

1.1.12. Validity. If any chapter, section, subsection, sentence, clause or phrase of this code is for any reason held to be unconstitutional, contrary to statute, exceeding the authority of the state as stipulated by statutes or otherwise inoperative, such decision shall not affect the validity of the remaining portion of this code.

SECTION 1.9 DIVISION OF THE STATE ARCHITECT

1.9.1. Division of the State Architect – Access Compliance.

General. The purpose of this code is to ensure that barrier-free design is incorporated in all buildings, facilities, site work and other improvements to which this code applies in compliance with state law to ensure that these improvements are accessible to and usable by persons with disabilities. Additions, alterations and structural repairs in all buildings and facilities shall comply with these provisions for new buildings, except as otherwise provided and specified herein.

The provisions of these regulations shall apply to any portable buildings leased or owned by a school district, and shall also apply to temporary and emergency buildings and facilities. Temporary buildings and facilities are not of permanent construction but are extensively used or are essential for public use for a period of time. Examples of temporary buildings or facilities covered include, but are not limited to: reviewing stands, temporary classrooms, bleacher areas, exhibit areas, temporary banking facilities, temporary health screening services, or temporary safe pedestrian passageways around a construction site.

In addition, to incorporate standards at least as restrictive as those required by the federal government for barrier-free design under (1) Title III (Public Accommodations and Commercial Facilities), Subpart D (New Construction and Alteration) and Appendix A (Americans with Disabilities Act Standards for Accessible Design) (see 28 C.F.R., Part 36), and (2) Title II (Public Entities), Section 35.151 (New Construction and Alterations) (see 28 C.F.R., Part 35) both from the Americans with Disabilities Act of 1990, and (3) under the Fair Housing Amendments Act of 1988. Some of these regulations may be more stringent than state law in order to meet the federal requirement.

1.9.1.1. Application. See Government Code commencing with Section 4450.

Publicly funded buildings, structures, sidewalks, curbs and related facilities shall be accessible to and usable by persons with disabilities as follows:

1.9.1.1.1. All buildings, structures, sidewalks, curbs and related facilities constructed in the state by the use of state, county or municipal funds, or the funds of any political subdivision of the state.

1.9.1.1.2. All buildings, structures and facilities that are leased, rented, contracted, sublet or hired by any municipal, county, or state division of government, or by a special district.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1.9.1.1.3. *All publicly funded buildings used for congregate residences or for one- or two-family dwelling unit purposes shall conform to the provisions applicable to living accommodations.*

1.9.1.1.4. *All existing publicly funded buildings and facilities when alterations, structural repairs or additions are made to such buildings or facilities. For detailed requirements on existing buildings, see Chapter 11B, Division IV.*

1.9.1.1.5. *With respect to buildings, structures, sidewalks, curbs and related facilities not requiring a building permit, building standards published in the California Building Standards Code relating to access for persons with disabilities and other regulations adopted pursuant to Government Code Section 4450, and in effect at the time construction is commenced, shall be applicable.*

1.9.1.2. Application. *See Health and Safety Code commencing with Section 19952.*

All privately funded public accommodations, as defined and commercial facilities, as defined, shall be accessible to persons with disabilities as follow:

Exception: *Certain types of privately funded multistory buildings do not require installation of an elevator to provide access above and below the first floor. See Chapter 11B.*

1.9.1.2.1. *Any building, structure, facility, complex or improved area, or portions thereof, which are used by the general public.*

1.9.1.2.2. *Any sanitary facilities which are made available for the public, clients or employees in such accommodations or facilities.*

1.9.1.2.3. *Any curb or sidewalk intended for public use that is constructed in this state with private funds.*

1.9.1.2.4. *All existing privately funded public accommodations when alterations, structural repairs or additions are made to such public accommodations as set forth under Chapter 11B.*

1.9.1.3. Application – *public housing and private housing available for public use. See Government Code Sections 4450 and 12955.1(d).*

1.9.1.4. Enforcing agency.

1.9.1.4.1. *The director of the Department of General Services where state funds are utilized for any project or where funds of counties, municipalities or other political subdivisions are utilized for the construction of elementary, secondary or community college projects.*

1.9.1.4.2. *The governing bodies where funds of counties, municipalities or other political subdivisions are utilized except as otherwise provided above.*

1.9.1.4.3. *The building department of every city, county, or city and county within the territorial area of its city, county, or city and county, where private funds are utilized. "Building department" means the department, bureau or officer charged with the enforcement of laws or ordinances regulating the erection or construction, or both the erection and construction, of buildings.*

1.9.1.5. Special conditions for persons with disabilities requiring appeals action ratification. *Whenever reference is made in these regulations to this section, the findings and determinations required to be rendered by the local enforcing agency shall be subject to ratification through an appeals process.*

1.9.1.6. Authority cited. *Government Code Section 4450.*

1.9.1.7. Reference cited. *Government Code Sections 4450 through 4461, 12955.1(d) and Health and Safety Code Sections 18949.1, 19952 through 19959.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

DIVISION II **SCOPE AND ADMINISTRATION**

Sections adopted or amended by state agencies are specifically indicated by an agency banner or identified in the Matrix Adoption Table.

SECTION 111 **CERTIFICATE OF OCCUPANCY**

111.2 Certificate issued. After the building official inspects the building or structure and finds no violations of the provisions of this code or other laws that are enforced by the department of building safety, the building official shall issue a certificate of occupancy that contains the following:

1. The building permit number.
2. The address of the structure.
3. The name and address of the owner.
4. A description of that portion of the structure for which the certificate is issued.
5. A statement that the described portion of the structure has been inspected for compliance with the requirements of this code for the occupancy and division of occupancy and the use for which the proposed occupancy is classified.
6. The name of the building official.
7. The edition of the code under which the permit was issued.
8. The use and occupancy, in accordance with the provisions of Chapter 3.
9. The type of construction as defined in Chapter 6.
10. The design occupant load.
11. If an automatic sprinkler system is provided, whether the sprinkler system is required.
12. Any special stipulations and conditions of the building permit.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 2 – DEFINITIONS**

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
Access Aisle						X														
Accessibility						X														
Accessible						X														
Accessible Element						X														
Accessible Means of Egress						X														
Accessible Route						X														
Accessible Route of Travel						X														
Accessible Space						X														
Adaptability						X														
Adaptable Dwelling Unit						X														
Addition						X														
Administrative Authority						X														
Aisle						X														
Aisle, Employee Areas						X														
Alteration (or Alter)						X														
Alternate Card Reader						X														
ANSI						X														
Approved (w/o notes)						X														
Approved Testing Agency						X														
Area of Refuge						X														
Assembly Area						X														
Assistive Device						X														
Automatic Door						X														
Bathroom						X														
Building (w/o exceptions and notes)						X														
Building Entrance on an Accessible Route						X														
Building, Existing						X														
Building Official						X														
CCR						X														
Circulation Path						X														
Clear						X														
Clear Floor Space						X														
Closed-Circuit Telephone						X														
Commercial Facilities						X														
Common Use Areas						X														
Comply With						X														
Covered Multifamily Dwellings						X														
Cross Slope						X														
Curb Cut						X														
Curb Ramp						X														
Detectable Warning						X														
Directional Sign						X														
Disability						X														
Disabled						X														
Dormitory						X														
Dwelling Unit						X														

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Adopting agency	BSC	SFM	H C D	D S A	OSH PD	CS A	DP H	AGR	D W R	C E C	C A	S L	SLC						
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4							
Adopt entire chapter																			
Adopt entire chapter as amended (amended sections listed below)																			
Adopt only those sections that are listed below						X													
Chapter/Section																			
Element						X													
Elevator, Passenger						X													
Enforcing Agency						X													
Entrance						X													
Equivalent Facilitation						X													
Existing Buildings						X													
Exit						X													
Facility (or Facilities)						X													
Free-Standing Pedestal						X													
Grab Bar						X													
Grade (Adjacent Ground Elevation)						X													
Ground Floor						X													
Guard (or Guardrail)						X													
Handrail						X													
Health Care Provider						X													
Historical Buildings						X													
If, If...Then						X													
Independent Entity						X													
International Symbol of Accessibility						X													
Kick Plate						X													
Level Accessible Area						X													
Level Area						X													
Lift, Platform (Wheelchair)						X													
Marked Crossing						X													
May						X													
Multistory Dwelling Unit						X													
Multiple-Accommodation Toilet Facility						X													
Newly Constructed						X													
NFPA						X													
Nosing (or Nose)						X													
Occupiable Space						X													
Open Riser						X													
Operable Part						X													
Passage Door						X													
Passenger Elevator						X													
Path of Travel						X													
Pedestrian						X													
Pedestrian Grade Separation						X													
Pedestrian Ramp						X													
Pedestrian Way						X													
Permanent						X													
Permit						X													
Persons with Disabilities						X													
Platform						X													
Platform (Wheelchair) Lift						X													
Powder Room						X													
Power-Assisted Door						X													
Professional Office of a Health Care Provider						X													
Public Accommodation						X													

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Adopting agency	BSC	SFM	H C D	D S A	OSH PD	CS A	DP H	AGR	D W R	C E C	C A	S L	SLC							
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
Public-Use Areas						X														
Public Way						X														
Qualified Historical Building (or Property)						X														
Ramp						X														
Reasonable Portion						X														
Recommended						X														
Remodeling						X														
Repair						X														
Riser						X														
Running Slope						X														
Sanitary Facility						X														
Service Entrance						X														
Shall						X														
Shopping Center or Shopping Mall						X														
Should						X														
Sidewalk						X														
Signage						X														
Single-Accommodation Sanitary Facility						X														
Site						X														
Site Development						X														
Sleeping Accommodations																				
Slope						X														
Space						X														
Specified Public Transportation						X														
Stage						X														
Stair						X														
Stairway						X														
Story						X														
Story, First						X														
Structural Frame						X														
Structure						X														
Tactile						X														
Technically Infeasible						X														
Temporary						X														
Text Telephone						X														
Transient Lodging						X														
Transit Boarding Platform						X														
Tread						X														
Type of Motor Fuel						X														
Unreasonable Hardship						X														
Vehicular or Pedestrian Arrival Points						X														
Vehicular Way						X														
Walk						X														
Wheelchair						X														
Wheelchair Occupant (or Wheelchair User)						X														
Work Station						X														

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 202 DEFINITIONS

ACCESS AISLE. [DSA-AC] See Chapter 11B, Section 1102B.

ACCESSIBILITY. [DSA-AC] See Chapter 11A, Section 1107A.1-A, and Chapter 11B, Section 1102B.

ACCESSIBLE. [DSA-AC] See Chapter 11A, Section 1107A.1-A, and Chapter 11B, Section 1102B.

ACCESSIBLE ELEMENT. [DSA-AC] See Chapter 11B, Section 1102B.

ACCESSIBLE MEANS OF EGRESS. See Section 1002.1.

ACCESSIBLE ROUTE. [DSA-AC] See Chapter 11A, Section 1107A.1-A.

ACCESSIBLE ROUTE OF TRAVEL. [DSA-AC] See Chapter 11B, Section 1102B.

ACCESSIBLE SPACE. [DSA-AC] See Chapter 11B, Section 1102B.

ADAPTABILITY. [DSA-AC] See Chapter 11B, Section 1102B.

ADAPTABLE DWELLING UNIT. [DSA-AC] See Chapter 11A, Section 1107A.1-A.

ADDITION. An extension or increase in floor area or height of a building or structure.

[DSA-AC] “Addition” is an extension, expansion, or increase in floor area or height of a building, facility or structure.

ADMINISTRATIVE AUTHORITY. [DSA-AC] See Chapter 11B, Section 1102B.

AISLE. See Section 1002.1.

[DSA-AC] See Chapter 11B, Section 1102B.

AISLE, EMPLOYEE AREAS. [DSA-AC] See Chapter 11B, Section 1102B.

ALTERATION or ALTER. Any construction or renovation to an existing structure other than repair or addition.

[DSA-AC] “Alteration or Alter” is any change, addition or modification in construction or occupancy or structural repair or change in primary function to an existing structure made by, on behalf of, or for the use of a public accommodation or commercial facility. Alterations include, but are not limited to, remodeling, renovation, rehabilitation, reconstruction, historic restoration, changes or rearrangement of the structural parts or elements, and changes or rearrangement in the plan configuration of walls and full-height partitions.

ALTERNATE CARD READER. [DSA-AC] See Chapter 11C, Section 1101C.1.

ANSI. [DSA-AC] means the American National Standards Institute.

APPROVED. Acceptable to the code official or authority having jurisdiction.

[DSA-AC] “Approved” means meeting the approval of the enforcing agency, except as otherwise provided by law, when used in connection with any system, material, type of construction, fixture or appliance as the result of investigations and tests conducted by the agency, or by reason of accepted principles or tests by national authorities or technical, health, or scientific organizations or agencies.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

APPROVED TESTING AGENCY. [DSA-AC] Any agency, which is determined by the enforcing agency, except as otherwise provided by law, to have adequate personnel and expertise to carry out the testing of systems, materials, type of construction, fixtures or appliances.

AREA OF REFUGE. See Section 1002.1.

ASSEMBLY AREA. [DSA-AC] See Chapter 11B, Section 1102B.

ASSISTIVE DEVICE. [DSA-AC] See Chapter 11A, Section 1107A.1-A.

AUTOMATIC DOOR. [DSA-AC] See Chapter 11A, Section 1107A.1-A, and Chapter 11B, Section 1102B.

BATHROOM. [DSA-AC] See Chapter 11A, Section 1107A.2-B.

BUILDING. Any structure used or intended for supporting or sheltering any use or occupancy.

BUILDING ENTRANCE ON AN ACCESSIBLE ROUTE. [DSA-AC] See Chapter 11A, Section 1107A.2-B.

BUILDING, EXISTING. [DSA-AC] A building erected prior to the adoption of this code, or one for which a legal building permit has been issued.

BUILDING OFFICIAL. The officer or other designated authority charged with the administration and enforcement of this code, or a duly authorized representative.

CCR [DSA-AC] means the California Code of Regulations.

CIRCULATION PATH. [DSA-AC] See Chapter 11B, Section 1102B.

CLEAR. [DSA-AC] See Chapter 11B, Section 1102B.

CLEAR FLOOR SPACE. [DSA-AC] See Chapter 11B, Section 1102B.

CLOSED-CIRCUIT TELEPHONE. [DSA-AC] See Chapter 11B, Section 1102B.

COMMERCIAL FACILITIES [DSA-AC] are facilities that are intended for nonresidential use and whose operations will affect commerce, including factories, warehouses, office buildings, and other buildings in which employment may occur. Commercial facilities shall not include railroad locomotives, railroad freight cars, railroad cabooses, railroad cars covered under Title II of the Americans with Disabilities Act of 1990, or facilities that are covered or expressly exempted from coverage under the Fair Housing Amendment Act of 1988 (42 USC 3601-3631, et seq.).

COMMON USE AREAS. [DSA-AC] See Chapter 11A, Section 1107A.3-C, and Chapter 11B, Section 1102B.

COMPLY WITH. [DSA-AC] See Chapter 11B, Section 1102B.

COVERED MULTIFAMILY DWELLINGS. [DSA-AC] See Chapter 11A, Section 1107A.3-C.

CROSS SLOPE. [DSA-AC] See Chapter 11A, Section 1107A.3-C, and Chapter 11B, Section 1102B.

CURB CUT. [DSA-AC] See Chapter 11A, Section 1107A.3-C, and Chapter 11B, Section 1102B.

CURB RAMP. [DSA-AC] See Chapter 11A, Section 1107A.3-C, and Chapter 11B, Section 1102B.

DETECTABLE WARNING. [DSA-AC] See Chapter 11A, Section 1107A.4-D, and Chapter 11B, Section 1102B.

DIRECTIONAL SIGN. [DSA-AC] A publicly displayed notice which indicates by use of words or symbols a recommended direction or route of travel.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

DISABILITY [DSA-AC] is (1) a physical or mental impairment that limits one or more of the major life activities of an individual, (2) a record of such an impairment, or (3) being regarded as having such an impairment.

DISABLED. [DSA-AC] See “Disability”.

DORMITORY. See Section 310.2 and 408.1.1.

DWELLING UNIT. A single unit providing complete, independent living facilities for one or more persons, including permanent provisions for living, sleeping, eating, cooking and sanitation.

[DSA-AC] See Chapter 11A, Section 1107A.4-D, and Chapter 11B, Section 1102B.

ELEMENT. [DSA-AC] See Chapter 11B, Section 1102B.

ELEVATOR, PASSENGER. [DSA-AC] See Chapter 11B, Section 1102B.

ENFORCING AGENCY. [DSA-AC] The designated department or agency as specified by statute or regulation.

ENTRANCE. [DSA-AC] See Chapter 11B, Section 1102B.

EQUIVALENT FACILITATION. [DSA-AC] See Chapter 11A, Section 1107A.5-E, and Chapter 11B, Section 1102B.

EXISTING BUILDINGS. [DSA-AC] See “Building, Existing.”

EXIT. See Section 1002.1.

FACILITY (or FACILITIES). [DSA-AC] See Chapter 11A, Section 1107A.6-F, and Chapter 11B, Section 1102B.

FREE-STANDING PEDESTAL. [DSA-AC] See Chapter 11C, Section 1101C.1.

GRAB BAR. [DSA-AC] See Chapter 11A, Section 1107A.7-G, and Chapter 11B, Section 1102B.

GRADE (Adjacent Ground Elevation) [DSA-AC] is the lowest point of elevation of the finished surface of the ground, paving or sidewalk within the area between the building and the property line or, when the property line is more than 5 feet (1524 mm) from the building, between the building and a line 5 feet (1524 mm) from the building. See Health and Safety Code Section 19955.3 (d).

GROUND FLOOR. [DSA-AC] See Chapter 11A, Section 1107A.7-G.

GUARD [DSA-AC] or GUARDRAIL. See Section 1002.1.

HANDRAIL. See Section 1002.1.

HEALTH CARE PROVIDER. [DSA-AC] See “Professional Office of a Health Care Provider” in Chapter 11B, Section 1102B.

HISTORICAL BUILDINGS. [DSA-AC] See “Qualified historical building or property,” C.C.R., Title 24, Part 8.

IF, IF . . . THEN. [DSA-AC] See Chapter 11B, Section 1102B.

INDEPENDENT ENTITY [DSA-AC] is a not-for-profit product safety testing and certification organization, dedicated to testing for public safety. An independent entity would operate for the testing, certification and quality assessment of products, systems and services.

INTERNATIONAL SYMBOL OF ACCESSIBILITY. [DSA-AC] See Chapter 11A, Section 1107A.9-I, and Chapter 11B, Section 1102B.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

KICK PLATE. [DSA-AC] See Chapter 11A, Section 1107A.11-K, and Chapter 11B, Section 1102B.

LEVEL ACCESSIBLE AREA. [DSA-AC] See Chapter 11C, Section 1101C.1.

LEVEL AREA. [DSA-AC] See Chapter 11A, Section 1107A.12-L, and Chapter 11B, Section 1102B.

LIFT, PLATFORM (WHEELCHAIR). [DSA-AC] See “Platform (Wheelchair) Lift” Chapter 11A, Section 1107A.16-P, and Chapter 11B, Section 1102B.

MARKED CROSSING. [DSA-AC] See Chapter 11A, Section 1107A.13-M, and Chapter 11B, Section 1102B.

MAY. [DSA-AC] See Chapter 11B, Section 1102B.

MULTIPLE-ACCOMMODATION TOILET FACILITY [DSA-AC] is a room that has more than one sanitary fixture, is intended for the use of more than one person at a time and which usually is provided with privacy compartments or screens shielding some fixtures from view. A bathroom serving a hotel guest room and a privacy toilet in small offices, stores and similar locations are not included in this category.

MULTISTORY DWELLING UNITS. [DSA-AC] See Chapter 11A, Section 1107A.13-M.

NEWLY CONSTRUCTED. [DSA-AC] See Chapter 11A, Section 1107A.14-N.

NFPA [DSA-AC] is the National Fire Protection Association.

NOSING (or NOSE). See Section 1002.1. [DSA-AC] See Chapter 11A, Section 1107A.14-N, and Chapter 11B, Section 1102B.

OCCUPIABLE SPACE. A room or enclosed space designed for human occupancy in which individuals congregate for amusement, educational or similar purposes or in which occupants are engaged at labor, and which is equipped with means of egress and light and ventilation facilities meeting the requirements of this code.

OPEN RISER. [DSA-AC] See Chapter 11A, Section 1107A.15-O, and Chapter 11B, Section 1102B.

OPERABLE PART. [DSA-AC] See Chapter 11B, Section 1102B.

PASSAGE DOOR. [DSA-AC] See Chapter 11A, Section 1107A.16-P, and Chapter 11B, Section 1102B.

PASSENGER ELEVATOR. [DSA-AC] See “Elevator, passenger” in Chapter 11B, Section 1102B.

PATH OF TRAVEL. [DSA-AC] See Chapter 11B, Section 1102B.

PEDESTRIAN. [DSA-AC] See Chapter 11A, Section 1107A.16-P, and Chapter 11B, Section 1102B.

PEDESTRIAN GRADE SEPARATION. [DSA-AC] See Chapter 11B, Section 1102B.

PEDESTRIAN RAMP. [DSA-AC] See Chapter 11A, Section 1107A.16-P, and Chapter 11B, Section 1102B.

PEDESTRIAN WAY. [DSA-AC] See Chapter 11A, Section 1107A.16-P, and Chapter 11B, Section 1102B.

PERMANENT [DSA-AC] shall mean facilities which, are intended to be used for periods longer than those designated in this code under the definition of “Temporary.”

PERMIT. An official document or certificate issued by the authority having jurisdiction which authorizes performance of a specified activity.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

PERSONS WITH DISABILITIES. [DSA-AC] See Chapter 11A, Section 1107A.16-P.

PLATFORM. See Section 410.2.

PLATFORM (WHEELCHAIR) LIFT. [DSA-AC] See Chapter 11A, Section 1107A.16-P and Chapter 11B, Section 1102B.

POWDER ROOM. [DSA-AC] See Chapter 11A, Section 1107A.16-P.

POWER-ASSISTED DOOR [DSA-AC] is a door used for human passage with a mechanism that helps to open the door, or relieves the opening resistance of a door, upon the activation of a switch or a continued force applied to the door itself.

PROFESSIONAL OFFICE OF A HEALTH CARE PROVIDER. [DSA-AC] See Chapter 11B, Section 1102B.

PUBLIC ACCOMMODATION [DSA-AC] includes, but is not limited to, any public use building or facility that may be classified into one or more of the following categories:

1. Places of public lodging.
2. Establishments serving food or drink open to public use.
3. Places of exhibition or entertainment open to public use.
4. Places of public gathering.
5. Sales or rental establishments open to public use.
6. Service establishments open to public use.
7. Stations used for public transportation.
8. Places of public display or collection.
9. Places of public recreation.
10. Places of public education.
11. Social service center establishments open to public use.
12. Places of exercise or recreation open to public use.

Examples of public accommodations for purposes of this code shall include, but not be limited to, the following private entities:

1. An inn, hotel, motel or other place of public lodging, except for a lodging house located within a building that contains not more than five rooms for rent or hire and that is actually occupied by the proprietor of such establishment as the residence of such proprietor.
2. A restaurant, bar or other establishment serving food or drink.
3. A motion picture house, theater, concert hall, stadium or other place of exhibition or entertainment.
4. An auditorium, convention center, lecture hall or other place of public gathering.
5. A bakery, grocery store, clothing store, hardware store, shopping center, or other sales or rental establishment.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

6. *A Laundromat, dry cleaner, bank, barber shop, beauty shop, travel service, shoe repair service, funeral parlor, gas station, office of an accountant or lawyer, pharmacy, insurance office, professional office of a health care provider, hospital or other service establishment.*
7. *A terminal, depot or other station used for specified public transportation.*
8. *A museum, library, gallery or other place of public display or collection.*
9. *A park, zoo, amusement park or other place of recreation.*
10. *A nursery, elementary, secondary, undergraduate or postgraduate private school, or other place of education.*
11. *A day care center, senior citizen center, homeless shelter, food bank, adoption agency or other social service center establishment.*
12. *A gymnasium, health spa, bowling alley, golf course or other place of exercise.*
13. *A church.*
14. *An office building.*
15. *A public curb or sidewalk.*

PUBLIC-USE AREAS. [DSA-AC] See Chapter 11A, Section 1107A.16-P, and Chapter 11B, Section 1102B.

PUBLIC WAY. See Section 1002.1.

QUALIFIED HISTORICAL BUILDING (or PROPERTY). [DSA-AC] See C.C.R. Title 24, Part 8.

RAMP. See Section 1002.1.

[DSA-AC] See Chapter 11A, Section 1107A.18-R and Chapter 11B, Section 1102B.

REASONABLE PORTION [DSA-AC] shall mean that segment of a building, facility, area, space or condition, which would normally be necessary if the activity therein is to be accessible by persons with disabilities.

RECOMMEND. [DSA-AC] Does not require mandatory acceptance, but identifies a suggested action that shall be considered for the purpose of providing a greater degree of accessibility to persons with disabilities.

REMODELING. [DSA-AC] See "Alteration or Alter."

REPAIR. The reconstruction or renewal of any part of an existing building for the purpose of its maintenance.

RISER. [DSA-AC] See Chapter 11A, Section 1107A.18-R, and Chapter 11B, Section 1102B.

RUNNING SLOPE. [DSA-AC] See Chapter 11B, Section 1102B.

SANITARY FACILITY. [DSA-AC] Any single water closet, urinal, lavatory, bathtub or shower, or a combination thereof, together with the room or space in which they are housed.

SERVICE ENTRANCE [DSA-AC] is an entrance intended primarily for the delivery of goods or services.

SHALL. [DSA-AC] See Chapter 11B, Section 1102B.

SHOPPING CENTER (or SHOPPING MALL). [DSA-AC] See Chapter 11B, Section 1102B.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SHOULD. [DSA-AC] See Chapter 11B, Section 1102B.

SIDEWALK. [DSA-AC] A surfaced pedestrian way contiguous to a street used by the public. (As differentiated from the definition of "Walk" in Chapter 11A, Section 1107A.23-W and Chapter 11B, Section 1102B.)

SIGNAGE [DSA-AC] is displayed verbal, symbolic, tactile, and/or pictorial information.

SINGLE-ACCOMMODATION SANITARY FACILITY [DSA-AC] A room that has not more than one of each type of sanitary fixture, is intended for use by only one person at a time, has no partition around the toilet, and has a door that can be locked on the inside by the room occupant.

SITE. [DSA-AC] A parcel of land bounded by a property line or a designated portion of a public right-of-way.

SITE DEVELOPMENT. [DSA-AC] "On-site" and "off-site" work, including, but not limited to, walks, sidewalks, ramps, curbs, curb ramps, parking facilities, stairs, planting areas, pools, promenades, exterior gathering or assembly areas and raised or depressed paved areas.

SLEEPING ACCOMMODATIONS. [DSA-AC] See Chapter 11A, Section 1107A.19-S, and Chapter 11B, Section 1102B.

SLOPE. [DSA-AC] See Chapter 11A, Section 1107A.19-S.

SPACE. [DSA-AC] A definable area, e.g., a room, toilet room, hall, assembly area, entrance, storage room, alcove, courtyard, or lobby.

SPECIFIED PUBLIC TRANSPORTATION. [DSA-AC] See Chapter 11B, Section 1102B.

STAGE. See Section 410.2.

STAIR. See Section 1002.1.

STAIRWAY. See Section 1002.1.

STORY. That portion of a building included between the upper surface of a floor and the upper surface of the floor or roof next above (also see "Basement," "Mezzanine" and Section 502.1). It is measured as the vertical distance from top to top of two successive tiers of beams or finished floor surfaces and, for the topmost story, from the top of the floor finish to the top of the ceiling joists or, where there is not a ceiling, to the top of the roof rafters.

[DSA-AC] See Chapter 11B, 1102B.

STORY, FIRST. [DSA-AC] See Chapter 11B, Section 1102B.

STRUCTURAL FRAME. [DSA-AC] See Chapter 11B, Section 1102B.

STRUCTURE. That which is built or constructed.

TACTILE. [DSA-AC] Describes an object that can be perceived using the sense of touch.

TECHNICALLY INFEASIBLE. See Section 3402.1.

[DSA-AC] "Technically infeasible" means, with respect to an alteration of a building or a facility, that it has little likelihood of being accomplished because existing structural conditions would require removing or altering a load-bearing member which is an essential part of the structural frame; or because other existing physical or site constraints prohibit modification or addition of elements, spaces, or features which are in full and strict compliance with the minimum requirements for new construction and which are necessary to provide accessibility.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

TEMPORARY [DSA-AC] shall mean buildings and facilities intended for use at one location for not more than one year and seats intended for use at one location for not more than 90 days.

TEXT TELEPHONE. [DSA-AC] See Chapter 11B, Section 1102B.

TRANSIENT LODGING. [DSA-AC] See Chapter 11B, Section 1102B and Chapter 11A, Section 1107A.20-T.

TRANSIT BOARDING PLATFORM. [DSA-AC] See Chapter 11B, Section 1102B.

TREAD. [DSA-AC] See Chapter 11A, Section 1107A.20-T, and Chapter 11B, Section 1102B.

TYPE OF MOTOR FUEL. [DSA-AC] See Chapter 11C, Section 1101C.1.

UNREASONABLE HARDSHIP [DSA-AC] exists when the enforcing agency finds that compliance with the building standard would make the specific work of the project affected by the building standard unfeasible, based on an overall evaluation of the following factors:

1. The cost of providing access.
2. The cost of all construction contemplated.
3. The impact of proposed improvements on financial feasibility of the project.
4. The nature of the accessibility which would be gained or lost.
5. The nature of the use of the facility under construction and its availability to persons with disabilities.

The details of any finding of unreasonable hardship shall be recorded and entered in the files of the enforcing agency.

VEHICULAR OR PEDESTRIAN ARRIVAL POINTS. [DSA-AC] See Chapter 11A, Section 1107A.22-V.

VEHICULAR WAY. [DSA-AC] See Chapter 11B, Section 1102B.

WALK. [DSA-AC] See Chapter 11A, Section 1107A.23-W, and Chapter 11B, Section 1102B.

WHEELCHAIR. [DSA-AC] A chair mounted on wheels to be propelled by its occupant manually or with the aid of electric power, of a size and configuration conforming to the recognized standard models of the trade.

WHEELCHAIR OCCUPANT (or WHEELCHAIR USER) [DSA-AC] is an individual who, due to a physical impairment or disability, utilizes a wheelchair for mobility.

WORKSTATION. See Section 415.2.

[DSA-AC] See Chapter 11B, Section 1102B.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE CHAPTER 3 - USE AND OCCUPANCY CLASSIFICATION

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
302.1						X														
310.2 Dormitory						X														

SECTION 302 CLASSIFICATION

302.1 General. Structures or portions of structures shall be classified with respect to occupancy in one or more of the groups listed below. A room or space that is intended to be occupied at different times for different purposes shall comply with all of the requirements that are applicable to each of the purposes for which the room or space will be occupied. Structures with multiple occupancies or uses shall comply with Section 508. Where a structure is proposed for a purpose that is not specifically provided for in this code, such structure shall be classified in the group that the occupancy most nearly resembles, according to the fire safety and relative hazard involved.

1. Assembly (see Section 303): Groups A-1, A-2, A-3, A-4 and A-5
2. Business (see Section 304): Group B
3. Educational (see Section 305): Group E
4. Factory and Industrial (see Section 306): Groups F-1 and F-2
5. High Hazard (see Section 307): Groups H-1, H-2, H-3, H-4 and H-5
6. Institutional (see Section 308): Groups I-1, I-2, I-2.1, I-3 and I-4
7. *Laboratory (see Section 202): Group B, unless classified as Group L (See Section 443) or Group H (see Section 307).*
8. Mercantile (see Section 309): Group M
9. **[SFM]** *Organized Camps (see Section 440): Group C10.*
10. **[SFM]** *Research Laboratories (see Section 443): Group L*
11. Residential (see Section 310): Groups R-1, R-2, R-2.1, R-3, R-3.1 and R-4
12. Storage (see Section 311): Groups S-1 and S-2
13. Utility and Miscellaneous (see Section 312): Group U

[SFM] *Existing buildings housing existing protective social care homes or facilities established prior to 1972 (see Section 3413).*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 310 RESIDENTIAL GROUP R

310.2 Definitions.

DORMITORY. A space in a building where group sleeping accommodations are provided in one room, or in a series of closely associated rooms, for persons not members of the same family group, under joint occupancy and single management, as in college dormitories or fraternity houses.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 4 - SPECIAL DETAILED REQUIREMENTS ON USE AND OCCUPANCY**

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
406.2.2						X														
410.2 Platform and Stage						X														
412.3.6						X														
420.4.4						X														

**SECTION 406
MOTOR-VEHICLE-RELATED OCCUPANCIES**

406.2 Parking garages.

406.2.2 Clear height. The clear height of each floor level in vehicle and pedestrian traffic areas shall not be less than 7 feet (2134 mm). *[DSA-AC] The clear height of vehicle and pedestrian areas required to be accessible shall comply with Chapter 11A or 11B, as applicable.*

**SECTION 410
STAGES AND PLATFORMS**

410.2 Definitions.

PLATFORM. A raised area within a building used for worship, the presentation of music, plays or other entertainment; the head table for special guests; the raised area for lecturers and speakers; boxing and wrestling rings; theater-in-the-round stages; and similar purposes wherein there are no overhead hanging curtains, drops, scenery or stage effects other than lighting and sound. A temporary platform is one installed for not more than 30 days.

STAGE. A space within a building utilized for entertainment or presentations, which includes overhead hanging curtains, drops, scenery or stage effects other than lighting and sound.

**SECTION 412
AIRCRAFT-RELATED OCCUPANCIES**

412.3 Airport traffic control towers.

412.3.6 Accessibility. *[DSA-AC] In air traffic control towers, an accessible route shall not be required to serve the cab and the equipment areas on the floor immediately below the cab.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 420 GROUPS R-1, R-2, R-2.1, R-3, R-4

420.4 Carbon monoxide alarms.

420.4.4 Visible alarms. *In buildings meeting the definition of "COVERED MULTIFAMILY DWELLINGS" in accordance with Chapter 11A and with fuel-burning appliances and/or attached garages as described in Section 420.4.1, all required carbon monoxide alarms shall be provided with the capability to support visible alarm notification appliances in accordance with NFPA 720 and Chapter 11B.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 9 - FIRE PROTECTION SYSTEMS**

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
907.4.2.2						X														
907.5.2.1						X														
907.5.2.1.1						X														
907.5.2.1.2						X														
907.5.2.1.3						X														
907.5.2.3						X														
907.5.2.3.1						X														
907.5.2.3.2						X														
907.5.2.3.3						X														
Table 907.5.2.3.3						X														
907.5.2.3.4						X														
907.5.2.3.5						X														

**SECTION 907
FIRE ALARM AND DETECTION SYSTEMS**

907.4 Initiating devices.

907.4.2 Manual fire alarm boxes.

907.4.2.2 Height. The height of the manual fire alarm boxes shall be a minimum of 42 inches (1067 mm) and a maximum of 48 inches (1219 mm) measured vertically, from the floor level to the *highest point of the* activating handle or lever of the box. *Manual fire alarm boxes shall also comply with Section 1117B.6 Item 4.*

Exception: [DSA-AC] *In existing buildings there is no requirement to retroactively relocate existing manual fire alarm boxes to a minimum of 42 inches (1067 mm) and a maximum of 48 inches (1219 mm) from the floor level to the activating handle or lever of the box.*

907.5 Occupant notification systems.

907.5.2 Alarm notification appliances. ...

907.5.2.1 Audible alarms. Audible alarm notification appliances shall be provided and emit a distinctive sound that is not to be used for any purpose other than that of a fire alarm.

In Group I-2 occupancies, audible appliances located in patient areas shall be only chimes or similar sounding appliances for alerting staff. See Section 907.6.5.

Exception: Visible alarm notification appliances shall be allowed in lieu of audible alarm notification appliances in *patient* areas of Group I-2 occupancies.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

907.5.2.1.1 Average sound pressure. The audible alarm notification appliances shall provide a sound pressure level of 15 decibels (dBA) above the average ambient sound level or 5 dBA above the maximum sound level having a duration of at least 60 seconds, whichever is greater, in every occupiable space within the building. The minimum sound pressure levels shall be: 75 dBA in occupancies in Group R; 90 dBA in mechanical equipment rooms and 60 dBA in other occupancies.

907.5.2.1.2 Maximum sound pressure. The maximum sound pressure level for audible alarm notification appliances shall be 110 dBA at the minimum hearing distance from the audible appliance. Where the average ambient noise is greater than 95 dBA, visible alarm notification appliances shall be provided in accordance with NFPA 72 and audible alarm notification appliances shall not be required.

907.5.2.1.3 Audible alarm signal. *The audible signal shall be the standard fire alarm evacuation signal, ANSI S3.41 Audible Emergency Evacuation Signal, “three pulse temporal pattern,” as described in NFPA 72.*

Exception: *The use of the existing evacuation signaling scheme shall be permitted where approved by the enforcing agency.*

907.5.2.3 Visible alarms. Visible alarm notification appliances shall be provided in accordance with Sections 907.5.2.3.1 through 907.5.2.3.5.

Exceptions:

1. *In other than Group I-2 and I-2.1, visible alarm notification appliances are not required in alterations, except where an existing fire alarm system is upgraded or replaced, or a new fire alarm system is installed.*
2. *Visible alarm notification appliances shall not be required in enclosed exit stairways, exterior exit stairs, and exterior exit ramps.*
3. *Visible alarm notification appliances shall not be required in elevator cars.*

907.5.2.3.1 Public and common use areas. Visible alarm notification appliances shall be provided in public use areas and common use areas, *including but not limited to:*

1. *Sanitary facilities including restrooms, bathrooms and shower rooms*
2. *Corridors*
3. *Music practice rooms*
4. *Band rooms*
5. *Gymnasiums*
6. *Multipurpose rooms*
7. *Occupational shops*
8. *Occupied rooms where ambient noise impairs hearing of the fire alarm*
9. *Lobbies*
10. *Meeting rooms*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

11. Classrooms

907.5.2.3.2 Employee work areas. Where employee work areas have audible alarm coverage, the notification appliance circuits serving the employee work areas shall be initially designed with a minimum of 20-percent spare capacity to account for the potential of adding visible notification appliances in the future to accommodate hearing impaired employee(s).

907.5.2.3.3 Groups R-1 and R-2.1. Group R-1 and R-2.1 dwelling units or sleeping units in accordance with Table 907.5.2.3.3 shall be provided with a visible alarm notification appliance, activated by both the in-room smoke alarm and the building fire alarm system.

907.5.2.3.4 Group R-2. In Group R-2 occupancies required by Section 907 to have a fire alarm system, all dwelling units and sleeping units shall be provided with the capability to support visible alarm notification appliances in accordance with NFPA 72.

907.5.2.3.5 Groups R-2.1, R-3.1 and R-4. Protective social care facilities which house persons who are hearing impaired, shall be provided with notification appliances for the hearing impaired installed in accordance with NFPA 72 and which shall activate upon initiation of the fire alarm system or the smoke alarms.

**TABLE 907.5.2.3.3
VISIBLE ALARMS**

NUMBER OF SLEEP UNITS	SLEEPING ACCOMMODATIONS WITH VISIBLE ALARMS
6 to 25	2
26 to 50	4
51 to 75	7
76 to 100	9
101 to 150	12
151 to 200	14
201 to 300	17
301 to 400	20
401 to 500	22
501 to 1,000	5% of total
1,001 and over	50 plus 3 for each 100 over 1,000

[DSA-AC & SFM] Also see Chapter 11B, Section 1111B.4.5, Tables 11B-3 and 11B-4.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 10 – MEANS OF EGRESS**

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
Accessible means of egress						X														
Area of refuge						X														
Exit						X														
Guard or guardrail						X														
Handrail						X														
Public way						X														
Stair						X														
Stairway						X														
1003.1						X														
1007.1						X														
1007.2						X														
1007.2.1						X														
1007.3						X														
1007.4						X														
1007.5						X														
1007.5.1						X														
1007.6						X														
1007.6.1						X														
1007.6.2						X														
1007.6.3						X														
1007.7						X														
1007.7.1						X														
1007.7.2						X														
1007.8						X														
1007.8.1						X														
1007.8.2						X														
1007.9						X														
1007.10						X														
1007.11						X														
1007.12						X														
1008 (1 st paragraph below title only)						X														
1008.1.9.7 (Item 5.1 only)						X														
1009 (1 st paragraph below title only)						X														
1009.4.2 Exc. 6						X														
1009.12 (2 nd paragraph only)						X														
1010 (1 st paragraph below title only)						X														
1011.3						X														
1012 (1 st paragraph below title only)						X														
1013.1						X														
1013.2						X														
1013.3						X														
1017 (1 st paragraph below title only)						X														

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
1017.2 Exc. Only General						X														
1022.8 (2 nd paragraph only)						X														

SECTION 1002 DEFINITIONS

1002.1 Definitions.

ACCESSIBLE MEANS OF EGRESS. A continuous and unobstructed way of egress travel from any accessible point in a building or facility to a public way.

AREA OF REFUGE. An area where persons unable to use stairways can remain temporarily to await instructions or assistance during emergency evacuation.

EXIT. That portion of a means of egress system which is separated from other interior spaces of a building or structure by fire-resistance-rated construction and opening protectives as required to provide a protected path of egress travel between the exit access and the exit discharge. Exits include exterior exit doors at the level of exit discharge, vertical exit enclosures, exit passageways, exterior exit stairways, exterior exit ramps and horizontal exits.

GUARD [DSA-AC] or GUARDRAIL. A building component or a system of building components located at or near the open sides of elevated walking surfaces that minimizes the possibility of a fall from the walking surface to a lower level.

HANDRAIL. A horizontal or sloping rail intended for grasping by the hand for guidance or support.

PUBLIC WAY. A street, alley or other parcel of land open to the outside air leading to a street, that has been deeded, dedicated or otherwise permanently appropriated to the public for public use and which has a clear width and height of not less than 10 feet (3048 mm).

STAIR. A change in elevation, consisting of one or more risers.

STAIRWAY. One or more flights of stairs, either exterior or interior, with the necessary landings and platforms connecting them, to form a continuous and uninterrupted passage from one level to another.

SECTION 1003 GENERAL MEANS OF EGRESS

1003.1 Applicability. The general requirements specified in Sections 1003 through 1013 shall apply to all three elements of the means of egress system, in addition to those specific requirements for the exit access, the exit and the exit discharge detailed elsewhere in this chapter.

Exception: *Exiting requirements for Fixed Guideway Transit Systems shall be as per Section 433.3.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

[DSA-AC] *In addition to the requirement of this chapter, means of egress, which provide access to, or egress from, buildings or facilities where accessibility is required for applications listed in Section 1.8.2.1.2 regulated by the Department of Housing and Community Development, or Section 1.9.1 regulated by the Division of the State Architect — Access Compliance, shall also comply with Chapter 11A or Chapter 11B, as applicable.*

SECTION 1007 ACCESSIBLE MEANS OF EGRESS

1007.1 Accessible means of egress required. Accessible means of egress shall comply with this section. Accessible spaces shall be provided with not less than one accessible means of egress. Where more than one means of egress is required by Section 1015.1 or 1021.1 from any accessible space, each accessible portion of the space shall be served by accessible means of egress *in at least the same number as required by Section 1015.1 or 1021.1. In addition to the requirements of this chapter, means of egress, which provide access to, or egress from, buildings for persons with disabilities, shall also comply with the requirements of Chapters 11A or 11B, as applicable.*

Exceptions:

1. Accessible means of egress are not required in alterations to existing buildings.
2. One accessible means of egress is required from an accessible mezzanine level in accordance with Section 1007.3, 1007.4 or 1007.5 *and Chapter 11A or 11B, as applicable.*
3. In assembly areas with sloped or stepped aisles, one accessible means of egress is permitted where the common path of travel is accessible and meets the requirements in Section 1028.8, *and Chapter 11A or 11B, as applicable.*

1007.2 Continuity and components. Each required accessible means of egress shall be continuous to a public way and shall consist of one or more of the following components:

1. Accessible routes complying with *Chapter 11A, Sections 1110A.1 and 1120A, or Chapter 11B, Section 1114B.1.2, as applicable.*
2. Interior exit stairways complying with Sections 1007.3, 1026, *and Chapter 11A, Section 1123A, or Chapter 11B, Section 1133B.4, as applicable.*
3. Exterior exit stairways complying with Sections 1007.3, 1026, *and Chapter 11A, Section 1115A, or Chapter 11B, Section 1133B.4, as applicable.*
4. Elevators complying with Section 1007.4 *and Chapter 11A, Section 1124A, or Chapter 11B, Section 1116B.1, as applicable.*
5. Platform lifts complying with Section 1007.5 *and Chapter 11A, Section 1124A, or Chapter 11B, Section 1116B, as applicable.*
6. Horizontal exits complying with Section 1025.
7. Ramps complying with Section 1010 *and Chapter 11A, Sections 1114A and 1122A, or Chapter 11B, Section 1133B.5, as applicable.*
8. Areas of refuge complying with Section 1007.6.

Exceptions:

1. Where the exit discharge is not accessible, an exterior area for assisted rescue must be provided in accordance with Section 1007.7.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. Where the exit stairway is open to the exterior, the accessible means of egress shall include either an area of refuge in accordance with Section 1007.6 or an exterior area for assisted rescue in accordance with Section 1007.7.

1007.2.1 Elevators required. In buildings where a required accessible floor is four or more stories above or below a level of exit discharge, at least one required accessible means of egress shall be an elevator complying with Section 1007.4.

Exceptions:

1. In buildings equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2, the elevator shall not be required on floors provided with a horizontal exit and located at or above the levels of exit discharge.
2. In buildings equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2, the elevator shall not be required on floors provided with a ramp conforming to the provisions of Section 1010.

1007.3 Stairways. In order to be considered part of an accessible means of egress, an exit access stairway as permitted by Section 1016.1 or exit stairway shall have a clear width of 48 inches (1219 mm) minimum between handrails and shall either incorporate an area of refuge within an enlarged floor-level landing or shall be accessed from either an area of refuge complying with Section 1007.6 or a horizontal exit. **[DSA-AC]** *In addition, exit stairways shall comply with Chapter 11A, Sections 1115A and 1123A, or Chapter 11B, Section 1133B.4, as applicable.*

Exceptions:

1. The area of refuge is not required at open exit access or exit stairways as permitted by Sections 1016.1 and 1022.1 in buildings that are equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2.
2. The clear width of 48 inches (1219 mm) between handrails is not required at exit access stairway as permitted by Section 1016.1 or exit stairways in buildings equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2.
3. Areas of refuge are not required at exit stairways in buildings equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2.
4. The clear width of 48 inches (1219 mm) between handrails is not required for exit stairways accessed from a horizontal exit.
5. Areas of refuge are not required at exit stairways serving open parking garages.
6. Areas of refuge are not required for smoke protected seating areas complying with Section 1028.6.2.
7. The areas of refuge are not required in Group R-2 occupancies.

1007.4 Elevators. In order to be considered part of an accessible means of egress, an elevator shall comply with the emergency operation and signaling device requirements of Section 2.27 of ASME A17.1. Standby power shall be provided in accordance with Chapter 27 and Section 3003. The elevator shall be accessed from either an area of refuge complying with Section 1007.6 or a horizontal exit.

Exceptions:

1. Elevators are not required to be accessed from an area of refuge or horizontal exit in open parking garages.
2. Elevators are not required to be accessed from an area of refuge or horizontal exit in buildings and facilities equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. Elevators not required to be located in a shaft in accordance with Section 708.2 are not required to be accessed from an area of refuge or horizontal exit.
4. Elevators are not required to be accessed from an area of refuge or horizontal exit for smoke protected seating areas complying with Section 1028.6.2.

1007.5 Platform lifts. Platform (wheelchair) lifts shall not serve as part of an accessible means of egress, except where allowed as part of a required accessible route in *Chapter 11A, Section 1121A, or Chapter 11B, Section 1116B.2 Items 1 through 4, as applicable*. Standby power shall be provided in accordance with Chapter 27 for platform lifts permitted to serve as part of a means of egress.

[DSA-AC] See *Chapter 11B, Section 1116B.2.5 for additional accessible means of egress requirements at platform (wheelchair) lifts*.

1007.5.1 Openness. Platform lifts on an accessible means of egress shall not be installed in a fully enclosed hoistway.

1007.6 Areas of refuge. Every required area of refuge shall be accessible from the space it serves by an accessible means of egress. The maximum travel distance from any accessible space to an area of refuge shall not exceed the travel distance permitted for the occupancy in accordance with Section 1016.1. Every required area of refuge shall have direct access to a stairway within an exit enclosure complying with Sections 1007.3 and 1022 or an elevator complying with Section 1007.4. Where an elevator lobby is used as an area of refuge, the shaft and lobby shall comply with Section 1022.9 for smokeproof enclosures except where the elevators are in an area of refuge formed by a horizontal exit or smoke barrier. **[DSA-AC]** *Areas of refuge shall comply with the requirements of this code and shall adjoin an accessible route of travel complying with Section 1114B.1.2.*

Exceptions:

1. A stairway serving an area of refuge is not required to be enclosed where permitted in Sections 1016.1 and 1022.1.
2. Smokeproof enclosure is not required for an elevator lobby used as an area of refuge where the elevator is not required to be enclosed.

1007.6.1 Size. Each area of refuge shall be sized to accommodate *two* wheelchair spaces of 30 inches by 48 inches (762 mm by 1219 mm). *The total number of such 30-inch by 48-inch (762 mm by 1219 mm) spaces per story shall be not less than one for every 200 persons of calculated occupant load served by the area of refuge.* Such wheelchair spaces shall not reduce the required means of egress width. Access to any of the required wheelchair spaces in an area of refuge shall not be obstructed by more than one adjoining wheelchair space.

Exception: *The enforcing agency may reduce the size of each required area of refuge to accommodate one wheelchair space that is not less than 30 inches by 48 inches (762 mm by 1219 mm) on floors where the occupant load is less than 200.*

1007.6.2 Separation. Each area of refuge shall be separated from the remainder of the story by a smoke barrier complying with Section 710 or a horizontal exit complying with Section 1025. Each area of refuge shall be designed to minimize the intrusion of smoke.

Exception: Areas of refuge located within an exit enclosure.

1007.6.3 Two-way communication. Areas of refuge shall be provided with a two-way communication system complying with Sections 1007.8.1 and 1007.8.2.

1007.7 Exterior area for assisted rescue. The exterior area for assisted rescue must be open to the outside air and meet the requirements of Section 1007.6.1. Separation walls shall comply with the requirements of Section 705 for exterior walls. Where walls or openings are between the area for assisted rescue and the interior of the building, the

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

building exterior walls within 10 feet (3048 mm) horizontally of a nonrated wall or unprotected opening shall have a fire-resistance rating of not less than 1 hour. Openings within such exterior walls shall be protected by opening protectives having a fire protection rating of not less than 3/4 hour. This construction shall extend vertically from the ground to a point 10 feet (3048 mm) above the floor level of the area for assisted rescue or to the roof line, whichever is lower.

1007.7.1 Openness. The exterior area for assisted rescue shall be at least 50 percent open, and the open area above the guards shall be so distributed as to minimize the accumulation of smoke or toxic gases.

1007.7.2 Exterior exit stairway. Exterior exit stairways that are part of the means of egress for the exterior area for assisted rescue shall provide a clear width of 48 inches (1219 mm) between handrails.

1007.8 Two-way communication. A two-way communication system shall be provided at the elevator landing on each accessible floor that is one or more stories above or below the story of exit discharge complying with Sections 1007.8.1 and 1007.8.2.

Exceptions:

1. Two-way communication systems are not required at the elevator landing where the two-way communication system is provided within areas of refuge in accordance with Section 1007.6.3.
2. Two-way communication systems are not required on floors provided with exit ramps conforming to the provisions of Section 1010.

1007.8.1 System requirements. Two-way communication systems shall provide communication between each required location and the fire command center or a central control point location approved by the fire department. Where the central control point is not constantly attended, a two-way communication system shall have a timed automatic telephone dial-out capability to a monitoring location or 911. The two-way communication system shall include both audible and visible signals.

1007.8.1.1 Visible communication method. [DSA-AC] *A button complying with Section 1117B.6 in the area of refuge shall activate both a light in the area of refuge indicating that rescue has been requested and a light at the central control point indicating that rescue is being requested. A button at the central control point shall activate both a light at the central control point and a light in the area of refuge indicating that the request has been received.*

1007.8.2 Directions. Directions for the use of the two-way communication system, instructions for summoning assistance via the two-way communication system and written identification of the location shall be posted adjacent to the two-way communication system.

1007.9 Signage. Signage indicating special accessibility provisions shall be provided as shown:

1. Each door providing access to an area of refuge from an adjacent floor area shall be identified by a sign complying with Section 1117B.5.1, Item 2, stating: AREA OF REFUGE.
2. Each door providing access to an exterior area for assisted rescue shall be identified by a sign stating: EXTERIOR AREA FOR ASSISTED RESCUE.

Signage shall comply with Section 1117B.5.1, Items 2 and 3, requirements for visual characters and include the International Symbol of Accessibility. Where exit sign illumination is required by Section 1011.2, the signs shall be illuminated. Additionally, tactile signage complying with Section 1117B.5.1, Item 1 and the International Symbol of Accessibility shall be located at each door to an area of refuge and exterior area for assisted rescue in accordance with Section 1011.3.

[DSA-AC] *Signs shall comply with Chapter 11A or Chapter 11B, Section 1117B.5.1, Items 2 and 3, as applicable.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1007.10 Directional signage. Direction signage indicating the location of the other means of egress and which are accessible means of egress shall be provided at the following:

1. At exits serving a required accessible space but not providing an approved accessible means of egress.
2. At elevator landings.
3. Within areas of refuge.

1007.11 Instructions. In areas of refuge and exterior areas for assisted rescue, instructions on the use of the area under emergency conditions shall be posted. The instructions shall include all of the following *and shall comply with Section 1117B.5.1, Item 2*:

1. Persons able to use the exit stairway do so as soon as possible, unless they are assisting others.
2. Information on planned availability of assistance in the use of stairs or supervised operation of elevators and how to summon such assistance.
3. Directions for use of the two-way communications system where provided.

1007.12 Alarms/emergency warning systems/accessibility. *If emergency warning systems are required, they shall activate a means of warning the hearing impaired. Emergency warning systems as part of the fire-alarm system shall be designed and installed in accordance with NFPA 72, as amended in Chapter 35.*

SECTION 1008 DOORS, GATES AND TURNSTILES

[DSA-AC] *In addition to the requirements of this section, means of egress, which provide access to, or egress from, buildings or facilities where accessibility is required for applications listed in Section 1.9.1 regulated by the Division of the State Architect--Access Compliance shall also comply with Chapter 11A or Chapter 11B, Section 1133B.2, as applicable.*

1008.1 Doors.

1008.1.9 Door operations.

1008.1.9.1 Hardware. Door handles, pulls, latches, locks and other operating devices on doors required to be accessible by *Chapters 11A or 11B* shall not require tight grasping, tight pinching or twisting of the wrist to operate.

1008.1.9.7 Delayed egress locks. ...

5. A sign shall be provided on the door located above and within 12 inches (305 mm) of the release device reading: *“KEEP PUSHING. THIS DOOR WILL OPEN IN 15 [30] SECONDS. ALARM WILL SOUND”* Sign lettering shall be at least 1 inch (25 mm) in height and shall have a stroke of not less than 1/8 inch (3.2 mm).
 - 5.1 *A tactile sign shall also be provided in Braille and raised characters, which complies with Section 1117B.5.1.1, Item 1.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1009 STAIRWAYS

[DSA-AC] In addition to the requirements of this section, means of egress, which provide access to, or egress from, buildings or facilities where accessibility is required for applications listed in Section 1.9.1 regulated by the Division of the State Architect--Access Compliance, shall also comply with Chapter 11A or Chapter 11B, Section 1133B.4, as applicable.

1009.4 Stair treads and risers. Stair treads and risers shall comply with Sections 1009.4.1 through 1009.4.5.

1009.4.1 Dimension reference surfaces. For the purpose of this section, all dimensions are exclusive of carpets, rugs or runners.

1009.4.2 Riser height and tread depth. ...

Exceptions:

6. See Section 3404.1 for the replacement of existing stairways. **[HCD 1]** See Chapter 34, Section 3403.1, Exception 2 for additions, alterations or repairs to existing buildings. **[DSA-AC]** For applications listed in Section 1.9.1 regulated by the Division of the State Architect--Access Compliance, see Chapter 11B, Section 1134B.

1009.12 Handrails. Stairways shall have handrails on each side and shall comply with Section 1012. Where glass is used to provide the handrail, the handrail shall also comply with Section 2407.

Exceptions:

1. Handrails for aisle stairs are not required where permitted by Section 1028.13.
2. Stairways within dwelling units, spiral stairways and aisle stairs serving seating only on one side are permitted to have a handrail on one side only.
3. Decks, patios and walkways that have a single change in elevation where the landing depth on each side of the change of elevation is greater than what is required for a landing do not require handrails.
4. In Group R-3 occupancies, a continuous run of treads or flight of stairs with less than four risers does not require handrails.
5. Changes in room elevations of three or fewer risers within dwelling units and sleeping units in Group R-2 and R-3 do not require handrails.

[DSA-AC] For applications listed in Section 1.9.1 regulated by the Division of the State Architect--Access Compliance, see Chapter 11B, Section 1133B.4.1.

SECTION 1010 RAMPS

[DSA-AC] In addition to the requirements of this section, means of egress, which provide access to, or egress from, buildings or facilities where accessibility is required for applications listed in Section 1.9.1 regulated by the Division of the State Architect--Access Compliance, shall also comply with Chapter 11A or Chapter 11B, Section 1133B.5, as applicable.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1011 EXIT SIGNS

1011.3 Tactile exit signs. *For the purposes of Section 1011.3, the term “tactile exit signs” shall mean those required signs that comply with Section 1117B.5.1, Item 1. Tactile exit signs shall be required at the following locations:*

1. *Each grade-level exterior exit door shall be identified by a tactile exit sign with the word, “EXIT.”*
2. *Each exit door that leads directly to a grade-level exterior exit by means of a stairway or ramp shall be identified by a tactile exit sign with the following words as appropriate:*
 - A. *“EXIT STAIR DOWN”*
 - B. *“EXIT RAMP DOWN”*
 - C. *“EXIT STAIR UP”*
 - D. *“EXIT RAMP UP”*
3. *Each exit door that leads directly to a grade-level exterior exit by means of an exit enclosure that does not utilize a stair or ramp, or by means of an exit passageway, shall be identified by a tactile exit sign with the words, “EXIT ROUTE.”*
4. *Each exit access door from an interior room or area that is required to have a visual exit sign, shall be identified by a tactile exit sign with the words, “EXIT ROUTE.”*
5. *Each exit door through a horizontal exit shall be identified by a tactile exit sign with the words “TO EXIT.”*

SECTION 1012 HANDRAILS

[DSA-AC] *In addition to the requirements of this section, means of egress, which provide access to, or egress from, buildings or facilities where accessibility is required for applications listed in Section 1.9.1 regulated by the Division of the State Architect--Access Compliance, shall also comply with Chapter 11A or Chapter 11B, Section 1133B.4.1 or 1133B.5.5, as applicable.*

SECTION 1013 GUARDS

1013.1 Where required. Guards shall be located along open-sided walking surfaces, including mezzanines, equipment platforms, stairs, ramps and landings that are located more than 30 inches (762 mm) measured vertically to the floor or grade below at any point within 36 inches (914 mm) horizontally to the edge of the open side. Guards shall be adequate in strength and attachment in accordance with Section 1607.7.

Exception: Guards are not required for the following locations:

1. On the loading side of loading docks or piers.
2. On the audience side of stages and raised platforms, including steps leading up to the stage and raised platforms.
3. On raised stage and platform floor areas, such as runways, ramps and side stages used for entertainment or presentations.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4. At vertical openings in the performance area of stages and platforms.
5. At elevated walking surfaces appurtenant to stages and platforms for access to and utilization of special lighting or equipment.
6. Along vehicle service pits not accessible to the public.
7. In assembly seating where guards in accordance with Section 1025.14 are permitted and provided.

1013.2 Height. Required guards shall be not less than 42 inches (1067 mm) high, measured vertically above the adjacent walking surfaces, adjacent fixed seating or the line connecting the leading edges of the treads.

Exceptions:

1. For occupancies in Group R-3, and within individual dwelling units in occupancies in Group R-2, guards on the open sides of stairs shall have a height not less than 34 inches (864 mm) measured vertically from a line connecting the leading edges of the treads.
2. For occupancies in Group R-3, and within individual dwelling units in occupancies in Group R-2, where the top of the guard also serves as a handrail on the open sides of stairs, the top of the guard shall not be less than 34 inches (864 mm) and not more than 38 inches (965 mm) measured vertically from a line connecting the leading edges of the treads.
3. The height in assembly seating areas shall be in accordance with Section 1028.14.
4. Along alternating tread devices and ship ladders, guards whose top rail also serves as a handrail, shall have height not less than 30 inches (762 mm) and not more than 34 inches (864 mm), measured vertically from the leading edge of the device tread nosing.

1013.3 Opening limitations. Required guards shall not have openings which allow passage of a sphere 4 inches (102 mm) in diameter from the walking surface to the required guard height.

Exceptions:

1. From a height of 36 inches (914 mm) to 42 inches (1067 mm), guards shall not have openings which allow passage of a sphere 4-3/8 inches (111 mm) in diameter.
2. The triangular openings at the open sides of a stair, formed by the riser, tread and bottom rail shall not allow passage of a sphere 6 inches (152 mm) in diameter.
3. At elevated walking surfaces for access to and use of electrical, mechanical or plumbing systems or equipment, guards shall not have openings which allow passage of a sphere 21 inches (533 mm) in diameter.
4. In areas that are not open to the public within occupancies in Group I-3, F, H or S, and for alternating tread devices and ship ladders, guards shall not have openings which allow passage of a sphere 21 inches (533 mm) in diameter.
5. In assembly seating areas, guards at the end of aisles where they terminate at a fascia of boxes, balconies and galleries shall not have openings which allow passage of a sphere 4 inches in diameter (102 mm) up to a height of 26 inches (660 mm). From a height of 26 inches (660 mm) to 42 inches (1067 mm) above the adjacent walking surfaces, guards shall not have openings which allow passage of a sphere 8 inches (203 mm) in diameter.
6. Within individual dwelling units and sleeping units in Group R-2 and R-3 occupancies, guards on the open sides of stairs shall not have openings which allow passage of a sphere 4-3/8 inches (111 mm) in diameter.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

7. *Lifeguard towers not open to the public, guards shall not have openings which allow passage of a sphere 21 inches (533 mm) in diameter.*

SECTION 1017 AISLES

[DSA-AC] *In addition to the requirements of this section, means of egress, which provide access to, or egress from, buildings or facilities where accessibility is required for applications listed in Section 1.9.1 regulated by the Division of the State Architect--Access Compliance, shall also comply with Chapter 11A or Chapter 11B, Section 1133B.6, as applicable.*

1017.2 Aisles in Groups B and M. In Group B and M occupancies, the minimum clear *aisle* width shall be determined by Section 1005.1 for the *occupant load* served, but shall not be less than 36 inches (914 mm).

Exception: Nonpublic *aisles* serving less than 50 people and not required to be *accessible* by Chapter 11B (see Sections 1103B.1 Exception 2, and 1123B.2 Exception) need not exceed 28 inches (711 mm) in width.

SECTION 1022 EXIT ENCLOSURES

1022.8 Floor identification signs. A sign shall be provided at each floor landing in exit enclosures connecting more than three stories designating the floor level, the terminus of the top and bottom of the exit enclosure and the identification of the stair or ramp. The signage shall also state the story of, and the direction to, the exit discharge and the availability of roof access from the enclosure for the fire department. The sign shall be located 5 feet (1524 mm) above the floor landing in a position that is readily visible when the doors are in the open and closed positions.

Tactile floor identification signs that comply with 1117B.5.1, Item 1 shall be located at the landing of each floor level, placed adjacent to the door on the latch side, in all enclosed stairways in buildings two or more stories in height to identify the floor level. At the exit discharge level, the sign shall include a raised five pointed star located to the left of the identifying floor level. The outside diameter of the star shall be the same as the height of the raised characters.

**CHAPTER 11
RESERVED**

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 11A – HOUSING ACCESSIBILITY**

NOTE: Dwelling units constructed as senior citizen housing may also be subject to the Unruh Civil Rights Act. Refer to Division I, Part 2 of the California Civil Code. For additional information regarding application, interpretation and enforcement, contact the California Department of Fair Employment and Housing.

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC	
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4									
Adopt entire chapter			X	X	X																
Adopt entire chapter as amended (amended sections listed below)						X															
Adopt only those sections that are listed below		X																			
Chapter/Section																					
1102A.3.1, Exc.						†															
1104A.2, Exc.						†															

The state agency does not adopt sections identified with the following symbol: †

Division I – APPLICATION, GENERAL PROVISIONS, AND DEFINITIONS

Division I Table of Contents

Section 1101A Application

Section 1102A Building Accessibility

Section 1103A Design and Construction

Section 1104A Covered Multifamily Dwellings

Section 1105A Garages, Carports and Parking Facilities

Section 1106A Site and Building Characteristics

Section 1107A Definitions

**SECTION 1101A
APPLICATION**

1101A.1 Scope. The application and authority of this chapter are identified and referenced in Sections 1.8.2.1.2 and 1102A for the Department of Housing and Community Development. Applicable sections are identified in the Matrix Adoption Tables of this code under the abbreviation HCD 1-AC. The provisions of this chapter shall apply to the following:

1. All newly-constructed covered multifamily dwellings.
2. New common use spaces serving existing covered multifamily dwellings.
3. Additions to existing buildings, where the addition alone meets the definition of a covered multifamily dwelling.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4. *Common use areas serving covered multifamily dwellings.*
5. *Where any portion of a building's exterior is preserved, but the interior of the building is removed, including all structural portions of floors and ceilings, the building is considered a new building for determining the application of this chapter.*

These building standards generally do not apply to public accommodations such as hotels and motels. Public use areas, public accommodations, and housing which is publicly funded as defined in Chapter 2 of this code are subject to provisions of the Division of the State Architect (DSA—AC) and are referenced in Section 1.9.1.1.

SECTION 1102A BUILDING ACCESSIBILITY

1102A.1 Where required. *Buildings or portions of buildings and facilities within the scope of this chapter shall be accessible to persons with disabilities. Each building on a building site shall be considered separately when determining the requirements contained in this chapter, except when calculating the number of units which must comply with Section 1102A.3.1. Dwelling units within a single structure separated by firewalls do not constitute separate buildings.*

Newly-constructed covered multifamily dwellings as defined in this chapter, include, but are not limited to, the following:

1. *Apartment buildings with 3 or more dwelling units including timeshare apartments not considered a place of public accommodation or transient lodging as defined in Health and Safety Code Section 19955 (a) and Chapter 2 of the California Building Code.*
2. *Condominiums with 4 or more dwelling units including timeshare condominiums not considered a place of public accommodation or transient lodging as defined in Health and Safety Code Section 19955 (a) and Chapter 2 of the California Building Code.*
3. *Lodging houses, as defined in Chapter 2 of the California Building Code, used as a residence with more than 3 but not more than 5 guest rooms.*
4. *Congregate residences, as defined in Chapter 2 of the California Building Code.*
5. *Dwellings with 3 or more efficiency units, as defined in Chapter 2 of this code, or Section 17958.1 of the California Health and Safety Code.*
6. *Shelters for homeless persons, not otherwise subject to the disabled access provisions of the Division of the State Architect—Access Compliance (DSA—AC).*
7. *Dormitories, as defined in Chapter 2 of this code, with 3 or more guest rooms as defined in Chapter 2 of the California Building Code.*
8. *Timeshare dwellings with 3 or more units, not considered a place of public accommodations or transient lodging as defined in Health and Safety Code Section 19955 (a) and Chapter 2 of the California Building Code.*
9. *Other Group R Occupancies in covered multifamily dwellings which are regulated by the Office of the State Fire Marshal. See Section 1.11.*
10. *Housing which is publicly funded as defined in Chapter 2 of this code is subject to provisions of the Division of the State Architect (DSA—AC). See Section 1111B.5.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1102A.2 Existing buildings. *The building standards contained in this chapter do not apply to the alteration, repair, rehabilitation or maintenance of multifamily dwellings constructed for first occupancy prior to March 13, 1991. Housing which is publicly funded as defined in Chapter 2 of this code is subject to provisions of the Division of the State Architect (DSA-AC). See Section 1111B.5.*

Covered multifamily dwellings shall be maintained in compliance with the accessibility standards in effect at the time of construction. Apartments constructed prior to March 13, 1991, shall be maintained in compliance with the accessibility standards in effect at the time of construction.

Additions shall be subject to the requirements of this chapter, provided the addition, when considered alone, meets the definition of a covered multifamily dwelling, as defined in this chapter. New common use spaces serving existing covered multifamily dwellings shall be subject to the requirements of this chapter.

Note: *For all existing public use areas, public accommodations, and housing which is publicly funded, see Chapter 11B, Division IV, Section 1134B, for provisions of the Division of the State Architect Access Compliance (DSA-AC).*

1102A.3 Multistory dwellings.

1102A.3.1 Multistory apartment or condominium dwellings in buildings with no elevator. *This section shall apply to multistory dwelling units on the ground floor of buildings without elevators for which an application for a construction permit is submitted on or after July 1, 2005.*

Exception: *Carriage units as defined in Section 1107A.3-C and regulated only by the Department of Housing and Community Development as referenced in Section 1.8.2.1.2*

At least 10 percent but not less than one of the multistory dwellings in apartment buildings with 3 or more dwelling units and/or condominiums with 4 or more dwelling units shall comply with the following:

- 1. The primary entry to the dwelling unit shall be on an accessible route unless exempted by site impracticality tests in Section 1150A.*
- 2. At least one powder room or bathroom shall be located on the primary entry level, served by an accessible route and shall comply with the provisions in Division IV.*
- 3. All rooms or spaces located on the primary entry level shall be served by an accessible route and shall comply with the provisions in Division IV. Rooms and spaces located on the primary entry level and subject to this chapter may include but are not limited to kitchens, powder rooms, bathrooms, living rooms, bedrooms, or hallways.*
- 4. Common use areas covered by this section shall be accessible as required by this chapter. Public use areas as defined in Chapter 2, Chapter 11A, and Chapter 11B of this code are subject to provisions of the Division of the State Architect (DSA-AC) and are referenced in Section 1.9.1.1.*

The minimum number of multifamily dwelling units which must comply with this section shall be calculated using the total number of all multistory dwelling units in buildings on a site which are subject to this section. Any fraction thereof shall be rounded to the next highest whole number.

1102A.3.2 Multistory dwelling units in buildings with one or more elevators. *Multistory dwelling units contained in buildings with elevators shall comply with this section. For multistory dwelling units in buildings with elevators, the story of the unit that is served by the building elevator is considered a ground floor and the primary entry floor to the unit and shall comply with the following:*

- 1. At least 1 powder room or bathroom shall be located on the primary entry level.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. *All rooms or spaces located on the primary entry level shall be served by an accessible route and shall comply with Division IV.*

1102A.4 Participation areas. *Access shall be provided to elements listed in Section 1104B.4.3, "Participation areas".*

1102A.5 Swimming pools. *Swimming pools and spas required to be accessible shall comply with the provisions of Section 1141A.*

1102A.6 Temporary restrictions. *During periods of partial or restricted use of a building or facility, the entrances used for primary access shall be accessible to and usable by persons with disabilities.*

SECTION 1103A DESIGN AND CONSTRUCTION

1103A.1 General.

1103A.1.1 *When buildings are required to be accessible, they shall be designed and constructed as provided in this chapter.*

Note: *Public use areas, public accommodations, and housing which is publicly funded as defined in Chapter 2 of this code are subject to provisions of the Division of the State Architect (DSA—AC) and are referenced in Section 1.9.1.1.*

SECTION 1104A COVERED MULTIFAMILY DWELLINGS

1104A.1 General. *All ground-floor dwelling units in nonelevator buildings shall be adaptable and on an accessible route, unless an accessible route is not required as determined by site impracticality provisions in Section 1150A. For buildings with elevators, see Section 1106A.*

Multistory dwelling units shall comply with Section 1102A.3.

1104A.2 Ground floors above grade. *Where the first floor containing dwelling units in a building is above grade, all units on that floor shall be served by an accessible route. This floor will be considered a ground floor and all dwelling units are considered covered multifamily dwelling units.*

Exception: *Carriage units as defined in Section 1107A.3-C and regulated only by the Department of Housing and Community Development as referenced in Section 1.8.2.1.2.*

Multistory dwelling units shall comply with Section 1102A.3.

SECTION 1105A GARAGES, CARPORTS AND PARKING FACILITIES

1105A.1 General. *Garages, carports and other parking facilities which are accessory to covered multifamily dwelling units, shall be accessible as required in Section 1109A.*

SECTION 1106A SITE AND BUILDING CHARACTERISTICS

1106A.1 General. *Covered multifamily dwellings with elevators shall be designed and constructed to provide at least one accessible entrance on an accessible route, regardless of terrain or unusual characteristics of the site. Covered multifamily dwellings without elevators shall be designed and constructed to provide at least one accessible entrance*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

on an accessible route unless terrain or unusual characteristics of the site prevent an accessible route based on the conditions listed below:

1. **Accessible entrance.** Regardless of site considerations described in Section 1150A, an accessible entrance on an accessible route is required when there is an elevator connecting the parking area with the dwelling units on a ground floor. (In this case, those dwelling units on the ground floor served by an elevator, and at least one of each type of public- and common-use areas, would be subject to these requirements.)
2. **Elevator building.** When a building elevator or elevators are provided as a means of access to dwelling units other than dwelling units on a ground floor (see Section 1104A.2), the building is an elevator building. All dwelling units become covered multifamily dwellings in that building. The elevator in that building must provide accessibility to all dwelling units in the building, regardless of the slope of the natural terrain. For multistory dwelling units in buildings with one or more elevators, see Section 1102A.3.2.

Note: Where a building elevator is provided only as means of creating an accessible route to covered multifamily dwelling units on a ground floor, the building is not considered to be an elevator building, only dwelling units located on the ground floor shall be required to comply with this chapter.

3. **Elevated walkway.** When an elevated walkway is planned between a building entrance and a vehicular or pedestrian arrival point, and the planned walkway has a slope no greater than 10 percent (1 unit vertical in 10 units horizontal), the floor being served by the elevated walkway becomes a ground floor and accessibility to all dwellings on that ground floor is required.

Note: Since the planned walkway meets the 10 percent slope criterion, it is required to provide an accessible route to the entrance, and the slope of the walkway must be reduced to 1 unit vertical in 12 units horizontal (8.33 percent slope) maximum.

1106A.2 Site impracticality. For tests to determine site impracticality due to terrain considerations in non-elevator buildings, see Section 1150A.

SECTION 1107A DEFINITIONS

1107A.1-A

ACCESSIBLE for covered multifamily dwellings is the public- or common-use areas of the building that can be approached, entered and used by persons with disabilities.

ACCESSIBLE ROUTE is a continuous and unobstructed path connecting all accessible elements and spaces in a building or within a site that can be negotiated by a person with a disability using a wheelchair, and that is also safe for and usable by persons with other disabilities. Interior accessible routes may include corridors, hallways, floors, ramps, elevators, and lifts. Exterior accessible routes may include parking access aisles, curb ramps, crosswalks at vehicular ways, walks, ramps, and lifts.

ACCESSIBILITY is the combination of various elements in a building or area which allows access, circulation and the full use of the building and facilities by persons with disabilities.

ADAPTABLE DWELLING UNIT is an accessible dwelling unit within a covered multifamily building as designed with elements and spaces allowing the dwelling unit to be adapted or adjusted to accommodate the user. See Division IV.

ASSISTIVE DEVICE is an aid, tool or instrument used by persons with disabilities to assist in activities of daily living.

AUTOMATIC DOOR is a door equipped with a power-operated mechanism and controls that open and close the door automatically upon receipt of a momentary actuating signal. The switch that begins the automatic cycle may be a photoelectric device, floor mat or manual switch.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1107A.2-B

BATHROOM is, for the purposes of this chapter, a room which includes a water closet (toilet), lavatory (sink) and a bathtub and/or a shower. It does not include single-fixture facilities or those with only a water closet and lavatory. It does include a compartmented bathroom. A compartmented bathroom is one in which the fixtures are distributed

among interconnected rooms. A compartmented bathroom is considered a single unit and is subject to the requirements of this chapter.

BUILDING ENTRANCE ON AN ACCESSIBLE ROUTE is an accessible entrance to a building that is connected by an accessible route to public transportation stops, to parking or passenger loading zones, or to public streets or sidewalks, if available.

1107A.3-C

CARRIAGE UNIT is a dwelling unit with living space on one or more floors immediately above a Group U, Division 1, private garage or garages. The footprint of the garage or garages is used as the footprint for the remaining floor or floors of the units above and the garage level contains no habitable space.

Note: Dwelling units located over a common garage shall not be considered carriage units.

COMMON-USE AREAS are private use areas within multifamily residential facilities where the use of these areas is limited exclusively to owners, residents, and their guests. The areas may be defined as rooms or spaces or elements inside or outside of a building.

COVERED MULTIFAMILY DWELLINGS are dwelling units in buildings consisting of 3 or more dwelling units or 4 or more condominium units. Covered multifamily dwellings include dwelling units listed in Section 1102A.1. Dwelling units within a single structure separated by firewalls do not constitute separate buildings.

Note: For buildings or complexes containing publicly funded dwelling units, see Chapter 11B, Section 1111B.5 for provisions of the Division of the State Architect — Access Compliance (DSA-AC).

CROSS SLOPE is the slope that is perpendicular to the direction of travel.

CURB CUT is an interruption of a curb at a pedestrian way, which separates surfaces that are substantially at the same elevation.

CURB RAMP is a sloping pedestrian way, intended for pedestrian traffic, which provides access between a walk or sidewalk and a surface located above or below an adjacent curb face.

1107A.4-D

DETECTABLE WARNING is a standardized surface or feature built into or applied to walking surfaces or other elements to warn visually impaired persons of hazards in the path of travel. Only approved DSA-AC detectable warning products and directional surfaces shall be installed as provided in the CCR, Title 24, Part 1 Articles 2, 3, and 4. Refer to CCR, Title 24, Part 12, Chapter 12-11A and B for building and facility access specifications for product approval for detectable warning products and directional surfaces.

Note: Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect - Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing, evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

DWELLING UNIT is a single unit of residence for a family of one or more persons. Examples of dwelling units covered by this chapter include condominiums, an apartment unit within an apartment building, and other types of dwellings in which sleeping accommodations are provided but toileting or cooking facilities are shared by occupants of more than one room or portion of the dwelling. Examples of the latter include dormitory rooms and sleeping accommodations in shelters intended for occupancy as residences for homeless persons.

1107A.5-E

EQUIVALENT FACILITATION is an alternate means of complying with the literal requirements of these standards and specifications that provides access consistent with the purpose of these standards and specifications.

Notes:

1. See Section 1.8.1, Purpose.
2. In determining equivalent facilitation, consideration shall be given to means that provide for the maximum independence of persons with disabilities while presenting the least risk of harm, injury or other hazard to such persons or others.

1107A.6-F

FACILITY (or FACILITIES) is a building, structure, room, site, complex or any portion thereof, that is built, altered, improved or developed to serve a particular purpose.

1107A.7-G

GRAB BAR is a bar for the purpose of being grasped by the hand for support.

GROUND FLOOR is the floor of a building with a building entrance on an accessible route. A building may have one or more ground floors.

1107A.8-H (No definitions)

1107A.9-I

INDEPENDENT ENTITY. See Chapter 2, Section 202.

INTERNATIONAL SYMBOL OF ACCESSIBILITY is that symbol adopted by Rehabilitation International's 11th World Congress for the purpose of indicating that buildings and facilities are accessible to persons with disabilities. See Chapter 11A, Figure 11A-1A.

1107A.10-J (No definitions)

1107A.11-K

KICK PLATE is an abrasion-resistant plate affixed to the bottom portion of a door to prevent a trap condition and protect its surface.

1107A.12-L

LEVEL AREA is a specified surface that does not have a slope in any direction exceeding $\frac{1}{4}$ inch (6.4 mm) in 1 foot (305 mm) from the horizontal (2.083-percent gradient).

LIFT, PLATFORM (WHEELCHAIR). See "Platform (Wheelchair) Lift."

1107A.13-M

MARKED CROSSING is a crosswalk or other identified marked path intended for pedestrian use in crossing a vehicular way.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

MULTISTORY DWELLING UNIT is a dwelling unit with finished living space located on one floor and the floor or floors immediately above or below it.

1107A.14-N

NEWLY CONSTRUCTED is a building that has never before been used or occupied for any purpose.

NOSE, NOSING is that portion of a tread projecting beyond the face of the riser immediately below.

1107A.15-O

OPEN RISER is the airspace between a tread projecting beyond the face of the riser immediately below.

1107A.16-P

PASSAGE DOOR is a door other than an exit door through which persons may traverse.

PEDESTRIAN is an individual who moves within walking areas with or without the use of walking-assistive devices such as crutches, leg braces, wheelchairs, etc.

PEDESTRIAN RAMP is a sloping accessible route intended for pedestrian traffic and is differentiated from a curb ramp.

PEDESTRIAN WAY is a route by which a pedestrian may pass.

PERSONS WITH DISABILITIES, for purposes of this chapter, "persons with disabilities" includes, but is not limited to, any physical or mental disability as defined in Government Code Section 12926.

PLATFORM (WHEELCHAIR) LIFT is a hoisting and lowering mechanism equipped with a car or platform, or support, which serves two landings of a building or structure and is designed to carry a passenger or passengers and/or luggage or other material a vertical distance as may be allowed by Section 1124A.11.

POWDER ROOM is a room containing a water closet (toilet) and lavatory (sink), and which is not defined as a bathroom in Section 1107A.2-B.

PRIMARY ENTRY is the principal entrance through which most people enter the building, as designated by the building official.

PRIMARY ENTRY LEVEL is the floor or level of the building on which the primary entry is located.

PUBLIC ACCOMMODATION. See Chapter 2, Section 202.

PUBLIC USE AREAS means interior or exterior rooms or spaces of a building that are made available to the general public and does not include Common Use Areas as defined in Section 1107A.3-C. Public Use Areas may be provided at a building that is privately or publicly owned.

1107A.17-Q (No definitions)

1107A.18-R

RAMP. See "Pedestrian ramp," Section 1107A.16-P.

RISER is the vertical distance from the top of a tread to the top of the next higher tread.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1107A.19-S

SIDEWALK. See “Sidewalk,” Chapter 2, Section 202.

SLEEPING ACCOMMODATIONS are rooms in which people may sleep; for example, dormitory and hotel or motel guest rooms or suites.

SLOPE is the relative steepness of the land between two points and is calculated as follows:

The horizontal distance and elevation change between the two points (e.g., an entrance and a passenger loading zone). The difference in elevation is divided by the distance and the resulting fraction is multiplied by 100 to obtain the percentage of slope.

For example: if a principal entrance is 10 feet (3048 mm) from a passenger loading zone, and the principal entrance is raised 1 foot (305 mm) higher than the passenger loading zone, then the slope is $1/10 \times 100 = 10$ percent.

1107A.20-T

TRANSIENT LODGING is a building, facility, or portion thereof, available to the public as an inn, hotel, motel, timeshare, or place where one or more dwelling units or sleeping accommodations are provided for transient guests, excluding inpatient medical care facilities and lodging houses with 5 or less guest rooms. Transient lodging may include but is not limited to, resorts, group homes, and dormitories.

TREAD is the horizontal member of a step.

TREAD DEPTH is the horizontal distance from front to back of tread, including nosing when used.

TREAD RUN is the horizontal distance from the leading edge of a tread to the leading edge of an adjacent tread.

1107A.21-U (No definitions)

1107A.22-V

VEHICULAR OR PEDESTRIAN ARRIVAL POINTS are public or resident parking areas, public transportation stops passenger loading zones, and public streets or sidewalks.

1107A.23-W

WALK is a surfaced pedestrian way not located contiguous to a street used by the public. (See Chapter 2, Section 202 definition for “Sidewalk.”)

WHEELCHAIR. See “Wheelchair,” Chapter 2, Section 202.

1107A.24-X (No definitions)

1107A.24-Y (No definitions)

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Division II – EXTERIOR FACILITIES

Division II Table of Contents

Section 1108A	General Requirements for Accessible Parking and Exterior Routes of Travel
Section 1109A	Parking Facilities
Section 1110A	Exterior Routes of Travel
Section 1111A	Changes in Level on Accessible Routes
Section 1112A	Curb Ramps on Accessible Routes
Section 1113A	Walks and Sidewalks on an Accessible Route
Section 1114A	Exterior Ramps and Landings on Accessible Routes
Section 1115A	Exterior Stairways
Section 1116A	Hazards on Accessible Routes

SECTION 1108A

GENERAL REQUIREMENTS FOR ACCESSIBLE PARKING AND EXTERIOR ROUTES OF TRAVEL

Notes:

1. In addition to provisions of this division, exterior routes of travel that provide access to, or egress from, buildings for persons with disabilities shall also comply with Chapter 10.
2. Public use areas, public accommodations, and housing which is publicly funded as defined in Chapter 2 of this code are subject to provisions of the Division of the State Architect (DSA-AC) and are referenced in Section 1.9.1.1.

SECTION 1109A

PARKING FACILITIES

1109A.1 Accessible parking required. Each parking facility provided for covered multifamily dwellings and facilities (e.g., swimming pools, club houses, recreation areas, and laundry rooms) that serve covered multifamily dwellings shall provide accessible parking as required by this section.

1109A.2 Parking facilities. Parking facilities shall include, but not be limited to, the following:

1. Garages.
2. Private garages.
3. Carports.
4. Off-street parking (parking lots/spaces).

1109A.2.1 Private garages. Private garages accessory to covered multifamily dwelling units shall be accessible as required in Section 1109A. Private garages include individual garages and multiple individual garages grouped together.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Exception: An attached private garage directly serving a single covered multifamily dwelling unit providing at least one of the following options:

1. A door leading directly from the covered dwelling unit which immediately enters the garage. The door shall comply on both sides with Sections 1132A through 1132A.9.
2. An accessible route of travel from the covered dwelling unit to an exterior door entering the garage. See Section 1132a.1 for requirements at both exit doors.
3. An accessible route of travel from the dwelling unit's primary entry door to the vehicular entrance at the garage. See Section 1132A.1 for requirements at the primary entry door.

1109A.3 Required accessible parking spaces. Accessible parking spaces shall be provided at a minimum rate of 2 percent of the covered multifamily dwelling units. At least one space of each type of parking facility shall be made accessible even if the total number exceeds 2 percent. When assigned parking is provided, signage as required by Section 1109A.8.8 shall not be required.

1109A.4 Assigned accessible parking spaces. When assigned parking spaces are provided for a resident or a group of residents, at least 2 percent of the assigned parking spaces serving covered multifamily dwelling units shall be accessible in each type of parking facility. At least one space of each type of parking facility shall be made accessible even if the total number exceeds 2 percent. When assigned parking is provided, signage as required by Section 1109A.8.8 shall not be required.

1109A.5 Unassigned and visitor parking spaces. When parking is provided for covered multifamily dwellings and is not assigned to a resident or a group of residents at least 5 percent of the parking spaces shall be accessible and provide access to grade-level entrances of covered multifamily dwellings and facilities (e.g., swimming pools, club houses, recreation areas, and laundry rooms) that serve covered multifamily dwellings. Accessible parking spaces shall be provided with signage as required by Section 1109A.8.8. Such signage shall not be blocked from view by a vehicle parked in the space.

1109A.6 Requests for accessible parking spaces. When assigned parking is provided, designated accessible parking for the dwelling unit shall be provided on request of residents with disabilities on the same terms and with the full range of choices (e.g., off-street parking, carport or garage) that are available for other residents.

1109A.7 Location of accessible parking spaces. The location of accessible parking spaces shall comply with the following:

1. Accessible parking spaces shall be located on the shortest possible accessible route to an accessible building, or covered multifamily dwelling unit entrance. All van accessible spaces may be grouped on one level of a parking facility.
2. When parking facilities are located adjacent to a building with multiple accessible entrances, accessible parking spaces shall be dispersed and located near the accessible building entrances.
3. When practical, the accessible route shall not cross lanes for vehicular traffic. When crossing vehicle traffic lanes is necessary, the accessible route shall be designated and marked as a crosswalk.
4. Parking facilities that do not serve a particular building shall have accessible parking spaces located on the shortest possible accessible route to an accessible pedestrian entrance of the parking facility.
5. Accessible parking spaces shall be located so that persons with disabilities are not compelled to wheel or walk behind parked cars other than their own.

Exception: When the enforcement agency determines that compliance with this section or providing equivalent facilitation would create an unreasonable hardship, parking spaces may be provided which would require a person with physical disabilities to wheel or walk behind other than accessible parking spaces.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1109A.8 Design and construction. Accessible parking required by this section shall be designed and constructed in accordance with Section 1109A.

1109A.8.1 Vertical clearances. All entrances, exits, and vehicular passageways to and from required accessible parking spaces within parking facilities, shall have a minimum vertical clearance of 8 feet 2 inches (2489 mm) from the floor to the lowest projection of the ceiling. Reflective warning signs complying with Section 1117B.5.4 for character height shall be installed at transitions from the 8 feet 2 inch ceiling to lower ceiling heights in vehicular passageways in the same parking level.

1109A.8.2 Arrangement of parking spaces. Parking spaces shall be arranged to comply with the following:

1. In each parking area, a bumper or curb shall be provided and located to prevent encroachment of cars over the required width of walkways.
2. Ramps, including curb ramps, shall not encroach into any accessible parking space or the adjacent loading and unloading access aisle.

1109A.8.3 Slope of accessible parking spaces and access aisles. Surface slopes of accessible parking spaces and access aisles shall be the minimum possible and shall not exceed $\frac{1}{4}$ inch (6.35 mm) per foot (2.083-percent gradient) in any direction.

1109A.8.4 Accessible parking space size. Accessible parking spaces shall comply with Sections 1109A.8.5 and 1109A.8.6.

1109A.8.5 Accessible single parking space. Where accessible single spaces are provided, they shall be constructed in accordance with the following:

1. Single spaces shall be 14 feet (4267 mm) wide and lined to provide a 9-foot (2743 mm) wide parking area and a 5-foot (1524 mm) wide loading and unloading access aisle on the passenger side of the vehicle (see Figure 11A-2B) with the vehicle parked in the forward position.
2. When more than one space is provided, two 9-foot (2743 mm) wide parking spaces may be lined on each side of a 5-foot (1524 mm) wide loading and unloading access aisle (see Figure 11A-2A, and 11A-2C).
3. The minimum length of each parking space shall be 18 feet (5486 mm).
4. The loading and unloading access aisle shall be marked by a border painted blue. Within the blue border, hatched lines a maximum of 36 inches (914 mm) on center shall be painted a color contrasting with the parking surface, preferably blue or white. The words "NO PARKING" shall be painted on the ground within each 5-foot (1524 mm) wide loading and unloading access aisle. This notice shall be painted in white letters no less than 12 inches (305 mm) high and located so that it is visible to traffic enforcement officials (see Figures 11A-2A, 11A-2B, and 11A-2C).

1109A.8.6 Van accessible parking space. One in every eight accessible spaces, but not less than one, shall be van accessible and shall be constructed in accordance with the following:

1. Each space shall be served by a loading and unloading access aisle at least 8 feet (2438 mm) wide, placed on the passenger side with the vehicle parked in the forward position.
2. The minimum length of each space shall be 18 feet (5486 mm).
3. Each space shall be designated "van accessible" as required by Section 1109A.8.8.
4. All van accessible spaces may be grouped on one level of a parking facility.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

5. The loading and unloading access aisle shall be marked by a border painted blue. Within the blue border, hatched lines a maximum of 36 inches (914 mm) on center shall be painted a color contrasting with the parking surface, preferably blue or white. The words "NO PARKING" shall be painted on the ground within each 8-foot (2438 mm) wide loading and unloading access aisle. This notice shall be painted in white letters no less than 12 inches (305 mm) high and located so that it is visible to traffic enforcement officials.

1109A.8.7 Adjacent parking. Parking spaces adjacent to accessible parking spaces shall not be considered as loading and unloading access aisles.

1109A.8.8 Parking signage. Each accessible parking space reserved for persons with disabilities shall be identified by a reflective sign permanently posted immediately adjacent to and visible from each stall or space, consisting of the "International Symbol of Accessibility" in white on a dark blue background. The sign shall not be smaller than 70 square inches (4516 mm²) in area and, when in a path of travel, shall be posted at a minimum height of 80 inches (2032 mm) from the bottom of the sign to the parking space finished grade. Signs may also be centered on the wall at the interior end of the parking space at a minimum height of 36 inches (914 mm) from the parking space finished grade, ground or sidewalk. Van accessible spaces shall comply with Section 1109A.8.6 and shall have an additional sign or additional language stating "Van Accessible" below the symbol of accessibility.

Note: When assigned resident parking is provided, signage is not required except for unassigned or visitor parking spaces.

An additional sign shall also be posted in a conspicuous place at each entrance to off-street parking facilities or immediately adjacent to and visible from each accessible stall or space. The sign shall not be less than 17 inches (432 mm) by 22 inches (559 mm) in size with lettering not less than 1 inch (25.4 mm) in height, and shall clearly and conspicuously state the following:

"Unauthorized vehicles parked in designated accessible spaces not displaying distinguishing placards or special license plates issued for persons with disabilities will be towed away at the owner's expense. Towed vehicles may be reclaimed at _____ or by telephoning _____."

Blank spaces are to be filled in with appropriate information as a permanent part of the sign.

In addition to the above requirements, the surface of each accessible parking space shall have a surface identification duplicating either of the following schemes:

1. By outlining or painting the stall or space in blue and outlining on the ground in the stall or space in white or suitable contrasting color the "International Symbol of Accessibility"; or,
2. By outlining the "International Symbol of Accessibility" in white on blue background. The "International Symbol of Accessibility" shall be located so that it is visible to a traffic enforcement officer when a vehicle is properly parked in the space and shall be 36 inches high by 36 inches wide (914 mm by 914 mm).

Note: See Figures 11A-2A, 11A-2B, and 11A-2C.

SECTION 1110A EXTERIOR ROUTES OF TRAVEL

1110A.1 Exterior accessible route. When a building or portion of a building is required to be accessible or adaptable, an accessible route shall be provided to all portions of the building, accessible building entrances and between the building and the public way. The accessible route shall be the most practical direct route and to the maximum extent feasible, coincide with the route for the general public and building residents.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Exterior accessible routes shall be provided as follows:

1. *Where more than one route of travel is provided, all routes shall be accessible.*
2. *At least one accessible route within the boundary of the site shall be provided from public transportation stops, accessible parking and accessible passenger loading and unloading zones, and public streets or sidewalks to the accessible building entrance they serve.*
3. *At least one accessible route shall connect accessible buildings, facilities, elements and spaces that are on the same site. Accessible routes shall be provided between accessible buildings and accessible site facilities when more than one building or facility is located on a site.*
4. *At least one accessible route shall connect accessible building or facility entrances with all accessible spaces, elements, and covered multifamily dwelling units.*
5. *An accessible route shall connect at least one accessible entrance of each covered multifamily dwelling unit with exterior spaces and facilities that serve the dwelling unit.*
6. *Where elevators are provided for vertical access, all elevators shall be accessible. See Section 1124A.*

Note: *If the slope of the finished grade between covered multifamily dwellings and a public use or common use facility (including parking) exceeds 1 unit vertical in 12 units horizontal (8.33-percent slope), or where other physical barriers (natural or artificial) or legal restrictions, all of which are outside the control of the owner, prevent the installation of an accessible route, an acceptable alternative is to provide access by a vehicular route, provided:*

1. *There is accessible parking on an accessible route for at least 2 percent of the covered multifamily dwelling units, and*
2. *Necessary site provisions such as parking spaces and curb ramps are provided at the public use or common use facility.*

1110A.2 Signs. *At every primary public entrance and at every major junction where the accessible route diverges from the circulation path along or leading to an accessible route, entrance or facility, there shall be a sign displaying the International Symbol of Accessibility.” Signs shall indicate the direction to accessible building entrances and facilities and shall comply with the requirements found in Sections 1143A.2.*

1110A.3 Flooring. *If carpet or carpet tile is used in a common-use area or public-use area on a ground or floor surface, it shall have firm backing or no backing. The maximum pile height shall be ½ inch (12.7 mm). Exposed edges of carpet shall be fastened to floor surfaces and have trim along the entire length of the exposed edge. Carpet edge trim shall comply with Section 1111A requirements for changes in level.*

1110A.3.1 Recessed doormats. *Recessed doormats shall be adequately anchored to prevent interference with wheelchair traffic.*

SECTION 1111A CHANGES IN LEVEL ON ACCESSIBLE ROUTES

1111A.1 Changes in level not exceeding ½ inch. *Abrupt changes in level along any accessible route shall not exceed ½ inch (12.7 mm). When changes in level do occur, they shall be beveled with a slope no greater than 1 unit vertical in 2 units horizontal (50-percent slope). Changes in level not exceeding ¼ inch (6.35 mm) may be vertical.*

1111A.2 Changes greater than ½ inch. *Changes in level greater than ½ inch (12.7 mm) shall be made by means of a sloped surface not greater than 1 unit vertical in 20 units horizontal (5-percent slope), or a curb ramp, ramp, elevator or platform (wheelchair) lift. Stairs shall not be part of an accessible route. When stairs are located along or adjacent to an accessible route they shall comply with Section 1115A for exterior stairways.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1112A CURB RAMPS ON ACCESSIBLE ROUTES

1112A.1 General. Curb ramps within the boundary of the site shall be constructed at each corner of street intersections and where a pedestrian way crosses a curb. The preferred and recommended location for curb ramps is in the center of the crosswalk of each street corner. Where it is necessary to locate a curb ramp in the center of the curb return, the street surfaces shall be marked to identify pedestrian crosswalks, and the lower end of the curb ramp shall terminate within such crosswalk areas. Curb ramps do not require handrails.

1112A.2 Obstructions. Curb ramps shall be located or protected to prevent obstruction by parked cars. Built-up curb ramps shall be located so that they do not project into vehicular traffic lanes, parking spaces, or the adjacent loading and unloading access aisle.

1112A.3 Width of curb ramps. Curb ramps shall be a minimum of 48 inches (1219 mm) in width.

1112A.4 Diagonal curb ramps. If diagonal (or corner-type) curb ramps have returned curbs or other well-defined edges, such edges shall be parallel to the direction of pedestrian flow.

The bottom of diagonal curb ramps shall have a 48-inch (1219 mm) minimum clear space as shown in Figures 11A-3A through 11A-3M. If diagonal curb ramps are provided at marked crossings, the 48-inch (1219 mm) clear space shall be within the markings (see Figures 11A-3A through 11A-3M). If diagonal curb ramps have flared sides, they shall also have at least a 24-inch-long (610 mm) segment of straight curb located on each side of the curb ramp and within the marked crossing. See Figures 11A-3A through 11A-3M.

1112A.5 Slope of curb ramps. The slope of curb ramps shall not exceed 1 unit vertical to 12 units horizontal (8.33-percent slope) and shall lie, generally, in a single sloped plane. Transitions from ramps to walks, gutters, or streets shall be flush and free of abrupt changes. Maximum slopes of adjoining gutters, road surface immediately adjacent to the curb ramp, or accessible route shall not exceed 1 unit vertical to 20 units horizontal (5-percent slope) within 4 feet (1219 mm) of the top and bottom of the curb ramp.

If a curb ramp is located where pedestrians must walk across the ramp, then it shall have flared sides; the maximum slope of the flare shall be 1 unit vertical in 10 units horizontal (10-percent slope). Curb ramps with returned curbs may be used where pedestrians would not normally walk across the ramp. See Figures 11A-3A through 11A-3M.

1112A.6 Level landing. A level landing 48 inches (1219 mm) deep shall be provided at the upper end of each curb ramp over its full width to permit safe egress from the ramp surface, or the slope of the fanned or flared sides of the curb ramp, shall not exceed 1 unit vertical to 12 units horizontal (8.33-percent slope).

1112A.7 Finish. The surface of each curb ramp and its flared sides shall be stable, firm and slip-resistant and shall be of contrasting finish from that of the adjacent sidewalk.

1112A.8 Border. All curb ramps shall have a grooved border 12 inches (305 mm) wide at the level surface of the sidewalk along the top and each side approximately $\frac{3}{4}$ inch (19 mm) on center. All curb ramps constructed between the face of the curb and the street shall have a grooved border at the level surface of the sidewalk. See Figures 11A-3A through 11A-3K.

1112A.9 Detectable warnings. See Chapter 11B, Section 1127B.5, Item 7.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1113A WALKS AND SIDEWALKS ON AN ACCESSIBLE ROUTE

1113A.1 Width and continuous surface. Walks and sidewalks subject to this chapter shall have a continuous common surface, not interrupted by steps or by abrupt changes in level exceeding ½ inch (12.7 mm). (See Section 1111A.3).

1113A.1.1 Width. Walks and sidewalks shall be a minimum of 48 inches (1219 mm) in width, except that walks serving an individual dwelling unit in covered multifamily buildings may be reduced to 36 inches (914 mm) in clear width except at doors.

1113A.1.2 Surfaces. Surfaces shall be slip-resistant as follows:

1. Surfaces with a slope of less than 6 percent gradient shall be at least as slip-resistant as that described as a medium salted finish.
2. Surfaces with a slope of 6 percent or greater gradient shall be slip-resistant.

1113A.1.3 Surface cross slopes. Surface cross slopes shall not exceed ¼ inch (6.35 mm) per foot (2.083-percent slope) except when the enforcing agency finds that due to local conditions it creates an unreasonable hardship, the cross slope may be increased to a maximum of ½ inch (12.7 mm) per foot (4.2-percent slope) for distances not to exceed 20 feet (6096 mm).

1113A.2 Walks with continuous gradients. All walks on an accessible route with continuous gradients shall have level areas at least 60 inches (1524 mm) in length at intervals of at least every 400 feet (122 m).

1113A.3 Five percent gradient. When the slope in the direction of travel of any walk on an accessible route exceeds 1 unit vertical in 20 units horizontal (5-percent slope), it shall comply with the ramp provisions of Section 1114A.

1113A.4 Level areas. Walks on an accessible route shall be provided with a level area not less than 60 inches by 60 inches (1524 mm by 1524 mm) at a door or gate that swings toward the walk, and not less than 48 inches wide by 44 inches (1219 mm by 1118 mm) deep at a door or gate that swings away from the walk. See Section 1126A.3.2 for strike edge maneuvering space at doors or gates.

1113A.5 Smooth surface. The bottom 10 inches (254 mm) of all doors and/or gates except automatic and sliding doors or gates shall have a smooth, uninterrupted surface to allow the door or gate to be opened by a wheelchair footrest without creating a trap or hazardous condition. Where narrow frame doors are used, a 10-inch (254 mm) high smooth panel shall be installed on the push side of the door, which will allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition.

1113A.6 Gratings. Walks, sidewalks and pedestrian ways on an accessible route shall be free of gratings whenever possible. Gratings located in the surface of any of these areas, grid openings in gratings shall be limited to ½ inch (12.7 mm) in the direction of traffic flow.

Exceptions:

1. Where the enforcement agency determines that compliance with this section would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.
2. This section shall not apply in those conditions where, due to legal or physical constraints, all or portions of the site of the project will not allow compliance with these building standards or equivalent facilitation on all or portions of one site without creating an unreasonable hardship.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1114A EXTERIOR RAMPS AND LANDINGS ON ACCESSIBLE ROUTES

1114A.1 Width. The width of ramps shall be consistent with the requirements for exits in Chapter 10 of this code, but in no case shall the ramp width be less than the following:

1. Ramps serving accessible entrances to covered multifamily buildings where the ramp is the only exit discharge path and serves an occupant load of 300 or more shall have a minimum clear width of 60 inches (1524 mm).
2. Ramps serving accessible entrances of covered multifamily dwellings with an occupant load of 10 or less may be 36 inches (914 mm) in clear width.
3. All other ramps shall have a minimum clear width of 48 inches (1219 mm).
4. Handrails, curbs, wheel guides and/or appurtenances shall not project into the required clear width of a ramp.

Note: See Section 1114A.6.2.4 for handrail projections.

1114A.2 Slope. The maximum slope of ramps on an accessible route shall be no greater than 1 unit vertical in 12 units horizontal (8.33-percent slope). Transitions from ramps to walks, gutters or streets shall be flush and free of abrupt changes.

Exception: Ramps serving decks, patios or balconies as specified in Section 1132A.4.

1114A.2.1 Cross slope. The cross slope of ramp surfaces shall be no greater than ¼ inch (6.35 mm) per foot (2.083-percent slope).

1114A.3 Outdoor ramps. Outdoor ramps, ramp landings and their approaches shall be designed so that water will not accumulate on the walking surface.

1114A.4 Landings. Ramp landings shall be level and comply with this section.

1114A.4.1 Location of landings. Landings shall be provided at the top and bottom of each ramp. Intermediate landings shall be provided at intervals not exceeding 30 inches (762 mm) of vertical rise and at each change of direction. Landings are not considered in determining the maximum horizontal distance of each ramp.

Note: Examples of ramp dimensions are:

SLOPE (GRADING %)	MAXIMUM RISE (INCHES)	MAXIMUM HORIZONTAL PROJECTION (Feet)
	(x 25.4 for mm)	(x 304.8) for mm)
1:12 (8.33%)	30	30
1:15 (6.67%)	30	37.5
1:16 (6.25%)	30	40
1:20 (5.00%)	30	50

1114A.4.2 Size of top landings. Top landings shall not be less than 60 inches (1524 mm) wide. Top landings shall have a minimum length of not less than 60 inches (1524 mm) in the direction of the ramp run.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

See Section 1126A.3 for maneuvering clearances at doors.

1114A.4.3 Landing width. *The minimum width of bottom and intermediate landings shall not be less than the width of the ramp.*

1114A.4.4 Encroachment of doors. *Doors in any position shall not reduce the minimum dimension of the landing to less than 42 inches (1067 mm) and shall not reduce the required width by more than 3 inches (76.2 mm) when fully open. (See Figure 11A-6D).*

1114A.4.5 Strike edge extension. *The width of the landing shall comply with Section 1126A.3 for strike edge extension and maneuvering space at doors.*

1114A.4.6 Change of direction. *Intermediate and bottom landings at a change of direction in excess of 30 degrees shall have a length in the direction of ramp run of not less than 72 inches (1829 mm). (See Figures 11A-6C and 11A-6D).*

1114A.4.7 Other intermediate landings. *Other intermediate landings shall have a dimension in the direction of ramp run of not less than 60 inches (1524 mm). (See Figure 11-A6C).*

1114A.5 Ramp height. *Ramps more than 30 inches (762 mm) above the adjacent floor or ground and open on one or both sides shall be provided with guardrails as required by Section 1013. Guardrails shall be continuous from the top of the ramp to the bottom of the ramp.*

1114A.6 Ramp handrails.

1114A.6.1 Where required. *Handrails shall be provided at each side of ramps when the slope exceeds 1 unit vertical in 20 units horizontal (5 percent slope). Handrails on all ramps shall be continuous.*

Exceptions:

1. *Curb ramps.*
2. *Ramps that serve an individual dwelling unit may have one handrail, except that ramps open on one or both sides shall have handrails provided on the open side or sides.*
3. *Ramps at exterior door landings with less than 6 inches (152 mm) rise or less than 72 inches (1829 mm) in length.*

1114A.6.2 Handrail configuration.

1114A.6.2.1 Handrail heights. *The top of handrails shall be 34 to 38 inches (864 to 965 mm) above the ramp surface.*

1114A.6.2.2 Handrail ends. *Handrail ends shall be returned.*

1114A.6.2.3 Handrail extension. *Handrails shall extend a minimum of 12 inches (305 mm) beyond the top and bottom of the ramp. Where the extension creates a hazard, the termination of the extension shall be rounded or returned smoothly to floor, wall or post. (See Figure 11A-5A).*

1114A.6.2.4 Handrail projections. *Handrails projecting from a wall shall have a space of 1½ inches (38.1 mm) between the wall and the handrail. Handrails shall not reduce the required minimum clear width of ramps. Handrails may be located in a recess if the recess is a maximum of 3 inches (76.2 mm) deep and extends at least 18 inches (457 mm) above the top of the rail. Any wall or other surface adjacent to the handrail shall be free of sharp or abrasive elements. (See Figure 11A-6B).*

1114A.6.2.5 Handrail grips. *The handgrip portion of handrails shall not be less than 1¼ inches (31.75 mm) nor more than 2 inches (50.8 mm) in cross-sectional dimension or the shape shall provide an equivalent gripping surface. The handgrip portion of handrails shall have a smooth surface with no*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

sharp corners. Edges shall have a minimum radius of 1/8 inch (3.17 mm). Handrails shall not rotate within their fittings. (See Figure 11A-6B).

Note: For public use areas, public accommodations, and housing which is publicly funded, see Chapter 11B, Division III, Section 1133B.5.5 for provisions of the Division of the State Architect—Access Compliance (DSA-AC).

1114A.7 Curbs and wheel guides. Ramps exceeding 10 feet (3048 mm) in length and ramp landings having a vertical drop exceeding 4 inches (101.6 mm), shall be provided with one of the following:

1. Guide curbs a minimum of 2 inches (50.8 mm) in height at each side; or
2. Wheel guide rails at each side, centered 2 to 4 inches (50.8 to 101.6 mm) above the surface of the ramp or ramp landing.

Exception: Ramps or ramp landings bounded by a wall or fence.

Note: See Figure 11A-5A.

SECTION 1115A EXTERIOR STAIRWAYS

1115A.1 General. Exterior stairways serving buildings on a site containing covered multifamily dwelling units shall comply with this section.

1115A.2 Open risers. Open risers are not permitted on exterior stairways.

Exceptions:

1. An opening of not more than ½ inch (12.7 mm) may be permitted between the base of the rise and the tread.
2. Risers constructed of grating containing openings of not more than ½ inch (12.7 mm) may be permitted.

1115A.3 Treads. All tread surfaces shall be slip resistant. Treads shall have smooth, rounded or chamfered exposed edges, and no abrupt edges at the nosing (lower front edge).

1115A.4 Nosing. Nosing shall not project more than 1¼ inches (31.8 mm) past the face of the riser below. Risers shall be sloped or the underside of the nosing shall have an angle not more than 30 degrees (0.52 rad) from the vertical. (See Figure 11A-6A).

1115A.5 Striping for the visually impaired. Exterior stairs serving buildings on a site containing multifamily dwelling units shall have the upper approach and all treads marked by a stripe providing clear visual contrast.

The stripe shall be a minimum of 2 inches (50.8 mm) wide to a maximum of 4 inches (101.6 mm) wide placed parallel to, and not more than 1 inch (25.4 mm) from, the nose of the step or upper approach. The stripe shall extend the full width of the step or upper approach and shall be of material that is at least as slip resistant as the other treads of the stair. A painted stripe shall be acceptable.

1115A.6 Exterior stairway handrails.

1115A.6.1 Where required. Stairways shall have handrails on each side. Intermediate handrails shall be located equidistant from the sides of the stairway and comply with Section 1012.9.

Exception: Stairways serving an individual dwelling unit may have one handrail, except that stairways open on one or both sides shall have handrails on the open side or sides.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1115A.6.2 Handrail configuration.

1115A.6.2.1 Handrail heights. The top of handrails shall be 34 to 38 inches (864 to 965 mm) above the nosing of the treads.

1115A.6.2.2 Handrail ends. Ends shall be returned or shall terminate in newel posts or safety terminals.

1115A.6.2.3 Handrail extension. Handrails shall extend a minimum of 12 inches (305 mm) beyond the top nosing and 12 inches (305 mm), plus the tread width, beyond the bottom nosing.

Where the extension creates a hazard, the termination of the extension shall be rounded or returned smoothly to floor, wall or post. Where the stairs are continuous from landing to landing, the inner rail shall be continuous and need not extend out into the landing. (See Figures 11A-6A and 11A-6E).

1115A.6.2.4 Handrail projections. Handrails projecting from a wall shall have a space of 1½ inches (38.1 mm) between the wall and the handrail.

Handrails may be located in a recess if the recess is a maximum of 3 inches (76.2 mm) deep and extends at least 18 inches (457 mm) above the top of the rail. Any wall or other surface adjacent to the handrail shall be free of sharp or abrasive elements. (See Figure 11A-6B).

1115A.6.2.5 Handrail grips. The handgrip portion of handrails shall not be less than 1¼ inches (31.75 mm) nor more than 2 inches (50.8 mm) in cross-sectional dimension or the shape shall provide an equivalent gripping surface. The handgrip portion of handrails shall have a smooth surface with no sharp corners. Edges shall have a minimum radius of 1/8 inch (3.17 mm). Handrails shall not rotate within their fittings. (See Figure 11A-6B).

Note: For public use areas, public accommodations, and housing which is publicly funded, see Chapter 11B, Division III, Section 1133B.4.2.6 for provisions of the Division of the State Architect—Access Compliance (DSA-AC).

SECTION 1116A HAZARDS ON ACCESSIBLE ROUTES

1116A.1 Warning curbs. Abrupt changes in level exceeding 4 inches (101.6 mm) in vertical dimension, such as changes in level at planters or fountains located in or adjacent to walks, sidewalks or other pedestrian ways shall be identified by curbs or other approved barriers projecting at least 6 inches (152.4 mm) in height above the walk or sidewalk surface to warn the blind of a potential drop-off.

Exceptions:

1. Between a walk or sidewalk and an adjacent street or driveway.
2. When a guardrail or handrail is provided with a wheel guide centered 2 to 4 inches (50.8 to 101.6 mm) above the surface of the walk or sidewalk.

1116A.2 Headroom clearance. Walks, pedestrian ways and other circulation spaces which are part of the required egress system shall have minimum clear headroom of 84 inches (2134 mm). Other walks, pedestrian ways and circulation spaces shall have minimum clear headroom of 80 inches (2032 mm). If the vertical clearance of an area adjoining an accessible route is reduced to less than 80 inches (2032 mm) nominal dimension, a guardrail or other barrier having its leading edge at or below 27 inches (686 mm) above the finished floor shall be provided. (See Figure 11A-1B.)

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Exception: Doorways and archways less than 24 inches (610 mm) in depth may have minimum clear headroom of 80 inches (2032 mm) nominal. (See Section 1126A.)

1116A.3 Overhanging obstructions. Any obstruction that overhangs a pedestrian way shall be a minimum of 80 inches (2032 mm) above the walking surface as measured from the bottom of the obstruction. Where a guy support is used parallel to a path of travel, including, but not limited to, sidewalks, a guy brace, sidewalk guy or similar device shall be used to prevent an overhanging obstruction (see Section 1116A.2 for required headroom clearance).

1116A.4 Free-standing signs. Wherever signs mounted on posts or pylons protrude from the post or pylons and the bottom edge of the sign is less than 80 inches (2032 mm) above the finished floor or ground level, the edges of such signs shall be rounded or eased and the corners shall have a minimum radius of 0.125 inches (see Section 1116A.2 for required headroom clearance).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Division III — BUILDING FEATURES

Division III Table of Contents

Section 1117A	<i>General Requirements for Accessible Entrances, Exits, Interior Routes of Travel and Facility Accessibility</i>
Section 1118A	<i>Egress and Areas for Evacuation Assistance</i>
Section 1119A	<i>Interior Routes of Travel</i>
Section 1120A	<i>Interior Accessible Routes</i>
Section 1121A	<i>Changes in Level on Accessible Routes</i>
Section 1122A	<i>Interior Ramps and Landings on Accessible Routes</i>
Section 1123A	<i>Interior Stairways</i>
Section 1124A	<i>Elevators and Platform (Wheelchair) Lifts</i>
Section 1125A	<i>Hazards on Accessible Routes</i>
Section 1126A	<i>Doors</i>
Section 1127A	<i>Common Use Facilities</i>

SECTION 1117A GENERAL REQUIREMENTS FOR ACCESSIBLE ENTRANCES, EXITS, INTERIOR ROUTES OF TRAVEL AND FACILITY ACCESSIBILITY

Note: *In addition to provisions of this division, interior routes of travel that provide access to, or egress from, buildings for persons with disabilities shall also comply with Chapter 10.*

1117A.1 General. *When buildings are required to be accessible, building facilities shall be accessible as provided in this division. Where specific floors of a building are required to be accessible, the requirements of this division shall apply only to the facilities located on accessible floors.*

1117A.2 Primary entrances and exterior exit doors. *All primary entrances and exterior ground floor exit doors to buildings and facilities on accessible routes shall be accessible to persons with disabilities.*

1117A.3 Separate dwelling unit entrances. *When a ground-floor dwelling unit of a building has a separate entrance, each such ground-floor dwelling unit shall be served by an accessible route, except where the terrain or unusual characteristics of the site prohibit an accessible route (see Section 1150A for site impracticality tests).*

1117A.4 Multiple entrances. *Only one entrance to covered multifamily buildings is required to be accessible to any one ground floor of a building, except in cases where an individual dwelling unit has a separate exterior entrance. Where the building contains clusters of dwelling units with each cluster sharing a different exterior entrance, more than one entrance may be required to be accessible, as determined by analysis of the site. In every case, the accessible entrance shall be on an accessible route to the covered dwelling units it serves.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1118A EGRESS AND AREAS OF REFUGE

1118A.1 General. Including but not limited to the requirements contained in this chapter for accessible routes, signage and emergency warning systems in buildings or portions of buildings required to be accessible shall be provided with accessible means of egress as required by Chapter 10. (See Section 1007.)

SECTION 1119A INTERIOR ROUTES OF TRAVEL

1119A.1 General. When a building or portion of a building is required to be accessible or adaptable, an accessible route shall be provided to all portions of the building, accessible building entrances and to covered multifamily dwelling units. The accessible route shall, to the maximum extent feasible, coincide with the route for the general public and other building residents. Accessible routes shall not pass through kitchens, storage rooms, restrooms, closets or other spaces used for similar purposes except within an individual dwelling unit.

Accessible routes shall be provided as follows:

1. Where more than one route of travel is provided, all routes shall be accessible.
2. At least one accessible route shall connect accessible building or facility entrances with all accessible spaces, elements and covered multifamily dwelling units.
3. An accessible route shall connect at least one accessible primary entrance of each covered multifamily dwelling unit with interior and exterior spaces and facilities that serve the unit.
4. Where elevators are provided for vertical access, all elevators shall be accessible.

1119A.2 Flooring. If carpet or carpet tile is used in a common use area or public use area on a ground or floor surface, it shall have firm backing or no backing. The maximum pile height shall be ½ inch (12.7 mm). Exposed edges of carpet shall be fastened to floor surfaces and have trim along the entire length of the exposed edge. Carpet edge trim shall comply with Section 1111A requirements for changes in level.

1119A.2.1 Recessed doormats. Recessed doormats shall be adequately anchored to prevent interference with wheelchair traffic.

SECTION 1120A INTERIOR ACCESSIBLE ROUTES

Note: For the purpose of this section, interior accessible routes shall include but not be limited to corridors, hallways, exit balconies and covered or enclosed walkways.

1120A.1 Widths. Interior accessible routes serving an occupant load of 10 or more shall not be less than 44 inches (1118 mm) in width. Interior accessible routes serving an occupant load of less than 10 shall not be less than 36 inches (914 mm) in width.

If a person in a wheelchair must make a turn around a corner or an obstruction, the minimum clear width of the accessible route shall be as shown in Figure 11A-1C.

1120A.2 Interior accessible routes over 200 feet (60960 mm). Interior accessible routes that exceed 200 feet (60960 mm) in length shall:

1. Have a minimum clear width of 60 inches (1524 mm); or

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. Have at a central location a 60-inch by 60-inch (1524 mm by 1524 mm) minimum wheelchair turning space or passing alcove; or
3. Have at a central location an intervening cross or tee that is a minimum of 44 inches (1118 mm) in width.

Note: See Figure 11A-1L.

1120A.3 Changes in elevation. Interior accessible routes which have changes in elevation shall be transitioned and comply with Section 1121A or 1122A.

Exception: Doors and thresholds as provided in Section 1126A.

SECTION 1121A CHANGES IN LEVEL ON ACCESSIBLE ROUTES

1121A.1 Changes in level not exceeding 1/2 inch. Abrupt changes in level along any accessible route shall not exceed 1/2 inch (12.7 mm). When changes in level do occur, they shall be beveled with a slope no greater than 1 unit vertical in 2 units horizontal (50-percent slope). Changes in level not exceeding 1/4 inch (6.35 mm) may be vertical.

1121A.2 Changes greater than 1/2 inch. Changes in level greater than 1/2 inch (12.7 mm) shall be made by means of a sloped surface not greater than 1 unit vertical in 20 units horizontal (5-percent slope), or a curb ramp, ramp, elevator or platform (wheelchair) lift. When stairs are located along or adjacent to an accessible route they shall comply with Section 1123A for interior stairways.

SECTION 1122A INTERIOR RAMPS AND LANDINGS ON ACCESSIBLE ROUTES

1122A.1 Width. The width of ramps shall be consistent with the requirements for exits in Chapter 10 of this code, but in no case shall the ramp width be less than the following:

1. Ramps serving accessible entrances to covered multifamily buildings where the ramp is the only exit discharge path and serves an occupant load of 300 or more shall have a minimum clear width of 60 inches (1524 mm).
2. Ramps serving accessible entrances to covered multifamily dwellings with an occupant load of 10 or less may be 36 inches (914 mm) in clear width.
3. All other ramps shall have a minimum clear width of 48 inches (1219 mm).
4. Handrails, curbs, wheel guides and/or appurtenances shall not project into the required clear width of a ramp.

Note: See Section 1122A.5.2.4 for handrail projections.

1122A.2 Slope. The maximum slope of ramps on an accessible route shall be no greater than 1 unit vertical in 12 units horizontal (8.33-percent slope).

1122A.2.1 Cross slope. The cross slope of ramp surfaces shall not exceed 1/4 inch (6.35 mm) per foot (2.083-percent slope).

1122A.3 Landings. Ramp landings shall be level and comply with this section.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1122A.3.1 Location of landings. Landings shall be provided at the top and bottom of each ramp. Intermediate landings shall be provided at intervals not exceeding 30 inches (762 mm) of vertical rise and at each change of direction. Landings are not considered in determining the maximum horizontal distance of each ramp.

Note: Examples of ramp dimensions are:

SLOPE (GRADING %)	MAXIMUM RISE (Inches)	MAXIMUM HORIZONTAL PROJECTION (Feet)
	(x 25.4 for mm)	(x 304.8) for mm)
1:12 (8.33%)	30	30
1:15 (6.67%)	30	37.5
1:16 (6.25%)	30	40
1:20 (5.00%)	30	50

1122A.3.2 Size of top landings. Top landings shall not be less than 60 inches (1524 mm) wide. Top landings shall have a minimum length of not less than 60 inches (1524 mm) in the direction of the ramp run. See Section 1126A.3 for maneuvering clearances at doors. (See Figure 11A-6C).

1122A.3.3 Landing width. The minimum width of bottom and intermediate landings shall not be less than the width of the ramp.

1122A.3.4 Encroachment of doors. Doors in any position shall not reduce the minimum dimension of the landing to less than 42 inches (1067 mm) and shall not reduce the required width by more than 3 inches (76.2 mm) when fully open. (See Figure 11A-6D).

1122A.3.5 Strike edge extension. The width of the landing shall comply with Section 1126A.3 for maneuvering clearances at doors.

1122A.3.6 Change of direction. Intermediate and bottom landings at a change of direction in excess of 30 degrees shall have a length in the direction of ramp run of not less than 72 inches (1829 mm). (See Figures 11A-6C and 11A-6D).

1122A.3.7 Other intermediate landings. Other intermediate landings shall have a dimension in the direction of ramp run of not less than 60 inches (1524 mm). (See Figure 11A-6C).

1122A.4 Ramp height. Ramps more than 30 inches (762 mm) above the adjacent floor or ground and open on one or both sides shall be provided with a guard as required by Section 1013. Guardrails shall be continuous from the top of the ramp to the bottom of the ramp.

1122A.5 Ramp handrails.

1122A.5.1 Where required. Handrails shall be provided at each side of ramps when the slope exceeds 1 unit vertical in 20 units horizontal (5-percent slope). Handrails on all ramps shall be continuous.

Exceptions:

1. Curb ramps.
2. Ramps that serve an individual dwelling unit may have one handrail, except that ramps open on one or both sides shall have handrails provided on the open side or sides.

1122A.5.2 Handrail configuration.

1122A.5.2.1 Handrail heights. The top of handrails shall be 34 to 38 inches (864 to 965 mm) above the ramp surface.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1122A.5.2.2 Handrail ends. Handrail ends shall be returned.

1122A.5.2.3 Handrail extension. Handrails shall extend a minimum of 12 inches (305 mm) beyond the top and bottom of the ramp. Where the extension creates a hazard, the termination of the extension shall be rounded or returned smoothly to floor, wall or post. (See Figure 11A-5A).

1122A.5.2.4 Handrail projections. Handrails projecting from a wall shall have a space of 1½ inches (38.1 mm) between the wall and the handrail. Handrails may be located in a recess if the recess is a maximum of 3 inches (76.2 mm) deep and extends at least 18 inches (457 mm) above the top of the rail. Any wall or other surface adjacent to the handrail shall be free of sharp or abrasive elements. (See Figure 11A-6B).

1122A.5.2.5 Handrail grips. The handgrip portion of handrails shall not be less than 1¼ inches (31.75 mm) nor more than 2 inches (50.8 mm) in cross-sectional dimension or the shape shall provide an equivalent gripping surface. The handgrip portion of handrails shall have a smooth surface with no sharp corners. Edges shall have a minimum radius of ⅛ inch (3.17 mm). Handrails shall not rotate within their fittings. (See Figure 11A-6B).

Note: For public use areas, public accommodations, and housing which is publicly funded, see Chapter 11B, Division III, Section 1133B.5.5 for provisions of the Division of the State Architect—Access Compliance (DSA-AC).

1122A.6 Curbs and wheel guides. Ramps exceeding 10 feet (3048 mm) in length, and ramp landings having a vertical drop exceeding 4 inches, shall be provided with one of the following:

1. Guide curbs a minimum of 2 inches (50.8 mm) in height at each side; or
2. Wheel guide rails at each side, centered 2 to 4 inches (50.8 to 101.6 mm) above the surface of the ramp or ramp landing.

Exception: Ramps or ramp landings bounded by a wall or fence.

Note: See Figure 11A-5A.

SECTION 1123A INTERIOR STAIRWAYS

1123A.1 General. Interior stairways serving buildings containing covered multifamily dwelling units shall comply with this section.

1123A.2 Open risers. Open risers shall not be permitted on interior stairways.

Exception: Stairways within an individual dwelling unit.

1123A.3 Treads. All tread surfaces shall be slip resistant. Treads shall have smooth, rounded or chamfered exposed edges and no abrupt edges at the nosing (lower front edge).

1123A.4 Nosing. Nosing shall not project more than 1¼ inches (31.8 mm) past the face of the riser below. Risers shall be sloped or the underside of the nosing shall have an angle not more than 30 degrees (0.52 rad) from the vertical. (See Figure 11A-6A)

1123A.5 Striping for the visually impaired. Interior stairs shall have the upper approach and lower tread marked by a stripe providing clear visual contrast.

Exception: Stairways within an individual dwelling unit.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

The stripe shall be a minimum of 2 inches (50.8 mm) wide to a maximum of 4 inches (101.6 mm) wide placed parallel to, and not more than 1 inch (25.4 mm) from, the nose of the step or upper approach. The stripe shall extend the full width of the step or upper approach and shall be of material that is at least as slip resistant as the other treads of the stair. A painted stripe shall be acceptable.

1123A.6 Interior stairway handrails.

1123A.6.1 Where required. Stairways shall have handrails on each side. Intermediate handrails shall be located equidistant from the sides of the stairway and comply with Section 1012.9.

Exception: Stairways serving an individual dwelling unit may have one handrail, except that stairways open on one or both sides shall have handrails on the open side or sides.

1123A.6.2 Handrail configuration.

1123A.6.2.1 Handrail heights. The top of handrails shall be 34 to 38 inches (864 to 965 mm) above the nosing of the treads.

1123A.6.2.2 Handrail ends. Ends shall be returned or shall terminate in newel posts or safety terminals.

1123A.6.2.3 Handrail extension. Handrails shall extend a minimum of 12 inches (305 mm) beyond the top nosing and 12 inches (305 mm), plus the tread width, beyond the bottom nosing. Where the extension creates a hazard, the termination of the extension shall be rounded or returned smoothly to floor, wall or post. Where the stairs are continuous from landing to landing, the inner rail shall be continuous and need not extend out into the landing. (See Figures 11A-6A and 11A-6E).

Exception: Stairways within an individual dwelling unit.

1123A.6.2.4 Handrail projections. Handrails projecting from a wall shall have a space of 1½ inches (38.1 mm) between the wall and the handrail.

Handrails may be located in a recess if the recess is a maximum of 3 inches (76.2 mm) deep and extends at least 18 inches (457 mm) above the top of the rail. Any wall or other surface adjacent to the handrail shall be free of sharp or abrasive elements. (See Figure 11A-6B).

1123A.6.2.5 Handrail grips. The handgrip portion of handrails shall not be less than 1¼ inches (31.75 mm) nor more than 2 inches (50.8 mm) in cross-sectional dimension or the shape shall provide an equivalent gripping surface. The handgrip portion of handrails shall have a smooth surface with no sharp corners. Edge shall have a minimum radius of 1/8 inch (3.17 mm). Handrails shall not rotate within their fittings. (See Figure 11A-6B).

Note: For public use areas, public accommodations, and housing which is publicly funded, see Chapter 11B, Division III, Section 1133B.4.2.6 for provisions of the Division of the State Architect—Access Compliance (DSA-AC).

SECTION 1124A ELEVATORS AND PLATFORM (WHEELCHAIR) LIFTS

1124A.1 General. Elevators provided in covered multifamily buildings shall be accessible. Elevators required to be accessible shall comply with this chapter, ASME A17.1, Safety Code for elevators and Escalators, Title 8, of the California Code of Regulations, under “Elevator Safety Orders,” and any other applicable safety regulations of other administrative authorities having jurisdiction.

Exception: Private elevators serving only one dwelling unit.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1124A.2 Location. *Passenger elevators shall be located on a major accessible route and provisions shall be made to ensure that they remain accessible and usable at all times that the building is occupied.*

1124A.3 Size of cab and control locations.

1124A.3.1 General. *Elevators serving covered multifamily buildings shall be sized to accommodate a wheelchair in accordance with this section.*

Exception: *When the enforcing agency determines that compliance with any requirement of this section would create an unreasonable hardship, an exception to the requirement shall be granted when equivalent facilitation is provided, and where it can be demonstrated that a person using a wheelchair can enter and operate the elevator.*

1124A.3.2 Car inside. *The car inside shall allow for the turning of a wheelchair. The minimum clear distance between walls or between wall and door, excluding return panels, shall not be less than 80 inches by 54 inches (2032 mm by 1372 mm) for center-opening doors, and 68 inches by 54 inches (1727 mm by 1372 mm) for side-slide opening doors. (See Figure 11A-7A). Minimum distance from wall to return panel shall not be less than 51 inches (1295 mm).*

1124A.3.2.1 Door size. *Elevator doors shall provide a minimum clear width of 36 inches (914 mm).*

1124A.3.3 Car controls.

1124A.3.3.1 Car control location. *Elevator floor buttons shall be within 54 inches (1372 mm) above the finish floor for side approach and 48 inches (1219 mm) for front approach. Except for photoelectric tube bypass switches, emergency controls, including the emergency stop and alarm, shall be grouped in or adjacent to the bottom of the panel and shall be no lower than 35 inches (889 mm) from the floor.*

For multiple controls only, one set must comply with these height requirements. Floor buttons shall be provided with visual indicators to show when each call is registered. The visual indicators shall be extinguished when each call is answered.

Note: *Where possible, a 48-inch (1219 mm) maximum height for elevator floor buttons is preferred.*

1124A.3.3.2 Car control buttons. *Passenger elevator car controls shall have a minimum dimension of $\frac{3}{4}$ inch (19.1 mm) and shall be raised $\frac{1}{8}$ inch (3.2 mm) plus or minus $\frac{1}{32}$ inch (0.8 mm) above the surrounding surface.*

Control buttons shall be illuminated, shall have square shoulders and shall be activated by a mechanical motion that is detectable.

All control buttons shall be designated by a 5/8-inch-minimum (15.9 mm) raised characters and standard raised symbols that comply with Section 1143A.8 and 1143A.9 immediately to the left of the control button. Contracted Grade 2 Braille that conforms to Section 1143A.9 shall be located immediately below the numeral, character or symbol. A minimum clear space of 3/8 inch (9.5 mm) or other suitable means of separation shall be provided between rows of control buttons. (See Figure 11A-7B).

The raised characters and symbols shall be white on a black background. Controls and emergency equipment identified by raised symbols shall include, but not be limited to, "door open", "door close", "alarm bell", "emergency stop" and "telephone." The call button for the main entry floor shall be designated by a raised star at the left of the floor designation.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1124A.3.4 Emergency telephone. The emergency telephone handset shall be positioned no higher than 48 inches (1219 mm) above the floor, and the handset cord shall be a minimum of 29 inches (737 mm) in length. If the telephone system is located in a closed compartment, the compartment door hardware shall be a lever type conforming to the provisions of Section 1126A.6.1. Emergency intercommunication shall not require voice communication.

1124A.4 Hall call buttons. Call operation buttons shall be centered 42 inches (1067 mm) above the floor. Buttons shall be a minimum of ¼ -inch (19.1 mm) in size and shall be raised 1/8-inch (3.2 mm) plus or minus 1/32-inch (0.8 mm) above the surrounding surface. The button designating the “Up” direction shall be on top.

Visual indication shall be provided to show each call registered and extinguished when answered. Objects adjacent to, and below, hall call buttons shall not project more than 4 inches (101.6 mm) from the wall. Hall call buttons shall be internally illuminated with a white light over the entire surface of the button.

1124A.5 Minimum illumination. The minimum illumination at the car controls threshold and the landing when the car and landing doors are open shall not be less than 5 foot-candles (54 lx).

1124A.6 Hall lantern. A visual and audible signal shall be provided at each hoistway entrance indicating to the prospective passenger the car answering the call and its direction of travel as follows:

1. The visual signal for each direction shall be a minimum of 2 1/2 inches (63.5 mm) high by 2 1/2 inches (63.5 mm) wide, and visible from the proximity of the hall call button.
2. The audible signal shall sound once for the “up” direction and twice for the “down” direction or of a configuration which distinguishes between up and down elevator travel.
3. The center line of the fixture shall be located a minimum of 6 feet (1829 mm) in height from the lobby floor.
4. The use of in-car lanterns, located in or on the car doorjamb, visible from the proximity of the hall call buttons and conforming to the above requirements of this section shall or will be acceptable.

Note: The use of arrow shapes are preferred for visible signals.

1124A.7 Door delay.

1124A.7.1 Hall call. The minimum acceptable time from notification that a car is answering a call (lantern and audible signal) until the doors of the car start to close shall be calculated by the following equations but shall be no less than 5 seconds.

$$T = D / (1.5 \text{ ft/s}) \text{ or } T = D / (445 \text{ mm/s})$$

Where T is the total time in seconds and D is the distance from a point in the lobby or landing area 60 inches (1524 mm) directly in front of the farthest call button controlling that car to the centerline of its hoistway door (see Figure 11A-7D). For cars with in-car lanterns, T begins when the lantern is visible from the vicinity of hall call buttons and an audible signal is sounded.

1124A.7.2 Door delay for car calls. The minimum acceptable time for the door to remain fully open after receiving a call shall not be less than 5 seconds.

1124A.8 Doorjamb marking. All elevator hoistway entrances shall have raised floor number designations provided on both jambs. Characters shall be raised Arabic numerals a minimum of 2 inches (50.8 mm) in height with raised Braille symbols placed below the corresponding raised characters. The raised characters shall be on a contrasting background with the centerline of the characters 60 inches (1524 mm) from the floor. Braille symbols shall conform to Sections 1117B.5.5 and 1117B.5.6. On the grade level, a raised five-pointed star shall be placed to the left of the raised character. The outside diameter of the star shall be 2 inches (50.8 mm). Braille shall be placed below the corresponding raised characters (see Figure 11A-7C).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1124A.9 Door protective and reopening devices. Doors closed by automatic means shall be provided with a door-reopening device that will function to stop and reopen a car door and adjacent hoistway door in case the car door is obstructed while closing.

This reopening device shall also be capable of sensing an object or person in the path of a closing door without requiring contact for activation at a nominal 5 inches and 29 inches (127 mm and 737 mm) above the floor.

Door-reopening devices shall remain effective for a period of not less than 20 seconds. After such an interval, the doors may close in accordance with the requirements of ANSI 17.1-86 and the American Society of Mechanical Engineers (ASME) document ASME 17.1-1990.

1124A.10 Operation and leveling. The elevator shall be automatic and be provided with a self-leveling feature that will automatically bring the car to the floor landings within a tolerance of plus or minus ½ inch (12.7 mm) under rated loading to zero loading conditions. This self-leveling shall, within its zone, be entirely automatic and independent of the operating device and shall correct the overtravel or undertravel. The car shall also be maintained approximately level with the landing, irrespective of load.

The clearance between the car platform sill and the edge of the hoistway landing shall be no greater than ¼ inches (31.75 mm).

1124A.11 Platform (wheelchair) lifts. Platform (wheelchair) lifts may be provided between levels, in lieu of passenger elevators, when the vertical distance between landings, as well as the structural design and safeguards are as allowed by ASME A18.1, Safety Standard for Platform Lifts and Stairway Chair Lifts, the State of California, the Department of Industrial Relations, Division of Occupational Safety and Health and any applicable safety regulations of other administrative authorities having jurisdiction.

If lifts are provided, they shall be designed and constructed to facilitate unassisted entry, operation and exit from the lift, and shall comply with restrictions and enhancements of this section in conjunction with Title 8 of the California Code of Regulations.

SECTION 1125A HAZARDS ON ACCESSIBLE ROUTES

1125A.1 Warning curbs. Abrupt changes in level exceeding 4 inches (101.6 mm) in vertical dimension, such as changes in level at planters or fountains located in or adjacent to walks, halls, corridors, passageways, aisles, pedestrian ways and other circulation spaces shall be identified by curbs projecting at least 6 inches (152.4 mm) in height above the walk or sidewalk surface to warn the blind of a potential drop-off.

Exception: When a guardrail or handrail is provided with a wheel guide centered 2 to 4 inches (50.8 to 101.6 mm) above the surface of the walk or sidewalk.

1125A.2 Headroom clearance. Walks, halls, corridors, passageways, aisles, pedestrian ways and other circulation spaces which are part of the required egress system shall have a minimum clear headroom of 84 inches (2134 mm). Other walks, pedestrian ways and circulation spaces shall have a minimum clear headroom of 80 inches (2032 mm). If the vertical clearance of an area adjoining an accessible route is reduced to less than 80 inches (2032 mm) nominal dimension, a guardrail or other barrier having its leading edge at or below 27 inches (686 mm) above the finished floor shall be provided. (See Figure 11A-1B).

Exception: Doorways and archways less than 24 inches (610 mm) in depth may have a minimum clear headroom of 80 inches (2032 mm) nominal. (See Section 1126A).

1125A.3 Overhanging obstructions. Any obstruction that overhangs a pedestrian way shall be a minimum of 80 inches (2032 mm) above the walking surface as measured from the bottom of the obstruction. Where a guy support is used parallel to a path of travel, including, but not limited to, sidewalks, a guy brace, sidewalk guy or similar device shall be used to prevent an overhanging obstruction (see Section 1125A.2 for required headroom clearance).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1125A.4 Free-standing signs. *Wherever signs mounted on posts or pylons protrude from the posts or pylons and the bottom edge of the sign is less than 80 inches (2032 mm) above the finished floor or ground level, the edges of such signs shall be rounded or eased and the corners shall have a minimum radius of 0.125 inches. (See Section 1125A.2 for required headroom clearance).*

SECTION 1126A DOORS

1126A.1 Width and height of doors. *Doorways which provide access to common use areas or covered multifamily dwellings shall comply with the following:*

1. *Permit the installation of a door not less than 36 inches (914 mm) in width, not less than 80 inches (2032 mm) in height and provide a clear width of not less than 32 inches (813 mm), measured with the door positioned at an angle of 90 degrees from its closed position.*
2. *Be capable of opening at least 90 degrees.*
3. *A pair of doors, manual or automatic, must have at least one leaf which provides a clear width of not less than 32 inches (813 mm), measured with the door positioned at an angle of 90 degrees from its closed position.*
4. *The width of any component in the egress system shall not be less than the minimum width required by Section 1005.*

Revolving doors shall not be used as required entrances for persons with disabilities.

1126A.2 Level floor or landing. *The floor or landing on each side of an exit door shall be level. (See Chapter 10).*

1126A.2.1 Thresholds and changes in elevation at doors. *The floor or landing shall not be more than ½ inch (12.7 mm) lower than the top of the threshold of the doorway. (See Figure 11A-8I).*

Changes in level between ¼ inch (6.35 mm) and ½ inch (12.7 mm) shall be beveled with a slope no greater than 1 unit vertical in 2 units horizontal (50% slope). Changes in level greater than ½ inch (12.7 mm) shall be accomplished by means of a ramp (see Section 1122A).

1126A.3 Maneuvering clearances at doors.

1126A.3.1 General. *The level floor or landing of an exit door shall have a length in the direction of the door swing of at least 60 inches (1524 mm) and a length opposite the direction of the door swing of at least 44 inches (1118 mm) measured at right angles to the plane of the door in its closed position. (See Figures 11A-8D, 11A-8E and 11A-8F for maneuvering spaces at sliding doors).*

1126A.3.2 Strike edge maneuvering space. *The width of the level area on the side to which the door swings shall extend at least 24 inches (610 mm) past the strike edge of the door for exterior doors and at least 18 inches (457 mm) past the strike edge for interior doors.*

Note: *Twenty-four inches (610 mm) is preferred for strike-side clearance.*

1126A.3.2.1 Front approach. *The following provisions shall apply to swinging doors with front approach:*

1. *For pull side approach, the level floor or landing shall extend in the direction of the door swing at least 60 inches (1524 mm). (See Figure 11A-8A).*
2. *For push side approach, the level floor or landing shall extend opposite the direction of the door swing at least 48 inches (1219 mm). (See Figure 11A-8A).*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. *Doors with push side approach having both a closer and a latch shall be provided with a clear and level area extending a minimum of 12 inches (305 mm) past the strike edge on the approach side of the door. (See Figure 11A-8A).*

1126A.3.2.2 Hinge side approach. *The following provisions shall apply to swinging doors with hinge side approach:*

1. *Doors with pull side approach shall be provided with a level floor or landing not less than 60 inches (1524 mm) in depth. A clear and level area shall extend a minimum of 36 inches (914 mm) past the strike edge on the approach side of the door. (See Figure 11A-8B).*

Exception: *Doors with pull side approach and a level floor or landing greater than 60 inches (1524 mm) in depth shall be provided with a clear and level area at least 24 inches (610 mm) past the strike edge of the door for exterior doors and at least 18 inches (457 mm) past the strike edge for interior doors.*

2. *Doors with push side approach shall have a level floor or landing not less than 44 inches (1118 mm) in depth, and shall be provided with a clear and level area extending a minimum of 54 inches (1372 mm) from the strike edge of the door jamb past the hinge side of the door. Doors with a latch and closer shall have a level floor or landing not less than 48 inches (1219 mm) depth at the push side of the door. (See Figure 11A-8B).*

1126A.3.2.3 Latch side approach. *The following provisions shall apply to swinging doors with latch side approach:*

1. *Doors with pull side approach shall have a level floor or landing not less than 60 inches (1524 mm) in depth, and shall be provided with a clear and level area extending a minimum of 24 inches (610 mm) past the strike edge on the approach side of the door. (See Figure 11A-8C).*

Exception: *Doors serving individual covered multifamily dwelling units shall have a minimum landing depth of 44 inches (1118 mm) except that doors with a closer shall have a minimum landing depth of 54 inches (1372 mm).*

2. *Doors with push side approach shall have a level floor or landing not less than 44 inches (1118 mm) in depth, and shall be provided with a clear and level area extending a minimum of 24 inches (610 mm) past the strike edge on the approach side of the door. Doors with a closer shall have a level floor or landing not less than 48 inches (1219 mm) depth at the push side of the door. (See Figure 11A-8C).*

1126A.3.3 Space between consecutive doors. *The minimum space between two hinged or pivoted doors in series, serving other than a required exit stairway, shall provide a minimum of 48 inches (1219 mm) plus the width of the door swinging into the space. Doors in a series shall swing either in the same direction or away from the space between the doors. (See Figure 11A-8G, and 11A-8H).*

Where the door opens into a stair or smokeproof enclosure, the landing need not have a minimum length of 60 inches (1524 mm). (See Figure 11A-8H).

1126A.4 Closer-effort to operate doors. *Maximum effort to operate doors shall not exceed 8½ pounds (38 N) for exterior doors and 5 pounds (22 N) for interior doors, such pull or push effort being applied at right angles to hinged doors and at the center plane of sliding or folding doors. Compensating devices or automatic door operators may be utilized to meet these standards.*

When fire doors are required, the maximum effort to operate the door may be increased to the minimum allowable by the appropriate enforcement agency, not to exceed 15 pounds (66.7 N).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1126A.4.1 Door closer. *If the door has a closer, then the sweep period of the closer shall be adjusted so that from an open position of 70 degrees, the door will take at least 3 seconds to move to a point 3 inches (75 mm) from the latch, measured to the landing edge of the door.*

1126A.5 Type of lock or latch. *The type of latch and lock required for all doors shall be in accordance with Chapter 10, Section 1008.*

1126A.6 Hand-activated door hardware. *Hand-activated door latching, locking and opening hardware shall be centered between 30 inches (762 mm) and 44 inches (1118 mm) above the floor. Latching and locking doors that are hand-activated and on an accessible route shall be operable with a single effort by lever type hardware, panic bars, push-pull activating bars or other hardware designed to provide passage without requiring the ability to grasp the opening hardware. Locked exit doors shall operate consistent with Section 1126A.4, in the direction of egress.*

1126A.6.1 Lever type hardware. *The lever or lever of actuated latches or locks shall be curved with a return to within ½ inch (12.7 mm) of the door to prevent catching on the clothing of persons during egress.*

Exception: *Group R and U occupancies with an occupant load of 10 or less.*

1126A.7 Smooth surface. *The bottom 10 inches (254 mm) of all doors and/or gates shall have a smooth, uninterrupted surface to allow the door or gate to be opened by a wheelchair footrest without creating a trap or hazardous condition. Where narrow frame doors are used, a 10-inch high (254 mm) smooth panel shall be installed on the push side of the door, which will allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition.*

Exception: *Automatic and sliding doors or gates.*

SECTION 1127A COMMON USE FACILITIES

Note: *For public use facilities, see Chapter 11B of this code.*

1127A.1 General. *When provided, common use areas and facilities in covered multifamily housing developments shall be accessible to persons with disabilities. Common use facilities include, but are not limited to, lobbies, toilet and bathing facilities, laundry facilities, community rooms, clubhouses, health and fitness facilities, game rooms and portions of common use tenant storage. All entrances, doors, fixtures and controls shall be on an accessible route. Facilities and fixtures required to be accessible shall comply with the following provisions:*

- 1. Doors.** *Doors to accessible bathrooms shall comply with Section 1126A. Doors shall not swing into the floor space required for any fixture.*
- 2. Clear Floor Space.** *All fixtures and controls shall be on an accessible route. Clear floor spaces at fixtures and controls, the accessible route and the turning space may overlap. This clear space shall comply with Sections 1127A.9.4 and 1127A.9.5.*
- 3. Water Closets.** *Where a toilet stall is provided, it shall comply with Section 1127A.2.1 or 1127A.2.2, and its water closet shall comply with Section 1127A.2.3.*
- 4. Lavatory and Mirrors.** *Where a lavatory and/or mirror is provided, it shall comply with Sections 1127A.3 and/or 1127A.8.3.*
- 5. Controls and Dispensers.** *Where controls, dispensers, receptacles or other types of equipment are provided, at least one of each shall be on an accessible route and shall comply with Sections 1127A. 8 and 1127A.9.5.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

6. **Bathing and Shower Facilities.** Where bathtubs or showers are provided, at least one fixture of each type provided shall be accessible per room. For bathtubs, see Section 1127A.5.2. For showers, see Section 1127A.5.3.
7. **Toilet Facilities.** Toilet facilities shall comply with Section 1127A.2.
8. **Laundry Facilities.** Laundry facilities shall comply with Section 1127A.10.
9. **Storage Facilities.** Storage facilities shall comply with Section 1127A.11.
10. **Fixed or Built-in Seating, Tables and Counters.** Fixed or built-in seating, tables and counters shall comply with Section 1127A.12.

1127A.2 Toilet facilities. When common use toilet facilities are provided for residents or guests, at least one percent of the total number of fixtures but not less than one of each type shall comply with this section.

1127A.2.1 Multiple-accommodation toilet facilities. Multiple-accommodation toilet facilities shall have the following:

Notes:

1. See definition in Chapter 2.
2. See Figure 11A-9A.
1. **Wheelchair Clearance.** A clear space measured from the floor to a height of 27 inches (686 mm) above the floor, within the sanitary facility room, of sufficient size to inscribe a circle with a diameter not less than 60 inches (1524 mm), or a clear space 56 inches by 63 inches (1422 mm by 1600 mm) in size. Other than the door to the accessible water closet compartment, a door, in any position, may encroach into this space by not more than 12 inches (305 mm).
2. **Clear Space at Fixtures.** Doors shall not swing into the floor space required for any fixture.
3. **Accessible Water Closet Compartment.** A water closet fixture located in a compartment shall provide a minimum 28-inch-wide (711 mm) clear space from a fixture, or a minimum 32-inch-wide (813 mm) clear space from a wall at one side of the water closet. The other side of the water closet shall provide 18 inches (457 mm) from the centerline of the water closet to the wall. The stall shall be a minimum of 60 inches (1524 mm) wide. A minimum 48-inch-long (1219 mm) clear space shall be provided in front of the water closet if the compartment has an end-opening door (facing the water closet). A minimum 60-inch-long (1524 mm) clear space shall be provided in a compartment with the door located at the side.
4. **Grab Bars.** Grab bars shall be installed in accordance with Section 1127A.4 and shall not project more than 3 inches (76.2 mm) into the clear spaces.
5. **Compartment Doors.** Compartment doors shall comply with the following:
 - 5.1. The water closet compartment shall be equipped with a door that has an automatic-closing device, and shall have a clear, unobstructed opening width of 32 inches (813 mm) when located at the end and 34 inches (864 mm) when located at the side with the door positioned at an angle of 90 degrees from its closed position.
 - 5.2. When standard compartment doors are used, with a minimum 9-inch (228.6 mm) clearance for footrests underneath and a self-closing device, clearance at the strike edge as specified in Section 1126A.3.2 is not required.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

5.3. *The inside and outside of the compartment door shall be equipped with a loop or U-shaped handle immediately below the latch. The latch shall be flip-over style, sliding or other hardware not requiring the user to grasp or twist.*

5.4. *Except for door-opening widths and door swings, a clear, unobstructed access of not less than 44 inches (1118 mm) shall be provided to water closet compartments designed for use by persons with disabilities, and the space immediately in front of a water closet compartment shall not be less than 48 inches (1219 mm) as measured at right angles to compartment door in its closed position.*

6. Large Toilet Rooms. *Where six or more stalls are provided within a multiple-accommodation toilet room, at least one stall shall comply with Section 1127A.2.1, Items 2 and 3. At least one additional stall shall be 36 inches (914 mm) wide with an outward swinging self-closing door and grab bars complying with Sections 1127A.4.3, 1127A.4.4 and 1127A.4.5 installed on each compartment side wall.*

1127A.2.2 Single-accommodation toilet facilities. *Single-accommodation toilet facilities shall comply with the following:*

- 1. Wheelchair Clearance.** *There shall be sufficient space in the toilet room for a wheelchair measuring 30 inches (762 mm) wide by 48 inches (1219 mm) long to enter the room and permit the door to close. There shall be in the room a clear floor space of at least 60 inches (1524 mm) in diameter, or a T-shaped space complying with Figure 11A-1D.*
- 2. Encroachment of Doors.** *Doors shall not encroach into the clear floor space specified in Item 1 of this section by more than 12 inches (305 mm), except for the panel door to any water closet compartment. (See Figure 11A-9B).*
- 3. Accessible Water Closet.** *The water closet shall be located in a space which provides a minimum 28-inch-wide (711 mm) clear space from a fixture or a minimum 32-inch-wide (813 mm) clear space from a wall at one side. The other side shall provide 18 inches (457 mm) from the centerline of the water closet to the wall. A minimum 48 inches (1219 mm) of clear space shall be provided in front of the water closet.*
- 4. Grab Bars.** *Grab bars shall be installed in accordance with Section 1127A.4.*
- 5. Accessible Route.** *All doors, fixtures and controls shall be on an accessible route. The minimum clear width of an accessible route shall be 36 inches (914 mm) except at doors (See Section 1126A). If a person in a wheelchair must make a turn around an obstruction, the minimum clear width of the accessible route shall be as shown in Figure 11A-1C. (See also Figure 11A-9B).*

1127A.2.3 Water closets. *Water closets required to be accessible shall comply with the following:*

- 1. Height.** *The height of accessible water closets shall be a minimum of 17 inches (432 mm) to a maximum of 19 inches (483 mm) measured to the top of a maximum 2-inch-high (50.8 mm) toilet seat.*
- 2. Controls.** *Controls shall be operable with one hand and shall not require tight grasping, pinching or twisting. Controls for the flush valves shall be mounted on the wide side of toilet areas, no more than 44 inches (1118 mm) above the floor. The force required to activate controls shall be no greater than 5 pound-force (lbf) (22.2 N).*
- 3. Toilet Seats.** *Seats shall not be sprung to return to a lifted position.*

1127A.2.4 Accessible urinals. *Urinals required to be accessible shall comply with the following:*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1. **Height and Wall Projection.** Urinals shall be floor mounted or wall hung. Where one or more wall-hung urinals are provided, at least one with a rim projecting a minimum of 14 inches (356 mm) to a maximum of 17 inches (432 mm) from the wall and a maximum of 17 inches (432 mm) above the floor shall be provided.
2. **Flush Controls.** Flush controls shall be operable with one hand, shall not require tight grasping, pinching or twisting of the wrist and shall be mounted no more than 44 inches (1118 mm) above the floor. The force required to activate controls shall be no greater than 5 pound-force (lbf) (22.2 N). Electronic automatic flushing controls are acceptable and preferable.
3. **Clear Floor Space.** Where urinals are provided, at least one shall have a clear floor space 30 inches by 48 inches (762 mm by 1219 mm) in front of the urinal to allow forward approach. This clear space shall comply with Sections 1127A.9.4 and 1127A.5.

1127A.3 Accessible lavatories. When common use lavatories are provided for residents or guests, at least one, and not less than 1 percent of all lavatories, shall comply with the following:

1. **Location.** Lavatories shall be installed with the centerline of the fixture a minimum of 18 inches (457 mm) horizontally from an adjoining wall or fixture. The top of the fixture rim shall be a maximum of 34 inches (864 mm) above the finished floor.
2. **Floor space.** A clear maneuvering space at least 30 inches by 48 inches (762 mm by 1219 mm) shall be provided in front of accessible lavatories to allow forward approach. Such clear floor space shall adjoin or overlap an accessible route and shall not extend into the knee and toe space underneath the lavatory more than 19 inches (483 mm). This clear space shall comply with Section 1127A.9.5 for allowable reach ranges.
3. **Knee and Toe Space.** Knee and toe space (see Figure 11A-9D) shall be provided as follows:
 - 3.1. The knee space shall be at least 30 inches (762 mm) wide and 8 inches deep (203.2 mm).
 - 3.2. The knee space shall be at least 29 inches (737 mm) high at the front face and reducing to not less than 27 inches (686 mm) at a point 8 inches (203.2 mm) back from the front edge.
 - 3.3. Knee space required by this section shall be clear and unobstructed.
 - 3.4. The toe space required in this section shall be provided as follows.
 - 3.4.1. Shall be at least 30 inches (762 mm) wide and centered on the lavatory.
 - 3.4.2. Shall be at least 17 inches (432 mm) deep, measured from the front edge.
 - 3.4.3. Shall be at least 9 inches (228.6 mm) high from the floor.
4. **Finished Floor.** The finished floor beneath the lavatory shall be extended to the wall.
5. **Plumbing Protection.** Hot water and drain pipes accessible under lavatories shall be insulated or otherwise covered. There shall be no sharp or abrasive surfaces under lavatories.
6. **Lavatory Faucet Controls.** Faucet controls and operation mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist.

The force required to activate controls shall be no greater than 5 pound-force (lbf) (22.2N). Lever operated, push type and electronically controlled mechanisms are examples of acceptable designs. Self-closing valves are allowed if the faucet remains open for at least 10 seconds.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1127A.4 Grab bars, tub and shower seats, fasteners and mounting devices.

1127A.4.1 General. Grab bars, tub and shower seats, fasteners and mounting devices required by this chapter shall comply with this section.

1127A.4.2 Location. Grab bars which are located on each side, or on one side and the back, of the accessible toilet stall or compartment shall be securely attached and centered 33 inches (838 mm) above and parallel to the floor, except that, where a tank-type toilet obstructs placement at 33 inches (838 mm), the grab bar may be centered as high as 36 inches (914 mm). The space between the grab bar and objects below shall be a minimum of 11/2 inches (38.1 mm). Grab bars shall be at least 42 inches (1067 mm) in length with the front end positioned 24 inches (610 mm) in front of the water closet stool. Grab bars at the back shall not be less than 36 inches (914 mm) in length. (See Figures 11A-9A and 11A-9B)

1127A.4.3 Diameter or width. The diameter or width of the gripping surfaces of a grab bar shall be 11/4 inches to 11/2 inches (31.75 mm to 38.1 mm) or of a shape that provides an equivalent gripping surface. If grab bars are mounted adjacent to a wall, the space between the wall and the grab bars shall be 1 1/2 inches (38.1 mm). (See Figure 11A-9C).

1127A.4.4 Structural strength. The structural strength of grab bars, tub and shower seats, fasteners, and mounting devices shall meet the following specifications:

1. Bending stress in a grab bar or seat induced by the maximum bending moment from the application of a 250-pound (1112 N) point load shall be less than the allowable stress for the material of the grab bar or seat.
2. Shear stress induced in a grab bar or seat by the application of a 250-pound (1112N) point load shall be less than the allowable shear stress for the material of the grab bar or seat, and if its mounting bracket or other support is considered to be fully restrained, then direct and torsional shear stresses shall not exceed the allowable shear stress.
3. Shear force induced in a fastener or mounting device from the application of a 250-pound (1112 N) point load shall be less than the allowable lateral load of either the fastener or mounting device or the supporting structure, whichever is the smaller allowable load.
4. Tensile force induced in a fastener by a direct tension force of a 250-pound (1112 N) point load, plus the maximum moment from the application of a 250-pound (1112 N) point load, shall be less than the allowable withdrawal load between the fastener and supporting structure.
5. Grab bars shall not rotate within their fittings.

1127A.4.5 Surface. A grab bar and any wall or other surface adjacent to it shall be free of any sharp or abrasive elements. Edges shall have a minimum radius of 1/8 inch (3.17 mm).

1127A.5 Bathing facilities.

1127A.5.1 General. When common use bathing facilities are provided for residents or guests, including showers, bathtubs or lockers, at least one of each type of fixture in each facility, and not less than 1 percent of all fixtures, shall comply with this section.

1127A.5.2 Bathtubs. Bathtubs required to be accessible shall comply with the following:

1. **Floor Space.** Clear floor space at bathtubs shall be as shown in Figure 11A-9E.
2. **Seat.** An in-tub seat or a seat at the head end of the tub shall be provided as shown in Figures 11A-9E and 11A-9F. The structural strength of seats and their attachments shall comply with Section 1127A.4.4. Seats shall be mounted securely and shall not slip during use.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. **Grab Bars.** *Grab bars complying with Sections 1127A.4.3, 1127A.4.4 and 1127A.4.5 shall be provided as shown in Figures 11A-9F and 11A-9G.*
4. **Controls.** *Faucets and other controls shall be located as shown in Figure 11A-9F. They shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist. The force required to activate controls shall be no greater than a 5 pound force (lbf) (22.2 N).*
5. **Shower Spray Unit.** *A shower spray unit with a hose at least 60 inches (1524 mm) long that can be used both as a fixed shower head and as a hand-held shower shall be provided.*
6. **Bathtub Enclosures.** *If provided, enclosures for bathtubs shall not obstruct controls or transfer from wheelchairs onto bathtub seats or into tubs. Enclosures on bathtubs shall not have tracks mounted on their rims.*

1127A.5.3 Showers. Showers required to be accessible shall comply with the following:

1. **Size.** *Showers shall be consistent with one of the following: (1) 60 inches (1524 mm) minimum in width between wall surfaces and 30 inches (762 mm) minimum in depth with a full opening width on the long side; or (2) 42 inches (1067 mm) in width between wall surfaces and 48 inches (1219 mm) minimum in depth with an entrance opening of 42 inches (1067 mm); or (3) showers 60 inches (1524 mm) minimum in width may be 36 inches (914 mm) minimum in depth as long as the entrance opening width is a minimum 36 inches (914 mm).*
2. **Thresholds.** *When a threshold or recessed drop is permitted, it shall be a maximum of ½ inch (12.7 mm) in height and shall be beveled or sloped at an angle not exceeding 45 degrees (100 percent gradient) from the horizontal.*
3. **Multiple Showers.** *Where, within the same functional area, two or more accessible showers are provided, there shall be at least one shower constructed opposite hand from the other or others (i.e., one left-hand control versus right-hand controls).*
4. **Accessories.** *Shower accessories shall include:*
 - 4.1. **Water Controls.** *Water controls of a single-lever design shall be located on the side wall of the compartment adjacent to the seat and operable with a maximum force of 5 pounds (22.2 N), mounted at 40 inches (1016 mm) [plus or minus 1 inch (25.4 mm) tolerance] above the shower floor. The centerline of the controls shall be within a reach range of no less than 18 inches (457 mm) and no more than 24 inches (610 mm) from the rear edge of the seat.*
 - 4.2. **Hand-held Sprayer Unit.** *A flexible hand-held sprayer unit with a hose at least 60 inches (1524 mm) long shall be provided within reach range of the seat at a distance not to exceed 27 inches (686 mm) horizontally measured from the rear seat edge to the centerline of the mounting bracket. This unit shall be mounted at a maximum height of 48 inches (1219 mm) [plus or minus 1 inch (25.4 mm) tolerance] above the shower floor.*
 - 4.3. **Sprayer Unit Alternative.** *Where accessible shower facilities are provided in areas subject to excessive vandalism, in lieu of providing the fixed flexible hose, two wall-mounted shower heads shall be installed. Each shower head shall be installed so that it can be operated independently of the other and shall have swivel angle adjustments, both vertically and horizontally. One shower head shall be located at a height of 48 inches (1219 mm) [plus or minus 1 inch (25.4 mm) tolerance] above the floor.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

- 4.4. Floor Slope.** *The maximum slope of the floor shall be 2 percent per foot in any direction. Where drains are provided, grate openings shall be a maximum of 1/4 inch (6.35 mm) and located flush with the floor surface.*
- 5. Shower Fixtures.** *Shower fixtures shall include:*
- 5.1.** *A folding seat located within 27 inches (686 mm) of the controls, mounted 18 inches (457 mm) above the floor and with a minimum space of 1 inch (25.4 mm) and maximum space of 1½ inches (38.1 mm) allowed between the edge of the seat and any wall. When folded, the seat shall not extend more than 6 inches (152.4 mm) from the mounting wall. (See Figures 11A-9H, 11A-9I, 11A-9J and 11A-9K).*
 - 5.2.** *Grab bars located on walls adjacent to and opposite the seat. Grab bars shall comply with the diameter, loading and projection requirements of Sections 1127A.4.3, 1127A.4.4 and 1127A.4.5. Grab bars shall be mounted between a minimum of 33 inches (838 mm) and a maximum of 36 inches (914 mm) above the shower floor with an L-shaped grab bar mounted on walls opposite and adjacent to the front edge of the seat, but not extended to include that portion of wall over the seat. (See Figure 11A-9H or 11A-9I).*
- 6. Soap Dish.** *When a soap dish is provided, it shall be located on the control wall at a maximum height of 40 inches (1016 mm) above the shower floor, and within reach limits from the seat.*
- 7. Enclosures.** *Enclosures, when provided for shower stalls, shall not obstruct transfer from wheelchairs onto shower seats.*

Note: See Figures 11A-9H, 11A-9I, 11A-9J and 11A-9K.

1127A.5.3.1 Open showers. *Where no separate shower compartments are provided, the shower for persons with disabilities shall be located in a corner with L-shaped grab bars extending along two adjacent walls with a folding seat adjacent to the shower controls. (See Figures 11A-9H, 11A-9I, 11A-9J and 11A-9K).*

1127A.6 Lockers.

1127A.6.1 General. *Where lockers are provided for residents or guests, at least one locker and not less than 1 percent of all lockers shall be accessible to persons with disabilities. A path of travel not less than 36 inches (914 mm) in clear width shall be provided to these lockers. See Section 1127A.9 for required clear space, allowable reach ranges and requirements for control and operating mechanisms.*

1127A.7 Signs.

1127A.7.1 General. *All accessible toilet and bathing facilities shall be identified by the “International Symbol of Accessibility.” Signs need not be provided for facilities within a dwelling unit or guestroom.*

1127A.7.2 Identification symbols. *Doorways leading to sanitary facilities shall be identified by a geometric symbol in compliance with this section. Geometric symbols shall be centered horizontally on the door at a height of 60 inches (1524 mm) above the finish floor of ground surface measured to the center of the symbol. Edges of accessibility signage shall be rounded, chamfered or eased. Corners shall have a minimum radius of 1/8 inch (3.2 mm). See Section 1143A.10, item 1, for additional signage requirements applicable to sanitary facilities.*

1127A.7.2.1 Men’s sanitary facilities. *Men’s sanitary facilities shall be identified by an equilateral triangle, ¼ inch (6.4 mm) thick with edges 12 inches (305 mm) long and a vertex pointing upward. The triangle symbol shall contrast with the door, either light on a dark background or dark on a light background.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1127A.7.2.2 Women’s sanitary facilities. Women’s sanitary facilities shall be identified by a circle, ¼ inch (6.4 mm) thick and 12 inches (305 mm) in diameter. The circle symbol shall contrast with the door, either light on a dark background or dark on a light background.

1127A.7.2.3 Unisex sanitary facilities. Unisex sanitary facilities shall be identified by a circle, ¼ inch (6.4 mm) thick and 12 inches (305 mm) in diameter with a ¼ inch (6.4 mm) thick triangle superimposed on the circle and within the 12-inch (305 mm) diameter. The triangle symbol shall contrast with the circle symbol, either light on a dark background or dark on a light background. The circle symbol shall contrast with the door, either light on a dark background or dark on a light background.

1127A.8 Toilet room fixtures and accessories.

1127A.8.1 Towel, sanitary napkins, waste receptacles. Where towel, sanitary napkins, waste receptacles and other similar dispensing and disposal fixtures are provided, at least one of each type shall be located with all operable parts, including coin slots, within 40 inches (1016 mm) from the finished floor. Controls and operating mechanisms shall comply with Section 1127A.9.6.4.

1127A.8.2 Toilet tissue dispensers. Toilet tissue dispensers shall be located on the wall within 12 inches (305 mm) of the front edge of the toilet seat. Dispensers that control delivery or that do not permit continuous paper flow shall not be used. (See Figure 11A-9B).

1127A.8.3 Mirrors. Where mirrors are provided, at least one shall be accessible. Mirrors shall be mounted with the bottom edge no higher than 40 inches (1016 mm) from the floor.

1127A.9 Space allowances and reach ranges in common use areas.

1127A.9.1 Wheelchair passage width. The minimum clear width for single wheelchair passage shall be 36 inches (914 mm) continuously. (See Figure 11A-1E).

Exception: Thirty-two inches (813 mm) in width is acceptable at a point not to exceed 24 inches (610 mm) in length.

1127A.9.2 Width for wheelchair passing. The minimum width for two wheelchairs to pass is 60 inches (1524 mm) (see Figure 11A-1F).

1127A.9.3 Wheelchair turning space. The space required for a wheelchair to make a 180-degree turn is a clear space of 60 inches (1524 mm) diameter (See Figure 11A-1D(a) or a T-shaped space, see Figure 11A-1D(b)).

1127A.9.4 Clear floor or ground space for wheelchairs.

1127A.9.4.1 Size and approach. The minimum clear floor or ground space required to accommodate a single, stationary wheelchair and occupant is 30 inches by 48 inches (762 mm by 1219 mm). (See Figure 11A-1G.) The minimum clear floor or ground space for wheelchairs may be positioned for forward or parallel approach to an object (See Figure 11A-1G). Clear floor or ground space for wheelchairs may be part of the knee space required under some objects.

1127A.9.4.2 Relationship of maneuvering clearances to wheelchair spaces. One full unobstructed side of the clear floor or ground space for a wheelchair shall adjoin or overlap an accessible route or adjoin another wheelchair clear floor space. If a clear floor space is located in an alcove or otherwise confined on all or a part of three sides, additional maneuvering clearances shall be provided as shown in Figure 11A-1H.

1127A.9.4.3 Surfaces of wheelchair spaces. Clear floor or ground spaces for wheelchairs shall comply with Sections 1119A.2, 1120A.3 and 1121A.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1127A.9.4.3.1 Gratings. Gratings located in ground and floor surfaces along accessible routes shall be limited to spaces no greater than ½-inch (12.7 mm) wide in one direction. If gratings have elongated openings, they shall be placed so that the long dimension is perpendicular to the dominant direction of traffic.

1127A.9.5 Reach ranges.

1127A.9.5.1 Forward reach. If the clear floor space allows only forward approach to an object, the maximum high forward reach allowed shall be 48 inches (1219 mm) and the minimum low forward reach shall be unobstructed and no less than 15 inches (381 mm) above the floor (see Figure 11A-1I(a)). If the high forward reach is over an obstruction, reach and clearances shall be as shown in Figure 11A-1I(b).

1127A.9.5.2 Side reach. If the clear floor space allows parallel approach by a person in a wheelchair, the maximum high side reach allowed shall be 54 inches (1372 mm) and the low side reach shall be no less than 9 inches (228.6 mm) above the floor (see Figure 11A-1J(a) and 11A-1J(b)). If the side reach is over an obstruction, the reach and clearances shall be as shown in Figure 11A-1J(c).

1127A.9.6 Controls and operating mechanisms.

Note: See also Section 1142A, for electrical installation.

1127A.9.6.1 General. Controls and operating mechanisms in accessible spaces, along accessible routes or as part of accessible elements (e.g., light switches and dispenser controls) shall comply with this section.

1127A.9.6.2 Clear floor space. Clear floor space complying with Section 1127A.9.4 that allows a forward or parallel approach by a person using a wheelchair shall be provided at controls, dispensers, receptacles and other operable equipment.

1127A.9.6.3 Height. Controls shall be located no higher than 48 inches (1219 mm), and no lower than 15 inches (381 mm), above the finished floor measured to the center of the grip. If the reach is over an obstruction (for example, washer or dryer) between 20 and 25 inches (508 and 635 mm) in depth, the maximum height is reduced to 44 inches (1118 mm) for forward approach, or 46 inches (1168 mm) for side approach, provided the obstruction is no more than 24 inches (610 mm) in depth. Controls that do not satisfy these specifications are acceptable, provided that comparable controls or outlets, that perform the same functions, are provided within the same area and are accessible.

1127A.9.6.4 Operation. Controls and operating mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist.

The force required to activate controls shall be no greater than 5 pounds (22.2 N) of force.

1127A.10 Common accessible laundry rooms.

1127A.10.1 General. Where common use laundry rooms are provided, at least one of each type of appliance provided in each laundry area shall be accessible, shall be on an accessible route and shall comply with this section. Such appliances include clothes washing machines, dryers, soap dispensers and any related features such as wash sinks, tables and storage areas.

Where laundry rooms are provided on floors of an elevator building, each laundry room shall be accessible. Where there is one laundry room on a ground floor in each building, each laundry room shall be accessible. Where there is a laundry room on the ground floor of a building and another located in the basement, it is acceptable to have only the ground floor laundry room accessible.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1127A.10.2 Clear floor space. There shall be a minimum clear space 30 inches perpendicular by 48 inches parallel (762mm by 1219 mm) in front of clothes washers and dryers required to be accessible. There shall be a minimum clear space 30 inches by 48 inches (762 mm by 1219 mm) provided for at least one of each type of fixture or appliance provided in the laundry room (e.g., soap dispensers, wash sinks, tables, storage areas).

1127A.10.3 Controls. Clothes washers and dryers including stacked clothes washers and dryers required to be accessible shall have controls (including coin slots) within the reach range of a seated user. Controls shall be located no higher than 48 inches (1219 mm), and no lower than 15 inches (381 mm), above the finished floor measured to the center of the grip. If the reach is over an obstruction (for example, washer or dryer) between 20 and 25 inches (508 and 635 mm) in depth, the maximum height is reduced to 44 inches (1118 mm) for forward approach, or 46 inches (1168 mm) for side approach. Controls that do not satisfy these specifications are acceptable, provided that comparable controls or outlets, that perform the same functions, are provided within the same area and are accessible. Controls shall be operable with one hand and not require tight grasping, pinching or twisting of the wrist.

1127A.10.4 Washing machines and clothes dryer. Washing machines and clothes dryers in accessible common use laundry rooms shall be front loading.

1127A.11 Storage.

1127A.11.1 General. If fixed storage facilities such as cabinets, shelves, closets or drawers are provided where access is required by Sections 1.8.2.1.2 and 1102A, at least one of each type of facility provided shall comply with this section. Additional storage may be provided outside of the reach ranges shown in Figure 11A-1J.

1127A.11.2 Clear floor space. A clear floor space at least 30 inches by 48 inches (762 mm by 1219 mm) complying with Section 1127A.9.4 that allows either a forward or parallel approach by a person using a wheelchair shall be provided at accessible storage facilities.

1127A.11.3 Height. Accessible storage spaces shall be within at least one of the reach ranges specified in Section 1127A.9.5. Clothes rods shall be a maximum of 54 inches (1372 mm) from the floor for a side approach (see Figure 11A-1J). Where the distance from the wheelchair to the clothes rod or shelf exceeds 10 inches (254 mm), as in closets without accessible doors, the height and depth to the rod or shelf shall comply with Figure 11A-1J.

1127A.11.4 Hardware. Hardware for accessible storage facilities shall comply with Section 1127A.9.6. Touch latches and U-shaped pulls are acceptable.

1127A.12 Fixed or built-in seating, tables and counters

1127A.12.1 Minimum seating. Where fixed or built-in seating, tables or counters are provided for residents or guests, 5 percent, but not less than one, shall be accessible as provided in this section.

1127A.12.2 Seating. When seating spaces for persons in wheelchairs are provided at fixed tables or counters, clear floor space complying with Section 1127A.9.4 shall be provided. Such clear floor space shall not overlap knee space by more than 19 inches (483 mm). (See Figure 11A-1K).

1127A.12.3 Knee clearance. When seating for persons in wheelchairs is provided at fixed tables or counters, knee spaces at least 27 inches (686 mm) high, 30 inches (762 mm) wide and 19 inches (483 mm) deep shall be provided. (See Figure 11A-1K).

1127A.12.4 Height of work surfaces. The tops of tables and counters shall be 28 inches to 34 inches (711mm to 864 mm) from the floor or ground.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Division IV – DWELLING UNIT FEATURES

Division IV Table of Contents

Section 1128A Covered Dwelling Units

Section 1129A Reserved

Section 1130A Accessible Route Within Covered Multifamily Dwelling Units

Section 1131A Changes in Level on Accessible Routes

Section 1132A Doors

Section 1133A Kitchens

Section 1134A Bathing and Toilet Facilities

Section 1135A Laundry Rooms

Section 1136A Electrical Receptacle, Switch and Control Heights

SECTION 1128A COVERED DWELLING UNITS

1128A.1 General. Covered multifamily dwelling units shall be adaptable and accessible into and throughout the dwelling unit as provided in this division.

Note: See Sections 1101A “Application” and 1102A “Building Accessibility” for dwelling units required to comply with this division.

SECTION 1129A Reserved

SECTION 1130A ACCESSIBLE ROUTE WITHIN COVERED MULTIFAMILY DWELLING UNITS

1130A.1 General. An accessible route shall be provided through all rooms and spaces of the dwelling unit. The accessible route shall pass through the primary entry door, and shall connect with all additional exterior doors, required clear floor spaces at kitchen appliances and bathroom fixtures. For the purpose of this section, “accessible routes” may include hallways, corridors and ramps.

Exception: An accessible route is not required from the interior of the unit into a basement or garage, except as provided in Section 1105A.1.

1130A.2 Width. The accessible route into and throughout covered multifamily dwelling units shall be at least 36 inches (914 mm) wide.

SECTION 1131A CHANGES IN LEVEL ON ACCESSIBLE ROUTES

1131A.1 Changes in level not exceeding 1/2 inch. Abrupt changes in level along any accessible route shall not exceed 1/2 inch (12.7 mm). When changes in level do occur, they shall be beveled with a slope no greater than 1 unit vertical in 2 units horizontal (50-percent slope). Changes in level not exceeding 1/4 inch (6.35 mm) may be vertical.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1131A.2 Changes greater than 1/2 inch. Changes in level greater than 1/2 inch (12.7 mm) shall be made by means of a ramp, elevator or platform (wheelchair) lift. See Section 1122A for ramps and Section 1124A.11 for platform (wheelchair) lifts.

SECTION 1132A DOORS

1132A.1 Primary entry doors and required exit doors. The primary entry door and all required exit doors shall comply with the requirements of this section. The requirements of Sections 1126A.3 shall apply to maneuvering clearances at the side of the door exposed to common or public use spaces (e.g. entry or exit doors which open from the covered multifamily dwelling unit into a corridor, hallway or lobby, or directly to the outside).

1132A.2 Interior doors and secondary exterior doors. Except as allowed by Section 1109A.2, doors intended for user passage and secondary exterior doors shall comply with this section. The provisions of this section shall apply to the dwelling unit side of doors leading from the interior of the dwelling unit to an unfinished basement or an attached garage.

1132A.3 Width and height of doors. Doors shall comply with the following:

1. Doors shall not be less than 6 feet 8 inches (2032 mm) in height.
2. Swinging doors shall provide a net clear opening width of not less than 32 inches (813 mm), measured with the door or doors positioned at an angle of 90 degrees from the closed position. A 34-inch (864 mm) door is acceptable. The primary entry door and all required exit doors shall comply with the requirements of Section 1126A.1.
3. Swinging doors shall be capable of opening at least 90 degrees.
4. A nominal 32-inch (813 mm) clear opening provided by a standard 6-foot wide (1829 mm) sliding patio door assembly is acceptable.
5. A pair of doors, manual or automatic, must have at least one leaf which provides a clear width of not less than 32 inches (813 mm), measured with the door positioned at an angle of 90 degrees from its closed position.
6. The width of any component in the means of egress system shall not be less than the minimum width required by Section 1005.

1132A.4 Level floor or landing. See also Chapter 10. The floor or landing on each side of a door shall be level. Primary entry doors, required exit doors or secondary exterior doors with changes in height between the interior surface or floor level and the exterior surface or floor level shall comply with the following:

1. Exterior landings of impervious construction (e.g., concrete, brick, flagstone) serving primary entry doors and required exit doors are limited to not more than 1/2 inch (12.7 mm) of change in height between floor surfaces. Changes in level shall comply with Section 1131A.
2. Exterior landings of pervious construction (e.g., wood decking with spaces) shall be the same level as the interior landing, except that secondary exterior doors may have no more than 1/2 inch (12.7 mm) of change in height between floor surfaces. Changes in level shall comply with Section 1131A.
3. Secondary exterior doors onto decks, patios or balcony surfaces constructed of impervious materials (e.g., concrete, brick, flagstone) may have a maximum change in height from the interior landing of 4 inches (101.6 mm). Changes in height greater than 1/2 inch (12.7 mm) shall be accomplished by means of a ramp complying with Section 1114A or by means of a platform constructed to the level of the floor as illustrated in Figure 11A-8J.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4. Secondary exterior doors onto decks, patios or balcony surfaces constructed of impervious materials (e.g. concrete, brick, flagstone) may have a maximum change in height from the interior landing of 1 inch (25.4 mm), provided a ramp with a maximum slope of 1:8 is permanently installed. (See Figure 11A-8K).
5. In buildings containing covered multifamily dwelling units, the floor or landing immediately outside the entry may be sloped up to 1/4 inch (6.35 mm) per foot (12 inches) (305 mm), in a direction away from the primary entrance of the dwelling unit for drainage.

1132A.4.1 Thresholds. Thresholds at the primary entry and required exit doors shall be no higher than 1/2 inch (12.7 mm). Thresholds at secondary exterior doors, including sliding door tracks, shall be no higher than 3/4 inch (19.05 mm). Changes in height at interior door thresholds (e.g., floor material changes at door thresholds) shall not exceed 1/2 inch (12.7 mm). Thresholds shall comply with the following:

1. Thresholds with a change in height of not more than 1/4 inch (6.35 mm) may be vertical.
2. Thresholds with a change in height between 1/4 inch (6.35 mm) and 3/4 inch (19.05 mm) shall be beveled with a slope no greater than 1 unit vertical in 2 units horizontal (50-percent slope).

1132A.5 Maneuvering clearances at doors.

1132A.5.1 General. Maneuvering clearances at interior doors shall provide a minimum length on both sides of the door of at least 42 inches (1067 mm) measured at a right angle to the plane of the door in its closed position.

Exceptions:

1. A 39-inch (991 mm) length is acceptable when a minimum clear opening width of 34 inches (864 mm) is provided.
2. The floor or landing on the dwelling unit side of the primary entry door and any required exit door shall have a minimum length of not less than 44 inches (1118 mm). Section 1126A.3 shall apply to maneuvering clearances at the side of the door exposed to common or public use spaces.

1132A.5.2 Strike edge maneuvering space at doors. The width of the level area on the side to which the door swings shall extend 18 inches (457 mm) past the strike edge for all doors. The width of the level area at the exterior side of the primary entry door and any required exit doors shall comply with Section 1126A.

Notes:

1. See Section 1134A for bathrooms that are required to be accessible.
2. Twenty-four inches (610 mm) is preferred for strike edge clearance.

1132A.6 Closer-effort to operate doors. Maximum effort to operate doors shall not exceed 8½ pounds (38 N) for exterior doors and 5 pounds (22 N) for interior doors, such pull or push effort being applied at right angles to hinged doors and at the center plane of sliding or folding doors. Compensating devices or automatic door operators may be utilized to meet these standards. When fire doors are required, the maximum effort to operate the door may be increased to the minimum allowable by the appropriate enforcement agency, not to exceed 15 pounds (66.7 N).

1132A.7 Type of lock or latch. The type of latch and lock required for all doors shall be in accordance with Chapter 10, Section 1008.

1132A.8 Hand-activated door hardware. Hand-activated door latching, locking and opening hardware shall be centered between 30 inches (762 mm) and 44 inches (1118 mm) above the floor. Latching and locking doors that are hand-activated and on an accessible route shall be operable with a single effort by lever-type hardware, panic bars, push-pull activating bars or other hardware designed to provide passage without requiring the ability to grasp the opening hardware. Locked exit doors shall operate consistent with Section 1132A.6, in the direction of egress.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1132A.8.1 Lever-type hardware. *The lever or lever of actuated latches or locks shall be curved with a return to within 1/2 inch (12.7 mm) of the door to prevent catching on the clothing of persons during egress in Group R and U occupancies with an occupant load greater than 10.*

1132A.9 Smooth surface. *The bottom 10 inches (254 mm) of all doors shall have a smooth, uninterrupted surface to allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition. Where narrow frame doors are used, a 10-inch-high (254 mm) smooth panel shall be installed on the push side of the door which will allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition.*

Exception: *Automatic and sliding doors.*

1132A.10 Door signal devices. *Every primary entrance to a covered multifamily dwelling unit shall be provided with a door buzzer, bell, chime or equivalent. The activating mechanism shall be mounted a maximum of 48 inches (1219 mm) above the floor and connected to permanent wiring.*

SECTION 1133A KITCHENS

1133A.1 General. *Kitchens shall be on an accessible route and shall comply with this section.*

1133A.2 Clear floor space. *Clear floor space at kitchens shall comply with the following:*

- 1. A clear floor space at least 30 inches (762 mm) by 48 inches (1219 mm) that allows a parallel approach by a person in a wheelchair shall be provided at the range or cooktop*
- 2. A clear floor space at least 30 inches (762 mm) by 48 inches (1219 mm) that allows either a parallel or forward approach shall be provided at the kitchen sink and all other fixtures or appliances including the oven, dishwasher, refrigerator/freezer and trash compactor*
- 3. The centerline of the 30-inch (762 mm) by 48-inch (1219 mm) clear floor space provided for parallel or forward approach shall be aligned with the centerline of the appliance or fixture. (See Figure 11A-10A).*

1133A.2.1 Clear width. *Kitchens shall have a minimum clear width measured between any cabinet, countertop or the face of any appliance (excluding handles and controls) that projects into the kitchen and the opposing cabinet, countertop, appliance or wall as follows:*

- 1. U-shaped kitchens, designed with parallel approach at a range or cooktop located at the base of the U, shall have a minimum clear width of at least 60 inches (1524 mm). (See Figure 11A-10A).*
- 2. U-shaped kitchens, designed with a cooktop or sink located at the base of the U which provides a 30-inch-wide (762 mm) knee space to a height of 27 inches (686 mm) above the floor to allow for a forward approach, shall have a clear width of at least 48 inches (1219 mm). (See Figure 11A-10A).*
- 3. All other kitchen designs shall provide a minimum clear width of at least 48 inches (1219 mm). (See Figure 11A-10A).*

1133A.3 Removable base cabinets. *Base cabinets directly under the kitchen sink counter area, including toeboard and shelving, shall be removable without the use of specialized tools or specialized knowledge in order to provide clearance for a wheelchair. The finish floor beneath the kitchen sink counter area shall be extended to the wall.*

1133A.4 Countertops. *Kitchen countertops shall comply with this section and shall be provided with the following (see Section 1133A.4.1 for repositionable countertop requirements)*

- 1. A minimum linear length of 30 inches (762 mm) of countertop shall be provided for the kitchen sink installation.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. A minimum linear length of 30 inches (762 mm) of countertop shall be provided for a work surface.
3. The sink and work surface may be a single integral unit a minimum of 60 inches (1524 mm) in length, or be separate components.

Exception: Two 15-inch (381 mm) minimum width breadboards may be provided in lieu of the required 30 inches (762 mm) of countertop work surface.

1133A.4.1 Repositionable countertops. *Repositionable countertops shall be provided in a minimum of 5 percent of the covered multifamily dwelling units. Repositionable countertops shall comply with the following:*

1. The kitchen sink and work surface space required by Section 1133A.4 shall be designed to enable repositioning to a minimum height of 28 inches (711 mm)
2. Base cabinets directly under the kitchen sink and work surface shall be removable to provide clearance for a wheelchair.
3. The sides of adjacent cabinets and the back wall, which may become exposed to moisture or food handling when a countertop is lowered, shall be constructed of durable, nonabsorbent materials appropriate for such uses.
4. Finished flooring shall be extended to the wall beneath the sink and work surface.

Exceptions:

1. Stone, cultured stone and tiled countertops may be used without meeting the repositioning requirements.
2. Two 15-inch (381 mm) minimum width breadboards may be provided in lieu of the required 30 inches (762 mm) of countertop work surface.

1133A.5 Lower shelving. *Lower shelving and/or drawer space shall be provided in the kitchen at a height of no more than 48 inches (1219 mm) above the floor.*

1133A.6 Kitchen sink faucet controls. *Faucet controls and operating mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist.*

The force required to activate controls shall be no greater than 5 pound force (22.2N). Lever-operated, push-type and electronically controlled mechanisms are examples of acceptable designs. Self-closing valves are allowed if the faucet remains open for at least 10 seconds.

SECTION 1134A BATHING AND TOILET FACILITIES

1134A.1 General. *All bathrooms, bathing and toilet facilities within covered multifamily dwelling units shall comply with this section.*

1134A.2 Number of complying bathrooms. *Bathrooms shall be designed to comply with one of the following options:*

Option 1. *All bathrooms within the dwelling unit shall be designed to comply with the following:*

1. Toilet, bathing and shower facilities shall comply with Section 1134A.4.
2. Bathtubs shall comply with Section 1134A.5.
3. Showers shall comply with Section 1134A.6.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4. *Water closets shall comply with Section 1134A.7.*
5. *Lavatories, vanities, mirrors and towel fixtures shall comply with Section 1134A.8.*
6. *Bathrooms shall be provided with an accessible route into and through the bathroom.*
7. *If a door is provided, it shall comply with the requirements of Section 1132A.5.*
8. *A minimum 18-inch (457 mm) clear maneuvering space shall be provided on the swing side of the door at the strike edge of the door.*
9. *Switches, outlets and controls shall comply with Section 1142A.*
10. *Reinforced walls to allow for the future installation of grab bars around the toilet, tub and shower shall comply with Sections 1134A.5 for bathtubs, 1134A.6 for showers and 1134A.7 for water closets. Grab bars shall comply with Section 1127A.4.*

Option 2. *Only one bathroom within the dwelling unit shall be designed to comply with the following:*

1. *Toilet, bathing and shower facilities shall comply with Section 1134A.4.*
2. *Bathtubs shall comply with Section 1134A.5.*
3. *Showers shall comply with Section 1134A.6.*
4. *Water closets shall comply with Section 1134A.7.*
5. *Lavatories, vanities, mirrors and towel fixtures shall comply with Section 1134A.8.*
6. *Where both a tub and shower are provided in the bathroom, at least one shall be made accessible. Additional requirements apply to dwelling units containing two or more bathrooms when a bathtub is provided as the accessible bathing fixture.*

Where two or more bathrooms are provided within the same dwelling unit and a bathtub is installed to comply with Option 2, item 6 in one bathroom and a shower stall is provided in a subsequent bathroom, both the bathtub selected to comply with Option 2, item 6 and at least one shower stall within the dwelling unit shall meet all the applicable accessibility requirements provided in Section 1134A. (See Section 1134A.5 for bathtubs, or Section 1134A.6 for showers.)

7. *When two or more lavatories are provided, at least one shall be made accessible and comply with Section 1134A.8.*
8. *Bathrooms shall be provided with an accessible route into and through the bathroom.*
9. *If a door is provided, it shall comply with the requirements of Section 1132A.5.*
10. *A minimum 18-inch (457 mm) clear maneuvering space shall be provided on the swing side of the door at the strike edge of the door.*
11. *Switches, outlets and controls shall comply with Section 1142A.*
12. *Reinforced walls to allow for the future installation of grab bars around the toilet, tub and shower shall comply with Sections 1134A.5 for bathtubs 1134A.6 for showers and 1134A.7 for water closets. Grab bars shall comply with Section 1127A.4.*

When Option 2 is used, all additional bathrooms must comply with Items 8 through 12 above.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1134A.3 Powder rooms. All powder rooms shall be designed to comply with Section 1134A.2, Option 2, Items 8 through 12. When the powder room is the only toilet facility located on an accessible level, it shall comply with the Option 2 Items listed above, plus all additional requirements located in Section 1134A.4, 1134A.7 and 1134A.8.4

1134A.4 Sufficient maneuvering space. Bathing and toilet facilities required to be adaptable shall provide sufficient maneuvering space for a person using a wheelchair or other mobility aid to enter and close the door, use the fixtures, reopen the door and exit.

Where the door swings into the bathroom or powder room, there shall be a clear maneuvering space outside the swing of the door of at least 30 inches by 48 inches (762 mm by 1219 mm) within the room. The clear maneuvering space shall allow the user to position a wheelchair or other mobility aid clear of the path of the door as it is closed and to permit use of fixtures.

Doors may swing into the required clear space at any fixture when a clear maneuvering space is provided outside the swing arc of the door so it can be closed.

Maneuvering spaces may include any knee space or toe space available below bathroom fixtures.

1134A.5 Bathtubs. Bathtubs required to be accessible shall comply with this section.

- 1. Floor Space.** There shall be a minimum clear floor space 48 inches parallel by 30 inches perpendicular (1219 mm by 762 mm) to the side of a bathtub or bathtub-shower combination (measured from the foot or drain end of the bathtub) to provide for the maneuvering of a wheelchair and transfer to and from the bathing facilities. The area under a lavatory may be included in the clear floor space provided the knee and toe space comply with Section 1134A.8. Cabinets under lavatories and toilets shall not encroach into the clear floor space.
- 2. Reinforced Walls for Grab Bars.** A bathtub installed without surrounding walls shall provide reinforced areas for the installation of floor-mounted grab bars.

Where a bathtub is installed with surrounding walls, grab bar reinforcement shall be located on each end of the bathtub, 32 inches to 38 inches (813 mm to 965 mm) above the floor, extending a minimum of 24 inches (610 mm) from the front edge of the bathtub toward the back wall of the bathtub. The grab bar reinforcement shall be a minimum of 6 inches (152.4 mm) nominal in height. (See Figure 11A-9G).

Grab bar reinforcement shall be installed on the back wall of the bathtub a maximum of 6 inches (152.4 mm) above the bathtub rim extending upward to at least 38 inches (965 mm) above the floor. Grab bar backing shall be installed horizontally to permit the installation of a 48-inch (1219 mm) grab bar with each end a maximum of 6 inches (152.4 mm) from the end walls of the bathtub. The grab bar reinforcement shall be a minimum of 6 inches (152.4 mm) nominal in height.

- 3. Bathtub Controls.** Faucet controls and operation mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist.

The force required to activate controls shall be no greater than 5 pound-force (22.2 N). Lever operated, push type and electronically controlled mechanisms are examples of acceptable designs.

- 4. Shower Unit.** A shower spray unit is not required in bathtubs.
- 5. Bathtub Enclosures.** Doors and panels of bathtub enclosures shall be substantially constructed from approved, shatter-resistant materials. Hinged doors shall open outward. Glazing used in doors and panels of bathtub enclosures shall be fully tempered, laminated safety glass or approved plastic. When glass is used, it shall have minimum thickness of not less than $\frac{1}{8}$ inch (3.17 mm) when fully tempered, or $\frac{1}{4}$ inch (6.35 mm) when laminated, and shall pass the test requirements of this part, Chapter 24, Glass and Glazing. Plastics used in doors and panels of bathtub enclosures shall be of a shatter-resistant type.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1134A.6 Showers. Showers required to be accessible shall comply with this section.

1. **Size.** When one or more shower stalls are provided within the same dwelling unit, at least one shower stall shall comply with one of the following requirements.
 - 1.1. The shower stall shall measure at least one shower stall shall measure at least 42 inches wide by 48 inches deep (1067 mm by 1219 mm) with an entrance opening of at least 36 inches (914 mm) or:
 - 1.2. The shower stall shall measure at least 30 inches deep by 60 inches wide (762 mm) by 1524 mm) with an entrance opening of a least 60 inches (1524 mm). A water closet may project a maximum of 12 inches (305 mm) into the opening provided that a minimum of 36 inches (914 mm) clear space is maintained between the water closet and the shower wall as illustrated in Figure 11A-9L or:
 - 1.3. Other shower stall configurations shall measure at least 36 inches deep by 60 inches wide (914 mm) by 1524 mm) with an entrance opening of at least 36 inches (914 mm) when a wall is installed on the opening side.
2. **Slope.** The maximum slope of the shower floor shall be $\frac{1}{2}$ inch (12.7 mm) per foot in any direction and shall slope toward the rear to drain. The floor surfaces shall be of Carborundum or grit-faced tile or of material providing equivalent slip resistance.
3. **Floor Space.** A clear maneuvering space at least 30 inches in width by 48 inches in length (762 mm by 1219 mm) shall be located outside the shower, flush and parallel to the control wall.
4. **Reinforced Walls for Grab Bars.** Grab bar reinforcement shall be installed continuous in the walls of showers 32 inches to 38 inches (813 mm to 965 mm) above the floor. The grab bar reinforcement shall be a minimum of 6 inches (152.4 mm) nominal in height.

Glass-walled shower stalls shall provide reinforcement for installation of floor-mounted or ceiling-mounted grab bars.

5. **Thresholds.** When a threshold is used, it shall be a maximum of 2 inches (50.8 mm) in height and have a beveled or sloped angle not exceeding 1 unit vertical in 2 units horizontal (26.6 degrees from the horizontal). Thresholds $\frac{1}{2}$ inch (12.7 mm) or less in height may have a beveled or sloped angle not exceeding 1 unit vertical in 1 unit horizontal (45 degrees from the horizontal).
6. **Shower Controls.** Faucet controls and operation mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist. The force required to activate controls shall be no greater than 5 pound-force (22.2N). Lever operated, push-type and electronically controlled mechanisms are examples of acceptable designs.
7. **Shower Enclosures.** Doors and panels of shower enclosures shall be substantially constructed from approved, shatter-resistant materials. Hinged shower doors shall open outward. Glazing used in doors and panels of shower enclosures shall be fully tempered, laminate safety glass or approved plastic. When glass is used, it shall have minimum thickness of not less than $\frac{1}{8}$ inch (3.17 mm) when fully tempered, or $\frac{1}{4}$ inch (6.35 mm) when laminated, and shall pass the test requirements of this part, Chapter 24, Glass and Glazing. Plastics used in doors and panels of shower enclosures shall be of shatter-resistant type.

1134A.7 Water closets. Water closets in bathrooms or powder rooms required to be accessible shall comply with this section.

1. **Floor Space.** The minimum floor space provided at a water closet shall be 48 inches (1219 mm) in clear width. The clear floor space shall extend past the front edge of the water closet at least 36 inches (914 mm). See Figure 11A-9M.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Exception: The 48-inch (1219 mm) minimum clear width may be reduced to 36 inches (914 mm) for lavatories, cabinets, wing walls, or privacy walls located immediately adjacent to a water closet which extend no more than 24 inches (610 mm) in depth.

Water closets shall be located within bathrooms in a manner that permits a grab bar to be installed on one side of the fixture. In locations where water closets are adjacent to walls vanities, lavatories or bathtubs, the centerline of the fixture shall be a minimum of 18 inches (457 mm) from the obstacle.

- 2. Reinforced Walls for Grab Bars.** Where the water closet is not placed adjacent to a side wall, the bathroom shall have provisions for installation of floor-mounted, foldaway or similar alternative grab bars.

Where the water closet is placed adjacent to a side wall, reinforcement shall be installed on both sides or one side and the back. If reinforcement is installed at the back, it shall be installed between 32 inches (813 mm) and 38 inches (965 mm) above the floor. The grab bar reinforcement shall be a minimum of 6 inches (152.4 mm) nominal in height. The backing shall be a minimum of 40 inches (1016 mm) in length.

Reinforcement installed at the side of the water closet shall be installed 32 inches to 38 inches (813mm to 965 mm) above the floor. The reinforcement shall be installed a maximum of 12 inches (305 mm) from the rear wall and shall extend a minimum of 26 inches (660 mm) in front of the water closet. The grab bar reinforcement shall be a minimum of 6 inches (152.4 mm) nominal in height.

- 3. Seat Height.** The minimum height of water closet seats shall be 15 inches (381 mm) above the floor.
- 4. Water Closet Controls.** Water closet controls shall be mounted no more than 44 inches (1118 mm) above the floor. The force required to activate controls shall be no greater than 5 pound-force (22.2 N).

1134A.8 Lavatories, vanities, mirrors and towel fixtures. Bathrooms or powder rooms required to be accessible shall have at least one accessible lavatory. Where mirrors and towel fixtures are provided, at least one of each shall be accessible.

- 1. Location.** Vanities and lavatories shall be installed with the centerline of the fixture a minimum of 18 inches (457 mm) horizontally from an adjoining wall or fixture to allow for forward approach. When parallel approach is provided, lavatories shall be installed with the centerline of the fixture a minimum of 24 inches (610 mm) horizontally from an adjoining wall or fixture. The top of the fixture rim shall be a maximum of 34 inches (864 mm) above the finished floor.
- 2. Floor Space.** A clear maneuvering space at least 30 inches by 48 inches (762 mm by 1219 mm) shall be provided at lavatories and shall be centered on the lavatory.
- 3. Cabinets.** Cabinets under lavatories are acceptable-provided the bathroom has space to allow a parallel approach by a person in a wheelchair and the lavatory cabinets are designed with adaptable knee and toe space.
- 4. Knee and Toe Space.** Knee and toe space shall be provided as follows:
 - 4.1.** The knee space shall be at least 30 inches (762 mm) wide and 8 inches (203.2 mm) deep.
 - 4.2.** The knee space shall be at least 29 inches (737 mm) high at the front face and reducing to not less than 27 inches (686 mm) at a point 8 inches (203.2 mm) back from the front edge.
 - 4.3.** The knee and toe space required in this section shall be provided by one of the following:
 - 4.3.1.** The space beneath the lavatory shall be left clear and unobstructed;
 - 4.3.2.** Any cabinet beneath the lavatory shall be removable without the use of specialized knowledge or specialized tools; or

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4.3.3. *Doors to the cabinet beneath the lavatory shall be removable or openable to provide the required unobstructed knee and toe space.*

4.4. *The toe space required in this section shall be provided as follows:*

4.4.1. *Shall be at least 30 inches (762 mm) wide and centered on the lavatory.*

4.4.2. *Shall be at least 17 inches (432 mm) deep, measured from the front edge.*

4.4.3. *Shall be at least 9 inches (228.6 mm) high from the floor.*

5. Finished Floor. *The finished floor beneath the lavatory shall be extended to the wall.*

6. Plumbing Protection. *Hot water and drain pipes exposed under lavatories shall be insulated or otherwise covered. There shall be no sharp or abrasive surfaces under lavatories.*

7. Lavatory Faucet Controls. *Faucet controls and operation mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist.*

The force required to activate controls shall be no greater than 5 pound-force (22.2 N). Lever operated, push-type and electronically controlled mechanisms are examples of acceptable designs. Self-closing valves are allowed if the faucet remains open for at least 10 seconds.

8. Mirrors and Towel Fixtures. *Where mirrors or towel fixtures are provided they shall be mounted with the bottom edge no higher than 40 inches (1016 mm) from the floor.*

SECTION 1135A LAUNDRY ROOMS

1135A.1 General. *If clothes washing machines and clothes dryers are provided in covered multifamily dwelling units, one of each type of appliance shall be provided. Where front-loading clothes washers are not provided, management shall provide assistive devices, on request of the occupant, to permit the use of top-loading clothes washers.*

SECTION 1136A ELECTRICAL RECEPTACLE, SWITCH AND CONTROL HEIGHTS

1136A.1 Receptacle heights. *Electrical receptacle outlets on branch circuits of 30 amperes or less and communication system receptacles shall be located no more than 48 inches (1219 mm) measured from the top of the receptacle outlet box or receptacle housing nor less than 15 inches (381 mm) measured from the bottom of the receptacle outlet box or receptacle housing to the level of the finished floor or working platform. If the reach is over an obstruction (for example, a kitchen base cabinet) between 20 and 25 inches (508 and 635 mm) in depth, the maximum height measured at the box is reduced to 44 inches (1118 mm) for forward approach, or 46 inches (1168 mm) for side approach, provided the obstruction is no more than 24 inches (610 mm) in depth. Obstructions shall not extend more than 25 inches (635 mm) from the wall beneath the receptacle.*

Outlets that do not satisfy these specifications are acceptable, provided that comparable outlets, that perform the same functions, are provided within the same area and are accessible.

Exceptions:

- 1. Receptacle outlets installed as part of permanently installed baseboard heaters are exempt.*
- 2. Required receptacle outlets shall be permitted in floors when adjacent to sliding panels or walls.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. *Baseboard electrical outlets used in relocatable partitions, window walls or other electrical convenience floor outlets are not subject to the minimum height requirements.*
4. *This section shall not apply to existing buildings when the enforcing agency determines that compliance with these standards would create an unreasonable hardship.*

Note: *The intent of the measurement is to ensure that receptacles fall within the reach range of 15 inches to 48 inches (381 to 1219 mm).*

1136A.2 Switch and control heights. *Controls or switches intended to be used by the occupant of the room or area to control lighting and receptacle outlets, appliances, alarms or cooling, heating and ventilating equipment shall be located no more than 48 inches (1219 mm) measured from the top of the outlet box nor less than 15 inches (381 mm) measured from the bottom of the outlet box to the level of the finished floor or working platform. If the reach is over a physical barrier or an obstruction (for example, a kitchen base cabinet) between 20 and 25 inches (508 and 635 mm) in depth, the maximum height is reduced to 44 inches (1118 mm) for forward approach, or 46 inches (1168 mm) for side approach, provided the obstruction is no more than 24 inches (610 mm) in depth. Physical barriers or obstructions shall not extend more than 25 inches (635 mm) from the wall beneath a control.*

Controls that do not satisfy these specifications are acceptable provided that comparable controls or outlets, that perform the same functions, are provided within the same area and are accessible.

Exception: *Appliances (e.g. kitchen stoves, dishwashers, range hoods, microwave ovens and similar appliances) which have controls located on the appliance.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Division V – FEATURES COMMON TO EXTERIOR AND INTERIOR OF BUILDINGS

Division V Table of Contents

Section 1137A	Other Features and Facilities
Section 1138A	Reserved
Section 1139A	Accessible Drinking Fountains
Section 1140A	Accessible Telephones
Section 1141A	Accessible Swimming Pools
Section 1142A	Electrical Receptacle, Switch and Control Heights
Section 1143A	Signage
Sections 1144A through 1149	Reserved

SECTION 1137A OTHER FEATURES AND FACILITIES

1137A.1 General. This division shall apply to features and facilities of common use areas on accessible floors or sites.

Note: The provisions in this division are not applicable to dwelling units.

SECTION 1138A Reserved

SECTION 1139A ACCESSIBLE DRINKING FOUNTAINS

1139A.1 General. Drinking fountains and water coolers in common use areas and/or sites shall comply with this section. A side approach drinking fountain is not acceptable.

1139A.2 Accessible route. Drinking fountains and water coolers shall be on an accessible route.

1139A.3 Design and construction. Wall-mounted and post-mounted cantilevered drinking fountains and water coolers shall be designed and constructed to comply with the following: (See Figure 11A-11A).

1. A clear floor space shall be provided in conformance with the following:
 - 1.1. A minimum clear floor space 30 inches by 48 inches (762mm by 1219 mm) to allow a person in a wheelchair to approach the unit facing forward.
 - 1.2. A clear knee space a minimum of 30 inches (762 mm) in width.
 - 1.3. A clear knee space a minimum of 18 inches (457 mm) in depth.
 - 1.4. A clear and unobstructed knee space under the drinking fountain not less than 27 inches (68 mm) in height and 8 inches (203.2 mm) in depth, the depth measurements being taken from the front edge of the fountain.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

- 1.5. A toe clearance of 9 inches (228.6 mm) in height above the floor and 17 inches (432 mm) in depth from the front edge of the fountain.
2. Water flow shall be provided in conformance with the following:
 - 2.1. The spout shall be located within 6 inches (152.4 mm) of the front edge of the drinking fountain and within 36 inches (914 mm) of the floor.
 - 2.2. A flow of water at least 4 inches (101.6 mm) high shall be available to allow the insertion of a cup or glass under the flow of water.
 - 2.3. The water stream from the bubbler shall be substantially parallel to the front edge of the drinking fountain.
 - 2.4. The force required to activate controls shall be no greater than 5 pound-force (22.2 N).
 - 2.5. Manually operated or electronically operated controls shall be located within 6 inches (152.4 mm) of the front edge of the fountain.

1139A.3.1 Location. Water fountains shall be located completely within alcoves or otherwise positioned so as not to encroach into pedestrian ways. The alcove in which the water fountain is located shall not be less than 32 inches (813 mm) in width and 18 inches (457 mm) in depth. Protruding objects located in alcoves or otherwise positioned so as to limit encroachment into pedestrian ways are permitted to project 4 inches (102 mm) into walks, halls, corridors, passageways or aisles. (See Figure 11A-11A).

Exception: When the enforcing agency determines that it would create an unreasonable hardship to locate the water fountain in an alcove, the water fountain may project into the path of travel, and the path of travel shall be identifiable to the blind as follows:

1. The surface of the path of travel at the water fountain shall be textured so that it is clearly identifiable by a blind person using a cane. The minimum textured area shall extend from the wall supporting the water fountain to 1 foot (305 mm) beyond the front edge of the water fountain and shall extend 1 foot (305mm) beyond each side of the water fountain, or
2. Wing walls shall be provided on each side of the water fountain. The wing walls shall project out from the supporting wall at least as far as the water fountain to within 6 inches (152.4 mm) of the surface of the path of travel. There shall also be a minimum of 32 inches (813 mm) clear between the wing walls.

SECTION 1140A ACCESSIBLE TELEPHONES

1140A.1 General. If public telephones are provided, they shall comply with this section. On floors where public telephones are provided, at least one telephone shall be accessible. On any floor where two or more banks of multiple telephones are provided, at least one telephone in each bank shall be accessible.

1140A.2 Clear floor or ground space. A clear floor or ground space at least 30 inches by 48 inches (762mm by 1219 mm) that allows either a forward or parallel approach by a person using a wheelchair shall be provided at telephones. Bases, enclosures and fixed seats shall not impede approaches to telephones by people who use wheelchairs. (See Figure 11A-11B). The minimum clear floor or ground space for wheelchairs may be positioned for forward or parallel approach to an object. Clear floor or ground space for wheelchairs may be part of the knee space required under some objects.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1140A.3 Relationship of maneuvering clearances to wheelchair spaces. One full unobstructed side of the clear floor or ground space for a wheelchair shall adjoin another wheelchair clear floor space. If a clear floor space is located in an alcove or otherwise confined on all or part of three sides, additional maneuvering clearances shall be provided.

1140A.4 Mounting height. The highest operable part of the telephone shall be within the reach ranges specified in Figure 11A-11B. Telephones mounted diagonally in a corner that require wheelchair users to reach diagonally shall have the highest operable part no higher than 54 inches (1372 mm) above the floor. (See Figure 11A-11B).

1140A.5 Enclosures. If telephone enclosures are provided, they may overhang the clear floor space required in Sections 1140A.2 and 1140A.3 with the following limits:

- 1. Side Reach Possible.** The overhang shall be no greater than 19 inches (483 mm). The height of the lowest overhanging part shall be equal to or greater than 27 inches (686 mm) above the floor.
- 2. Full-height Enclosures.** Entrances to full-height enclosures shall be a minimum of 30 inches (762 mm) in width.
- 3. Forward Reach Required.** If the overhang is greater than 12 inches (305 mm), then the clear width of the enclosure shall be 30 inches (762 mm) minimum; if the clear width of the enclosure is less than 30 inches (762 mm), then the height of the lowest overhanging part shall be equal to or greater than 27 inches (686 mm).

1140A.6 Equipment for hearing impaired people. Telephones shall be equipped with a receiver that generates a magnetic field in the area of the receiver cap. A reasonable number of the public telephones provided, but always at least one on each floor or in each bank, whichever is more, in a building or facility, shall be equipped with a volume control. Such telephones shall be capable of a minimum of 12 dbA and a maximum of 18 dbA above normal. If an automatic reset is provided, 18 dbA may be exceeded. Public telephones with volume control shall be hearing aid compatible and shall be identified by a sign containing a depiction of a telephone handset with radiating sound waves. (See Figure 11A-11D).

1140A.7 Text telephones. If a total of four or more public pay telephones are provided at the interior and exterior of a site, and if at least one of the total number provided is located in an interior location, at least one interior public text telephone shall be provided.

1140A.7.1 Signage. Text telephones shall be identified by the International TTY symbol (see Figure 11A-11C). If a facility has a public text telephone, directional signage indicating the location of the nearest such telephone shall be placed adjacent to all banks of telephones that do not contain a text telephone. Such directional signage shall include the International TTY symbol. If a facility has no banks of telephones, the directional signage shall be provided at the entrance or in a building directory.

1140A.8 Controls. Telephones shall have push-button controls where service for such equipment is available.

1140A.9 Cord length. The cord from the telephone to the handset shall be at least 29 inches (737 mm) long.

1140A.10 Telephone books. If telephone books are provided, they shall be located in a position that complies with the reach ranges in Figures 11A-1I and 11A-1J.

SECTION 1141A ACCESSIBLE SWIMMING POOLS

1141A.1 General. Swimming pools in common use areas shall comply with the provisions of this section and Chapter 31B.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1141A.2 Swimming pool deck areas. *Swimming pool deck areas must be accessible, and a mechanism to assist persons with disabilities gain entry into the pool and exit from the pool shall be provided. Such a mechanism may consist of a swimming pool lift device as long as the device meets all of the following criteria:*

1. *Has a seat that meets all of the following:*
 - 1.1. *The seat must be rigid;*
 - 1.2. *The seat must be not less than 17 inches (432 mm) and not more than 19 inches (483 mm), inclusive of any cushioned surface that might be provided, above the pool deck;*
 - 1.3. *The seat must have two armrests. The armrest on the side of the seat by which access is gained shall be either removable or fold clear of the seat;*
 - 1.4. *The seat must have a back support that is at least 12 inches (305 mm) tall; and*
 - 1.5. *The seat must have an occupant restraint for use by the occupant of the seat and the restraint must meet the standards for operable controls in compliance with Section 1127A.9.6.4.*
2. *Be capable of unassisted operation from both the deck and water levels.*
3. *Be stable and not permit unintended movement when a person is getting into or out of the seat.*
4. *Be designed to have a live-load capacity of not less than 300 pounds.*
5. *Be positioned so that, if the pool has water of different depths, it will place the operator into water that is at least 3 feet (914 mm) deep.*
6. *Be capable of lowering the operator at least 18 inches (457 mm) below the surface of the water.*

SECTION 1142A ELECTRICAL RECEPTACLE, SWITCH AND CONTROL HEIGHTS

1142A.1 Receptacle heights. *Electrical receptacle outlets on branch circuits of 30 amperes or less and communication system receptacles shall be located no more than 48 inches (1219 mm) measured from the top of the receptacle outlet box or receptacle housing nor less than 15 inches (381 mm) measured from the bottom of the receptacle outlet box or receptacle housing to the level of the finished floor or working platform. If the reach is over an obstruction (for example, a kitchen base cabinet) between 20 and 25 inches (508 and 635 mm) in depth, the maximum height measured at the box is reduced to 44 inches (1118 mm) for forward approach, or 46 inches (1168 mm) for side approach, provided the obstruction is no more than 24 inches (610 mm) in depth. Obstructions shall not extend more than 25 inches (635 mm) from the wall beneath the receptacle.*

Outlets that do not satisfy these specifications are acceptable provided that comparable outlets, that perform the same functions, are provided within the same area and are accessible.

Exceptions:

1. *Receptacle outlets installed as part of permanently installed baseboard heaters are exempt.*
2. *Required receptacle outlets shall be permitted in floors when adjacent to sliding panels or walls.*
3. *Baseboard electrical outlets used in relocatable partitions, window walls or other electrical convenience floor outlets are not subject to the minimum height requirements.*
4. *This section shall not apply to existing buildings when the enforcing agency determines that compliance with these standards would create an unreasonable hardship.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Note: The intent of the measurement is to ensure that receptacles fall within the reach range of 15 inches to 48 inches (381 mm to 1219 mm).

1142A.2 Switch and control heights. Controls or switches intended to be used by the occupant of the room or area to control lighting and receptacle outlets, appliances, alarms or cooling, heating and ventilating equipment shall be located no more than 48 inches (1219 mm) measured from the top of the outlet box nor less than 15 inches (381 mm) measured from the bottom of the outlet box to the level of the finished floor or working platform. If the reach is over a physical barrier or an obstruction (for example, a kitchen base cabinet) between 20 and 25 inches (508 and 635 mm) in depth, the maximum height is reduced to 44 inches (1118 mm) for forward approach, or 46 inches (1168 mm) for side approach, provided the obstruction is no more than 24 inches (610 mm) in depth. Physical barriers or obstructions shall not extend more than 25 inches (635 mm) from the wall beneath a control.

Controls that do not satisfy these specifications are acceptable provided that comparable controls or outlets, that perform the same functions, are provided within the same area and are accessible.

SECTION 1143A SIGNAGE

1143A.1 General. When signs and/or identification devices are provided they shall comply with this section.

Exception: Signs need not be provided within dwelling units.

1143A.2 Identification signs. When signs identify permanent rooms and spaces of a building or site, they shall comply with Sections 1143A.5, 1143A.6, 1143A.8, 1143A.9 and 1143A.10.

Note: See Section 1124A for additional signage requirements applicable to elevators and Section 1127A.7 for sanitary facilities.

1143A.3 Directional and informational signs. When signs direct to or give information about permanent rooms and spaces of a building or site, they shall comply with Sections 1143A.5, 1143A.6 and 1143A.7.

1143A.4 Accessibility signs. When signs identify, direct or give information about accessible elements and features of a building or site, they shall include the appropriate symbol of accessibility and shall comply with Section 1143A.5 and, when applicable, Section 1143A.10.

1143A.5 Finish and contrast. Characters, symbols and their background shall have a non-glare finish. Characters and symbols shall contrast with their background, either light on a dark background or dark on a light background.

1143A.6 Proportions. Characters on signs shall have a width-to-height ratio of between 3:5 and 1:1 and a stroke width-to-height ratio of between 1:5 and 1:10.

1143A.7 Character height. Characters and numbers on signs shall be sized according to the viewing distance from which they are to be read. The minimum height is measured using an uppercase "X." Lowercase characters are permitted. For signs suspended or projected above the finish floor greater than 80 inches (2032 mm), the minimum character height shall be 3 inches (76 mm).

1143A.8 Raised characters and pictorial symbol signs. When raised characters are required or when pictorial symbols (pictograms) are used on such signs, they shall conform to the following requirements:

- 1. Character Type.** Characters on signs shall be raised $\frac{1}{32}$ -inch (0.794 mm) minimum and shall be sans serif uppercase characters accompanied by Grade 2 Braille complying with Section 1143A.9.
- 2. Character Size.** Raised characters shall be a minimum of $\frac{5}{8}$ inch (15.9 mm) and a maximum of 2 inches (51 mm) high.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. **Pictorial Symbol Signs (Pictograms).** *Pictorial symbol signs (pictograms) shall be accompanied by the verbal description placed directly below the pictogram. The outside dimension of the pictogram field shall be a minimum of 6 inches (152 mm) in height.*
4. **Character Placement.** *Characters and Braille shall be in a horizontal format. Braille shall be placed a minimum of $\frac{3}{8}$ inch (9.5 mm) and a maximum of $\frac{1}{2}$ inch (12.7 mm) directly below the tactile characters, flush left or centered. When tactile text is multilined, all Braille shall be placed together below all lines of tactile text.*

1143A.9 Braille. *Contracted Grade 2 Braille shall be used wherever Braille is required in other portions of these standards. Dots shall be $\frac{1}{10}$ inch (2.54 mm) on center in each cell with $\frac{2}{10}$ -inch (5.08 mm) space between cells, measured from the second column of dots in the first cell to the first column of dots in the second cell. Dots shall be raised a minimum of $\frac{1}{40}$ inch (0.635 mm) above the background. Braille dots shall be domed or rounded.*

1143A.10 Mounting location and height. *Where permanent identification signs are provided for rooms and spaces, signs shall be installed on the wall adjacent to the latch side of the door. Where there is no wall space on the latch side, including at double leaf doors, signs shall be placed on the nearest adjacent wall, preferably on the right.*

Where permanent identification signage is provided for rooms and spaces, it shall be located on the approach side of the door as one enters the room or space. Signs that identify exits shall be located on the same side of the door as the visual exit sign.

Mounting height shall be 60 inches (1524 mm) above the finish floor to the centerline of the sign. Mounting location shall be determined so that a person may approach within 3 inches (76 mm) of the signage without encountering protruding objects or standing within the swing of a door.

Note: See also Section 1127A.7 for additional signage requirements applicable to sanitary facilities.

SECTION 1144A

Reserved

SECTION 1145A

Reserved

SECTION 1146A

Reserved

SECTION 1147A

Reserved

SECTION 1148A

Reserved

SECTION 1149A

Reserved

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Division VI — SITE IMPRACTICALITY TESTS

Division VI Table of Contents

Section 1150A Site Impracticality Tests

Test No. 1	Individual Building Test
Test No. 2	Site Analysis Test
Test No. 3	Unusual Characteristics Test

SECTION 1150A SITE IMPRACTICALITY TESTS

1150A.1 General. Covered multifamily dwellings in buildings without an elevator, located on sites with difficult terrain conditions or unusual characteristics, may employ the site impracticality tests in this division for determining the accessibility and adaptability provisions required by this chapter.

Except as provided for in Section 1102A.3.1, the provisions of this section do not apply to multistory dwelling units in nonelevator buildings.

SINGLE BUILDING WITH ONE COMMON (LOBBY) ENTRANCE

The following may only be used for determining required access to covered multifamily dwelling units, in a single building with one common (lobby) entrance, located on a site with difficult terrain conditions or unusual characteristics:

All ground floor units in nonelevator buildings shall be adaptable and on an accessible route unless an accessible route to the common (lobby) entrance is not required as determined by Test No. 1, Individual Building Test, or Test No. 3, Unusual Characteristics Test, as described in this section.

Sites where either Test No. 1 or Test No. 3 is used and it is determined that an accessible route to the common (lobby) entrance is not required shall comply with the features listed in Section 1150A.2 unless exempted by Test No. 3, Unusual Characteristics Test.

Test No. 1—Individual Building Test may only be used if the site has terrain over 15 percent slope.

Test No. 3—Unusual Characteristics Test may be used if applicable.

Provisions to Test Nos. 1 and 2. Where a building elevator is provided only as means of creating an accessible route to covered multifamily dwelling units on a ground floor, the building is not considered to be an elevator building for purposes of this code; hence, only the ground floor dwelling units would be covered.

TEST NO. 1—INDIVIDUAL BUILDING TEST

It is not required by this code to provide an accessible route when the terrain of the site is such that both of the following apply:

1. The slopes of the undisturbed site measured between the planned entrance and all vehicular or pedestrian planned entrance exceed 15 percent; and 2. The slopes of the planned finished grade measured between the entrance and all vehicular or pedestrian arrival points within 50 feet (15 240 mm) of the planned entrance also exceed 15 percent. and

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. *The slopes of the planned finished grade measured between the entrance and all vehicular or pedestrian arrival points within 50 feet (15 240 mm) of the planned entrance also exceed 15 percent.*

If there are no vehicular or pedestrian arrival points within 50 feet (15 240 mm) of the planned entrance, the slope for the purposes of Test No. 1 will be measured to the closest vehicular or pedestrian arrival point.

For purposes of these requirements, vehicular or pedestrian arrival points include public or resident parking areas, public transportation stops, passenger loading zones and public streets or sidewalks. To determine site impracticality, the slope would be measured at ground level from the point of the planned entrance on a straight line to (1) each vehicular or pedestrian arrival point that is within 50 feet (15 240 mm) of the planned entrance, or (2) if there are no vehicular or pedestrian arrival points within the specified area, the vehicular or pedestrian arrival point closest to the planned entrance. In the case of sidewalks, the closest point to the entrance will be where a public sidewalk entering the site intersects with the walk to the entrance. In the case of resident parking areas, the closest point to the planned entrance will be measured from the entry point to the parking area that is located closest to the planned entrance.

TEST NO. 2—SITE ANALYSIS TEST

For a site having multiple buildings, or a site with a single building with multiple entrances, it is not required to provide an accessible route to all ground floor units under the following conditions:

1. *Calculate the percentage of the total buildable area of the undisturbed site with a natural grade less than 10-percent slope. The analysis of the existing slope (before grading) shall be done on a topographic survey with 2-foot (610 mm) contour intervals with slope determination made between each successive interval. The accuracy of the slope analysis shall be certified by a licensed engineer, landscape architect, architect or surveyor.*
2. *Determine the requirement of providing an accessible route to planned multifamily dwellings based on the topography of the existing natural terrain. The minimum percentage of ground floor units required on an accessible route shall equal the percentage of the total buildable area (not restricted-use areas) of the undisturbed site with an existing natural grade of less than 10-percent slope. In no case shall less than 20 percent of the ground floor dwelling units be on an accessible route and comply with the provisions of Division IV.*
3. *In addition to the percentage established in paragraph (2), all additional ground floor units in a building, or ground floor units served by a particular entrance, that fall within an 8.33-percent slope between their planned entrances and an arrival point shall be on an accessible route and comply with the provisions of Division IV.*
4. *All additional ground floor units in a building, or ground floor units served by a particular entrance, not on an accessible route shall comply with the features listed in Section 1150A.2.*

TEST NO. 3—UNUSUAL CHARACTERISTICS TEST

Unusual characteristics include sites located in a state or federally designated floodplain or coastal high-hazard areas and sites subject to other similar requirements of law or code that require the lowest floor or the lowest structural member of the lowest floor to be designed to a specified level at or above the base flood elevation. An accessible route to a building entrance is impractical due to unusual characteristics of the site when:

1. *The original site characteristics result in a difference in finished grade elevation exceeding 30 inches (762 mm) and 10 percent measured between an entrance and all vehicular or pedestrian arrival points within 50 feet (15 240 mm) of the planned entrance; or*
2. *If there are no vehicular or pedestrian arrival points within 50 feet (15 240 mm) of the planned entrance, the unusual characteristics result in a difference in finished grade elevation exceeding 30 inches (762 mm) and 10 percent measured between an entrance and the closest vehicular or pedestrian arrival point.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1150A.2 Additional requirements for Section 1150A.

All other ground floor dwelling units in nonelevator buildings shall be made to comply with the following requirements:

1. *Grab bar reinforcement: see Section 1134A.*
2. *Thirty-two inch (813 mm) clear door interior opening width: see Section 1132A.3.*
3. *Lever hardware: see Section 1132A.8.*
4. *Door signal devices: see Section 1132A.10.*
5. *Clear space by doors: see Chapters 10 and 11A.*
6. *Minimum 15-inch (381 mm) water closet seat height: see Section 1134A.7, Item 3.*
7. *Electrical receptacle outlet height: see Section 1136A.*
8. *Lighting and environmental control height: see Section 1136A.*
9. *Faucet controls: see Section 1134A.8, Item 7.*
10. *Water closet, bathtub and lavatory minimum space requirements: see Section 1134A.*
11. *Removable cabinets under the kitchen sink counter area: see Section 1133A.3.*

DIVISION VII – FIGURES

[11A-1A through 11A-11E](#) (link to separate document for 11A Figures)

HOUSING ACCESSIBILITY

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 11B - ACCESSIBILITY TO PUBLIC BUILDINGS, PUBLIC ACCOMMODATIONS,
COMMERCIAL BUILDINGS AND PUBLICLY FUNDED HOUSING**

NOTE: For housing accessibility, see Chapter 11A.

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC X	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below		X																		
Chapter/Section																				

Division I – NEW BUILDINGS

**SECTION 1101B
SCOPE**

See Chapter 1, Section 1.9.1.5

1101B.1 General.

1. Buildings or facilities or portions of buildings shall be accessible to persons with disabilities as required by this chapter.
2. Departures from particular technical and scoping requirements of this chapter by the use of other designs and technologies are permitted where the alternative designs and technologies used will provide equivalent or greater access to and usability of the building or facility.
3. In determining equivalent facilitation, consideration shall be given to means that provide for the maximum independence of persons with disabilities while presenting the least risk of harm, injury or other hazard to such persons or others.

1101B.2 Design. The design and construction of accessible building and facility elements shall be in accordance with this chapter.

1101B.3 Maintenance of accessible features.

1. A public accommodation shall maintain in operable working condition those features of facilities and equipment that are required to be accessible to and usable by persons with disabilities.
2. This section does not prohibit isolated or temporary interruptions in service or access due to maintenance or repairs.

1101B.4 Dimension conventions. Dimensions that are not stated as “maximum” or “minimum” are absolute.

1101B.5 Construction and manufacturing tolerances. All dimensions are subject to conventional industry tolerances except where the requirement is stated as a range with specific minimum and maximum end points.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1101B.6 Commercial facilities located in private residences.

1. When a commercial facility is located in a private residence, the portion of the residence used exclusively as a residence is not covered by this chapter, except as required by Section 1111B.5, but that portion used both for the commercial facility and for residential purposes is covered by the new construction and alterations requirements of this code.
2. The portion of the residence covered extends to those elements used to enter the commercial facility, including the homeowner's front sidewalk, if any, the door or entryway, and hallways; and those portions of the residence, interior or exterior, available to or used by employees or visitors of the commercial facility, including sanitary facilities.

1101B.7 Provisions for adults. Unless otherwise indicated, the dimensions and specifications in these regulations are based upon adult dimensions and anthropometrics.

SECTION 1102B DEFINITIONS

For additional definitions pertinent to the Division of the State Architect-Access Compliance accessibility requirements, see Chapter 2, Section 202.

For the purpose of the chapter, certain terms are defined as follows:

ACCESS AISLE is an accessible pedestrian space adjacent to or between parking spaces that provides clearances in conformance with this chapter.

ACCESSIBILITY is the combination of various elements in a building, facility, site, or area, or portion thereof which allows access, circulation and the full use of the building and facilities by persons with disabilities in conformance with this chapter.

ACCESSIBLE is approachable and usable by persons with disabilities in compliance with this code.

ACCESSIBLE ELEMENT is an element specified by the regulations adopted by the Division of the State Architect-Access Compliance.

ACCESSIBLE MEANS OF EGRESS. See Section 1002.1.

ACCESSIBLE ROUTE OF TRAVEL is a continuous unobstructed path connecting all accessible elements and spaces in an accessible building or facility that can be negotiated by a person with a disability using a wheelchair and that is also safe for and usable by persons with other disabilities, and that is consistent with the definition of "Path of travel" in this section. Interior accessible routes may include corridors, floors, ramps, elevators, lifts and clear floor space at fixtures. Exterior accessible routes may include parking access aisles, curb ramps, crosswalks at vehicular ways, walks, sidewalks, ramps, and lifts. An accessible route does not include stairs, steps, or escalators.

ACCESSIBLE SPACE is a space that complies with the regulations adopted by the Division of the State Architect-Access Compliance.

ADAPTABILITY is the capability of spaces or facilities to be readily modified and made accessible.

ADMINISTRATIVE AUTHORITY is a governmental agency that adopts or enforces regulations and guidelines for the design, construction, or alteration of buildings and facilities.

AISLE is a circulation path between objects such as seats, tables, merchandise, equipment, displays, shelves, desks, etc., that provides clearances in conformance with this chapter.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

AISLE, EMPLOYEE AREAS (as required for architectural accessibility) is a space that serves as a passageway, which is created by architectural components such as walls, fixed cabinetry or fixtures and not moveable components such as furniture.

AREA OF REFUGE. See Section 1002.1.

ASSEMBLY AREA is a room or space accommodating a group of individuals for recreational, educational, political, social or amusement purposes, or for the consumption of food and drink.

AUTOMATIC DOOR is a door equipped with a power operated mechanism and controls that open and close the door automatically upon receipt of a momentary actuating signal. The switch that begins the automatic cycle may be a photoelectric device, floor mat or manual switch.

CIRCULATION PATH is an exterior or interior way of passage from one place to another for pedestrians, including, but not limited to, walks, hallways, courtyards, stairways and stair landings.

CLEAR means unobstructed.

CLEAR FLOOR SPACE is the minimum unobstructed floor or ground space required to accommodate a single, stationary wheelchair and occupant.

CLOSED-CIRCUIT TELEPHONE is a telephone with dedicated line(s) such as a house phone, courtesy phone or phone that must be used to gain entrance to a facility.

COMMON USE AREAS are those interior and exterior rooms, spaces or elements that are made available for the use of a restricted group of people (for example, occupants of a homeless shelter, the occupants of an office building or the guests of such occupants).

COMPLY WITH means to meet one or more specifications of these regulations.

CROSS SLOPE is the slope that is perpendicular to the direction of travel (as differentiated from running slope).

CURB CUT is an interruption of a curb at a pedestrian way, which separates surfaces that are substantially at the same elevation.

CURB RAMP is a sloping pedestrian way, intended for pedestrian traffic, which provides access between a walk or sidewalk and a surface located above or below an adjacent curb face, as differentiated from a ramp.

DETECTABLE WARNING is a standardized surface or feature built into or applied to walking surfaces or other elements to warn visually impaired persons of hazards in the path of travel. Only approved DSA-AC detectable warning products and directional surfaces shall be installed as provided in the California Code of Regulations (CCR), Title 24, Part 1, Articles 2, 3 and 4. Refer to CCR Title 24, Part 12, Chapter 12-11A and B, for building and facility access specifications for product approval for detectable warning products and directional surfaces.

Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect-Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

DWELLING UNIT is a single unit of residence for a family of one or more persons. Examples of dwelling units covered by this chapter include condominiums, an apartment unit within an apartment building and other types of dwellings in which sleeping accommodations are provided but toileting or cooking facilities are shared by occupants of more than one room or portion of the dwelling. Examples of the latter include dormitory rooms and sleeping accommodations in shelters intended for occupancy as residences for homeless persons.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

ELEMENT is an architectural or mechanical component of a building, facility, space or site; for example, a telephone, curb ramp, door, drinking fountain, seating or water closet.

ELEVATOR, PASSENGER is an elevator used primarily to carry passengers.

ENTRANCE means any access point to a building or portion of a building or facility used for the purpose of entering. An entrance includes the approach walk, the vertical access leading to the entrance platform, the entrance platform itself, vestibules if provided, the entry door(s) or gate(s), and the hardware of the entry door(s) or gate(s).

EQUIVALENT FACILITATION is an alternate means of complying with the literal requirements of these standards and specifications that provides access in terms of the purpose of these standards and specifications. See Section 1.9.1.5.

EXIT. See Section 1002.1.

FACILITY (or FACILITIES) is a building, structure, room, site, complex or any portion thereof that is built, altered, improved or developed to serve a particular purpose. Facilities shall include all or any portion of buildings, structures, site developments, complexes, equipment, roads, walks, sidewalks, passageways, parking lots or other real or personal property located on a site.

GRAB BAR is a bar for the purpose of being grasped by the hand for support.

GUARD (or GUARDRAIL). See Section 1002.1.

HANDRAIL. See Section 1002.1.

HEALTH CARE PROVIDER. See “Professional office of a health care provider.”

IF, IF...THEN denotes a specification that applies only when the conditions described are present.

INDEPENDENT ENTITY. See Section 202. Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect–Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

INTERNATIONAL SYMBOL OF ACCESSIBILITY is that symbol adopted by Rehabilitation International’s 11th World Congress for the purpose of indicating that buildings and facilities are accessible to persons with disabilities. See Figure 11B-6.

KICK PLATE is an abrasion-resistant plate affixed to the bottom portion of a door to prevent a trap condition and protect its surface.

LEVEL AREA is a specified surface that does not have a slope in any direction exceeding one unit vertical in 50 units horizontal (2-percent slope).

LIFT, PLATFORM (WHEELCHAIR). See “Platform (Wheelchair) Lift.”

MARKED CROSSING is a crosswalk or other identified path intended for pedestrian use in crossing a vehicular way.

MAY denotes an option or alternative.

NEWLY CONSTRUCTED. See Chapter 11A, Section 1107A.14-N.

NOSE, NOSING is that portion of a stair tread or landing at the top of a stairway flight projecting beyond the face of the riser immediately below.

OPEN RISER is the space between two adjacent stair treads not closed by a riser.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

OPERABLE PART is a part of a piece of equipment or appliance used to insert or withdraw objects, or to activate, deactivate or adjust the equipment or appliance (for example, coin slot, pushbutton, handle).

PASSAGE DOOR is a door other than an exit door through which persons may traverse.

PATH OF TRAVEL is a passage that may consist of walks and sidewalks, curb ramps and pedestrian ramps, lobbies and corridors, elevators, other improved areas or a necessary combination thereof, that provides free and unobstructed access to and egress from a particular area or location for pedestrians and/or wheelchair users. A “path of travel” includes a continuous, unobstructed way of pedestrian passage by means of which a particular area may be approached, entered and exited, and which connects a particular area with an exterior approach (including sidewalks, streets, and parking areas), an entrance to the facility, and other parts of the facility. In existing buildings, when alterations, structural repairs or additions are made, the term “path of travel” also includes the sanitary facilities, telephones, drinking fountains and signs serving the altered area.

PEDESTRIAN is an individual who moves in walking areas with or without the use of walking assistive devices such as crutches, leg braces, wheelchairs, white cane, service animal, etc.

PEDESTRIAN GRADE SEPARATION is a structure erected over or under an obstacle such as a freeway, roadway, street, railroad, stream, etc., and intended primarily for pedestrian use.

PEDESTRIAN WAY is a route by which a pedestrian may pass.

PLATFORM. See Section 410.2.

PLATFORM (WHEELCHAIR) LIFT is a hoisting and lowering mechanism equipped with a car or platform or support that serves two landings of a building or structure and is designed to carry a passenger or passengers and (or) luggage or other material a vertical distance as may be allowed.

PROFESSIONAL OFFICE OF A HEALTH CARE PROVIDER is a location where a person or entity, regulated by the State to provide professional services related to the physical or mental health of an individual, makes such services available to the public. The facility housing the professional office of a health care provider only includes floor levels housing at least one health care provider, or any floor level designed or intended for use by at least one health care provider.

PUBLIC USE AREA means interior or exterior rooms or spaces of a building that are made available to the general public and does not include common use areas. Public use areas may be provided at a building that is privately or publicly owned.

PUBLIC WAY. See Section 1002.1.

RAMP is a walking surface which has a running slope greater than one unit vertical in 20 units horizontal (5-percent slope) intended for pedestrian traffic and as differentiated from a curb ramp.

RISER is the upright member between two adjacent stair treads.

RUNNING SLOPE is the slope that is parallel to the direction of travel (as differentiated from cross slope).

SHALL denotes a mandatory specification or requirement.

SHOPPING CENTER (or SHOPPING MALL) is one or more sales or rental establishments or stores. A shopping center may include a series of buildings on a common site, connected by a common pedestrian access route on, above or below the ground floor, that is either under common ownership or common control or developed either as one project or as a series of related projects. For the purposes of this section, “shopping center” or “shopping mall” includes a covered mall building.

SHOULD denotes an advisory specification or recommendation.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SIDEWALK. See Section 202.

SLEEPING ACCOMMODATIONS are rooms in which people may sleep; for example, dormitory and hotel or motel guest rooms or suites.

SPECIFIED PUBLIC TRANSPORTATION is transportation by bus, rail or any other conveyance (other than by aircraft) that provides the general public with general or special service (including charter service) on a regular and continuing basis.

STAGE. See Section 410.2.

STAIR. See Section 1002.1.

STAIRWAY. See Section 1002.1.

STORY means that portion of a building included between the upper surface of any floor and the upper surface of the floor next above, except that the topmost story shall be that portion of a building included between the upper surface of the topmost floor and the ceiling or roof above. If the finished floor level directly above a basement or unused under-floor space is more than six feet (1829 mm) above grade for more than 50 percent of the total perimeter or is more than 12 feet (3658 mm) above grade at any point, the basement or unused under-floor space shall be considered as a story. There may be more than one floor level within a story as in the case of a mezzanine or mezzanines.

STORY, FIRST means the lowest story in a building which qualifies as a story and which provides the basic services or functions for which the building is used. A floor level in a building having only one floor level shall be classified as a first story, if the floor level is not more than 4 feet (1219 mm) below grade, for more than 50 percent of the total perimeter, or more than 8 feet (2438 mm) below grade at any point.

STRUCTURAL FRAME is considered to be the columns and the girders, beams, trusses and spandrels having direct connections to the columns and all other members which are essential to the stability of the building as a whole.

TEXT TELEPHONE is machinery or equipment that employs interactive text-based communications through the transmission of coded signals across the standard telephone network. Text telephones can include, for example, devices known as TTYs (teletypewriters) or computers.

TRANSIENT LODGING is a building, facility or portion thereof, excluding inpatient medical care facilities, that contains one or more dwelling units or sleeping accommodations. Transient lodging may include, but is not limited to, resorts, group homes, hotels, motels and dormitories.

TRANSIT BOARDING PLATFORM is a horizontal, generally level surface, whether raised above, recessed below or level with a transit rail, from which persons embark/disembark a fixed rail vehicle.

TREAD is the horizontal member of a step.

VEHICULAR WAY is a route intended for vehicular traffic, such as a street, driveway or parking lot.

WALK is a surfaced pedestrian way not located contiguous to a street used by the public. (As differentiated from the definition of "Sidewalk" in Section 202.)

WORK STATION is an area defined by equipment and/or work surfaces intended for use by employees only, and generally for one or a small number of employees at a time. Examples include ticket booths; the employee side of grocery store checkstands; the bartender area behind a bar; the employee side of snack bars, sales counters and public counters; guardhouses; toll booths; kiosk vending stands; lifeguard stations; maintenance equipment closets; counter and equipment areas in restaurant kitchens; file rooms; storage areas; etc.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1103B BUILDING ACCESSIBILITY

1103B.1 Scope. Accessibility to buildings or portions of buildings shall be provided for all occupancy classifications except as modified or enhanced by this chapter. Occupancy requirements in this chapter may modify general requirements, but never to the exclusion of them. When a building or facility contains more than one use, the occupancy specific accessibility provisions for each portion of the building or facility shall apply.

An accessible route of travel complying with Section 1114B.1.2 shall connect all elements and spaces within a building or facility. Multistory buildings and facilities must provide access to each level, including mezzanines, by ramp or passenger elevator complying with Section 1116B. If more than one elevator is provided, each passenger elevator shall comply with Section 1116B.

Exceptions:

1. Floors or portions of floors not customarily occupied, including, but not limited to, nonoccupiable or employee spaces accessed only by ladders, catwalks, crawl spaces, very narrow passageways or freight (nonpassenger) elevators, and frequented only by service personnel for repair or maintenance purposes, including, but not limited to, elevator pits and elevator penthouses, piping and equipment catwalks, and machinery rooms.
2. The following types of privately funded multistory buildings do not require a ramp or elevator above and below the first floor:
 - 2.1. Multistoried office buildings (other than the professional office of a health care provider) and passenger vehicle service stations less than three stories high or less than 3,000 square feet (279 m²) per story.
 - 2.2. Any other privately funded multistoried building that is not a shopping center, shopping mall or the professional office of a health care provider, or a terminal, depot or other station used for specified public transportation, or an airport passenger terminal and that is less than three stories high or less than 3,000 square feet (279 m²) per story if a reasonable portion of all facilities and accommodations normally sought and used by the public in such a building are accessible to and usable by persons with disabilities.

The elevator exception set forth in this section does not obviate or limit in any way the obligation to comply with the other accessibility requirements in this code. For example, floors above or below the accessible ground floor must meet the requirements of this section except for elevator service. If toilet or bathing facilities are provided on a level not served by an elevator, then toilet or bathing facilities must be provided on the accessible ground floor.

If a building or facility is eligible for this exception but a passenger elevator is nonetheless planned, that elevator shall meet the requirements of Section 1116B and shall serve each level in the building. A passenger elevator that provides service from a garage to only one level of a building or facility is not required to serve other levels.

In existing buildings, where elevators are required by Section 1134B.2 or 1103B.1, if an escalator or stair is installed where none existed previously and major structural modifications are necessary for such installation, then a means of accessible vertical access via ramp, elevator or lift shall be provided.

1103B.2 Distance to elevators. In new construction of buildings where elevators are required by Section 1103B.1, and which exceed 10,000 square feet (929 m²) on any floor, an accessible means of vertical access via ramp, elevator or lift shall be provided within 200 feet (60 960 mm) of travel of each stair and each escalator. In existing buildings that exceed 10,000 square feet (929 m²) on any floor and in which elevators are required by Sections 1134B.2 and 1103B.1, whenever a newly constructed means of vertical access is provided via stairs or an escalator, an accessible means of vertical access via ramp, elevator or lift shall be provided within 200 feet (60 960 mm) of travel of each new stair or escalator.

Exception: Stairs used solely for emergency egress.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1104B ACCESSIBILITY FOR GROUP A OCCUPANCIES

1104B.1 General. All Group A occupancies shall be accessible as provided in this chapter. See also the general requirements in Section 1114B.1.1.

1104B.2 Assistive-listening systems in assembly areas. Assembly areas, conference and meeting rooms shall provide assistive-listening systems for persons with hearing impairments as provided in this section.

Exception: This section does not apply to systems used exclusively for paging, or background music, or a combination of these two uses.

- 1. Number of personal receivers required.** The minimum number of receivers to be provided shall be equal to 4 percent of the total number of seats, but in no case less than two.
- 2. Types of listening systems.** Types of assistive-listening systems include, but are not limited to, audio-induction loops, radio frequency systems (AM or FM) and infrared transmission.
- 3. Location.** If the assistive-listening system provided is limited to specific areas or seats, then such areas or seats shall be within a 50-foot (15 240 mm) viewing distance of the stage or playing area and shall have a complete view of the stage or playing area.
- 4. Signage.** A sign shall be posted in a prominent place (for example, a customer service counter, ticket booth or assembly area entrance) indicating the availability of assistive-listening devices. The sign complying with Section 1117B.5.1, Items 2 and 3 shall include the International Symbol of Access for Hearing Loss complying with Figure 11B-14C and include wording that states "Assistive-Listening System Available."
- 5. Fees and charges.** Nothing in this section shall preclude a facility charging for such assistive-listening system its usual fee for audiovisual equipment. However, no surcharge may be placed directly on any particular individual with a disability or any group of individuals with disabilities to cover the costs of such equipment.
- 6. Permanent and portable systems.** Permanently installed assistive-listening systems are required in areas if (1) they accommodate at least 50 persons or if they have audio-amplification systems, and (2) they have fixed seating. If portable assistive-listening systems are used for conference or meeting rooms, the system may serve more than one room. An adequate number of electrical outlets or other supplementary wiring necessary to support a portable assistive-listening system shall be provided.

1104B.3 Auditoriums, assembly halls, theaters and related facilities.

1104B.3.1 Seating. In all assembly places where seating is provided, there shall be spaces for persons using wheelchairs and semi-ambulant persons, as provided in this section.

Exceptions:

- 1.** In existing buildings and facilities when the enforcing agency determines that compliance with the seating requirements of this code would create an unreasonable hardship, such requirements shall not apply. When the unreasonable hardship finding is applied, at least 1 percent of the total seating provided shall be accessible to and usable by persons with disabilities who use wheelchairs, and such seating shall comply with the level requirements and the individual space requirements of this code.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. When an existing theater is subdivided into more than one facility having upper levels not accessible by ramp or elevator, and the enforcing agency determines that full compliance with this code would create an unreasonable hardship, such upper levels need not be made accessible, provided all facilities at grade are accessible and any event, showing of motion pictures or other activities made available to the public in all of the facilities are scheduled to ensure that all such functions are available to the public in the accessible facility.

1104B.3.2 Accessibility to key facilities. Seating for persons with disabilities shall be accessible from the main lobby or from a primary entrance, together with related toilet facilities.

1104B.3.3 Variety of locations. Accessible seating or accommodations in places of public amusement and resort, including theaters, concert halls and stadiums, shall be provided in a variety of locations so as to provide persons with disabilities a choice of admission prices otherwise available to members of the general public.

1104B.3.4 Wheelchair spaces.

1. The number of such spaces is as shown in Table 11B-1.

**TABLE 11B-1
WHEELCHAIR SEATING SPACES**

SEATING CAPACITY	NO. OF WHEELCHAIR SEATING SPACES
4 to 25	1
26 to 50	2
51 to 300	4
301 to 500	6

In addition, 1 percent, but not less than one, of all fixed seats, shall be aisle seats with no armrests on the aisle side, or removable or folding armrests on the aisle side. Each such seat shall be identified by a sign or marker with the International Symbol of Accessibility (see Figure 11B.6). Signage notifying patrons of the availability of such seats shall be posted at the ticket office. Signs and markers shall comply with Section 1117B.5.1, Items 2 and 3, as applicable.

2. When the seating capacity exceeds 500, one additional wheelchair seating space shall be provided for each total seating capacity increase of 100.
3. The ground or floor at spaces shall be level and shall comply with Section 1124B.

1104B.3.5 Placement of wheelchair locations. Wheelchair areas shall be an integral part of any fixed seating plan, and shall be arranged so as to provide persons with disabilities a choice of admission prices and lines of sight comparable to those for members of the general public. Each wheelchair area shall adjoin an accessible route which shall also serve as a means of egress in case of emergency. At least one companion fixed seat shall be provided next to each wheelchair seating area. When the seating capacity exceeds 300, wheelchair spaces shall be provided in more than one location in addition to complying with Section 1104B.3.3.

Exceptions:

1. Accessible viewing positions where seating capacity is less than 300 may be clustered for bleachers, balconies and other areas having sight lines that require slopes of greater than one unit vertical in 20 units horizontal (5-percent slope). Equivalent accessible viewing positions may be located on levels having accessible egress.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. *Where it is determined that dispersing accessible seating throughout an existing assembly area would create an unreasonable hardship, accessible seating areas may be clustered. Each accessible seating area shall have provisions for companion seating and shall be located on an accessible route that also serves as a means of emergency egress.*

1104B.3.6 Size of wheelchair location. *Each wheelchair location shall provide minimum clear floor or ground space as shown in Figure 11B-15, and shall adjoin an egress aisle on at least one side.*

1104B.3.7 Removable seats. *Readily removable seats may be installed in these wheelchair spaces when such spaces are not required to accommodate wheelchair users.*

1104B.3.8 Seating for semi-ambulant individuals. *In addition to spaces provided for wheelchair users as noted in Sections 1104B.3.4 through 1104B.3.7 above, there shall be provided seating for semi-ambulant individuals. The number of such seating shall be equal to at least 1 percent of the total seating and shall be no fewer than two. Such seats shall provide at least 24 inches (610 mm) clear leg space between the front of the seat to the nearest obstruction or to the back of the seat immediately in front.*

1104B.3.9 Life safety. *In determining the location of seating for persons with disabilities, life safety shall be considered, and all seating provided must comply with the fire and panic safety requirements of the State Fire Marshal.*

1104B.3.10 Access to performing areas. *An accessible route shall connect wheelchair seating locations with performing areas, including stages, arena floors, dressing rooms, locker rooms and other spaces used by performers.*

1104B.3.11 Stages, enclosed and unenclosed platforms, and orchestra pits. *Stages, enclosed and unenclosed platforms and orchestra pits shall be made accessible to persons with disabilities.*

Exceptions:

1. *When the enforcing agency finds that requiring compliance with this code, for an enclosed or unenclosed platform or depressed area not more than 24 inches (610 mm) above or below an adjacent accessible level, would create an unreasonable hardship, the enclosed and unenclosed platform or depressed area shall be made accessible by a portable ramp with a slope not exceeding 1 unit vertical in 12 units horizontal (8.33 percent slope).*
2. *In existing buildings and facilities, all stages, enclosed or unenclosed platforms, and orchestra pits need not be accessible when the enforcing agency determines that compliance with this code would create an unreasonable hardship.*

1104B.3.12 Ticket booths. *Customer and employee sides of ticket booths and of concession and refreshment sales facilities shall be made accessible to persons with disabilities.*

1104B.3.13 Miscellaneous areas. *Public toilets and other public areas shall be made accessible to persons with disabilities.*

1104B.4 Stadiums, grandstands, bleachers, athletic pavilions, gymnasiums and miscellaneous sport-related facilities.

1104B.4.1 Spectator seating. *Spectator seating shall comply with Section 1104B.3.*

1104B.4.2 Ticket booth. *Ticket booths shall comply with Section 1104B.3.12.*

1104B.4.3 Participation areas. *Participation areas shall be accessible to persons with disabilities, including the following listed and similar activity areas:*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1. *Tennis, racquetball and handball courts.*
2. *Gymnasium floor areas and general exercise rooms.*
3. *Basketball, volleyball and badminton courts, and bowling lanes.*
4. *Swimming pool deck areas shall be accessible, and a mechanism to assist persons with disabilities in gaining entry into the pool and in exiting from the pool shall be provided. Such a mechanism may consist of a swimming pool lift device that meets all of the following criteria:*
 - 4.1. *Have a seat that meets all of the following:*
 - 4.1.1. *The seat shall be rigid;*
 - 4.1.2. *The seat shall be not less than 17 inches (423 mm) and not more than 19 inches (483 mm), inclusive of any cushioned surface that might be provided, above the pool deck;*
 - 4.1.3. *The seat shall have two armrests. The armrest on the side of the seat by which access is gained shall be either removable or fold clear of the seat;*
 - 4.1.4. *The seat shall have a back support that is at least 12 inches (305 mm) tall;*
 - 4.1.5. *The seat shall have an occupant restraint for use by the occupant of the seat, and the restraint shall meet the standards for operable controls in compliance with Section 1117B.6, Items 1 through 4.*
 - 4.2. *Be capable of unassisted operation from both the deck and water levels.*
 - 4.3. *Be stable and not permit unintended movement when a person is getting into or out of the seat.*
 - 4.4. *Be designed to have a live-load capacity of not less than 300 pounds (137 kg).*
 - 4.5. *Be positioned so that, if the pool has water of different depths, it will place the operator into water that is at least 3 feet (914 mm) deep.*
 - 4.6. *Lower the operator at least 18 inches (457 mm) below the surface of the water.*
5. *Athletic team rooms and facilities, playing fields and running tracks.*

1104B.4.4 Clubrooms. *Clubrooms shall be made accessible to persons with disabilities.*

1104B.4.5 Sanitary and locker facilities. *Where spectator and/or participant sanitary and/or locker facilities are provided, they shall conform with the requirements in Section 1115B.*

1104B.5 Dining, banquet and bar facilities.

1. **General.** *Dining, banquet, and bar facilities shall be made accessible to persons with disabilities as provided in this section. All areas where each type of functional activity occurs shall be made accessible.*

Exceptions:

1. *Existing buildings, when the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. *Existing buildings, these regulations shall not apply when legal or physical constraints would not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.*
- 2. Entrance.** *Access to these facilities shall be provided at entrances and exits as required by Section 1133B.1.1.*
- 3. Raised or sunken areas.** *All raised or sunken areas, including dining areas, loggias and outdoor seating areas, shall be accessible. A raised platform where a head table or speaker's lectern is located shall be accessible. Open edges of raised or sunken areas shall be protected as required by Sections 1013 Guards, 1133B.8.1 Warning Curbs, or by other means as required by this code. For existing buildings, see Section 1120B, Floors and Levels.*
- 4. Seating.** *Each dining, banquet and bar area shall have one wheelchair seating space for each 20 seats, with at least one minimum wheelchair seating space per functional area. Such seating shall be designed and arranged to permit use by wheelchair occupants, and shall comply with Section 1122B, Fixed or Built-in Seating, Tables, and Counters. Access to such seating spaces shall be provided with main aisles not less than 36 inches (914 mm) clear width. In establishments where separate areas are designated for smoking and non-smoking patrons, the required number of accessible fixed tables (or counters) shall be proportionally distributed between the smoking and non-smoking areas. Accessible seating spaces shall be integrated with general seating to allow a reasonable selection of seating area and to avoid having one area specifically highlighted as the area for persons with disabilities. The ratio of accessible seating is based on the total number of seats provided. Where food or drink is served at counters exceeding 34 inches (865 mm) in height for consumption by customers seated or standing at the counter, a portion of the main counter which is 60 inches (1525 mm) in length minimum shall be provided in compliance with Section 1122B.*
- 5. Food service aisles.** *Food service aisles shall be a minimum of 36 inches (914 mm) of clear width with a preferred width of 42 inches (1067 mm) where passage of stopped wheelchairs by pedestrians is desired. Tray slides shall be mounted no higher than 34 inches (864 mm) above the floor as shown in Figure 11B-16. If self-service shelves are provided, at least 50 percent of each type must be within the reach ranges in Sections 1118B.5 and 1118B.6.*
- 6. Tableware and condiment areas.** *Self-service tableware, dishware, condiments, food and beverage display shelves and dispensing devices shall comply with Sections 1118B and 1122B.4. See Figure 11B-17.*
- 7. Restrooms.** *Restrooms and powder rooms shall conform to the requirements in Section 1115B.*
- 8. Food preparation areas.** *Access to food preparation areas shall comply with the provisions for entrance doors and doorways in Section 1008, and aisles in Sections 1017 and 1017.2.*

1104B.6 Religious facilities.

1104B.6.1 General. *Religious facilities shall be made accessible to persons with disabilities as provided in this section.*

Exception: *In existing buildings, when the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided.*

1104B.6.2 Sanctuary. *Sanctuary areas shall be made accessible to persons with disabilities.*

1104B.6.2.1 *Wheelchair seating spaces in these areas shall conform to the requirements in Section 1104B.3.1.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1104B.6.2.2 *Wheelchair access shall be provided to raised platforms, choir rooms, choir lofts, performing areas and other similar areas.*

Exception: *In existing buildings, these regulations shall not apply to choir lofts when the enforcing agency determines that such compliance would create an unreasonable hardship.*

1104B.6.3 Assembly areas. *Assembly areas shall be made accessible to persons with disabilities. Enclosed and unenclosed platforms and stages in assembly areas shall conform to these requirements.*

1104B.6.4 Classrooms and offices. *Classrooms and offices shall have entry doors that conform to the requirements in Chapter 10.*

1104B.6.5 Sanitary facilities. *Sanitary facilities shall conform to the requirements in Section 1115B.*

SECTION 1105B ACCESSIBILITY FOR GROUP B OCCUPANCIES

Group B occupancies shall be accessible as provided in this chapter. See also the general requirements in Section 1114B.1.1.

Exceptions:

- 1. In existing buildings, when the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided.*
- 2. In existing buildings, the provisions of this section shall not apply when legal or physical constraints will not allow compliance with these building standards or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.*
- 3. For floors and levels in new and existing buildings, see Section 1120B.*

1105B.1 General. *The provisions of this section apply to the specified types of facilities and identify specific requirements of accessibility and usability which shall be provided for each of the listed occupancy uses.*

1105B.2 Group B occupancies. *Group B Occupancies used for assembly purposes shall conform to the requirements as specified in Section 1114B.1.1. For floors and levels in dining, banquet and bar facilities, see Section 1120B.*

1105B.3 Office buildings and personal and public service facilities. *Office buildings and personal and public service facilities shall conform to the provisions of this section.*

1105B.3.1 Facilities covered. *Facilities covered in this section are those that are used by the public as customers, clients, visitors or which are potentially places of employment and shall include, but not be limited to, the following requirements:*

- 1. All types of general and specialized business professional offices, including those related to professional medicine or dentistry, insurance, real estate, attorneys, credit bureaus, consultants, counseling and accounting.*
- 2. All types of sales establishments, including outlets for all general and special merchandise and equipment, including personal and household furnishings and supplies, foods, sporting equipment, office supplies, vehicles and related parts and supplies, building materials and pet shops.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. *All personal and public service facilities, including banks, savings and loan companies, credit unions, newspaper and printing establishments, photographic studios, launder mats, cleaning and laundry outlets, veterinarian clinics and hospitals, automobile rental agencies, travel bureaus, public utility facilities, police stations and detention facilities, courtrooms and fire stations.*
4. *In addition to the requirements of this section, all areas used for business transactions with the public shall comply with Sections 1110B.1 Sales and 1122B Fixed or Built in Seating, Tables, and Counters.*

1105B.3.2 Business and professional offices. *Areas to be made accessible include the following:*

1. *Client and visitor areas and office areas, together with related toilet rooms.*
2. *Conference rooms, counseling rooms or cubicles and similar areas.*
3. *Employee work areas shall have a minimum of 36 inches (914 mm) clear width access, except as modified in other portions of these regulations. See Sections 1133B.6.1 and 1133B.6.2.*
4. *Professional medical and dental offices shall be made accessible and shall also comply with Section 1109B.*

1105B.3.3 Personal and public service facilities. *Areas to be made accessible include the following:*

1. *Client and visitor areas, office areas, and related toilet rooms shall be made accessible.*
2. *Employee work areas shall have a minimum of 36 inches (914 mm) clear width access, except as modified in other portions of these regulations. See Sections 1133B.6.1 and 1133B.6.2.*
3. *Automated teller machines used by a financial institution and its customers for the primary purposes of executing financial transactions shall be located on an accessible route of travel complying with Section 1114B.1.2 and shall comply with Section 1117B.7.*

1105B.3.4 Public utility facilities. *Areas to be made accessible include the following:*

1. *Office areas, meeting rooms and similar areas together with related toilet rooms shall be made accessible.*
2. *Public tour areas, to the extent that such public tours are conducted through or about a facility, or where the public is permitted to walk in such areas, shall provide accessibility in those portions of the facility and grounds where this occurs.*

Exceptions:

1. *Facilities located in operational areas which would not have any reasonable availability to or usage by persons who use wheelchairs for mobility are not subject to the wheelchair accessibility requirements of these regulations.*
2. *When the enforcing agency determines that compliance with this subsection would create an unreasonable hardship, an exception to such provision shall be granted when equivalent facilitation is provided.*
3. *Visitor overlook facilities, orientation areas and similar public use areas, and any sanitary facilities that serve these facilities shall be made accessible.*
4. *Where public parking is provided, spaces shall be provided for persons with disabilities as specified in Sections 1129B and 1130B.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1105B.3.5 Police department, law enforcement, fire department facilities and courtrooms. Areas to be made accessible include the following:

1. Office areas, conference rooms, classrooms, dispatch rooms and similar areas, along with related sanitary facilities, shall be made accessible.
2. Detention area visitor rooms shall be made accessible.
3. At least one detention cell facility with supporting sanitary facilities shall be made accessible.
4. Courtroom areas, including the judge's chambers and bench, counsel tables, jury box, witness stand and public seating area shall be made accessible.

1105B.3.6 Miscellaneous general standards.

1. Circulation aisles and pedestrian ways shall be sized according to functional requirements and in no case shall be less than 36 inches (914 mm) in clear width.
2. Storage areas. The doorway providing access to all such areas shall not be less than 32 inches (813 mm) in clear width. Storage areas shall be made accessible in the number and dimensions provided in Section 1125B.

SECTION 1106B ACCESSIBILITY FOR GROUP E OCCUPANCIES

1106B.1 General. Group E occupancies shall be accessible as provided in this chapter. See also the general requirements in Section 1114B.1.1.

Exceptions:

1. In existing buildings, when the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided.
2. In existing buildings, where the enforcing agency determines that, because of physical constraints, compliance with these regulations or equivalent facilitation would create an unreasonable hardship, these regulations shall not apply. See Section 1.9.1.5.

1106B.2 Laboratory rooms. Laboratory rooms shall have at least one workstation and at least 5 percent of all workstations accessible to and usable by persons with disabilities in compliance with Section 1118B, Space Allowance and Reach Ranges, and Section 1122B, Fixed or Built-in Seating, Tables, and Counters.

Exception: Where the enforcing agency determines that it would create an unreasonable hardship to require compliance with these regulations for special use rooms such as laboratory preparation rooms, supply rooms, small research laboratories, and areas containing specialized equipment not readily usable by persons with particular disabilities, such facilities need not comply with these regulations, except that a clear width of 32 inches (813 mm) shall be maintained into such rooms.

1106B.3 Teaching facility cubicles, study carrels, etc. Teaching facility cubicles, study carrels, etc., shall have 5 percent, but always at least one cubicle or carrel in each group (language, dental, audiovisual, typing, drafting, darkrooms, etc.) made accessible to and usable by persons with disabilities in compliance with Section 1118B, Space Allowance and Reach Ranges, and Section 1122B, Fixed or Built-in Seating, Tables and Counters.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1106B.4 Library general use areas.

1. **General.** Library general use areas such as those housing card files, book stacks, periodicals, reading and study areas, reference areas, information desks, circulation counters, reserve areas, special facilities or collections, etc., shall be made accessible to persons with disabilities.
2. **Open book stacks.** Open book stacks (those available for customer use) shall be on an accessible route complying with Section 1114B.1.2, may be of normal height, and shall have main aisles no less than 44 inches (1118 mm) in clear width and side, range and end aisles no less than 36 inches (914 mm) in clear width.

In existing buildings, multitiered, closed book stacks (those restricted to employee use) are exempt from these accessibility standards.
3. **Height of book shelves.** Unless an attendant is available to assist persons with disabilities, all book shelving shall be located not more than 54 inches (1372 mm) above the floor.
4. **Card catalogs and magazine displays.** Minimum clear aisle space and maximum reach heights at card catalogs and magazine displays shall comply with Section 1118B, with a height of 48 inches (1219 mm) preferred irrespective of reach allowed.
5. **Reading and study areas.** At least 5 percent or a minimum of one of each element of fixed seating, tables, study carrels, computers or similar workstations shall be on an accessible route complying with Section 1114B.1.2, and shall comply with Section 1118B, "Space Allowance and Reach Ranges", Section 1122B, "Fixed or Built-in Seating, Tables, and Counters" and Section 1133B.6 "Aisles".
6. **Check-out areas.** At least one lane at each check-out area shall be on an accessible route complying with Section 1114B.1.2, and shall have a portion of the counter which is at least 36 inches (914 mm) in length with a maximum height of 34 inches (864 mm) above the finish floor with a 36 inch (914 mm) wide aisle on the customer side. Any traffic control or book security gates or turnstiles shall comply with Section 1133B.2.3.4.

SECTION 1107B FACTORIES AND WAREHOUSES

Factories and warehouses shall conform to the provisions of this section, Section 1103B.1 and 1103B.1, Exception 2, for multistory buildings. See also the general requirements in Section 1114B.1.1.

Exception: In existing buildings, when the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided.

1107B.1 Factories.

1. Major or principal floor areas shall be made accessible.
2. Office areas shall be made accessible.
3. Sanitary facilities serving these areas shall be made accessible.

1107B.2 Warehouses.

1. Miscellaneous warehousing areas which are located on the floor nearest grade and those areas on other floors that are otherwise provided with access by level entry, ramp or elevator shall be made accessible.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. Office areas shall be made accessible.
3. Sanitary facilities serving these areas shall be made accessible.

SECTION 1108B ACCESSIBILITY FOR GROUP H OCCUPANCIES

1108B.1 General. Group H occupancies shall be accessible as provided in this chapter. See also the general requirements in Section 1114B.1.1.

Exceptions:

1. In existing Group H occupancies, when the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation and protection are provided.
2. In existing Group H occupancies, the provisions of this section shall not apply when legal or physical constraints prevent compliance with these building standards or the provisions of equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.

1108B.2 Accessible sanitation facilities. Accessible sanitation facilities in all Group H occupancies shall be provided as specified in this chapter.

1108B.3 Accessible routes. Entrances, stairs, ramps, doors, turnstiles, corridors, walks, sidewalks and hazards shall provide accessibility as specified in Section 1133B.

1108B.4 Accessible floors and levels. Accessible floors and levels shall comply with the requirements specified in this chapter.

1108B.5 Employee work areas. Employee work areas shall be accessible by means of a 36-inch (914 mm) minimum aisle width and a 32-inch (813 mm) minimum clear opening door width, as specified in Sections 1133B.6.1 and 1133B.6.2.

1108B.6 Accessible facilities covered in this chapter are those that are used by the public as customers, clients, visitors or which are potential places of employment.

SECTION 1109B ACCESSIBILITY FOR GROUP I OCCUPANCIES

1109B.1 General. All Group I occupancies shall be accessible as provided in this chapter. See also the general requirements in Section 1114B.1.1.

Exception: In existing buildings, when the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided.

1109B.2 Entrance. At medical care facilities in which people receive physical or medical treatment or care and where persons may need assistance in responding to an emergency and where the period of stay may exceed twenty-four hours, at least one accessible entrance shall be protected from the weather by canopy or roof overhang. Such entrances shall incorporate a passenger loading zone complying with Section 11131B.2.

1109B.3 Patient bedrooms and toilet rooms. Patient bedrooms and associated toilet facilities shall be made accessible as follows:

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1. *Long-term care facilities, including skilled nursing facilities, intermediate care facilities, bed and care and nursing homes shall have at least 50 percent of patient bedrooms and toilet rooms, and all public use and common use areas, accessible.*
2. *General-purpose hospitals, psychiatric facilities and detoxification facilities shall have at least 10 percent of patient bedrooms and toilets, and all public use and common use areas, accessible.*
3. *Hospitals and rehabilitation facilities that specialize in treating conditions that affect mobility, or units within either that specialize in treating conditions that affect mobility, shall have all patient bedrooms and toilets and all public use and common use areas accessible.*

Exceptions:

1. *In existing buildings, when patient bedrooms are being added or altered as part of a planned renovation of an entire wing, a department, or other discrete area of an existing medical facility, the accessible rooms provided shall comply with Section 1109B.4 and shall be consistent with the percentage of rooms required to be accessible by 1109B.3, until the number of accessible patient bedrooms in the facility equals the overall number that would be required if the facility were newly constructed. (For example, if 20 patient bedrooms are being altered in the obstetrics department of a hospital, 2 of the altered rooms must be made accessible. If, within the same hospital, 20 patient bedrooms are being altered in a unit that specializes in treating mobility impairments, all of the altered rooms must be made accessible.) Where toilet/bathrooms are part of patient bedrooms which are added or altered and required to be accessible, each such patient toilet/bathroom shall comply with Section 1109B.5.*
2. *In existing buildings, when patient bedrooms are being added or altered individually, and not as part of an alteration of the entire area, the altered patient bedrooms shall comply with Section 1109B.4, unless either: a) the number of accessible rooms provided in the department or area containing the altered patient bedroom equals the number of accessible patient bedrooms that would be required if the percentage requirements of Section 1109B.3 were applied to that department or area; or b) the number of accessible patient bedrooms in the facility equals the overall number that would be required if the facility were newly constructed. Where toilet/bathrooms are part of patient bedrooms which are added or altered and required to be accessible, each such toilet/bathroom shall comply with Section 1109B.5.*

1109B.4 Patient bedroom areas. Accessible patient bedrooms shall comply with the following requirements:

1. *Each bedroom shall have a turning space measuring 60 inches (1524 mm) clear in diameter, or that is a T-shaped space complying with Figure 11B-12. In rooms with two beds, it is preferable that this space be located between beds.*
2. *Each bedroom shall have a minimum clear floor space of 36 inches (914 mm) along each side of the bed, and shall provide an accessible route to each side of the bed.*
3. *Each bedroom shall have an accessible door that complies with Section 1133B.2.*

1109B.5 Patient toilet rooms and bathing facilities. Patient toilet rooms and bathing facilities required to be accessible shall comply with Section 1115B.

1109B.6 Diagnostic and treatment areas. Diagnostic and treatment areas and, where applicable, at least one dressing room, sanitary facility, etc., for each unit or suite shall be made accessible.

1109B.7 Waiting areas, offices and sanitary facilities. Waiting areas, offices and sanitary facilities serving them shall be made accessible as covered in other portions of these standards.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1109B.8 Offices and suites. In buildings that house offices and suites of physicians, dentists, etc., all such offices or suites shall be made accessible, subject to other provisions of these regulations.

SECTION 1110B ACCESSIBILITY FOR GROUP M OCCUPANCIES

1110B.1 Sales.

1110B.1.1 General areas. General sales, display and office areas together with related toilet rooms shall be made accessible. See also the general requirements in Section 1114B.1.1.

Exceptions:

1. Minor specialized display areas that do not exceed 200 square feet (18.6 m²) in floor area and to which the general public is excluded need not be made accessible.
2. Offices in sales facilities that do not exceed 5,000 square feet (465 m²) in total area, that are located on nonaccessible levels, need not be made accessible.

1110B.1.2 Work areas. Sales employee workstations shall be located on accessible levels, and the customer side of sales or check-out stations shall be accessible. Employee work areas shall be sized and arranged to provide access to employees in wheelchairs.

1110B.1.3 Check stands. Where check stands are provided, the minimum number of check stands that are accessible shall be as shown in Table 11B-2. When not all check stands are accessible, accessible check stands shall be identified by a sign clearly visible to a person in a wheelchair displaying the International Symbol of Accessibility complying with Section 1117B.5.8. The sign shall be a minimum of 4 inches by 4 inches (102 mm by 102 mm). When check stands are open for customer use, a minimum of one accessible check stand shall always be available. As check stands are opened and closed based on fluctuating customer levels, the number of accessible check stands available shall comply with Table 11B-2.

**TABLE 11B-2
CHECK STANDS**

TOTAL NUMBER OF CHECK STANDS OF EACH DESIGN	MINIMUM NUMBER OF CHECK STANDS OF EACH DESIGN TO BE ACCESSIBLE
1 to 4	1
5 to 8	2
9 to 15	3
over 15	3 plus 20% of additional aisles

Accessible check stands shall provide a minimum clear checkout aisle width of 36 inches (914 mm) with a maximum adjoining counter height not exceeding 38 inches (965 mm) above the finish floor. The top of the counter lip shall not exceed 40 inches (1016 mm) above the finish floor.

In existing buildings, at least one checkout aisle shall be accessible in facilities with less than 5,000 square feet (465 m²) of selling space. In facilities of 5,000 square feet (465 m²) or more of selling space, at least one of each design of checkout aisle shall be made accessible when altered until the number of accessible checkout aisles of each design equals the number required in new construction.

Examples of checkout aisles of different design include those which are specifically designed to serve different functions. A different design includes, but is not limited to, the following features: length of belt or no belt, or permanent signage designating the aisle as an express lane.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1110B.1.4 Point-of-sale machines. All point-of-sale machines used by customers for the primary purpose of executing transactions between the business entity and the customer shall comply with Section 1117B.7.

1110B.1.5 Turnstiles. See Section 1133B.2.3.4.

1110B.1.6 Theft prevention barriers. Where shopping cart theft prevention barriers are used, they shall conform to the following requirements:

1. Each entrance and exit provided for public use shall be accessible to and usable by persons with disabilities.
2. Shopping cart barriers located at a public entrance or exit shall be designed to provide a clear, unobstructed opening at least 32 inches (813 mm) in width for ingress and egress of persons with disabilities.
3. Where gates are used, they shall open in the direction of travel, provide a clear unobstructed opening 32 inches (813 mm) in width and be maintained unlocked during business hours. Gates shall not operate a publicly audible alarm system or require more than 5 foot-pounds of force (22.2 N·m).
4. Where a clear unobstructed opening is provided, a level area is required on both sides of the clear opening or gate which extends a minimum of 44 inches (1118 mm) on each side of the opening and is at least 48 inches (1219 mm) in width.
5. Where a gate is used, the level area on both sides of the clear opening or gate shall be a minimum of 60 inches (1524 mm) in width and extend a minimum of 60 inches (1524 mm) (measured from the gate in a closed position) in the direction of the gate swing. The level area opposite the gate swing shall be a minimum of 48 inches (1219 mm) in width and extend a minimum of 42 inches (1067 mm).
6. Where a gate is used, the bottom of the gate shall be within 3 inches (76 mm) of the surface of the path of travel. The surface of the gate on each side shall be smooth to present no hazard to persons with disabilities using the gate and shall be structurally adequate to allow it to be opened with the wheelchair foot pedals.
7. The path of travel to and through the clear opening or gate shall be designed to prevent barriers from obstructing it and shall be continuously maintained unobstructed during business hours. Also, the design shall specifically prevent parked vehicles from obstructing ingress and egress.
8. Interior and exterior pedestrian traffic barriers (posts, rails, turnstiles, etc.) shall allow unobstructed travel for persons with disabilities through a 32-inch (813 mm) clear opening.

1110B.2 Miscellaneous general standards.

1110B.2.1 Circulation. Shelves or display units allowing self-service by customers in mercantile occupancies shall be located on an accessible route of travel complying with Section 1114B.1.2. Circulation aisles and pedestrian ways shall be sized according to functional requirements and in no case shall be less than 36 inches (914 mm) in clear width.

1110B.2.2 Storage areas. The doorway providing access to all such areas shall not be less than 32 inches (813 mm) in clear width. Storage areas shall be made accessible in the number and dimensions provided in Section 1125B.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1111B ACCESSIBILITY FOR GROUP R OCCUPANCIES

1111B.1 General. *Group R occupancies shall be accessible or adaptable as provided in this chapter. Public-use and common-use areas serving adaptable guest and/or dwelling units shall be accessible. See also the general accessibility requirements in Section 1114B.1.1.*

Exception: *When the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided.*

1111B.2 Public and common use rooms or areas. *Public- and common-use rooms and similar areas shall be made accessible to persons with disabilities, subject to specific provisions contained in other portions of these regulations. See also general requirements in Section 1114B.1.1.*

At least one of each type of amenity (such as washers, dryers and similar equipment installed for the use of occupants) in each common area shall be accessible and shall be located on an accessible route to any accessible unit or sleeping accommodation.

Exception: *Where elevators are not required, accessible amenities are not required on inaccessible floors as long as one of each type is provided in common areas on accessible floors.*

1111B.3 Recreational facilities. *When recreational facilities are provided, including swimming pools, they shall comply with Sections 1104B.4.3 and 1132B.2.*

1111B.4 Hotels, motels, inns, dormitories, resorts, homeless shelters, halfway houses, transient group homes and similar places of transient lodging. *Hotels, motels, inns, dormitories, resorts, homeless shelters, halfway houses, transient group homes and similar places of transient lodging shall provide access for persons with disabilities in accordance with the provisions of the accessibility requirements of this California Building Code, except as herein provided.*

Facilities with multibed rooms or spaces shall comply with Sections 1111B.4.2 and 1111B.4.3.

Occupancies which are not homeless shelters but are being altered to provide shelter accommodations shall meet the requirements of this section.

1111B.4.1 Available range of accommodations. *Accessible guest rooms or suites shall be dispersed among the various classes of sleeping accommodations to provide a range of options applicable to room sizes, costs, amenities provided and the number of beds provided.*

1111B.4.2 Guest rooms and suites. *Places of transient lodging shall incorporate the accessibility requirements of this code as modified by this chapter in at least one guest room or dormitory room together with their sanitary facilities as required in Table 11B-3. All accessible sleeping rooms or suites required by Table 11B-3 shall comply with the requirements of Section 1111B.4.5 for hearing impaired guests.*

1111B.4.2.1 Spaces. *Where provided as part of an accessible unit, sleeping room or suite, the following spaces shall be accessible and shall be on an accessible route complying with Section 1114B.1.2:*

1. *The living area;*
2. *The dining area;*
3. *At least one sleeping area;*
4. *Patios, terraces or balconies;*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

5. *Where full bathrooms are provided, at least one full bathroom (that is, one with a water closet, a lavatory and a bathtub or shower);*
6. *Where only half baths are provided, at least one half bath;*
7. *Carports, garages or parking spaces.*

1111B.4.2.2 Accessible route. *Guest rooms and suites shall be on an accessible route complying with Section 1114B.1.2. An accessible route shall also connect all accessible spaces and elements, including telephones, within the unit, sleeping room or suite.*

1111B.4.2.3 Doors.

1111B.4.2.3.1 Doors into and within covered rooms and suites. *Doors and doorways designed to allow passage into and within all sleeping rooms, suites or other covered units shall comply with Section 1133B.2.*

1111B.4.2.3.2 Doors into and within all other rooms and suites. *Doors and doorways designed to allow passage into and within all other sleeping rooms and suites shall comply with Section 1133B.2.2.*

1111B.4.2.4 Alterations in existing facilities. *When guest rooms are being altered in an existing facility, or portion thereof, subject to the requirements of this section, at least one guest room or suite that complies with the accessibility requirements of this code as modified by this chapter shall be provided for each 25 guest rooms, or fraction thereof, of rooms being altered until the number of such rooms provided equals the number required to be accessible in Table 11B-3. In addition, at least one guest room or suite that complies with the requirements of Section 1111B.4.5 shall be provided for each 25 guest rooms, or fraction thereof, of rooms being altered until the number of such rooms equals the number required to be accessible in Table 11B-4.*

1111B.4.3 Access to beds. *Accessible sleeping rooms shall have a 36-inch (914 mm) clear width maneuvering space located along both sides of a bed, except that where two beds are provided, this requirement can be met by providing a 36-inch-wide (914 mm) maneuvering space located between the beds.*

In addition, there shall be a clear space under the bed for the use of a personal lift device. The clear space shall be on a long side of the bed adjacent to an accessible aisle. The clear space shall extend horizontally to points not more than 12 inches (305 mm) from each end of the bed, vertically not less than 7 inches (178 mm), and not less than 30 inches (762 mm) deep.

1111B.4.4 Kitchens, kitchenettes or wet bar facilities. *When accommodations are provided with kitchens, kitchenettes, wet bar units or similar amenities, they shall be accessible and meet the requirements of Section 1133A. Kitchens shall be provided per the number required to be accessible in conformance with Table 11B-3.*

1111B.4.5 Visible alarms, notification devices and telephones for persons with hearing impairments. *In addition to those accessible sleeping rooms and suites required by Section 1111B.4.2, additional sleeping rooms and suites shall be provided with the following features as required by Table 11B-4 as follows:*

1111B.4.5.1 Visible alarms. *Visible alarms shall be provided and shall comply with NFPA 72 and Chapter 9, Section 907.5.2.3.*

1111B.4.5.2 Visual notification devices. *Visual notification devices shall also be provided in units, sleeping rooms and suites to alert room occupants of incoming telephone calls and a door knock or bell. Notification devices shall not be connected to visible alarm signal appliances.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1111B.4.5.3 Telephones. Permanently installed telephones shall have volume controls complying with Section 1117B.2.8; an accessible electrical outlet within 48 inches (1219 mm) of a telephone connection shall be provided to facilitate the use of a text telephone.

1111B.4.6 Bathrooms in hotels, motels, inns, dormitories, resorts, homeless shelters, halfway houses, transient group homes and similar places of transient lodging. Required accessible bathrooms for places of transient lodging shall comply with the following provisions:

1. **Doors.** Doors to accessible bathrooms shall comply with Section 1133B.2. Doors shall not swing into the floor space required for any fixture.
2. **Clear floor space.** All fixtures and controls shall be on an accessible route. There must be within the bathroom a clear floor space measuring 30 inches by 60 inches (762 mm by 1524 mm). The clear floor spaces at fixtures and controls, the accessible route and the turning space may overlap.
3. **Water closets.** If a toilet compartment is provided, it shall comply with Section 1115B.3.1 or 1115B.3.2; its water closet shall comply with Section 1115B.4.1 of this code.
4. **Lavatory and mirrors.** If a lavatory and/or mirror is provided, they shall comply with Sections 1115B.4.3 and 1115B.8.1, as applicable.
5. **Controls and dispensers.** If controls, dispensers, receptacles or other types of equipment are provided, then at least one of each shall be on an accessible route and shall comply with Section 1117B.6, Controls and Operating Mechanisms.
6. **Bathing and shower facilities.** If tubs or showers are provided, then at least one accessible tub that complies with Section 1115B.4.5 or at least one accessible shower that complies with Section 1115B.4.4 of this code shall be provided.
7. **Toilet facilities.** Toilet facilities shall comply with Section 1111B.4.6, as modified for hotel, motel and dormitory accommodations.

Hotel and motel bathrooms beyond those specified in Section 1111B.4 shall provide the following features:

1. All bathroom fixtures shall be in a location that allows a person using a wheelchair measuring 30 inches by 48 inches (762 mm by 1219 mm) to touch the wheelchair to any lavatory, urinal, water closet, tub, sauna, shower stall and any other similar sanitary installation, if provided.
2. All bathroom entrance doors shall have a clear opening width of 32 inches (813 mm) and shall be either sliding doors or shall be hung to swing in the direction of egress from the bathroom.

1111B.4.7 Storage areas. Fixed or built-in storage facilities located within accessible sleeping rooms or suites required by Table 11B-3 shall be accessible in the number and dimensions provided in Section 1125B.

1111B.4.8 Dormitory rooms. Dormitory rooms beyond those specified herein shall comply with the adaptability requirements of Section 1111B.5.

1111B.5 Buildings and complexes containing publicly funded dwelling units.

1111B.5.1 General. Buildings and complexes containing publicly funded dwelling units shall be accessible as required by Chapter 11A, Housing Accessibility, except that scoping requirements for covered multifamily dwellings include one or more publicly funded dwelling units, and are required to comply with Division IV - Accessibility for Existing Buildings, beginning with Section 1134B.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**TABLE 11B-3
ADDITIONAL ACCESSIBILITY REQUIRED IN GUEST ROOMS OR SUITES***

TOTAL NUMBER OF ROOMS	FULLY ACCESSIBLE ROOMS	PLUS ADDITIONAL ACCESSIBLE ROOMS WITH ROLL-IN SHOWERS
1 to 25	0	1
26 to 50	1	1
51 to 75	3	1
76 to 100	4	1
101 to 150	5	2
151 to 200	6	2
201 to 300	7	3
301 to 400	8	4
401 to 500	9	4 plus 1 for each additional 100 over 400
501 to 1,000	2% of total	4 plus 1 for each additional 100 over 400
1,001 and over	20 plus 1 for each 100 over 1,000	

*Provisions of this chapter are additional modifications to general requirements listed in Section 1114B.1.1.

**TABLE 11B-4
ADDITIONAL ACCESSIBILITY REQUIRED FOR HEARING IMPAIRED IN GUEST ROOMS***

TOTAL NUMBER OF ROOMS	NUMBER OF ROOMS EQUIPPED FOR HEARING IMPAIRED
1 to 25	1
26 to 50	2
51 to 75	3
76 to 100	4
101 to 150	5
151 to 200	6
201 to 300	7
301 to 400	8
401 to 500	9
501 to 1,000	2% of total
1,001 and over	20 plus 1 for each 100 over 1,000

*Provisions of this chapter are additional modifications to general requirements listed in Section 1114B.1.1. For Group I-1 and R-1 occupancies, also see Section 907.5.2.3.3.

SECTION 1112B
Reserved

SECTION 1113B
Reserved

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1114B FACILITY ACCESSIBILITY

When buildings are required to be accessible, buildings and facilities shall be accessible as provided in this section.

1114B.1 Design and construction.

1114B.1.1 General. When accessibility is required by this chapter, it shall be designed and constructed to meet the minimum requirements of the following sections:

Chapter 11B, Accessibility; Division I, New Buildings; Division II, Site Accessibility; Division III, Accessibility for Entrances, Exits and Paths of Travel; and Division IV, Accessibility for Existing Buildings

Entrances – [for HCD 1-AC] Section 1120A.1; [for DSA-AC] Section 1133B.1.1

Doors – [for HCD 1-AC] Sections 1114A.4.4, 1117A.2, 1122A.3.4, 1126A, 1132A; [for DSA-AC] Section 1133B.2

Corridors – [for HCD 1-AC] Section 1120A; [for DSA-AC] Section 1133B.3

Stairways – [for HCD 1-AC] Sections 1115A.6, 1123A; [for DSA-AC] Section 1133B.4

Ramps – [for HCD 1-AC] Sections 1112A, 1114A, 1122A; [for DSA-AC] Section 1133B.5

Aisles – [for DSA-AC] Section 1133B.6

Walks and Sidewalks – [for HCD 1-AC] Section 1113A; [for DSA-AC] Section 1133B.7

Hazards – [for HCD 1-AC] Sections 1116A, 1125A; [for DSA-AC] Section 1133B.8

Elevators – [for HCD 1-AC] Section 3003; [for DSA-AC] Section 1116B

Platform (Wheelchair) Lifts – [for HCD 1-AC] Section 1124A; [for DSA-AC] Section 1116B.2

Alarms – [for DSA-AC] Chapter 9, Sections 907.9.1 and 907.9.2

Bathing and Toilet Facilities – [for DSA-AC] Section 1115B

Signs and Identification – [for DSA-AC] Section 1117B.5

Detectable Warnings – [for DSA-AC] Sections 1121B.3.1 Item 8(a), 1127B.5.7, 1133B.8.5, Part 12 – Chapters 12-11A and 12-11B

Other Building Components – [for DSA-AC] Section 1117B

1114B.1.2 Accessible route of travel. When a building, or portion of a building, is required to be accessible or adaptable, an accessible route of travel complying with Sections 1102B, 1114B, 1124B, 1133B.3, 1133B.5, 1133B.7 and 1133B.8.6 shall be provided to all portions of the building, to accessible building entrances and between the building and the public way. All walks, halls, corridors, aisles, skywalks, tunnels, and other spaces that are part of an accessible route shall comply with the applicable provisions of this code. Except within an individual dwelling unit, an accessible route of travel shall not pass through kitchens, storage rooms, restrooms, closets or other spaces used for similar purposes. At least one accessible route within the boundary of the site shall be provided from public transportation stops, accessible parking and accessible passenger loading zones and public streets or sidewalks to the accessible building entrance they serve. The

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

accessible route shall, to the maximum extent feasible, coincide with the route for the general public. At least one accessible route shall connect accessible buildings, facilities, elements and spaces that are on the same site. At least one accessible route shall connect accessible building or facility entrances with all accessible spaces and elements and with all accessible dwelling units within the building or facility. An accessible route shall connect at least one accessible entrance of each accessible dwelling unit with those exterior and interior spaces and facilities that serve the accessible dwelling unit.

Where more than one route of travel is provided, all routes shall be accessible. Unless otherwise indicated, the minimum clear width of an accessible route shall not be less than 36 inches (914 mm) except at doors complying with Section 1133B.2 or obstructions complying with Figure 11B-10. If a person in a wheelchair must make a turn around an obstruction the minimum clear width of the accessible route shall be as shown in Figure 11B-5E(a) and (b).

Exception: Where an elevator is provided for vertical access, only one elevator is required. Where more than one elevator is provided, all elevators shall be accessible. See Section 1114B.1.1 for a list of code sections applicable to accessible routes of travel.

1114B.1.3 Primary entry access. All entrances and all exterior ground-level exits shall be accessible in compliance with Section 1133B.1.1.

1114B.1.4 Signs. See Section 1117B.5.

1114B.1.5 Adaptable dwelling units. See Section 1111B.

1114B.2 Egress and areas of refuge.

1114B.2.1 General. In buildings or facilities or portions of buildings or facilities required to be accessible, accessible means of egress shall be provided as required by Chapter 10.

1114B.2.2 Alarms/emergency warning systems/accessibility. If emergency warning systems are provided, they shall include both audible alarms and visible alarms complying with NFPA 72 and Chapter 9, Sections 907.5.2.1 and 907.5.2.3.

SECTION 1115B BATHING AND TOILET FACILITIES (SANITARY FACILITIES)

1115B.1 General. Bathing and toilet facilities that serve buildings, facilities or portions of buildings or facilities that are required by these standards to be accessible to persons with disabilities, shall be on an accessible route and shall conform to the following requirements.

The accessible fixtures and controls required in this section shall be on an accessible route. An unobstructed turning space complying with Section 1115B.3.1, Item 1, or 1115B.3.2, Item 1, as applicable, shall be provided within an accessible toilet facility. The clear floor spaces at fixtures and controls, the accessible route and the turning space may overlap.

See Section 1111B.4.6 and Chapter 11A for bathrooms in residential occupancies.

Exception: In existing buildings or facilities, when the enforcing agency determines that compliance with any building standard under this section would create an unreasonable hardship, an exception to such standard may be granted when equivalent facilitation is provided. When equivalent facilitation is used, the following criteria shall apply:

1. All sanitary facilities are not required to comply with these building standards when the enforcing agency determines that sanitary facilities are accessible to and usable by persons with disabilities within a reasonable distance of accessible areas.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

- When existing sanitary facilities are not being altered to provide accessibility, signage complying with Sections 1117B.5.1, Items 2 and 3, and 1117B.5.8.1 shall be provided at such inaccessible facilities indicating the location of the nearest accessible sanitary facility.

1115B.1.1 Separate and unisex facilities. Where separate facilities are provided for persons of each sex, these facilities shall be accessible to persons with disabilities. Where unisex facilities are provided, these facilities shall be accessible to persons with disabilities.

1115B.1.2 Where used by children. Where facilities are to be used solely by small children, the specific heights and clearances may be adjusted to meet their accessibility needs. See Table 1115B-1 for suggested mounting heights and clearances.

**TABLE 1115B-1
SUGGESTED DIMENSIONS FOR CHILDREN'S USE**

The Division of the State Architect—Access Compliance recommends the following dimensions as adequately serving the needs of children in projects under our jurisdiction. These recommendations are based on the federal "Recommendations for Accessibility for Children in Elementary School" and other recognized publications on access for children:			
A = Adult Dimensions (age 12 and over) E = Elementary Dimensions K = Kindergarten and Preschool Dimensions			
		SUGGESTED	
DIMENSION	A (inches)	E (inches)	K (inches)
Toilet centering from wall	18	15	12
Toilet seat height/Dimensions to top of seat	17-19	15	10-12
Grab bar height (side)	33	27	20-22
Toilet paper in front of toilet	12 max	6 max	6 max
Napkin disposal in front of toilet	12 max	12 max	N/A
Dispenser or mirror height	40 max	36 max	32 max
Lavatory/sink top height	34 max	29 max	24 max
Lavatory/sink knee clearance	27 min	24 min	19 min
Urinal lip height	17 max	15 max	13 min
Urinal flush handle height	44 max	37 max	32 max
Drinking fountain bubbler height	36 max	32 max	30 max
Drinking fountain knee clearance	27 min	24 min	22 min
Ramp/stair handrail height	34-38	27	22

For SI: 1 inch = 25.4 mm.

1115B.2 Bathing and shower facilities. Where facilities for bathing are provided for the public, clients or employees, including showers or bathtubs, at least one shower or bathtub and support facilities such as lockers, and not less than 1 percent of all facilities, shall be accessible.

1115B.3 Toilet facilities.

1115B.3.1 Multiple-accommodation toilet facilities. Multiple-accommodation toilet facilities shall have the following:

- Wheelchair clearance.** A clear space measured from the floor to a height of 27 inches (686 mm) above the floor, within the sanitary facility room, of sufficient size to inscribe a circle with a diameter not less than 60 inches (1524 mm) in size. Other than the door to the accessible water closet compartment, a door, in any position, may encroach into this space by not more than 12 inches (305 mm).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. **Clear floor space at fixtures.** Doors shall not swing into the clear floor space required for any fixture. Doors may swing into that portion of maneuvering space which does not overlap the fixture's required clear floor space. See Figures 11B-1E (c) and (e).
3. **Accessible fixtures.** Provide a minimum of one accessible water closet in compliance with Section 1115B.4.1. At least 5 percent of lavatories, but not less than one lavatory, shall be accessible in compliance with Section 1115B.4.3.
4. **Accessible water closet compartment.** Accessible water closet compartments shall comply with the following:
 - 4.1. The compartment shall be a minimum of 60 inches (1524 mm) wide.
 - 4.2. If the compartment has a side-opening door, either in-swinging or out-swinging, a minimum 60 inches (1524 mm) wide and 60 inches (1524 mm) deep maneuvering space shall be provided in front of the water closet.
 - 4.3. If the compartment has an end-opening door (facing the water closet), either in-swinging or out-swinging, a minimum 60 inches (1524 mm) wide and 48 inches (1219 mm) deep maneuvering space shall be provided in front of the water closet. The door shall be located in front of the clear floor space and diagonal to the water closet, with a maximum stile width of 4 inches (102 mm).
 - 4.4. The water closet compartment shall be equipped with a door that has an automatic-closing device, and shall have a clear, unobstructed opening width of 32 inches (813 mm) when located at the end and 34 inches (864 mm) when located at the side with the door positioned at an angle of 90 degrees from its closed position.
 - 4.5. The inside and outside of the compartment door shall be equipped with a loop or U-shaped handle immediately below the latch. The latch shall be flip-over style, sliding or other hardware not requiring the user to grasp or twist. Except for door-opening widths and door swings, a clear, unobstructed access of not less than 44 inches (1118 mm) shall be provided to water closet compartments designed for use by persons with disabilities. Maneuvering space at the compartment door shall comply with Sections 1133B.2.4.2 and 1133B.2.4.3, and in no case shall the space immediately outside of the water closet compartment door be less than 48 inches (1219 mm) as measured perpendicular to the compartment door in its closed position.
5. **Large toilet rooms.** Where six or more compartments are provided within a multiple-accommodation toilet room, in addition to the water closet and compartment required by Items 3 and 4 above, provide at least one ambulatory accessible compartment. The ambulatory accessible compartment shall be 36 inches (914 mm) wide with an outward swinging self-closing door and parallel grab bars complying with Section 1115B.4.1, Item 3.
6. **Interior surfaces.** Toilet room floors shall have a stable, firm, slip resistant surface in compliance with Section 1124B.1.

1115B.3.2 Single-accommodation toilet facilities. Single-accommodation toilet facilities shall have the following:

1. **Wheelchair clearance.** There shall be sufficient space in the toilet room for a wheelchair measuring 30 inches (762 mm) wide by 48 inches (1219 mm) long to enter the room and permit the door to close. There shall be in the room a clear floor space of at least 60 inches (1524 mm) in diameter, or a T-shaped space complying with Figure 11B-12 (a) and (b). No door shall encroach into this space for more than 12 inches (305 mm). See Figure 11B-1A.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. **Clear floor space at fixtures.** Doors shall not swing into the clear floor space required for any fixture. Doors may swing into that portion of maneuvering space which does not overlap the fixture's required clear floor space. See Figure 11B-1E (a).
3. **Accessible water closet.** Provide one accessible water closet in compliance with Section 1115B.4.1. A minimum 60 inches (1524 mm) wide and 48 inches (1219 mm) deep maneuvering space shall be provided in front of the water closet.
4. **Accessible route.** All doors, fixtures and controls shall be on an accessible route. The minimum clear width of an accessible route shall be 36 inches (914 mm) except at doors (see Section 1133B.2). If a person in a wheelchair must make a turn around an obstruction, the minimum clear width of the accessible route shall be as shown in Figure 11B-5E. See also Figure 11B-1A.
5. **Interior surfaces.** Toilet room floors shall have a stable, firm, slip resistant surface in compliance with Section 1124B.1.
6. **Accessible lavatory.** Provide one accessible lavatory in compliance with Section 1115B.4.3.
7. **Privacy latch.** The entrance door shall contain a privacy latch which complies with Section 1117B.6, Controls and Operating Mechanisms.

For bathrooms serving residential occupancies, see Section 1111B.4.6 and Chapter 11A.

Exception: In an existing building, a single-accommodation toilet facility may have the water closet fixture located in an area which provides a clear space of not less than 36 inches (914 mm) wide by 48 inches (1219 mm) long in front of the water closet.

1115B.4 Accessible fixtures.

1115B.4.1 Accessible water closets. Water closets required to be accessible shall comply with this subsection:

1. The centerline of the water closet fixture shall be 18 inches (457 mm) from the side wall or partition. On the other side of the water closet, provide a minimum of 28 inches (711 mm) wide clear floor space if the water closet is adjacent to a fixture or a minimum of 32 inches (813 mm) wide clear floor space if the water closet is adjacent to a wall or partition. This clear floor space shall extend from the rear wall to the front of the water closet.
2. Provide clear floor space and maneuvering space at accessible water closets in compliance with Section 1115B.4.1, Item 2. Refer to Section 1115B.3.1, Items 4.2 and 4.3 for additionally required maneuvering space at multiple-accommodation toilet facilities. Refer to Section 1115B.3.2, Item 3 for additionally required maneuvering space at single-accommodation toilet facilities.
 - 2.1. Where a water closet is not within a water closet compartment, clear floor space around the water closet shall be 60 inches (1524 mm) minimum measured perpendicular from the side wall closest to the water closet and 56 inches (1422 mm) minimum measured perpendicular from the rear wall. See Figure 11B-1E (a).
 - 2.2. Where a wall mounted water closet is installed within an accessible water closet compartment, clear floor space around the water closet shall be 60 inches (1524 mm) minimum measured perpendicular from the side wall closest to the water closet and 56 inches (1422 mm) minimum measured perpendicular from the rear wall. Where a floor mounted water closet is installed within an accessible water closet compartment, clear floor space around the water closet shall be 60 inches (1524 mm) minimum measured perpendicular from the side wall and 59 inches (1499 mm) minimum measured perpendicular from the rear wall. See Figures 11B-1E (b), (c), (d) and (e).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2.3. Where a water closet is installed within an accessible water closet compartment with an in-swinging door, a minimum 60 inches (1524 mm) wide by 36 inches (914 mm) deep maneuvering space shall be provided in front of the clear floor space required in Item 2.2. See Figures 11B-1E (c) and (e).

Exception: An adjacent fixture at the rear wall is permitted to encroach into the required clear floor space at the wide side of the water closet where clearances are provided in compliance with Section 1115B.4.1, Item 1.

3. Grab bars for water closets not located within a compartment shall comply with Section 1115B.7 and shall be provided on the side wall closest to the water closet and on the rear wall. Grab bars for water closets located within an accessible compartment shall comply with Section 1115B.7 and shall be provided on the side wall closest to the water closet and on the rear wall. Grab bars for water closets located within ambulatory accessible compartments shall comply with Section 1115B.7 and shall be provided on both sides of the compartment.

Grab bars shall not project more than 3 inches (76 mm) into the required clear floor space.

3.1. Side wall. The side grab bar shall be 42 inches (1067 mm) long minimum, located 12 inches (305 mm) maximum from the rear wall and extend 54 inches (1372 mm) minimum from the rear wall with the front end positioned 24 inches (610 mm) minimum in front of the water closet. The side grab bar shall be securely attached and centered 33 inches (838 mm) above and parallel to the floor.

3.2. Rear wall. The rear grab bar shall be 36 inches (914 mm) long minimum and extend from the centerline of the water closet 12 inches (305 mm) minimum on one side and 24 inches (610 mm) minimum on the other side. The rear grab bar shall be securely attached and centered 33 inches (838 mm) above and parallel to the floor, except that where a tank-type toilet is used which obstructs placement at 33 inches (838 mm), the grab bar may be as high as 36 inches (914 mm) and the space between the grab bar and the top of the tank shall be 1½ inches (38 mm) minimum.

4. The height of accessible water closets shall be a minimum of 17 inches (432 mm) and a maximum of 19 inches (483 mm) measured to the top of a maximum 2-inch (51 mm) high toilet seat.

Exception: A 3-inch (76 mm) high seat shall be permitted only in alterations where the existing fixture is less than 15 inches (381 mm) high.

5. Controls shall be operable with one hand and shall not require tight grasping, pinching or twisting. Controls for the flush valves shall be mounted on the wide side of toilet areas, no more than 44 inches (1118 mm) above the floor. The force required to activate controls shall be no greater than 5 pounds-force (lbf) (22.2 N).
6. See Section 1134A.7 for additional requirements for water closets in publicly funded housing and all nonresidential occupancies.
7. Automatic spring to lifted position seats are not allowed.

1115B.4.2 Accessible urinals. Urinals required to be accessible shall comply with this subsection.

1. Urinals shall be floor mounted, stall-type or wall hung. Where one or more wall-hung urinals are provided, at least one with an elongated rim projecting a minimum of 14 inches (356 mm) from the wall and a maximum of 17 inches (432 mm) from the wall and a maximum of 17 inches (432 mm) above the floor shall be provided.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. Flush controls shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist and shall be mounted no more than 44 inches (1118 mm) above the floor. The force required to activate controls shall be no greater than 5 lbf (22.2 N). Electronic automatic flushing controls are acceptable and preferable.
3. Where urinals are provided, at least one shall have a clear floor space 30 inches by 48 inches (762 mm by 1219 mm) in front of the urinal to allow forward approach. This clear space shall comply with Section 1118B.4.

1115B.4.3 Accessible lavatories. Lavatories required to be accessible shall comply with this subsection. The requirements of this subsection shall apply to lavatory fixtures, vanities and built-in lavatories.

1. Faucet controls and operating mechanisms shall be operable with one hand in accordance with this chapter and shall not require tight grasping, pinching or twisting of the wrist. The force required to activate controls shall be no greater than 5 lbf (22.2 N). Lever-operated, push-type and electronically controlled mechanisms (preferable) are examples of acceptable designs. Self-closing valves are allowed if the faucet remains open for at least 10 seconds.
2. Lavatories, when located adjacent to a side wall or partition, shall be a minimum of 18 inches (457 mm) to the centerline of the fixture. All lavatories that are designated to be accessible shall be a minimum 17 inches (432 mm) in horizontal depth and mounted with the rim or counter edge no higher than 34 inches (864 mm) above the finished floor and with vertical clearance measured from the bottom of the apron or the outside bottom edge of the lavatory of 29 inches (737 mm) reducing to 27 inches (686 mm) at a point located 8 inches (203 mm) back from the front edge. In addition, a minimum 9-inch-high (230 mm) toe clearance must be provided extending back toward the wall to a distance no more than 6 inches (150 mm) from the back wall. The toe clearance space must be free of equipment or obstructions.
3. A clear floor space 30 inches by 48 inches (762 mm by 1219 mm) complying with Section 1118B.4 shall be provided in front of a lavatory to allow forward approach. Such clear floor space shall adjoin or overlap an accessible route and shall extend a maximum of 19 inches (483 mm) into knee and toe space underneath the lavatory. See Figure 11B-1D, Knee Clearance.
4. Hot water and drainpipes accessible under lavatories shall be insulated or otherwise covered. There shall be no sharp or abrasive surfaces under lavatories.

1115B.4.4 Accessible showers. Showers required to be accessible shall comply with this subsection:

1115B.4.4.1 Size and clearances. Accessible showers shall comply with one of the following:

1. Roll-in shower 60 inches (1524 mm) minimum in width between wall surfaces and 30 inches (762 mm) minimum in depth with a full opening width on the long side. Shower compartment size and clear floor space shall comply with Figure 11B-2A.
2. Alternate roll-in shower 60 inches (1524 mm) minimum in width between wall surfaces and 36 inches (914 mm) in depth with an entrance opening width of 36 inches (914 mm) minimum. Shower compartment size and clear floor space shall comply with Figure 11B-2B.
3. Alternate roll-in shower with optional enclosure 60 inches (1524 mm) minimum in width between wall surfaces and 36 inches (914 mm) minimum in depth as long as the entrance opening width is a minimum 36 inches (914 mm). Shower compartment size and clear floor space shall comply with Figure 11B-2C.

1115B.4.4.2 Thresholds. Thresholds in roll-in type showers shall be ½ inch (12.7 mm) high maximum and shall comply with Section 1124B.2.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1115B.4.4.3 Orientation. Where, within the same functional area, two or more accessible showers are provided, there shall be at least one shower constructed opposite hand from the other or others (that is, one left-hand controls versus right-hand controls).

1115B.4.4.4 Water controls. Water controls shall be of a single-lever design, operable with one hand, and shall not require tight grasping, pinching or twisting of the wrist. The force required to activate controls shall be no greater than 5 lbf (22.2N). The centerline of the controls shall be located 39 inches (991 mm) to 41 inches (1041 mm) above the shower floor.

1. Controls in a 60-inch (1524 mm) minimum by 30-inch (762 mm) minimum roll-in shower shall be located on the back wall of the compartment adjacent to the seat and the centerline of the controls shall be within a range of no less than 19 inches (457 mm) and no more than 27 inches (610 mm) from the seat wall as shown in Figure 11B-2A.
2. Controls in a 60-inch (1524 mm) minimum by 36-inch (914 mm) alternate roll-in shower shall be located on the side wall of the compartment adjacent to the seat and the centerline of the controls shall be within a range of no less than 19 inches (457 mm) and no more than 27 inches (610 mm) from the seat wall as shown in Figure 11B-2B.
3. Controls in a 60-inch (1524 mm) minimum by 36-inch (914 mm) minimum alternate roll-in shower with optional enclosure shall be located on the back wall of the compartment adjacent to the seat and the centerline of the controls shall be within a range of no less than 19 inches (457 mm) and no more than 27 inches (610 mm) from the seat wall as shown in Figure 11B-2C.

1115B.4.4.5 Hand-held sprayer unit. A flexible hand-held sprayer unit with a hose at least 60 inches (1524 mm) long that can be used both as a fixed shower head and as a hand-held shower shall be provided. This unit shall be mounted such that the top of the mounting bracket is at a maximum height of 48 inches (1219 mm) above the shower floor.

1. The hand-held sprayer unit in a 60-inch (1524 mm) minimum by 30-inch (762 mm) minimum roll-in shower shall be located on the back wall of the compartment adjacent to the seat and the centerline of the unit shall be no more than 27 inches (610 mm) from the seat wall as shown in Figure 11B-2A.
2. The hand-held sprayer unit in a 60-inch (1524 mm) minimum by 36-inch (914 mm) alternate roll-in shower shall be located on the side wall of the compartment adjacent to the seat and the centerline of the unit shall be 18 inches (457 mm) from the seat wall as shown in Figure 11B-2B.
3. The hand-held sprayer unit in a 60-inch (1524 mm) minimum by 36-inch (914 mm) minimum alternate roll-in shower with optional enclosure shall be located on the back wall of the compartment adjacent to the seat and the centerline of the unit shall be no more than 27 inches (610 mm) from the seat wall as shown in Figure 11B-2C.

1115B.4.4.6 Sprayer unit alternative. Except within guest rooms and suites in hotels, motels and similar transient lodging establishments, where accessible shower facilities are provided in areas subject to excessive vandalism, in lieu of providing the fixed flexible hose, two wall-mounted shower heads shall be installed. Each shower head shall be installed so that it can be operated independently of the other and shall have swivel angle adjustments, both vertically and horizontally. One shower head shall be located at a height of 48 inches (1219 mm) above the floor.

1115B.4.4.7 Floor slope. The maximum slope of the floor shall be one unit vertical in 50 units horizontal (2-percent slope) in any direction. Where drains are provided, grate openings shall be a maximum of ¼ inch (6.4 mm) and located flush with the floor surface.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1115B.4.4.8 Shower accessories. *Shower accessories shall include:*

1. *A folding seat mounted 18 inches (457 mm) above the floor, and with a minimum space of 1 inch (25 mm) and maximum space of 1½ inches (38 mm) allowed between the edge of the seat and any wall. When folded, the seat shall not extend more than 6 inches (152 mm) from the mounting wall. The seat dimensions and mounting position shall comply with Figures 11B-2A, 11B-2B, 11B-2C and 11B-2D. The structural strength of seats and their attachments shall comply with 1115B.7.2.*
2. *Grab bars located on walls adjacent to and opposite the seat. Grab bars shall also comply with the diameter, loading and projection requirements of Section 1115B.7. Grab bars shall be mounted between a minimum of 33 inches (838 mm) and a maximum of 36 inches (914 mm) above the shower floor with an L-shaped grab bar mounted on walls opposite and adjacent to the front edge of the seat, but not extended to include that portion of wall over the seat. See Figure 11B-2A or 11B-2B.*

1115B.4.4.9 Soap dish. *When a soap dish is provided, it shall be located on the control wall at a maximum height of 40 inches (1016 mm) above the shower floor, and within reach limits from the seat.*

1115B.4.4.10 Enclosures. *Enclosures, when provided for shower compartments, shall not obstruct controls or obstruct transfer from wheelchairs onto shower seats.*

See Figures 11B-2A, 11B-2B, 11B-2C and 11B-2D.

1115B.4.5 Accessible bathtubs. *Bathtubs required to be accessible shall comply with this subsection.*

1. **Floor space.** *Clear floor space at bathtubs shall be as shown in Figure 11B-8.*
2. **Seat.** *An in-tub seat or a seat at the head end of the tub shall be provided as shown in Figures 11B-8 and 11B-9. The structural strength of seats and their attachments shall comply with Section 1115B.7.2. Seats shall be mounted securely and shall not slip during use.*
3. **Grab bars.** *Grab bars complying with Section 1115B.7 shall be provided as shown in Figure 11B-9.*
4. **Controls.** *Faucets and other controls shall be located as shown in Figure 11B-9. They shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist. The force required to activate controls shall be no greater than 5 lbf (22.2 N).*
5. **Shower unit.** *A shower spray unit with a hose at least 60 inches (1524 mm) long that can be used both as a fixed shower head and as a hand-held shower shall be provided.*
6. **Bathtub enclosures.** *If provided, enclosures for bathtubs shall not obstruct controls or transfer from wheelchairs onto bathtub seats or into tubs. Enclosures on bathtubs shall not have tracks mounted on their rims.*

1115B.5 Passageways. *Passageways leading to sanitary facilities shall have a clear access. All doorways leading to such sanitary facilities shall comply with Section 1133B.2, Doors. Doors shall not swing into the clear floor space required for any fixture. Accessible fixtures and controls shall be on an accessible route.*

1115B.6 Identification symbols. *Doorways leading to sanitary facilities shall be identified by a geometric symbol in compliance with this section. Geometric symbols shall be centered horizontally on the door at a height of 60 inches (1524 mm) above the finish floor or ground surface measured to the center of the symbol. Edges of signs shall be rounded, chamfered or eased. Corners of signs shall have a minimum radius of ¼ inch (3.2 mm). See Section 1117B.5.1, Item 1 for additional signage requirements applicable to sanitary facilities.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1115B.6.1 Men's sanitary facilities shall be identified by an equilateral triangle, ¼ inch (6.4 mm) thick with edges 12 inches (305 mm) long and a vertex pointing upward. The triangle symbol shall contrast with the door, either light on a dark background or dark on a light background.

1115B.6.2 Women's sanitary facilities shall be identified by a circle, ¼ inch (6.4 mm) thick and 12 inches (305 mm) in diameter. The circle symbol shall contrast with the door, either light on a dark background or dark on a light background.

1115B.6.3 Unisex sanitary facilities shall be identified by a circle, ¼ inch (6.4 mm) thick and 12 inches (305 mm) in diameter with a ¼ inch (6.4 mm) thick triangle superimposed on the circle and within the 12-inch (305 mm) diameter. The triangle symbol shall contrast with the circle symbol, either light on a dark background or dark on a light background. The circle symbol shall contrast with the door, either light on a dark background or dark on a light background.

1115B.7 Grab bars, tub and shower seats. All grab bars, tub and shower seats shall comply with this section.

1115B.7.1 Diameter or width. The diameter or width of the gripping surfaces of a grab bar shall be 1¼ inches to 1½ inches (32 mm to 38 mm) or the shape shall provide an equivalent gripping surface. If grab bars are mounted adjacent to a wall, the space between the wall and the grab bars shall be 1½ inches (38 mm). See Figure 11B-1C.

1115B.7.2 Structural strength. The structural strength of grab bars, tub and shower seats, fasteners and mounting devices shall meet the following specifications:

1. Bending stress in a grab bar or seat induced by the maximum bending moment from the application of a 250-pound (1112 N) point load shall be less than the allowable stress for the material of the grab bar or seat.
2. Shear stress induced in a grab bar or seat by the application of a 250-pound (1112 N) point load shall be less than the allowable shear stress for the material of the grab bar or seat, and its mounting bracket or other support is considered to be fully restrained, then direct and torsional shear stresses shall not exceed the allowable shear stress.
3. Shear force induced in fastener or mounting device from the application of a 250-pound (1112 N) point load shall be less than the allowable lateral load of either the fastener or mounting device or the supporting structure, whichever is the smaller allowable load.
4. Tensile force induced in a fastener by a direct tension force of a 250-pound (1112 N) point load, plus the maximum moment from the application of a 250-pound (1112 N) point load, shall be less than the allowable withdrawal load between the fastener and supporting structure.
5. Grab bars shall not rotate within their fittings.

1115B.7.3 Surface. A grab bar and any wall or other surface adjacent to it shall be free of any sharp or abrasive elements. Edges shall have a minimum radius of ¼ inch (3.2 mm).

1115B.8 Accessories.

1115B.8.1 Mirrors.

1115B.8.1.1 All mirrors located above accessible lavatories or countertops shall be installed with the bottom edge of the reflecting surface 40 inches (1016 mm) maximum above the finish floor or ground.

1115B.8.1.2 When mirrors are provided at locations other than above lavatories or countertops, at least one shall be installed with the bottom edge of the reflecting surface 35 inches (890 mm) maximum above the finish floor or ground.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1115B.8.1.3 *Mirrors in fitting and dressing areas shall comply with Section 1117B.8.*

1115B.8.2 Medicine cabinets. *If medicine cabinets are provided, at least one shall be located with a usable shelf no higher than 44 inches (1118 mm) above the floor. A clear floor space 30 inches by 48 inches (762 mm by 1219 mm) complying with Section 1118B.4 shall be provided in front of a medicine cabinet to allow a forward or parallel approach.*

1115B.8.3 Towel, sanitary napkins, waste receptacles, dispensers and controls. *Where towel, sanitary napkins, waste receptacles, dispensers, other equipment and controls are provided, at least one of each type shall be located on an accessible route, with all operable parts, including coin slots, within 40 inches (1016 mm) from the finished floor and shall comply with Section 1117B.6, Controls and Operating Mechanisms.*

1115B.8.4 Toilet tissue dispensers. *Toilet tissue dispensers shall be located on the wall within 12 inches (305 mm) of the front edge of the toilet seat, mounted below the grab bar, at a minimum height of 19 inches (485 mm), and 36 inches (914 mm) maximum to the far edge from the rear wall. Dispensers that control delivery or that do not permit continuous paper flow shall not be used. See Figure 11B-1A.*

1115B.8.5 Lockers. *Where lockers are provided for the public, clients, employees, members or participants, at least one locker and not less than 1 percent of all lockers shall be made accessible to persons with disabilities. A path of travel not less than 36 inches (914 mm) in clear width shall be provided to these lockers.*

SECTION 1116B ELEVATORS AND PLATFORM (WHEELCHAIR) LIFTS

1116B.1 Elevators. *Passenger elevators shall be accessible. Elevators required to be accessible shall be designed and constructed to comply with this section and with the ASME A17.1, Safety Code for Elevators and Escalators. Freight elevators shall not be considered as meeting the requirements of this section unless the only elevators provided are used as combination passenger and freight elevators for the public and employees.*

1116B.1.1 General. *Size of cab and control locations and requirements for accommodation of persons with disabilities.*

In buildings two or more stories in height, served by an elevator, or a building served by an elevator required by Chapter 11B, or a building served by an elevator required for accessibility by Section 1.9.1, if more than one passenger elevator is provided, each full passenger elevator shall comply with this chapter.

Exceptions:

- 1. In existing buildings, when the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception to such regulation shall be granted when equivalent facilitation is provided.*
- 2. In existing buildings, where existing shaft configuration or technical infeasibility prohibits strict compliance with Section 1116B.1.8, the minimum car plan dimensions may be reduced by the minimum amount necessary, but in no case shall the inside car area be smaller than 48 inches (1219 mm) by 48 inches (1219 mm).*
- 3. In existing buildings, equivalent facilitation may be provided with an elevator car of different dimensions where it can be demonstrated that a person using a wheelchair can enter and operate the elevator and when all other elements required to be accessible comply with the applicable provisions of Section 1116B.*
- 4. These provisions shall not apply to existing buildings when legal or physical constraints will not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1116B.1.2 Operation and leveling. *The elevator shall be automatic and provided with a self-leveling feature that will automatically bring the car to the floor landings within a tolerance of plus or minus ½ inch (12.7 mm) under normal loading and unloading conditions. This self-leveling shall, within its zone, be entirely automatic and independent of the operating device and shall correct the overtravel or undertravel. The car shall also be maintained approximately level with the landing, irrespective of load.*

The clearance between the car platform sill and the edge of the hoistway landing shall be no greater than ¼ inches (32 mm).

1116B.1.3 Door operation. *Power-operated horizontally sliding car and hoistway doors opened and closed by automatic means shall be provided.*

1116B.1.4 Door size. *Minimum clear width for elevator doors shall be 36 inches (914 mm).*

1116B.1.5 Door protective and reopening device. *Doors closed by automatic means shall be provided with a door-reopening device that will function to stop and reopen a car door and adjacent hoistway door in case the car door is obstructed while closing.*

This reopening device shall also be capable of sensing an object or person in the path of a closing door without requiring contact for activation at a nominal 5 inches and 29 inches (127 mm and 737 mm) above the floor.

Door-reopening devices shall remain effective for a period of not less than 20 seconds.

After such an interval, the doors may close in accordance with the requirements of ASME A17.1.

1116B.1.6 Hall call. *The minimum acceptable time from notification that a car is answering a call (lantern and audible signal) until the doors of the car start to close shall be calculated by the following equation:*

$$T = D / (1.5 \text{ ft/s}) \text{ or } T = D / (455 \text{ mm/s})$$

Where T is the total time in seconds and D is the distance from a point in the lobby or landing area 60 inches (1524 mm) directly in front of the farthest call button controlling that car to the centerline of its hoistway door (see Figure 11B-40D). For cars with in-car lanterns, T begins when the lantern is visible from the vicinity of hall call buttons and an audible signal is sounded. The minimum acceptable notification time shall be 5 seconds.

1116B.1.7 Car call. *The minimum acceptable time for doors to remain fully open shall not be less than 5 seconds.*

1116B.1.8 Car inside. *The car inside shall allow for the turning of a wheelchair. The minimum clear distance between walls or between wall and door, excluding return panels, shall not be less than 80 inches by 54 inches (2032 mm by 1372 mm) for center opening doors, and 68 inches by 54 inches (1727 mm by 1372 mm) for side-slide opening doors. See Figure 11B-40A. Minimum distance from wall to return panel shall not be less than 51 inches (1295 mm). Elevator floor surfaces shall comply with Section 1124B—Ground and Floor Surfaces.*

The centerline of elevator floor buttons shall be no higher than 54 inches (1372 mm) above the finish floor for side approach and 48 inches (1219 mm) for front approach. Emergency controls, including the emergency stop and alarm, shall be grouped in or adjacent to the bottom of the panel and shall be no lower than 2 feet 11 inches (889 mm) from the floor.

For multiple controls only, one set must comply with these height requirements. Floor buttons shall be provided with visual indicators to show when each call is registered. The visual indicators shall be extinguished when each call is answered.

Emergency two-way communication systems between the elevator and a point outside the hoistway

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

shall comply with ASME A17.1. The emergency telephone handset shall be positioned no higher than 4 feet (1219 mm) above the floor, and the handset cord shall be a minimum of 2 feet 5 inches (737 mm) in length. It shall be identified by a raised telephone symbol and corresponding Braille lettering complying with Section 1117B.5.1, Item 1, and located adjacent to the device. If the telephone system is located in a closed compartment, the compartment door hardware shall comply with Section 1117B.6 Item 4. Emergency intercommunication shall not require voice communication.

Where possible, a 48-inch (1219 mm) maximum height for elevator floor buttons is preferred.

Controls shall be located on a front wall if cars have center opening doors, and at the side wall or at the front wall next to the door if cars have side opening doors. See Figure 11B-40A.

1116B.1.9 Car controls. Identification for the visually impaired shall be as follows:

Passenger elevator car controls shall have a minimum dimension of $\frac{3}{4}$ inch (19.1 mm) and shall be raised $\frac{1}{8}$ inch (3.2 mm) plus or minus $\frac{1}{32}$ inch (0.8 mm) above the surrounding surface.

Control buttons shall be illuminated, shall have square shoulders and shall be activated by a mechanical motion that is detectable.

All control buttons shall be designated by $\frac{5}{8}$ inch (15.9 mm) minimum raised characters and standard raised symbols that conform to Sections 1117B.5.2, 1117B.5.3, 1117B.5.5 and 1117B.5.7 immediately to the left of the control button. Contracted (Grade 2) Braille that conforms to Section 1117B.5.6 shall be located immediately below the character or symbol. A minimum clear space of $\frac{3}{8}$ inch (9.5 mm) or other suitable means of separation shall be provided between rows of control buttons. See Figure 11B-40B.

The raised characters and symbols shall be white on a black background.

Controls and emergency equipment identified by raised symbols shall include, but not be limited to, "door open," "door close," "alarm bell," "emergency stop" and "telephone." The call button for the main entry floor shall be designated by a raised star at the left of the floor designation.

In elevator cars, a visual car position indicator shall be provided above the car control panel or over the door to show the position of the elevator in the hoistway. As the car passes or stops at a floor served by the elevators, the corresponding numerals shall illuminate, and an audible signal shall sound. Numerals shall be a minimum of $\frac{1}{2}$ inch (13 mm) high. The audible signal shall be no less than 20 decibels with a frequency no higher than 1,500 Hz. An automatic verbal announcement of the floor number at which a car stops or which a car passes may be substituted for the audible signal.

1116B.1.10 Hall call buttons. The centerline of the hall call buttons shall be 42 inches (1067 mm) above the floor. Buttons shall be a minimum of $\frac{3}{4}$ inch (19.1 mm) in size and shall be raised $\frac{1}{8}$ inch (3.2 mm) [plus or minus $\frac{1}{32}$ inch (0.8 mm)] above the surrounding surface. The button designating the up direction shall be on top. Visual indication shall be provided to show each call registered and extinguished when answered. Objects adjacent to, and below, hall call buttons shall not project more than 4 inches (102 mm) from the wall. Hall call buttons shall be internally illuminated with a white light over the entire surface of the button.

1116B.1.11 Handrails. A handrail shall be provided on one wall of the car, preferably the rear. The rails shall be smooth, and the inside surface at least $1\frac{1}{2}$ inches (38 mm) clear of the walls at a nominal height of 32 inches (813 mm) from the floor. Nominal equals ± 1 inch (25 mm). Thirty-two inches (813 mm) is required to reduce interference with car controls where the lowest button is centered at 35 inches (889 mm) above floor.

1116B.1.12 Minimum illumination. The minimum illumination at the car controls threshold and the landing when the car and landing doors are open shall not be less than 5 foot-candles (54 lux).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1116B.1.13 Hall lantern. A visual and audible signal shall be provided at each hoistway entrance indicating to the prospective passenger the car answering the call and its direction of travel as follows:

The visual signal for each direction shall be a minimum of 2½ inches (64 mm) high by 2½ inches (64 mm) wide and visible from the proximity of the hall call button.

The audible signal shall sound once for the “up” direction and twice for the “down” direction or shall have verbal annunciators that say “up” or “down.”

The centerline of the fixture shall be located a minimum of 6 feet (1829 mm) in height from the lobby floor.

The use of in-car lanterns, located in or on the car doorjamb, visible from the proximity of the hall call buttons and conforming to the above requirements, shall be acceptable.

The use of arrow shapes is preferred for visible signals.

1116B.1.14 Doorjamb marking. Passenger elevator landing jambs on all elevator floors shall have the number of the floor on which the jamb is located designated by raised characters that are a minimum of 2 inches (51 mm) in height and conform to Section 1117B.5.5 located 60 inches (1524 mm) on center above the floor on the jamb panels on both sides of the door so that they are visible from within the elevator. On the main entry level, a raised five-pointed star shall be placed to the left of the raised character. The outside diameter of the star shall be 2 inches (51 mm)) and all points shall be of equal length. Raised characters, including the star, shall be white on a black background. Contracted (Grade 2) Braille complying with Section 1117B.5.6 shall be placed below the corresponding raised characters and the star. The Braille translation for the star shall be “MAIN”.

The raised characters shall otherwise comply with Sections 1117B.5.2 and 1117B.5.3. See Figure 11B-40C. Permanently applied plates are acceptable if they are permanently fixed to the jambs.

1116B.1.15 Location. Passenger elevators shall be on an accessible route, located near a major path of travel, and provisions shall be made to ensure that they remain accessible and usable at all times the building is occupied.

1116B.2 Platform (wheelchair) lifts. Platform (wheelchair) lifts shall comply with this section.

Platform (wheelchair) lifts may be provided as part of an accessible route only for the following conditions:

1. To provide an accessible route to a performing area in an assembly occupancy, or to a speaking area or similar place (such as a dais or “head table”) in an assembly or Group B Occupancy.
2. To comply with the wheelchair viewing position line-of-sight and dispersion requirements of Section 1104B.3.5.
3. To provide access to incidental occupiable spaces and rooms which are not open to the general public and which house no more than five persons, including, but not limited to, equipment control rooms and projection booths.
4. To provide access where existing site constraints or other constraints make use of a ramp or an elevator infeasible.

Exception: In existing buildings, the installation of platform (wheelchair) lifts as part of an accessible path of travel for additions or alterations is not limited to the four conditions listed in this section.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1116B.2.1 General. When platform (wheelchair) lifts are provided, the vertical distance between landings, as well as the structural design and safeguards, shall be as allowed by ASME A18.1 Safety Standard for Platform Lifts and Stairway Chair Lifts; the Department of Industrial Relations, Division of Occupational Safety and Health; and any applicable safety regulations of other administrative authorities having jurisdiction.

1116B.2.2 Unassisted entry. Platform (wheelchair) lifts shall be designed and constructed to facilitate unassisted entry, operation and exit from the lift and shall comply with the restrictions and enhancements of this section in conjunction with Title 8, of the California Code of Regulations.

1116B.2.3 Landing size. In new construction, the minimum size of landings at platform lifts shall be 60 inches by 60 inches (1524 mm by 1524 mm). Other dimensions may be substituted where it can be demonstrated that a person using a wheelchair measuring 30 inches by 48 inches (762 mm by 1219 mm) can enter and operate the lift safely.

1116B.2.4 Relationship to the path of travel. Level and clear floor areas or landings at platform lifts shall be part of “path of travel” requirements.

Exceptions:

1. The provisions of this section shall not apply to existing buildings when physical constraints will not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.
2. When the enforcing agency determines that compliance with any regulation under this section would create an unreasonable hardship, an exception to such regulation shall be granted when equivalent facilitation is provided.

1116B.2.5 When provided as a means of egress. Platform (wheelchair) lifts, when provided as a component in an accessible means of egress, shall conform to the requirements of Section 1116B.2.5.

1116B.2.5.1 Standby power. To ensure continued operation in case of primary power loss, platform (wheelchair) lifts shall be provided with standby power or with self-rechargeable battery power that provides sufficient power to operate all platform lift functions for a minimum of five upward and downward trips.

1116B.2.5.2 Platform (wheelchair) lifts, when provided per Section 1116B.1 Item 2 are permitted to be a component of an accessible means of egress when the area served by the platform (wheelchair) lift does not serve more than four wheelchair viewing positions and where any one of the following conditions exist:

1. The building has a supervised automatic sprinkler system.
2. The maximum distance from the point where the wheelchair occupant is seated to a point where the occupant has a choice of two directions of travel to an exit shall not exceed 30 feet (9144 mm). The length of the path of travel shall include the vertical travel distance of the lift.

1116B.2.6 Doors and gates. Lifts shall have low energy power-operated doors or gates. Doors and gates shall remain open for 20 seconds minimum. End doors shall be 32 inches (813 mm) minimum clear width. Side doors shall be 42 inches (1067 mm) minimum clear width.

Exception: Lifts having doors or gates on opposite sides shall be permitted to have manual doors or gates.

1116B.2.7 Restriction sign. A sign complying with Section 1117B.5.1, Items 2 and 3 shall be securely fastened in a conspicuous place at each landing and on the platform. The sign shall state “No Freight” in letters not less than 5/8 inch (16 mm) high and include the International Symbol of Accessibility.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1117B OTHER BUILDING COMPONENTS

1117B.1 Accessible drinking fountains. Where drinking fountains are provided, they shall comply with this section:

- 1. General.** Where only one drinking fountain area is provided on a floor, there shall be a drinking fountain that is accessible to individuals who use wheelchairs in accordance with this section and one accessible to those who have difficulty bending or stooping. This can be accommodated by the use of "hi-low" fountains, or by such other means as would achieve the required accessibility for each group on each floor.

Where more than one drinking fountain is provided on a floor, 50 percent of those provided shall comply with Items 1, 2, 4 and 5 of this section and shall be on an accessible route complying with 1114B.1.2. All drinking fountains shall comply with Item 3 of this section.

- 2. Clearances.** Wall- and post-mounted cantilevered drinking fountains shall be a minimum of 18 inches (457 mm) and a maximum of 19 inches (483 mm) in depth and shall have a clear knee space between the bottom of the apron and the floor or ground not less than 27 inches (686 mm) in height, 30 inches (762 mm) in width, and 8 inches (203 mm) in depth, the depth measurements being taken from the front edge of the fountain back toward the wall or mounting post. The knee clearance space must be free of equipment or obstructions. Additionally, there shall be toe clearance of 9 inches (229 mm) in height above the floor and 17 inches (432 mm) in depth from the front edge of the fountain. The toe clearance space must be free of equipment or obstructions. A clear floor space at least 30 inches (762 mm) by 48 inches (1219 mm) complying with Section 1118B.4 shall be provided in front of the drinking fountain to allow forward approach. At "hi-low" type fountains, center the 30 inch (762 mm) by 48 inch (1219 mm) clear floor space on the "low" fountain fixture. A side approach drinking fountain is not acceptable.
- 3. Alcoves.** All drinking fountains shall be located completely within alcoves, positioned completely between wing walls, or otherwise positioned so as not to encroach into pedestrian ways. The alcove in which a drinking fountain is located shall not be less than 32 inches (813 mm) in width and 18 inches (457 mm) in depth. Wing walls shall project out from the supporting wall at least as far as the drinking fountain to within 6 inches (152 mm) of the surface of the path of travel. There shall also be a minimum of 32 inches (813 mm) clear between wing walls. See Figure 11B-3A of this code. Additionally, alcoves and space between wing walls shall comply with Section 1118B.4, Item 2. Protruding objects located in alcoves, located between wing walls or otherwise positioned so as to limit encroachment into pedestrian ways are permitted to project 4 inches (102 mm) into walks, halls, corridors, passageways or aisles.
- 4.** The bubbler shall be activated by a manually operated system complying with Section 1117B.6, Item 4 that is front mounted or side mounted and located within 6 inches (152 mm) of the front edge of the fountain or an electronically controlled device. The bubbler outlet orifice shall be located within 6 inches (152 mm) of the front edge of the drinking fountain and within 36 inches (914 mm) of the floor. The water stream from the bubbler shall be substantially parallel to the front edge of the drinking fountain.
- 5.** The spout shall provide a flow of water at least 4 inches (102 mm) high so as to allow the insertion of a cup or glass under the flow of water. On an accessible drinking fountain with a round or oval bowl, the spout must be positioned so the flow of water is within 3 inches (75 mm) of the front edge of the fountain.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1117B.2 Telephones.

1117B.2.1 General. If public pay telephones, public closed-circuit telephones or other public telephones are provided, they shall comply with this section to the extent required by the following table. See Figure 11B-4.

Number of each type of telephone provided on each floor	Minimum number of telephones required to comply with Section 1117B.2 ¹
1 or more single units	At least 50 percent of telephone units per floor but not less than one.
1 telephone bank	At least 50 percent of telephone units per bank but not less than one.
2 or more banks	At least 50 percent of telephone units per bank but not less than one. At least 1 telephone per floor shall meet the requirements for a forward reach telephone.

¹Additional public telephones may be installed at any height.

1117B.2.2 Clear floor or ground space. A clear floor or ground space at least 30 inches by 48 inches (762 mm by 1219 mm) that allows either a forward or parallel approach by a person using a wheelchair shall be provided at telephones.

1117B.2.3 Size and approach. The minimum clear floor or ground space required to accommodate a single, stationary wheelchair and occupant is 30 inches by 48 inches (762 mm by 1219 mm). The minimum clear floor or ground space for wheelchairs may be positioned for forward or parallel approach to an object. Clear floor or ground space for wheelchairs may be part of the knee space required under some objects. See Figure 11B-5A.

1117B.2.4 Relationship of maneuvering clearances to wheelchair spaces. One full unobstructed side of the clear floor or ground space for a wheelchair shall adjoin another wheelchair clear floor space. If a clear floor space is located in an alcove or otherwise confined on all or part of three sides, additional maneuvering clearances shall be provided. See Figure 11B-5A.

1117B.2.5 Floor surfaces of wheelchair spaces. Floor surfaces of wheelchair spaces shall conform to Section 1124B. Bases, enclosures and fixed seats shall not impede approaches to telephones by people who use wheelchairs.

1117B.2.6 Mounting height. The highest operable part of the telephone shall be within the reach ranges specified in Sections 1118B.5 and 1118B.6. Telephones mounted diagonally in a corner that require wheelchair users to reach diagonally shall have the highest operable part no higher than 54 inches (1372 mm) above the floor. See Figure 11B-4.

1117B.2.7 Enclosures. If telephone enclosures are provided, they may overhang the clear floor space required in Sections 1117B.2.2, 1117B.2.3 and 1117B.2.4 within the following limits:

- 1. Side reach possible.** Where a parallel approach is provided at a telephone within an enclosure, the enclosure and counter may extend beyond the face of the telephone a maximum of 10 inches (254 mm). The enclosure and counter may not overlap the required clear floor or ground space. See Figure 11B-4.
- 2. Full-height enclosures.** Entrances to full-height enclosures shall be 30 inches (762 mm) minimum. See Figure 11B-4.
- 3. Forward reach required.** Where a front approach is provided at a telephone within an enclosure, the counter may extend beyond the face of the telephone a maximum of 20 inches (508 mm) into the required clear floor or ground space and the enclosure may extend beyond the

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

face of the telephone a maximum of 24 inches (610 mm). If an additional 6 inches (152 mm) in width of clear floor space is provided, creating a clear floor space of 36 inches by 48 inches (914 mm by 1219 mm), the enclosure may extend more than 24 inches (610 mm) beyond the face of the telephone. See Figure 11B-4.

4. **Protruding telephone enclosures.** Where telephone enclosures protrude into walks, halls, corridors or aisles, they shall also comply with Section 1133B.8.6.

1117B.2.8 Telephone equipment for hearing impaired persons. Telephones shall be equipped with a receiver that generates a magnetic field in the area of the receiver cap. All telephones required to be accessible shall be equipped with a volume control. In addition, 25 percent, but never less than one, of all other public telephones provided shall be equipped with a volume control and shall be dispersed among all types of public telephones, including closed circuit telephones, throughout the building or facility. If banks of public telephones are provided, at least one in each bank shall be equipped with a volume control. Such telephones shall be capable of a minimum of 12 dBA and a maximum of 18 dBA above normal. If an automatic reset is provided, 18 dBA may be exceeded. Public telephones with volume control shall be hearing aid compatible and shall be identified by a sign containing a depiction of a telephone handset with radiating sound waves.

1117B.2.9 Text telephones.

1117B.2.9.1 Where required.

1. If a total of four or more public pay telephones (including both interior and exterior phones) are provided at a site, and if at least one of the total is in an interior location, then at least one interior public text telephone shall be provided.
2. If an interior public pay telephone is provided in a stadium or arena, in a convention center, in a hotel with a convention center or in a covered mall, at least one interior public text telephone shall be provided in the facility.
3. If a public pay telephone is located in or adjacent to a hospital emergency room, hospital recovery room or hospital waiting room, one public text telephone shall be provided at each location.
4. If alterations to existing buildings or facilities with less than four exterior or interior public pay telephones would increase the total number to four or more telephones with at least one in an interior location then a text telephone shall be provided.
5. If alterations to one or more exterior or interior public pay telephones occur in an existing building or facility with four or more public telephones with at least one in an interior location then a text telephone shall be provided.

1117B.2.9.2 General. Text telephones shall comply with the following requirements:

1. Text telephones used with a pay telephone shall be permanently affixed within or adjacent to the telephone enclosure. If an acoustic coupler is used, the telephone cord shall be sufficiently long to allow connection of the text telephone and the telephone receiver.
2. Where a bank of telephones in the interior of a building consists of three or more public pay telephones, at least one public pay telephone in each such bank shall be equipped with a shelf and an electrical outlet within or adjacent to the telephone enclosure. The telephone handset shall be capable of being placed flush on the surface of the shelf. The shelf shall be capable of accommodating a text telephone and shall have 6 inches (152 mm) minimum vertical clearance in the area where the text telephone is to be placed.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. *Equivalent facilitation may be substituted for the requirements of this section. For example, a portable text telephone may be made available in a hotel at a registration desk if it is available on a 24-hour basis for use with nearby public pay phones. In this instance, at least one pay phone shall comply with Item 2 above. In addition, if an acoustic coupler is used, the telephone handset cord shall be sufficiently long to allow connection of the text telephone and the telephone receiver. Directional signage shall comply with Section 1117B.5.1 Items 2 and 3.*

1117B.2.9.3 Signage. *Text telephones shall be identified by the international TTY symbol (see Figure 11B-14A). If a facility has a public text telephone, directional signage indicating the location of the nearest such telephone shall be placed adjacent to all banks of telephones that do not contain a text telephone. Such directional signage shall include the international TTY symbol. If a facility has no banks of telephones, the directional signage shall be provided at the entrance or in a building directory.*

1117B.2.10 Controls. *Telephones shall have push-button controls where service for such equipment is available.*

1117B.2.11 Cord length. *The cord from the telephone to the handset shall be at least 29 inches (737 mm) long.*

1117B.2.12 Telephone books. *If telephone books are provided, they shall be located in a position that complies with the reach ranges in Sections 1118B.5 and 1118B.6.*

1117B.3 Kitchens. *See Section 1133A.*

1117B.4 Swimming pools. *See Section 1104B.4.3.*

1117B.5 Signs and identification. *California's standards for signage are more stringent than Section 4.30 of the ADA Standards for Accessible Design.*

1117B.5.1 General. *When new or additional signs and/or identification devices are provided, or when existing signs and/or identification devices are replaced or altered, the new or altered signs and/or identification devices shall comply with Section 1117B.5. The addition of or replacement of signs and/or identification devices shall not trigger any additional path of travel requirements.*

1. **Identification signs.** *When signs identify permanent rooms and spaces of a building or site, they shall comply with Sections 1117B.5.2, 1117B.5.3, 1117B.5.5, 1117B.5.6 and 1117B.5.7. For other means of egress signs and identification provisions adopted by SFM and DSA-AC, see Chapter 10, Sections 1011.3 for Tactile Exit Signs, 1022.8 for Floor Identification Signs, 1008.1.9.7 for Delayed Egress Locks, 1007.9, 1007.10 and 1007.11 for Accessible Means of Egress, and 1007.4 for Elevators. See also Section 1116B for additional signage requirements applicable to elevators and Section 1115B.6 for sanitary facilities.*
2. **Directional and informational signs.** *When signs direct to or give information about permanent rooms and functional spaces of a building or site, they shall comply with Sections 1117B.5.2, 1117B.5.3 and 1117B.5.4.*
3. **Accessibility signs.** *When signs identify, direct to or give information about accessible elements and features of a building or site, they shall include the appropriate symbol of accessibility and shall comply with Sections 1117B.5.2 and 1117B.5.8.*
4. **Plan review and inspection.** *Signs and identification as specified in Section 1117B.5.1, when included in the construction of new buildings or facilities, or when included, altered or replaced due to additions, alterations or renovations to existing buildings or facilities, and when a permit is required, shall comply with the following plan review and inspection requirements:*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4.1. Plan review. Plans, specifications or other information indicating compliance with these regulations shall be submitted to the enforcing agency for review and approval.

4.2. Inspection. Signs and identification shall be field inspected after installation and approved by the enforcing agency prior to the issuance of a final certificate of occupancy per Division II Chapter 1, Section 111, or final approval where no certificate of occupancy is issued. The inspection shall include, but not be limited to, verification that Braille dots and cells are properly spaced and the size, proportion and type of raised characters are in compliance with these regulations.

4.3. Other signs and identification. Tactile exit signage in Sections 1011.3 and 1011.3.2, tactile floor identification signs in stairways in Section 1022.8, tactile special egress-control device signs in Section 1008.1.9.7, elevator car control identification required in Sections 1116B.1.8 and 1116B.1.9, elevator doorjamb marking required in Section 1116B.1.14, and sanitary facilities signage required in Section 1115B.6 shall also comply with this section.

1117B.5.2 Finish and contrast. Characters, symbols and their background shall have a nonglare finish. Characters and symbols shall contrast with their background, either light on a dark background or dark on a light background.

1117B.5.3 Proportions. Characters on signs shall be selected from fonts that have a width-to-height ratio of between 3:5 (60 percent) and 1:1 (100 percent) measured by the width of the uppercase letter “O” and height of the uppercase letter “I”, and a stroke width-to-height ratio of between 1:5 (20 percent) and 1:10 (10 percent) measured by the width and height of the uppercase letter “I”.

1117B.5.4 Character height. Characters on signs required to be accessible by Section 1117B.5.1, Items 2 and 3 shall be sized according to the following table. The minimum height is measured using an uppercase letter “I”. Lowercase characters are permitted. Viewing distance shall be measured as the horizontal distance between the character and an obstruction preventing further approach towards the sign.

Visual Character Height

Height to Finish Floor or Ground From Baseline of Character	Horizontal Viewing Distance	Minimum Character Height
40 inches (1015 mm) to less than or equal to 70 inches (1780 mm)	Less than 72 inches (1830 mm)	5/8 inch (16 mm)
	72 inches (1830 mm) and greater	5/8 inch (16 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 72 inches (1830 mm)
Greater than 70 inches (1780 mm) to less than or equal to 120 inches (3050 mm)	Less than 180 inches (4570 mm)	2 inches (51 mm)
	180 inches (4570 mm) and greater	2 inches (51 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 180 inches (4570 mm)
Greater than 120 inches (3050 mm)	Less than 21 feet (6400 mm)	3 inches (75 mm)
	21 feet (6400 mm) and greater	3 inches (75 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 21 feet (6400 mm)

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1117B.5.5 Raised characters and pictorial symbol signs. When raised characters are required or when pictorial symbols (pictograms) are used on such signs, they shall conform to the following requirements:

1. **Character type.** Characters on signs shall be raised $\frac{1}{32}$ inch (0.794 mm) minimum and shall be sans serif uppercase characters accompanied by contracted (Grade 2) Braille complying with Section 1117B.5.6.
2. **Character size.** Raised characters shall be a minimum of $\frac{5}{8}$ inch (15.9 mm) and a maximum of 2 inches (51 mm) high.
3. **Pictorial symbol signs (pictograms).** Pictorial symbol signs (pictograms) shall be accompanied by the verbal description placed directly below the pictogram. The outside dimension of the pictogram field shall be a minimum of 6 inches (152 mm) in height.
4. **Character placement.** Characters and Braille shall be in a horizontal format. Braille shall be placed a minimum of $\frac{3}{8}$ inch (9.5 mm) and a maximum of $\frac{1}{2}$ inch (12.7 mm) directly below the tactile characters; flush left or centered. When tactile text is multilined, all Braille shall be placed together below all lines of tactile text.

1117B.5.6 Braille. Contracted (Grade 2) Braille shall be used wherever Braille is required in other portions of these standards. Dots shall be $\frac{1}{10}$ inch (2.54 mm) on center in each cell with $\frac{2}{10}$ -inch (5.08 mm) space between cells, measured from the second column of dots in the first cell to the first column of dots in the second cell. Dots shall be raised a minimum of $\frac{1}{40}$ inch (0.635 mm) above the background. Braille dots shall be domed or rounded.

1117B.5.7 Mounting location and height. Where permanent identification signs are provided for rooms and spaces, signs shall be installed on the wall adjacent to the latch side of the door. Where there is no wall space on the latch side, including at double leaf doors, signs shall be placed on the nearest adjacent wall, preferably on the right.

Where permanent identification signage is provided for rooms and spaces they shall be located on the approach side of the door as one enters the room or space. Signs that identify exits shall be located on the approach side of the door as one exits the room or space.

Mounting height shall be 60 inches (1524 mm) above the finish floor to the center line of the sign. Mounting location shall be determined so that a person may approach within 3 inches (76 mm) of signage without encountering protruding objects or standing within the swing of a door.

See also Section 1115B.6 for additional signage requirements applicable to sanitary facilities.

1117B.5.8 Symbols of accessibility.

1117B.5.8.1 International Symbol of Accessibility. The International Symbol of Accessibility shall be the standard used to identify facilities that are accessible to and usable by physically disabled persons as set forth in these building standards and as specifically required in this section. See Figure 11B-6.

Exception: Signs need not be provided for facilities within an adaptable dwelling unit, or within an accessible patient or guest room.

1117B.5.8.1.1 Color of symbol. The symbol specified above shall consist of a white figure on a blue background. The blue shall be equal to Color No. 15090 in Federal Standard 595B.

Exception: The appropriate enforcement agency may approve other colors to complement decor or unique design. The symbol contrast shall be light on dark or dark on light.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1117B.5.8.1.2 Entrance signs. Entrances to buildings and facilities that are accessible to and usable by persons with disabilities shall be identified with a minimum of one International Symbol of Accessibility and with additional directional signs, utilizing the symbol, at junctions where the accessible route of travel diverges from the regular circulation path, to be visible to persons along approaching circulation paths. In existing buildings and facilities, entrances which are not accessible shall have directional signage complying with Section 1117B.5.1, Items 2 and 3, which indicates the location of and route to the nearest accessible entrance.

Exception:

1. An International Symbol of Accessibility is not required at entrances to individual rooms, suites, offices, sales or rental establishments, or other such spaces when all entrances to the building or facility are accessible and persons entering the building or facility have passed through one or more entrances with signage complying with this section.
2. An International Symbol of Accessibility is not required at entrances to machinery spaces frequented only by service personnel for maintenance, repair, or occasional monitoring of equipment; for example, elevator pits or elevator penthouses; mechanical, electrical or communications equipment rooms; piping or equipment catwalks; electric substations and transformer vaults; and highway and tunnel utility facilities.

1117B.5.8.1.3 Information posted. Buildings that provide specific sanitary facilities and/or elevators for public use that conform to these building standards shall have this information posted in the building lobby, preferably as part of the building directory. The information shall be accompanied by the International Symbol of Accessibility. Inaccessible sanitary facilities shall have directional signage complying with 1117B.5.1, Items 2 and 3, to indicate the location of the nearest accessible sanitary facility.

1117B.5.8.2 International TTY symbol. Where the international TTY symbol is required, it shall comply with Figure 11B-14A.

1117B.5.8.3 Volume control telephones. Where telephones with volume controls are required to be identified, the identification symbol shall be a telephone handset with radiating sound waves, such as shown in Figure 11B-14B.

1117B.5.8.4 Assistive listening systems. Where assistive listening systems are required to be identified by the International Symbol of Access for Hearing Loss, it shall comply with Figure 11B-14C.

1117B.5.9 Traffic-control devices. Pole-supported pedestrian traffic-control buttons shall be identified with color coding consisting of a textured horizontal yellow band 2 inches (51 mm) in width encircling the pole, and a 1-inch-wide (25 mm) dark border band above and below this yellow band. Color coding should be placed immediately above the control button. Control buttons shall be located no higher than 48 inches (1219 mm) above the surface adjacent to the pole.

1117B.5.10 Signs for text telephones. Whenever signs shall refer to text telephones for people who are deaf or hard of hearing, the term "TTY" shall be used; the term "TDD" shall not be used.

1117B.5.11 Cleaner air symbol. Strictly for publicly funded facilities or any facilities leased or rented by state of California, not concessionaires. This symbol shall be the standard used to identify a room, facility and paths of travel that are accessible to and usable by people who are adversely impacted by airborne chemicals or particulate(s) and/or the use of electrical fixtures and/or devices. When used, the symbol shall comply with Figure 11B-40.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1117B.5.11.1 Color and size of symbol. *The symbol shall be used when the following minimum conditions are met. The symbol, which shall include the text “Cleaner Air” as shown, shall be displayed either as a negative or positive image within a square that is a minimum of 6 inches on each side. The symbol may be shown in black and white or in color. When color is used, it shall be Federal Blue (Color No. 15090 Federal Standard 595B) on white, or white on Federal Blue. There shall be at least a 70-percent color contrast between the background of the sign from the surface that it is mounted on.*

Strictly for publicly funded public facilities or any facilities leased or rented by State of California; not concessionaires.

1117B.5.11.2 Conditions of use. *Use of the cleaner air symbol is voluntary. The cleaner air symbol shall be permitted for use to identify a path of travel, and a room or a facility when the following is met.*

- 1. Floor or wall coverings, floor or wall covering adhesives, carpets, formaldehyde-emitting particleboard cabinetry, cupboards or doors have not been installed or replaced in the previous 12 months.*
- 2. Incandescent lighting provided in lieu of fluorescent or halogen lighting, and electrical systems and equipment shall be operable by or on behalf of the occupant or user of the room, facility or path of travel.*
- 3. Heating, ventilation, air conditioning and their controls shall be operable by or on behalf of the occupant or user.*
- 4. To maintain “cleaner-air” designation only nonirritating, nontoxic products will be used in cleaning, maintenance, disinfection, pest management or for any minimal touch-ups that are essential for occupancy of the area. Deodorizers or Fragrance Emission Devices and Systems (FEDS) shall not be used in the designated area. Pest control practices for cleaner air areas shall include the use of bait stations using boric acid, sticky traps and silicon caulk for sealing cracks and crevices. Areas shall be routinely monitored for pest problems. Additional nontoxic treatment methods, such as temperature extremes for termites, may be employed in the event of more urgent problems. These pest control practices shall not be used 48 hours prior to placement of the sign, and the facility shall be ventilated with outside air for a minimum of 24 hours following use or application.*
- 5. Signage shall be posted requesting occupants or users not to smoke or wear perfumes, colognes or scented personal care products. Fragranced products shall not be used in the designated cleaner-air room, facility or path of travel.*
- 6. A log shall be maintained on site, accessible to the public either in person or by telephone, e-mail, fax or other accessible means as requested. One or more individuals shall be designated to maintain the log. The log shall record any product or practice used in the cleaner air designated room, facility or path of travel, as well as scheduled activities, that may impact the cleaner-air designation. The log shall also include the product label as well as the Material Safety Data Sheets (MSDS).*

1117B.5.11.3 Removal of symbol. *If the path of travel, room and/or facility identified by the cleaner air symbol should temporarily or permanently cease to meet the minimum conditions as set forth above, the cleaner air symbol shall be removed and shall not be replaced until the minimum conditions are again met.*

1117B.6 Controls and operating mechanisms.

- 1. General.** *Controls and operating mechanisms in accessible spaces, along accessible routes or as parts of accessible elements (for example, light switches and dispenser controls) and those required to be accessible by Section 1.9.1 shall comply with the requirements of this section.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. **Clear floor space.** Clear floor space complying with Section 1118B.4 that allows a forward or parallel approach by a person using a wheelchair shall be provided at controls, dispensers, receptacles and other operable equipment.
3. **Height.** The highest operable part of all controls, dispensers, receptacles and other operable equipment shall be placed within at least one of the reach ranges specified in Sections 1118B.5 and 1118B.6.

Exception: These requirements do not apply where the use of special equipment dictates otherwise or where electrical and communication systems receptacles are not normally intended for use by building occupants.

4. **Operation.** Controls and operating mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist. The force required to activate controls shall be no greater than 5 pounds (22.2 N) of force.
5. **Installation heights of electrical switches and receptacle outlets.**

5.1 Electrical switches. Controls and switches intended to be used by the occupant of the room or area to control lighting and receptacle outlets, appliances or cooling, heating and ventilating equipment, shall be located no more than 48 inches (1219 mm) measured from the top of the outlet box nor less than 15 inches (381 mm) measured from the bottom of the outlet box to the level of the finish floor or working platform.

5.2 Electrical receptacle outlets. Electrical receptacle outlets on branch circuits of 30 amperes or less and communication system receptacles shall be located no more than 48 inches (1219 mm) measured from the top of the receptacle outlet box or receptacle housing nor less than 15 inches (381 mm) measured from the bottom of the receptacle outlet box or receptacle housing to the level of the finish floor or working platform.

Exceptions:

1. Receptacle outlets installed as part of permanently installed baseboard heaters are exempt.
2. Required receptacle outlets shall be permitted in floors when adjacent to sliding panels or walls.
3. Baseboard electrical outlets used in relocatable partitions, window walls or other electrical convenience floor outlets are not subject to the minimum height requirements.
4. This section shall not apply to existing buildings when the enforcing agency determines that compliance with these standards would create an unreasonable hardship.

1117B.7 Automated teller machines and point of sale machines.

1117B.7.1 Definitions.

AUTOMATED TELLER MACHINE (ATM) means any electronic information processing device, including a point-of-sale machine, used by a financial institution or other business entity and its customers for the primary purpose of executing financial transactions between itself and its customers. For the purposes of this section, "automated teller machine" includes point-of-sale machines used in grocery stores, ticket sales facilities and other business entities, but does not include card reading devices located on fuel pump islands at gasoline service stations and motor vehicle fuel facilities.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

ATM SITE means that immediate area which is within or made or to be made part of an existing building or a building to be constructed, and to which one or more ATMs is or shall be affixed.

ATM INSTALLATION means a single ATM structurally affixed to a building or other structure.

1117B.7.2 General. Where ATMs are provided for the public, they shall comply with this section.

Exceptions:

1. In grocery stores and other retail outlets with point-of-sale machines located at individual check stands, machines that are located at accessible check stands must be made accessible. Where machines are located away from individual check stands, they must all be made accessible.
2. Where the enforcing agency determines that compliance with this regulation would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided through the use of other methods or materials.
3. In existing buildings, these regulations shall not apply when legal or physical constraints would not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.
4. Drive-up only ATMs are not required to comply with this section.
5. Card reading devices located on fuel pump islands at gasoline service stations and motor-vehicle fuel facilities shall comply with the requirements of Chapter 11C.

1117B.7.3 Controls. Controls for user activation shall comply with the requirements of Section 1117B.6, Item 4, which states that controls and operating mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist. The force required to activate controls shall be no greater than 5 lbf (22.2 N).

1117B.7.4 Clearances and reach range. Free-standing or built-in units not having a clear space under them shall comply with the following as to clearance and reach range.

1117B.7.4.1 Where one ATM is provided. Where one ATM is provided at a location, it shall meet the specifications of Section 4.34 of the Americans with Disabilities Act Standards for Accessible Design as follows:

1. The ATM shall be located so that clear floor space complying with Section 1118B.4 is provided to allow a person using a wheelchair to make a forward approach, a parallel approach, or both, to the machine.
2. **Forward approach only.** If only a forward approach is possible, operable parts of all controls shall be placed within the forward reach range specified in Section 1118B.5.
3. **Parallel approach only.** If only a parallel approach is possible, operable parts of controls shall be placed as follows:
 - 3.1. **Reach depth not more than 10 inches (254 mm).** Where the reach depth to the operable parts of all controls as measured from the vertical plane perpendicular to the edge of the unobstructed clear floor space at the farthest protrusion of the ATM or surround is not more than 10 inches (254 mm), the maximum height from the floor shall be 54 inches (1372 mm).

3.2. Reach depth more than 10 inches (254 mm). Where the reach depth to the operable parts of any control as measured from the vertical plane perpendicular to the edge of the unobstructed clear floor space at the farthest protrusion of the ATM or surround is more than 10 inches (254 mm), the maximum height from the floor shall be as shown in Table 11B-5.

4. **Forward and parallel approach.** If both a forward and parallel approach are possible, operable parts of controls shall be placed within at least one of the reach ranges in Item 2 or 3.
5. **Bins.** Where bins are provided for envelopes, waste paper, or other purposes, at least one of each type provided shall comply with the applicable reach ranges in Item 2, 3 or 4.

Exception: Where a function can be performed in a substantially equivalent manner by using an alternate control, only one of the controls needed to perform that function is required to comply with this section. If the controls are identified by tactile markings, such markings shall be provided on both controls.

1117B.7.4.2 Where two ATMs are provided. Where two ATMs are provided at a location, one shall comply with Section 1117B.7.4.1, except that the highest operable part shall be 48 inches (1219 mm) maximum. The second ATM is not regulated as to height, including height of display.

1117B.7.4.3 Where three or more ATMs are provided. Where three or more ATMs are provided, two shall be used to satisfy Section 1117B.7.4.2 above. For the additional ATMs beyond the first two, at least 50 percent shall comply with Section 1117B.7.4.1. The remainder are not regulated as to height, including height of display. If features provided differ from ATM to ATM, all features shall be equally represented among the accessible ATMs.

1117B.7.5 Display. LED, cathode ray or other screen devices intended to be viewed by the user shall be positioned so they are readily visible to and usable by a person sitting in a wheelchair with approximate eye level of 45 inches (1143 mm), and shall comply with the following requirements:

1. **Vertically mounted screen devices.** If mounted vertically or tipped no more than 30 degrees away from the viewer, the center line of screens and other screen devices shall be located a maximum of 52 inches (1321 mm) above grade.
2. **Angle-mounted screen devices.** If mounted at an angle between 30 degrees and 60 degrees tipped away from the viewer, the center line of screens and other screen devices shall be located a maximum of 44 inches (1118 mm) above grade.
3. **Horizontally mounted screen devices.** If mounted at an angle between 60 degrees and 90 degrees tipped away from the viewer, the center line of screens and other screen devices shall be located a maximum of 34 inches (864 mm) above grade.

Exception: ATMs unregulated as to height in Sections 1117B.7.4 through 1117B.7.4.3 above are also exempt from this section.

1117B.7.6 ATM equipment for persons with vision impairments. Instructions and all information for use shall be made accessible to and independently usable by persons with vision impairments.

**TABLE 11B-5
MAXIMUM REACH DEPTH FOR AUTOMATED TELLER MACHINES**

REACH DEPTH (X)	MAXIMUM HEIGHT (Y)
(inches)	(inches)
x 25.4 for mm	
10	54
11	53.5
12	53
13	52.5
14	51.5
15	51
16	50.5
17	50
18	49.5
19	49
20	48.5
21	47.5
22	47
23	46.5
24	46

See Figure 11B-5F (d).

1117B.8 Fitting and dressing rooms. Where fitting or dressing rooms are provided for male or female customers, patients, employees or the general public, 5 percent, but never less than one, of dressings rooms for each type of use in each cluster of dressing rooms shall be accessible and located on an accessible route complying with Section 1114B.1.2. Examples of types of dressing rooms are those serving different genders or distinct and different functions as in different treatment or examination facilities. Where only unisex dressing rooms are provided, accessible unisex dressing rooms may be used to fulfill this requirement.

Entry doors shall conform to the requirements of Section 1133B.2 and aisles leading to such doors shall conform to Sections 1133B.6.1 and 1133B.6.2.

The bottom of mirrors provided for use by persons with disabilities shall not be greater than 20 inches (508 mm) from the floor. Mirrors to be used by persons with disabilities shall be full length, measuring at least 18 inches (457 mm) wide by 54 inches (1372 mm) high, and shall be mounted in a position affording a view to a person on the bench as well as to a person in a standing position.

Clothing hooks shall be located not greater than 48 inches (1219 mm) from the floor.

Every accessible dressing room shall have a 24-inch by 48-inch (610 mm by 1219 mm) bench fixed to the wall along the longer dimension. The bench shall be mounted 17 to 19 inches (432 to 483 mm) above the finish floor. Clear floor space shall be provided alongside the bench to allow a person using a wheelchair to make a parallel transfer onto the bench. The structural strength of the bench and attachments shall comply with Section 1115B.7.2. Where installed in conjunction with showers, swimming pools or other wet locations, water shall not accumulate upon the surface of the bench and the bench shall have a slip-resistant surface.

The minimum clear space within the room shall be 60 inches (1524 mm) in width and length. No door shall encroach into the required space.

1117B.9 Accessible sinks. Sinks required to be accessible shall comply with this subsection.

1. A clear floor space at least 30 inches by 48 inches (762 mm by 1219 mm) complying with Section 1118B.4 shall be provided in front of a sink to allow forward approach. The clear floor space shall be on an accessible route and shall extend a maximum of 19 inches (485 mm) underneath the sink (see Figure 11B-1D).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. Each accessible sink shall be a maximum of 6½ inches (165 mm) deep. Sinks shall be mounted with the counter or rim no higher than 34 inches (865 mm) above the finish floor. Knee clearance that is at least 27 inches (685 mm) high, 30 inches (762 mm) wide and 19 inches (485 mm) deep shall be provided underneath sinks. Hot water and drain pipes exposed under sinks shall be insulated or otherwise configured so as to protect against contact. There shall be no sharp or abrasive surfaces under sinks.
3. Faucet controls and operating mechanisms shall be operable with one hand and shall not require tight grasping, pinching or twisting of the wrist. The force required to activate controls shall be not greater than 5 lbf (22.2 N). Lever-operated, push-type and electronically controlled mechanisms are examples of acceptable designs. Self-closing valves are allowed if the faucet remains open for at least 10 seconds.

SECTION 1118B SPACE ALLOWANCE AND REACH RANGES

1118B.1 Wheelchair passage width. The minimum clear width for single wheelchair passage shall be 32 inches (813 mm) at a point and 36 inches (914 mm) continuously. See Figure 11B-10. In addition, wheelchair passage widths shall comply with Figure 11B-5E(a) and (b) for circulation around obstructions.

1118B.2 Width for wheelchair passing. The minimum width for two wheelchairs to pass is 60 inches (1524 mm). See Figure 11B-11.

1118B.3 Wheelchair turning space. The space required for a wheelchair to make a 180-degree turn is a clear space of 60 inches (1524 mm) diameter [see Figure 11B-12(a)] or a T-shaped space. See Figure 11B-12(b).

1118B.4 Clear floor or ground space for wheelchairs.

1. **Size and approach.** The minimum clear floor or ground space required to accommodate a single, stationary wheelchair and occupant is 30 inches by 48 inches (762 mm by 1219 mm). The minimum clear floor or ground space for wheelchairs may be positioned for forward or parallel approach to an object. Clear floor or ground space for wheelchairs may be part of the knee space required under some objects. See Figure 11B-5A.
2. **Relationship of maneuvering clearances to wheelchair spaces.** One full unobstructed side of the clear floor or ground space for a wheelchair shall adjoin or overlap an accessible route or adjoin another wheelchair clear floor space. If a clear floor space is located in an alcove or otherwise confined on all or a part of three sides, additional maneuvering clearances shall be provided as shown in Figure 11B-5A(b).
3. **Surfaces for wheelchair spaces.** Clear floor or ground spaces for wheelchairs shall comply with Section 1124B Ground and Floor Surfaces.

1118B.5 Forward reach. If the clear floor space allows only forward approach to an object, the maximum high forward reach allowed shall be 48 inches (1219 mm) [see Figure 11B-5C(a)]. The minimum low forward reach is 15 inches (381 mm). If the high forward reach is over an obstruction, reach and clearances shall be as shown in Figure 11B-5C(b).

1118B.6 Side reach. If the clear floor space allows parallel approach by a person in a wheelchair, the maximum high side reach allowed shall be 54 inches (1372 mm) and the low side reach shall be no less than 9 inches (229 mm) above the floor [see Figure 11B-5D(a) and (b)]. If the side reach is over an obstruction, the reach and clearances shall be as shown in Figure 11B-5D(c).

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1119B SPECIAL STANDARDS OF ACCESSIBILITY FOR BUILDINGS WITH HISTORICAL SIGNIFICANCE

See Section 1135B.

SECTION 1120B FLOORS AND LEVELS

1120B.1 Floors Within Each Story. *In buildings and facilities, floors of a given story shall be a common level throughout, or shall be connected by pedestrian ramps, passenger elevators or platform (wheelchair) lifts.*

Exceptions:

1. *In existing buildings, other than dining banquet and bar facilities, when the enforcing agency determines that compliance with this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided.*
2. *In existing dining, banquet and bar facilities, when the enforcing agency determines that compliance with this section would create an unreasonable hardship, an exception shall be granted, provided that a minimum of 75 percent of the dining, banquet and bar area shall be a common level throughout or shall be connected by pedestrian ramps, passenger elevators or special lifts and provided that the same services and décor are provided in an accessible space usable by the general public and are not restricted to use by people with disabilities.*
3. *In existing buildings, this section shall not apply when legal or physical constraints would not allow compliance with this section or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.5.*
4. *Where specifically exempted in other portions of this code.*

1120B.2 Floor Surface. *The surface of floors shall be slip resistant and shall comply with Section 1124B.*

SECTION 1121B TRANSPORTATION FACILITIES

1121B.1 General. *Every station, bus stop, bus stop pad, terminal, building or other transportation facility shall incorporate the accessibility requirements of this code as modified by this chapter. The exceptions for elevators in Section 1103B do not apply to a terminal, depot or other station used for specified public transportation, or an airport passenger terminal, or facilities subject to Title II of the Americans with Disabilities Act. In such a facility, any area housing passenger services, including boarding and debarking, loading and unloading, baggage claim, dining facilities, and other common areas open to the public must be on an accessible route from an accessible entrance.*

1121B.2 Bus stops and terminals.

1121B.2.1 New construction. *Where provided, bus stop pads shall have a firm, stable surface with a minimum clear length of 96 inches (2438 mm) (measured from the curb or vehicle roadway edge) and a minimum clear width of 60 inches (1524 mm) (measured parallel to the vehicle roadway) to the maximum extent allowed by legal or site constraints. Bus stop pads shall connect to streets, sidewalks or pedestrian paths as part of an accessible route complying with Section 1114B.1.2. Newly constructed bus stop pads must provide a square curb surface between the pad and road or other detectable warning in accordance with Section 1133B.8.5.*

Bus stop pads shall be at same slope as roadway in the direction parallel to roadway, and maximum one unit vertical in 50 units horizontal (2-percent slope) perpendicular to roadway.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Where provided, bus stop shelters shall be installed so as to permit a wheelchair user to enter the shelter from the public way and access a clear floor area of 30 inches by 48 inches (762 mm by 1219 mm) complying with Section 1117B.4, completely within the shelter. Such shelters shall be connected by an accessible route to the boarding area. Where provided, all bus route identification signs shall comply with Section 1117B.5.1, Item 2.

Only approved DSA-AC detectable warning products and directional surfaces shall be installed as provided in the California Code of Regulations (CCR), Title 24, Part 1, Articles 2, 3 and 4. Refer to CCR Title 24, Part 12, Chapters 12-11A and B, for building and facility access specifications for product approval for detectable warning products and directional surfaces.

Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect—Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing, evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

1121B.2.2 Bus stop siting and alterations.

1. Bus stop sites shall be chosen such that the areas where lifts or ramps are to be deployed comply with Section 1121B.2.1.
2. When new bus route identification signs are installed or old signs are replaced, they shall comply with the requirements of Section 1121B.2.1.

1121B.3 Fixed facilities and stations.

1121B.3.1 New construction. New stations in rapid rail, light rail, commuter rail, intercity bus, intercity rail, high speed rail, and other fixed guideway systems (for example, automated guideway transit, monorails, etc.) shall comply with the following provisions, as applicable:

1. Elements such as ramps, elevators or other circulation devices, fare vending or other ticketing areas, and fare collection areas shall be placed to minimize the distance which wheelchair users and other persons who cannot negotiate steps may have to travel compared to the general public. The circulation paths, each including an accessible entrance and an accessible route, for persons with disabilities shall, to the maximum extent practicable, coincide with the circulation path for the general public. Where a circulation path is different, signage complying with Section 1117B.5.1, Items 2 and 3, shall be provided to indicate direction to and identify the accessible entrance and accessible route.
2. If different entrances to a station serve different transportation fixed routes or groups of fixed routes, entrances serving each group or route shall comply with Section 1133B.1.
3. Direct connections to commercial, retail or residential facilities shall have an accessible route complying with Section 1114B.1.2 from the point of connection to boarding platforms and all transportation system elements used by the public. Any elements provided to facilitate future direct connections shall be on an accessible route connecting boarding platforms and all transportation system elements used by the public.
4. Where signs are provided at entrances to stations identifying the station or the entrance, or both, at least one sign at each entrance shall comply with Section 1117B.5.1, Item 1. Such signs shall be placed in uniform locations at entrances within the transit system.

Exception: Where the station has no defined entrance, but signage is provided, the accessible signage shall be placed in a central location.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

5. *Stations covered by this section shall have identification signs complying with Section 1117B.5.1, Item 2. Signs shall be placed at frequent intervals and shall be clearly visible from within the vehicle on both sides when not obstructed by another train. When station identification signs are placed close to vehicle windows (that is, on the side opposite from boarding) each shall have the top of the highest letter or symbol below the top of the vehicle window and the bottom of the lowest letter or symbol above the horizontal mid-line of the vehicle window.*
6. *Lists of stations, routes or destinations served by the station and located on boarding areas, platforms or mezzanines shall comply with Section 1117B.5.1, Item 2. A minimum of one sign identifying the specific station and complying with Section 1117B.5.1, Item 1, shall be provided on each platform or boarding area. All signs referenced in this paragraph shall be placed in uniform locations within the transit system.*
7. *Automatic fare vending, collection and adjustment (for example, add-fare) systems shall comply with Section 1117B.7. Such devices shall be located on an accessible route complying with Section 1114B.1.2.*

If self-service fare collection devices are provided for the use of the general public, a minimum of 5 percent but not less than one accessible device for entering, and at least one for exiting, unless one device serves both functions, shall be provided at each location where such devices are provided.

Accessible fare collection devices shall have a minimum clear opening width of 32 inches (813 mm) and shall comply with the applicable requirements of Section 1117B.6.

Gates which must be pushed open by wheelchair or mobility aid users shall have a smooth continuous surface extending from 2 inches (51 mm) above the floor to 27 inches (686 mm) above the floor and shall comply with Sections 1133B.1 and 1133B.2.

8. *Platform edges bordering a drop-off and not protected by platform screens or guards shall have a detectable warning. Such detectable warnings shall comply with the following provisions as applicable, and shall run the full length of the platform drop-off.*
 - (a) **Detectable warnings at transit boarding platforms.** *Transit boarding platforms shall have a detectable warning texture extending the full length of the loading area. This detectable warning texture shall have the following features.*

Width 24 to 36 inches (610 mm to 914 mm) placed at the edge of the drop-off or safe area.

Durable, slip-resistant material having a surface texture composed of raised, truncated domes with a diameter of nominal 0.9 inch (22.9 mm) at the base tapering to 0.45 inch (11.4 mm) at the top, a height of nominal 0.2 inch (5.08 mm), and a center-to-center spacing of nominal 2.35 inches (59.7 mm) in compliance with Figure 11B-23A. "Nominal" as used here shall be in accordance with California State Referenced Standards Code Sections 12-11A and B-102. The detectable warning shall contrast visually with adjoining surfaces, either light on dark or dark on light. The material used to provide contrast shall be an integral part of the walking surface. Warning surfaces shall differ from adjoining walking surfaces in resiliency or sound-on-cane contact. This surface shall be reserved for warning.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Color yellow conforming to Federal Color No. 33538, as shown in Table IV of Standard No. 595B. Where the color value contrast between the yellow warning and the main walking surface is less than 70 percent, a 1 inch-wide (25 mm) black strip shall separate the yellow warning from the main walking surface. Contrast shall be determined by:

$$\text{Contrast} = [(B1-B2)/B1] \times 100 \text{ percent where}$$

B1 = light reflectance value (LRV) of the lighter area and
B2 = light reflectance value (LRV) of the darker area.

Only approved DSA-AC detectable warning products and directional surfaces shall be installed as provided in the California Code of Regulations (CCR), Title 24, Part 1, Articles 2, 3 and 4. Refer to CCR Title 24, Part 12, Chapters 12-11A and B, for building and facility access specifications for product approval for detectable warning products and directional surfaces.

Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect—Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

- (b) Detectable directional texture at boarding platforms.** At transit boarding platforms, the pedestrian access shall be identified with a detectable directional texture. This detectable directional texture shall comply with Figure 11B-23B and shall be 0.1 inch (2.54 mm) in height that tapers off to 0.04 inch (1.02 mm), with bars raised 0.2 inch (5.08 mm) from the surface. The raised bars shall be 1.3 inches (33.02 mm) wide and 3 inches (76 mm) from center-to-center of each bar. This surface shall differ from adjoining walking surfaces in resiliency or sound-on-cane contact. The color of the directional texture shall comply with Section 1121B.3.1, Item 8(a). This surface will be placed directly behind the yellow detectable warning texture specified in Section 1121B.3.1, Item 8(a), aligning with all doors of the transit vehicles where passengers will embark. The width of the directional texture shall be equal to the width of the transit vehicle's door opening. The depth of the texture shall not be less than 36 inches (914 mm).

Only approved DSA-AC detectable warning products and directional surfaces shall be installed as provided in the California Code of Regulations (CCR), Title 24, Part 1, Articles 2, 3 and 4. Refer to CCR Title 24, Part 12, Chapters 12-11A and B, for building and facility access specifications for product approval for detectable warning products and directional surfaces.

Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect—Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

- 9.** In stations covered by this section, rail-to-platform height in new stations shall be coordinated with the floor height of new vehicles so that the vertical difference, measured when the vehicle is at rest, is within plus or minus $\frac{5}{8}$ inch (15.9 mm) under normal passenger load conditions.

For rapid rail, light rail, commuter rail, high speed rail, and intercity rail systems in new stations, the horizontal gap, measured when the new vehicle is at rest, shall be no greater than 3 inches (76 mm).

For slow moving automated guideway "people mover" transit systems, the horizontal gap in new stations shall be no greater than 1 inch (25 mm).

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Exceptions:

1. Existing vehicles operating in new stations may have a vertical difference with respect to the new platform within plus or minus 1½ inches (38 mm).
 2. In light rail, commuter rail and intercity rail systems where it is not operationally or structurally feasible to meet the horizontal gap or vertical difference requirements, mini-high platforms, car-borne or platform-mounted lifts, ramps or bridge plates, or similar manually deployed devices, meeting the applicable requirements of 36 CFR Part 1192, or 49 CFR Part 38 shall suffice.
10. Stations shall not be designed or constructed so as to require persons with disabilities to board or alight from a vehicle at a location other than one used by the general public.
 11. Illumination levels in the areas where signage is located shall be uniform and shall minimize glare on signs. Lighting along circulation routes shall be of a type and configuration to provide uniform illumination.
 12. Text Telephones. The following shall be provided in accordance with Sections 1117B.2.9.2 and 1117B.2.9.3:
 - (a) If an interior public pay telephone is provided in a transit facility (as defined by the federal Department of Transportation) at least one interior public text telephone shall be provided in the station.
 - (b) Where four or more public pay telephones serve a particular entrance to a rail station and at least one is in an interior location, at least one interior public text telephone complying with Sections 1117B.2.9.2 and 1117B.2.9.3 shall be provided to serve that entrance.
 13. Where it is necessary to cross tracks to reach boarding platforms, the route surface shall be level and flush with the rail top at the outer edge and between rails, except for a maximum 2½-inch (64 mm) gap on the inner edge of each rail to permit passage of wheel flanges. Such crossings shall comply with Section 1133B.8.5. Where gap reduction is not practicable, an above-grade or below-grade accessible route shall be provided.
 14. Where public address systems are provided to convey information to the public in terminals, stations, or other fixed facilities, a means of conveying the same or equivalent information to persons with hearing loss or who are deaf shall be provided.
 15. Where clocks are provided for use by the general public, the clock face shall be uncluttered so that its elements are clearly visible. Hands, numerals, and/or digits shall contrast with the background either light-on-dark or dark-on-light. Where clocks are mounted overhead, numerals and/or digits shall comply with Section 1117B.5.4. Clocks shall be placed in uniform locations throughout the facility and system.
 16. Where provided in below-grade stations, escalators shall have a minimum clear width of 32 inches (813 mm). At the top and bottom of each escalator run, at least two contiguous treads shall be level beyond the comb plate before the risers begin to form. All escalator treads shall be marked by a strip of clearly contrasting color, 2 inches (51 mm) in width, placed parallel to and on the nose of each step. The strip shall be of a material that is at least as slip resistant as the remainder of the tread. The edge of the tread shall be apparent from both ascending and descending directions.
 17. Where provided, elevators shall be glazed or have transparent panels to allow an unobstructed view both into and out of the car. Elevators shall comply with Section 1116B.

Exception: Elevator cars with a clear floor area in which a 60-inch-diameter (1524 mm) circle can be inscribed may be substituted for the minimum car dimensions of Section 1116B and Figure 11B-40A.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

18. *Where provided, ticketing areas shall comply with Section 1122B.5, and the customer side of the baggage check-in area shall be accessible.*
19. *Where provided, baggage check-in and retrieval systems shall be on an accessible route complying with Section 1114B.1.2 and shall have space immediately adjacent complying with Section 1118B.*

If unattended security barriers are provided, at least one gate shall comply with Sections 1133B.1 and 1133B.2. Passageways containing security barriers shall comply with Section 1133B.2.3.4.

Gates which must be pushed open by wheelchair or mobility aid users shall have a smooth continuous surface extending from 2 inches (51 mm) above the floor to 27 inches (686 mm) above the floor.

1121B.3.2 Existing facilities—alterations. *Alterations of transportation facilities shall comply with Section 1134B.*

1121B.4 Airports.

1121B.4.1 New construction.

1. *Elements such as ramps, elevators or other vertical circulation devices, ticketing areas, security checkpoints or passenger waiting areas shall be placed to provide equitable travel distances for wheelchair users and other persons who cannot negotiate steps compared to the route for the general public.*
2. *The circulation paths, each including an accessible entrance and an accessible route, for persons with disabilities shall, to the maximum extent practicable, coincide with the circulation path for the general public. Where a circulation path is different, signage complying with Section 1117B.5.1, Items 2 and 3, shall be provided to indicate direction to and identify the accessible entrance and accessible route.*
3. *Where provided, ticketing areas shall comply with Section 1122B.5, and the customer side of the baggage check-in area shall be accessible.*
4. *Where public pay telephones are provided, and at least one is at an interior location, a public text telephone shall be provided in compliance with Sections 1117B.2.9.2 and 1117B.2.9.3. Additionally, if four or more public pay telephones are located in any of the following locations, at least one public text telephone shall also be provided in that location: (a) a main terminal outside the security areas; (b) a concourse within the security areas; or (c) a baggage claim area in a terminal.*
5. *Where provided, baggage check-in and retrieval systems shall be on an accessible route complying with Section 1114B.1.2 and shall have space immediately adjacent complying with Section 1118B.*

If unattended security barriers are provided, at least one gate shall comply with Sections 1133B.1 and 1133B.2. Passageways containing security barriers shall comply with Section 1133B.2.3.4.

Gates which must be pushed open by wheelchair or mobility aid users shall have a smooth continuous surface extending from 2 inches (51 mm) above the floor to 27 inches (686 mm) above the floor.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

6. *Terminal information systems which broadcast information to the general public through a public address system shall provide a means to provide the same or equivalent information to persons with a hearing loss or who are deaf. Such methods may include, but are not limited to, visual paging systems using video monitors and computer technology. For persons with certain types of hearing loss such methods may include, but are not limited to, an assistive listening system complying with Section 1104B.2.*
7. *Where clocks are provided for use by the general public the clock face shall be uncluttered so that its elements are clearly visible. Hands, numerals and/or digits shall contrast with their background either light-on-dark or dark-on-light. Where clocks are mounted overhead, numerals and/or digits shall comply with Section 1117B.5.4. Clocks shall be placed in uniform locations throughout the facility.*

SECTION 1122B FIXED OR BUILT-IN SEATING, TABLES, AND COUNTERS

1122B.1 Minimum number. *Where fixed or built-in seating, tables or counters are provided in accessible public use or common use areas, 5 percent, but never less than one, must be accessible as provided in this section. An accessible route of travel complying with Section 1114B.1.2 shall lead to and through such fixed or built-in seating areas or tables.*

1122B.2 Seating. *If seating spaces for persons in wheelchairs are provided at fixed tables or counters, clear floor space complying with Section 1118B.4 shall be provided. Such clear floor space shall not overlap knee space by more than 19 inches (483 mm) (see Figure 11B-13).*

1122B.3 Knee clearance. *If seating for persons in wheelchairs is provided at fixed tables or counters, knee spaces at least 27 inches (686 mm) high, 30 inches (762 mm) wide and 19 inches (483 mm) deep shall be provided (see Figure 11B-13).*

Exception: *Knee clearance is not required at checkout counters or service counters.*

1122B.4 Height of work surfaces. *The tops of tables and counters shall be 28 inches to 34 inches (711 mm to 864 mm) from the floor or ground.*

Where a single counter contains more than one transaction station, such as (but not limited to) a bank counter with multiple teller windows or a retail sales counter with multiple cash register stations, at least 5 percent, but never less than one, of each type of station shall be located at a section of counter that is at least 36 inches (914 mm) long and no more than 28 to 34 inches (711 to 864 mm) high.

1122B.5 Sales and service counters, teller windows, and information counters. *In department stores and miscellaneous retail stores where counters have cash registers and are provided for sales or distribution of goods or services to the public, at least one of each type shall have a portion of the counter which is at least 36 inches (915 mm) in length with a maximum height of 34 inches (864 mm) above the finish floor and located on an accessible route complying with Section 1114B.1.2.*

At ticketing counters, teller stations in a bank, registration counters in hotels and motels, box office ticket counters and other counters that may not have a cash register but at which goods or services are sold or distributed, a portion of the main counter which is a minimum of 36 inches (915 mm) in length shall be provided with a maximum height of 34 inches (864 mm).

Exception: *In existing buildings where it is determined that providing an accessible counter would create an unreasonable hardship, equivalent facilitation may consist of one of the following:*

1. *An auxiliary counter, in close proximity to the main counter, meeting these requirements may be provided.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. *Provision of a folding shelf attached to the main counter on which an individual with disabilities can write.*

SECTION 1123B ACCESS TO EMPLOYEE AREAS

1123B.1 General. *Employee areas shall comply with the accessibility requirements of this chapter.*

1123B.2 Work stations. *Specific work stations need only comply with aisle width (Sections 1133B.6.1 and 1133B.6.2) and floors and levels (Section 1120B), and entryways shall be 32 inches (813 mm) in clear width.*

Exception: *Accessibility is not required to (1) observation galleries used primarily for security purposes; or (2) in nonoccupiable spaces accessed only by ladders, catwalks, crawl spaces, very narrow passageways or freight (nonpassenger) elevators, and frequented only by service personnel for repair purposes; such spaces include, but are not limited to, elevator pits, elevator penthouses, mechanical rooms, piping or equipment catwalks.*

SECTION 1124B GROUND AND FLOOR SURFACES

1124B.1 General. *Ground and floor surfaces along accessible routes and in accessible rooms and spaces, including floors, walks, ramps, stairs and curb ramps, shall be stable, firm, slip resistant and shall comply with this section.*

1124B.2 Changes in level. *Changes in level up to ¼ inch (6.4 mm) may be vertical and without edge treatment [see Figure 11B-5E(c)]. Changes in level between ¼ inch (6.4 mm) and ½ inch (12.7 mm) shall be beveled with a slope no greater than one unit vertical in 2 units horizontal (50-percent slope) [see Figure 11B-5E(d)]. Changes in level greater than ½ inch (12.7 mm) shall be accomplished by means of a curb ramp, ramp, elevator or platform lift that complies with Sections 1127B.5, 1133B.5, 1116B.1 or 1116B.2, respectively.*

1124B.3 Carpet. *If carpet or carpet tile is used on a ground or floor surface, then it shall be securely attached; have a firm cushion, pad or backing or no cushion or pad; and have a level loop, textured loop, level-cut pile or level-cut/uncut pile texture. The maximum pile height shall be ½ inch (12.7 mm). See Figure 11B-7E(b). Exposed edges of carpet shall be fastened to floor surfaces and have trim along the entire length of the exposed edge. Carpet edge trim shall comply with Section 1124B.2.*

1124B.4 Gratings. *If gratings are located in walking surfaces, then they shall have spaces no greater than ½ inch (12.7 mm) wide in one direction (see Figure 11B-7E). If gratings have elongated openings, then they shall be placed so that the long dimension is perpendicular to the dominant direction of travel (see Figure 11B-7E).*

SECTION 1125B STORAGE

1125B.1 General. *If fixed storage facilities such as cabinets, shelves, closets or drawers are provided where access is required by Section 1.9.1, at least one of each type shall comply with this section. Additional storage may be provided outside of the reach ranges shown in Figure 11B-5D.*

1125B.2 Clear floor space. *A clear floor space at least 30 inches by 48 inches (762 mm by 1219 mm) complying with Section 1118B.4 that allows either a forward or parallel approach by a person using a wheelchair shall be provided at accessible storage facilities.*

1125B.3 Height. *Accessible storage spaces shall be within at least one of the reach ranges specified in Sections 1118B.5 and 1118B.6. Clothes rods shall be a maximum of 54 inches (1372 mm) from the floor for a side approach (See Figure 11B-5D). Where the distance from the wheelchair to the clothes rod or shelf exceeds 10 inches (254 mm),*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

as in closets without accessible doors, the height and depth to the rod or shelf shall comply with Figure 11B-5D.

1125B.4 Hardware. *Hardware for accessible storage facilities shall comply with Section 1117B.6. Touch latches and U-shaped pulls are acceptable.*

SECTION 1126B VENDING MACHINES AND OTHER EQUIPMENT

Spaces for vending machines and other equipment shall comply with Section 1118B and shall be located on an accessible route complying with Section 1114B.1.2. Controls for vending machines and other equipment shall comply with Section 1117B.6, Controls and Operating Mechanisms.

Division II – SITE ACCESSIBILITY

SECTION 1127B EXTERIOR ROUTES OF TRAVEL

1127B.1 General. Site development and grading shall be designed to provide access to all entrances and exterior ground floor exits, and access to normal paths of travel, and where necessary to provide access, shall incorporate pedestrian ramps, curb ramps, etc. Access shall be provided within the boundary of the site from public transportation stops, accessible parking spaces, passenger loading zones if provided, and public streets or sidewalks. When more than one building or facility is located on a site, accessible routes of travel complying with Section 1114B.1.2 shall be provided between buildings and accessible site facilities, accessible elements, and accessible spaces that are on the same site. The accessible route of travel shall be the most practical direct route between accessible building entrances, accessible site facilities and the accessible entrance to the site. If access is provided for pedestrians from a pedestrian tunnel or elevated walkway, entrances to the building from each tunnel or walkway must be accessible.

Exceptions:

1. Where the enforcing agency determines that compliance with these regulations would create an unreasonable hardship because of topography, natural barriers, etc., an exception may be granted when equivalent facilitation is provided through the use of other methods and materials.
2. In existing buildings, this section shall not apply in those conditions where, due to legal or physical constraints, the site of the project would not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.

1127B.2 Design and construction. When accessibility is required by this section, it shall be designed and constructed in accordance with this Building Code. See Section 1114B.1 for a list of applicable sections.

1127B.3 Signs. At every primary public entrance and at every major junction where the accessible route of travel diverges from the regular circulation path along or leading to an accessible route of travel, entrance or facility, there shall be a sign displaying the International Symbol of Accessibility. Signs shall indicate the direction to accessible building entrances and facilities and shall comply with the requirements found in Sections 1117B.5.1 Item 2 and 1117B.5.8.1.

1127B.4 Outside stairways. See Section 1133B.4.

1127B.5 Curb ramps.

1. **General.** Curb ramps shall be constructed at each corner of street intersections and where a pedestrian way crosses a curb. Built-up curb ramps shall be located so that they do not project into vehicular traffic lanes. The preferred and recommended location for curb ramps is in the center of the crosswalk of each street corner. Where it is necessary to locate a curb ramp in the center of the curb return and the street surfaces are marked to identify pedestrian crosswalks, the lower end of the curb ramp shall terminate within such crosswalk areas. See Figure 11B-20C, Case E and Figure 11B-22.
2. **Width of curb ramps.** Curb ramps shall be a minimum of 4 feet (1219 mm) in width and shall lie, generally, in a single sloped plane, with a minimum of surface warping and cross slope.
3. **Slope of curb ramps.** The slope of curb ramps shall not exceed one unit vertical in 12 units horizontal (8.33-percent slope). The slope shall be measured as shown in Figure 11B-20E. Transitions from ramps to walks, gutters or streets shall be flush and free of abrupt change. Maximum slopes of adjoining gutters, road surface immediately adjacent to the curb ramp, or accessible route shall not exceed one unit vertical in 20 units horizontal (5-percent slope) within 4 feet (1219 mm) of the bottom of the curb ramp. The slope of the fanned or flared sides of curb ramps shall not exceed one unit vertical in 10 units horizontal (10 percent slope).

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4. **Level landing.** A level landing 4 feet (1219 mm) deep shall be provided at the upper end of each curb ramp over its full width to permit safe egress from the ramp surface, or the slope of the flared or flared sides of the curb ramp shall not exceed one unit vertical in 12 units horizontal (8.33-percent slope).
5. **Finish.** The surface of each curb ramp and its flared sides shall comply with Section 1124B, Ground and Floor Surfaces, and shall be of contrasting finish from that of the adjacent sidewalk.
6. **Border.** All curb ramps shall have a grooved border 12 inches (305 mm) wide at the level surface of the sidewalk along the top and each side approximately $\frac{3}{4}$ inch (19 mm) on center. All curb ramps constructed between the face of the curb and the street shall have a grooved border at the level surface of the sidewalk. See Figures 11B-19A and 11B-19B.
7. **Detectable warnings.** Curb ramps shall have a detectable warning that extends the full width and depth of the curb ramp, excluding the flared sides, inside the grooved border. Detectable warnings shall be slip-resistant and consist of raised truncated domes with a diameter of nominal 0.9 inch (22.9 mm) at the base tapering to 0.45 inch (11.4 mm) at the top, a height of nominal 0.2 inch (5.08 mm) and a center-to-center spacing of nominal 2.35 inches (59.7 mm) in compliance with Figure 11B-23A. "Nominal" here shall be in accordance with Section 12-11A and B-102, State Referenced Standards Code. The detectable warning shall contrast visually with adjoining surfaces, either light-on-dark or dark-on-light. The material used to provide contrast shall be an integral part of the walking surface. The domes may be constructed in a variety of methods, including cast in place or stamped, or may be part of a prefabricated surface treatment.

Only approved DSA-AC detectable warning products and directional surfaces shall be installed as provided in the California Code of Regulations (CCR), Title 24, Part 1, Articles 2, 3 and 4. Refer to CCR Title 24, Part 12, Chapter 12-11A and B, for building and facility access specifications for product approval for detectable warning products and directional surfaces.

Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect–Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing, evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

8. **Obstructions.** Curb ramps shall be located or protected to prevent their obstruction by parked vehicles.
9. **Diagonal curb ramps.** If diagonal (or corner-type) curb ramps have returned curbs or other well-defined edges, such edges shall be parallel to the direction of pedestrian flow. The bottom of diagonal curb ramps shall have 48 inches (1219 mm) minimum clear space as shown in Figure 11B-22(c) and (d). If diagonal curb ramps are provided at marked crossings, the 48-inch (1219 mm) clear space shall be within the markings [see Figure 11B-22(c) and (d)]. If diagonal curb ramps have flared sides, they shall also have at least a 24 inch (610 mm) long segment of straight curb located on each side of the curb ramp and within the marked crossing [see Figure 11B-22 (c)].

Notes:

1. For additional curb details, see Figures 11B-19A and 11B-19B.
2. If the distance from curb to back of sidewalk is too short to accommodate a ramp and a 4-foot (1219 mm) platform as in Figure 11B-20A, Case A, the sidewalk may be depressed longitudinally as in Figure 11B-20A, Case B, or Figure 11B-20B, Case C, or may be widened as in Figure 11B-20B, Case D.
3. If the sidewalk is less than 5 feet (1524 mm) wide, the full width of the sidewalk shall be depressed as shown in Figure 11B-20B, Case C.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4. *As an alternate to Figure 11B-20A, Case A, one ramp may be placed in the center of the curb return as in Figure 11B-20C, Case E.*
5. *When a ramp is located in the center of a curb return, the crosswalk configuration must be similar to that shown on the plan to accommodate wheelchairs. See Figure 11B-22.*
6. *If the planting area width is equal to or greater than the ramp length, the ramp side slope distance equals 3 feet (914 mm). See Figure 11B-20D, Case G.*
7. *For Figure 11B-20C, Case F, and Figure 11B-20D, Case G, the longitudinal portion of the sidewalk may need to be depressed as shown in Figure 11B-20A, Case B.*
8. *If located on a curve, the sides of the ramp need not be parallel, but the minimum width of the ramp shall be 4 feet (1219 mm).*
9. *The ramp shall have a 12-inch-wide (305 mm) border with ¼-inch (6 mm) grooves approximately ¾ inch (19 mm) on center. See grooving detail, Figure 11B-20D, Case H.*

SECTION 1128B PEDESTRIAN GRADE SEPARATION (OVERPASSES AND UNDERPASSES)

Pedestrian ramps on pedestrian grade separations shall comply with the requirements of Section 1133B.5 for ramps.

Cross slopes of walking surfaces shall be the minimum possible and shall not exceed one unit vertical in 50 units horizontal (2-percent slope). The slope of any appreciably warped walking surface shall not exceed one unit vertical in 12 units horizontal (8.33-percent slope) in any direction. Where pedestrian grade separations cross streets or other vehicular traffic ways, and where a street level crossing can reasonably and safely be used by persons with physical disabilities, there shall be provided conforming curb ramps and a usable pathway.

Exceptions:

1. *When the grade differential of the walking surface of a pedestrian grade separation exceeds 14 feet (4267 mm) due to required height clearance and grade conditions, and the enforcing agency finds that because of right-of-way restrictions, topography or natural barriers, wheelchair accessibility or equivalent facilitation would create an unreasonable hardship, such accessibility need not be provided. However, the requirements in these regulations relating to other types of mobility shall be complied with.*
2. *For existing facilities, this section shall not apply where, due to legal or physical constraints, the site of the project will not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.*

SECTION 1129B ACCESSIBLE PARKING REQUIRED

1129B.1 General. *Each lot or parking structure where parking is provided for the public as clients, guests or employees, shall provide accessible parking as required by this section. Accessible parking spaces serving a particular building shall be located on the shortest accessible route of travel (complying with Section 1114B.1.2) from adjacent parking to an accessible entrance. In parking facilities that do not serve a particular building, accessible parking shall be located on the shortest accessible route of travel to an accessible pedestrian entrance of the parking facility. In buildings with multiple accessible entrances with adjacent parking, accessible parking spaces shall be dispersed and located closest to the accessible entrances. Table 11B-6 establishes the number of accessible parking spaces required.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1129B.2 Medical Care Outpatient Facilities. At facilities providing medical care and other services for persons with mobility impairments, parking spaces complying with this section shall be provided in accordance with Table 11B-6 except as follows:

1. **Outpatient units and facilities.** Ten percent of the total number of parking spaces provided shall serve each such outpatient unit or facility.
2. **Units and facilities that specialize in treatment or services for persons with mobility impairments.** Twenty percent of the total number of parking spaces provided shall serve each such unit or facility.

**TABLE 11B-6
SPACES REQUIRED**

Establishes the number of accessible parking spaces required.

TOTAL NUMBER OF PARKING SPACES IN LOT OR GARAGE	MINIMUM REQUIRED NUMBER OF SPACES
1-25	1
26-50	2
51-75	3
76-100	4
101-150	5
151-200	6
201-300	7
301-400	8
401-500	9
501-1,000	*
1,001 and over	**

*Two percent of total.

**Twenty plus one for each 100, or fraction over 1,001.

1129B.3 Parking space size. Accessible parking spaces shall be located as near as practical to a primary entrance and shall be sized as follows:

1. **Dimensions.** Where single spaces are provided, they shall be 14 feet (4267 mm) wide and lined to provide a 9-foot (2743 mm) parking area and a 5-foot (1524 mm) loading and unloading access aisle on the passenger side of the vehicle. When more than one space is provided in lieu of providing a 14-foot-wide (4267 mm) space for each parking space, two spaces can be provided within a 23-foot-wide (7010 mm) area lined to provide a 9-foot (2743 mm) parking area on each side of a 5-foot (1524 mm) loading and unloading access aisle in the center. The loading and unloading access aisle shall be marked by a border painted blue. Within the blue border, hatched lines a maximum of 36 inches (914 mm) on center shall be painted a color contrasting with the parking surface, preferably blue or white. See Figure 11B-18A. Parking access aisles shall be part of an accessible route of travel (complying with Section 1114B.1.2) to the building or facility entrance. Parked vehicle overhangs shall not reduce the clear width of an accessible route. The minimum length of each parking space, shall be 18 feet (5486 mm). The words "NO PARKING" shall be painted on the ground within each 5-foot (1524 mm) loading and unloading access aisle. This notice shall be painted in white letters no less than 12 inches (305 mm) high and located so that it is visible to traffic enforcement officials. See Figures 11B-18A, 11B-18B and 11B-18C.
2. **Van space(s).** One in every eight accessible spaces, but not less than one, shall be served by a loading and unloading access aisle 96 inches (2438 mm) wide minimum placed on the side opposite the driver's side when the vehicle is going forward into the parking space and shall be designated van accessible as required by Section 1129B.4. All such spaces may be grouped on one level of a parking structure. The loading and unloading access aisle shall be marked by a border painted blue. Within the blue border, hatched lines a maximum of 36 inches (914 mm) on center shall be painted a color contrasting with the parking surface, preferably blue or white. The words "NO PARKING" shall be painted on the ground within each 8-foot (2438 mm) loading and unloading access aisle. This notice shall be painted in white letters no less than 12 inches (305 mm) high and located so that it is visible to traffic enforcement officials. See Figures 11B-18A, 11B-18B and 11B-18C.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

- 3. Arrangement of parking space.** *In each parking area, a bumper or curb shall be provided if required to prevent encroachment of cars over the required width of walkways. Also, the space shall be located so a person with a disability is not compelled to wheel or walk behind parking spaces other than that person's own accessible parking space. Pedestrian ways which are accessible to persons with disabilities shall be provided from each such parking space to related facilities, including curb cuts or ramps as needed. Ramps shall not encroach into any accessible parking space or the adjacent access aisle. See Figures 11B-18A through 11B-18C.*

Exceptions:

- 1. Where the enforcing agency determines that compliance with any regulation of this section would create an unreasonable hardship, a variance or waiver may be granted when equivalent facilitation is provided.*
- 2. Parking spaces may be provided which would require a person with a disability to wheel or walk behind a parking space other than that person's own accessible parking space when the enforcing agency determines that compliance with these regulations or providing equivalent facilitation would create an unreasonable hardship. See Section 1.9.1.5.*
- 4. Slope of parking space and access aisle.** *Surface slopes of accessible parking spaces and access aisles shall be the minimum possible and shall not exceed one unit vertical in 50 units horizontal (2-percent slope) in any direction.*
- 5. Vertical clearance.** *Provide minimum vertical clearance of 98 inches (2489 mm) at accessible parking spaces and along at least one vehicle access route to such spaces from site entrances and exits.*

1129B.4 Identification of parking spaces for off-street parking facilities. *Each parking space reserved for persons with disabilities shall be identified by a reflectorized sign permanently posted immediately adjacent to and visible from each stall or space, consisting of the International Symbol of Accessibility in white on a dark blue background. The sign shall not be smaller than 70 square inches (4516 mm²) in area and, when in a path of travel, shall be posted at a minimum height of 80 inches (2032 mm) from the bottom of the sign to the parking space finished grade. Signs may also be centered on the wall at the interior end of the parking space. An additional sign or additional language below the symbol of accessibility shall state "Minimum Fine \$250."*

Van accessible spaces complying with Section 1129B.3, Item 2 shall have an additional sign or additional language stating "Van Accessible" below the symbol of accessibility. Signs identifying accessible parking spaces shall be located so they cannot be obscured by a vehicle parked in the space.

An additional sign shall also be posted in a conspicuous place at each entrance to off-street parking facilities, or immediately adjacent to and visible from each accessible stall or space. The sign shall not be less than 17 inches by 22 inches (432 mm by 559 mm) in size with 1 inch (25 mm) high minimum lettering which clearly and conspicuously states the following:

"Unauthorized vehicles parked in designated accessible spaces not displaying distinguishing placards or special license plates issued for persons with disabilities will be towed away at the owner's expense. Towed vehicles may be reclaimed at _____ or by telephoning _____."

Blank spaces are to be filled in with appropriate information as a permanent part of the sign.

In addition to the above requirements, the surface of each accessible parking space or stall shall have a surface identification duplicating either of the following schemes:

- 1. By outlining or painting the stall or space in blue and outlining on the ground in the stall or space in white or suitable contrasting color a profile view depicting a wheelchair with occupant; or*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. *By outlining a profile view of a wheelchair with occupant in white on blue background. The profile view shall be located so that it is visible to a traffic enforcement officer when a vehicle is properly parked in the space and shall be 36 inches high by 36 inches wide (914 mm by 914 mm). See Figures 11B-18A through 11B-18C.*

SECTION 1130B PARKING STRUCTURES

1130B.1 *All entrances to and vertical clearances within parking structures shall comply with Section 1129B.3, Item 5 where required for accessibility to accessible parking spaces.*

Exceptions:

1. *Where the enforcing agency determines that compliance with Section 1130B.1 would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.*
2. *This section shall not apply to existing buildings where the enforcing agency determines that, due to legal or physical constraints, compliance with these regulations or equivalent facilitation would create an unreasonable hardship. See Section 1.9.1.5.*

1130B.2 *When direct access is provided for pedestrians from a parking garage to a building, each direct entrance from the garage to the building must be accessible.*

SECTION 1131B PASSENGER DROP-OFF AND LOADING ZONES

1131B.1 Location. *When provided, passenger drop-off and loading zones shall be located on an accessible route of travel (complying with Section 1114B.1.2) and shall comply with 1131B.2.*

1131B.2 Passenger loading zones.

1. **General.** *Where provided, one passenger drop-off and loading zone shall provide an access aisle at least 60 inches (1524 mm) wide and 20 feet (6096 mm) long adjacent and parallel to the vehicle pull-up space. Vehicle standing spaces and access aisles shall be level with surface slopes not exceeding one unit vertical in 50 units horizontal (2-percent slope) in all directions. If there are curbs between the access aisle and the vehicle pull-up space, a curb ramp shall be provided. Each passenger drop-off and loading zone designed for persons with disabilities shall be identified by a reflectorized sign, complying with Section 1117B.5.1 Items 2 and 3, permanently posted immediately adjacent to and visible from the passenger drop-off or loading zone stating "Passenger Loading Zone Only" and including the International Symbol of Accessibility, in white on dark blue background.*
2. **Vertical clearance.** *Provide minimum vertical clearance of 114 inches (2896 mm) at accessible passenger loading zones and along at least one vehicle access route to such areas from site entrances and exits.*

1131B.3 Valet parking. *Valet parking facilities shall provide a passenger loading zone complying with Section 1131B.2 above and shall be located on an accessible route of travel (complying with Section 1114B.1.2) to the entrance of the facility. The parking space requirements of Sections 1129B through 1130B apply to facilities with valet parking.*

1131B.4 Bus stop pads and shelters. *See Section 1121B.2.1.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1132B OUTDOOR OCCUPANCIES

1132B.1 General. *Outdoor occupancies shall be accessible as required in this chapter. See also the general requirements in Section 1114B.1.1.*

1132B.2 Parks and recreational areas. *The following parks and recreational areas shall comply with these regulations.*

Exceptions:

1. *In existing buildings, when the enforcing agency determines that compliance would create an unreasonable hardship, a variance shall be granted when equivalent facilitation is provided.*
 2. *Where the enforcing agency finds that, in specific areas, the natural environment would be materially damaged by compliance with these regulations, such areas shall be subject to these regulations only to the extent that such material damage would not occur.*
 3. *Automobile access shall not be provided or paths of travel shall not be made accessible when the enforcing agency determines that compliance with these regulations would create an unreasonable hardship.*
-
1. **Campsites.** *Campsites, a minimum of two and no fewer than three for each 100 campsites provided, shall be accessible by a level path or ramp and shall have travel routes with slopes not exceeding one unit vertical in 12 units horizontal (8.33-percent slope) to sanitary facilities. Permanent sanitary facilities serving campgrounds shall be accessible to wheelchair occupants.*
 2. **Beaches, picnic areas.** *Beaches, picnic areas, day-use areas, vista points and similar areas shall be accessible.*
 3. **Sanitary facilities.** *Sanitary facilities, to the extent that such facilities are provided, each public use area that is accessible to wheelchair occupants by automobile, walks or other paths of travel.*
 4. **Boat docks.** *Boat docks, fishing piers, etc., shall be accessible.*
 5. **Parking lots.** *Parking lots shall be provided with accessible parking spaces and with curb cuts leading to all adjacent walks, paths or trails.*
 6. **Trails and paths.** *Trails, paths and nature walk areas, or portions of these, shall be constructed with gradients which will permit at least partial use by wheelchair occupants. Hard surface paths or walks shall be provided to serve buildings and other functional areas.*
 7. **Nature trails.** *Nature trails and similar educational and informational areas shall be accessible to the blind by the provision of rope guidelines, raised Arabic numerals and symbols for identification, information signs, and related guide and assistance devices.*

For museums, orientation buildings, visitor centers, office buildings, retail stores, restaurants, etc., and sanitary facilities serving these uses, see Sections 1104B through 1111B and sections listed in Section 1114B.1.1.

1132B.3 Highway rest areas. *The specific standards of accessibility for highway rest areas and similar facilities shall be as follows in Section 1132B.3.1, subject to other provisions in these regulations.*

1132B.3.1 Permanent facilities. *At least one kind of permanent functional area or facility, as applicable, shall be accessible to persons with disabilities, including:*

1. *A sanitary facility for each sex.*
2. *At least one picnic table and one additional table for each 20 tables, or fraction thereof provided.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. *Information and display areas*
4. *Drinking fountains.*
5. *At least one parking space.*
6. *Curb ramps conforming to Section 1127B.5 shall be provided at pedestrian ways where appropriate.*

Division III – ACCESSIBILITY FOR ENTRANCES, EXITS AND PATHS OF TRAVEL

This division includes additional requirements which supersede less restrictive requirements in Chapter 10 where access is required.

SECTION 1133B GENERAL ACCESSIBILITY FOR ENTRANCES, EXITS AND PATHS OF TRAVEL

1133B.1 Building accessibility. See this chapter.

1133B.1.1 Entrances.

1133B.1.1.1 Entrances and exterior ground floor exit doors.

1133B.1.1.1.1 All entrances and exterior ground-floor exit doors to buildings and facilities shall be made accessible to persons with disabilities. Such entrances shall be connected by an accessible route (complying with Section 1114B.1.2) to public transportation stops, to accessible parking and passenger loading zones and to public streets or sidewalks, if available. Entrances shall be connected by an accessible route to all accessible spaces or elements within the building or facility. Doorways shall have a minimum clear opening of 32 inches (813 mm) with the door open 90 degrees, measured between the face of the door and the opposite stop (see Figure 11B-5B). Openings more than 24 inches (610 mm) in depth shall comply with Section 1118B.

Exceptions:

1. Exterior ground-floor exits serving smoke-proof enclosures, stairwells and exit doors servicing stairs only need not be made accessible.
2. Exits in excess of those required by Chapter 10, and which are more than 24 inches (610 mm) above grade are not required to be accessible. Such doors shall have signs warning that they are not accessible. Warning signs shall comply with Section 1117B.5.1 Item 2.
3. In existing buildings where the enforcing agency determines that compliance with the building standards of this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided. Equivalent facilitation would require at least one entrance to be accessible to and usable by persons with disabilities.
4. These building standards shall not apply to existing buildings when legal or physical constraints will not allow compliance with these building standards or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5, Special Conditions for Persons with Disabilities Requiring Appeals Action Ratification.

1133B.1.1.1.2 Temporary restrictions. During periods of partial or restricted use of a building or facility, the entrances used for primary access shall be accessible to and usable by persons with disabilities.

1133B.1.1.1.3 Recessed doormats. Recessed doormats shall be adequately anchored to prevent interference with wheelchair traffic.

1133B.1.1.1.4 Gates. All gates, including ticket gates, shall meet all applicable specifications for doors.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1133B.1.1.1.5 Service Entrances. *In existing buildings and facilities, a service entrance shall not be the sole accessible entrance unless it is the only entrance to a building or facility (for example, in a factory or garage).*

1133B.2 Doors.

1133B.2.1 Type of lock or latch. *See Chapter 10, Section 1008.1.8.*

1133B.2.2 Width and height. *Every required exit doorway shall be of a size as to permit the installation of a door not less than 3 feet (914 mm) in width and not less than 6 feet 8 inches (2032 mm) in height.*

When installed in exit doorways, exit doors shall be capable of opening at least 90 degrees and shall be so mounted that the clear width of the exitway is not less than 32 inches (813 mm) measured between the face of the door and the opposite stop (see Figure 11B-5B). In computing the exit width the net dimension of the exitway shall be used.

Exception: *Doors not requiring full user passage, such as shallow closets, may have the clear opening reduced to 20 inches (510 mm) minimum.*

1133B.2.3 Hinged doors. *For hinged doors, the opening width shall be measured with the door positioned at an angle of 90 degrees from its closed position.*

1133B.2.3.1 Pairs of doors. *Where a pair of doors is utilized, at least one of the doors shall provide a clear, unobstructed opening width of 32 inches (813 mm) with the leaf positioned at an angle of 90 degrees from its closed position.*

1133B.2.3.2 Automatic and power-assisted doors. *If an automatic door is used, then it shall comply with BHMA A156.10. Slowly opening, low-powered, automatic doors shall comply with BHMA A156.19. Such doors shall not open to back check faster than 3 seconds and shall require no more than 15 lbf (66.72 N) to stop door movement. If a power-assisted door is used, its door-opening force shall comply with 1133B.2.5 and its closing shall conform to the requirements in BHMA A156.19. When an automatic door operator is utilized to operate a pair of doors, at least one of the doors shall provide a clear, unobstructed opening width of 32 inches (813 mm) with the door positioned at an angle of 90 degrees from its closed position.*

Exceptions:

1. *The provisions of Section 1133B.2.3 shall not apply to existing buildings, except when otherwise required under conditions applicable to access for persons with disabilities. In existing buildings, the following shall apply:*

Where the occupant load is less than 10, except Group I, Division 1 Occupancies, or where the occupant load is greater than 10 and it is determined that compliance with Section 1133B.2.3 would create an unreasonable hardship, a projection of 5/8 inch (16 mm) maximum will be permitted for the latch side stop.

2. *In existing buildings, the provisions of this section shall not apply when legal or physical constraints will not allow compliance with these building standards or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.*

1133B.2.3.3 Revolving doors. *Revolving doors shall not be used as a required entrance for persons with disabilities.*

1133B.2.3.4 Turnstiles, rails and pedestrian controls. *Where turnstiles and crowd control barriers are utilized in a facility for the purpose of providing fully controlled access, such as where an admission price is charged, a door or gate that is accessible to persons with disabilities shall be*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

provided adjacent to each turnstile exit or entrance. This alternate passageway shall be maintained in an unlocked condition during business hours and the door or gate shall not activate a publicly audible alarm system. The door or gate may be latched where all gates are restricted and controlled by an attendant and a sign is posted stating, "All gates are restricted and controlled by an attendant". The accessible door or gate shall provide the same use pattern. Where posts, rails or other pedestrian controls are utilized to create crowd control aisles or lanes, a minimum of one lane shall be accessible and shall provide a minimum aisle width no less than indicated in Figure 11B-5E (a) and (b) with 32 inches (813 mm) of clear opening.

Exception: In existing buildings, Section 1133B.2.3 shall not apply when physical constraints or equivalent facilitation will not allow compliance with these building standards without creating an unreasonable hardship. See Section 1.9.1.5.

1133B.2.4 Floor level at doors. Regardless of the occupant load, there shall be a floor or landing on each side of a door.

1133B.2.4.1 Thresholds. The floor or landing shall not be more than ½ inch (12.7 mm) lower than the threshold of the doorway. Change in level between ¼ inch (6 mm) and ½ inch (12.7 mm) shall be beveled with a slope no greater than one unit vertical in 2 units horizontal (50-percent slope). Change in level greater than ½ inch (12.7 mm) shall be accomplished by means of a ramp. See Section 1133B.5.1.

1133B.2.4.2 Maneuvering clearances at doors. Minimum maneuvering clearances at doors shall be as shown in Figures 11B-26A, 11B-26B and 11B-26C. The floor or ground area within the required maneuvering clearances shall be level and clear.

The level area shall have a length in the direction of door swing of at least 60 inches (1524 mm) and the length opposite the direction of door swing of 48 inches (1219 mm) as measured at right angles to the plane of the door in its closed position.

Exception: The length opposite the direction of door swing shall be a minimum of 44 inches (1118 mm) where the door has no closer and approach to the door by a person in a wheelchair can be made from the latch side, or if the door has neither latch nor closer and approach can be made from the hinge side. See Figure 11B-26A and 11B-26B.

1133B.2.4.3 The width of the level area on the side to which the door swings shall extend 24 inches (610 mm) past the strike edge of the door for exterior doors and 18 inches (457 mm) past the strike edge for interior doors.

Twenty-four inches (610 mm) is preferred for strike-side clearance.

1133B.2.4.4 The space between two consecutive door openings in a vestibule, serving other than a required exit stairway shall provide a minimum of 48 inches (1219 mm) of clear space from any door opening into such vestibule when the door is positioned at an angle of 90 degrees from its closed position. Doors in a series shall swing either in the same direction or away from the space between the doors. See Figures 11B-30 and 11B-31.

1133B.2.4.5 Recessed doors. Where a door required to be accessible by Section 1133B.1.1.1 is located in a recess or alcove where the distance from the face of the wall to the face of the door is greater than 8 inches, strike side clearances as prescribed in Section 1133B.2.4.3 shall be provided. See Figure 11B-33(a).

1133B.2.5 Door opening force. The maximum force required to push or pull open a door shall comply with this section. Push or pull force for a hinged door shall be measured perpendicular to the door face at the door opening hardware or 30 inches (762 mm) from the hinged side, whichever is farther from the hinge. Push or pull force for a sliding or folding door shall be measured parallel to the door at the door pull or latch.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Compensating devices or automatic door operators complying with Section 1133B.2.3.2 may be used to meet the maximum force limits.

1. *Required fire doors shall have the minimum opening force allowable by the appropriate administrative authority, not to exceed 15 lbf (66.7 N).*
2. *Other than required fire doors, interior doors shall have a maximum opening force of 5 lbf (22.2 N).*
3. *Other than required fire doors, exterior doors shall have a maximum opening force of 5 lbf (22.2 N).*

Exceptions:

1. *Exterior doors to machinery spaces including, but not limited to, elevator pits or elevator penthouses; mechanical, electrical or communications equipment rooms; piping or equipment catwalks; electric substations and transformer vaults; and highway and tunnel utility facilities.*
2. *When, at a single location, one of every 8 exterior door leafs, or fraction of 8, is a powered door, other exterior doors at the same location, serving the same interior space, may have a maximum opening force of 8.5 lbf (37.8 N). The powered leaf(s) shall be located closest to the accessible route.*
 - a. *Powered doors shall comply with Section 1133B.2.3.2. Powered doors shall be fully automatic doors complying with Builders Hardware Manufacturers' Association (BHMA) A156.10 or low energy operated doors complying with BHMA A156.19.*
 - b. *Powered doors serving a building or facility with an occupancy of 150 or more shall be provided with a back-up battery or back-up generator. The back-up power source shall be able to cycle the door a minimum of 100 cycles.*
 - c. *Powered doors shall be controlled on both the interior and exterior sides of the doors by sensing devices, push plates, vertical actuation bars or other similar operating devices complying with Section 1117B.6.*

At each location where push plates are provided there shall be two push plates; the centerline of one push plate shall be 7 inches (178 mm) minimum and 8 inches (203 mm) maximum above the floor or ground surface and the centerline of the second push plate shall be 30 inches (762 mm) minimum and 44 inches (1219 mm) maximum above the floor or ground surface. Each push plate shall be a minimum of 4 inches (102 mm) diameter or a minimum of 4 inches by 4 inches (102 mm by 102 mm) square and shall display the International Symbol of Accessibility complying with Section 1117B.5.8.1.

At each location where vertical actuation bars are provided the operable portion shall be located so the bottom is 5 inches (127 mm) maximum above the floor or ground surface and the top is 35 inches (889 mm) minimum above the floor or ground surface. The operable portion of each vertical actuation bar shall be a minimum of 2 inches (51 mm) wide and shall display the International Symbol of Accessibility complying with Section 1117B.5.8.1.

Where push plates, vertical actuation bars or other similar operating devices are provided, they shall be placed in a conspicuous location. A level and clear floor or ground space for forward or parallel approach complying with Sections 1118B.4 and 1124B.1 shall be provided, centered on the operating device. Doors shall not swing into the required clear floor or ground space.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

- d. *Signage identifying the accessible entrance required by Section 1127B.3 shall be placed on, or immediately adjacent to, each powered door. Signage shall be provided in compliance with BHMA A156.10 or BHMA 156.19, as applicable.*
- e. *In addition to the requirements of Item d, where a powered door is provided in buildings or facilities containing assembly occupancies of 300 or more, a sign displaying the International Symbol of Accessibility measuring 6 inches by 6 inches (152 mm by 152 mm), complying with Section 1117B.5.8.1, shall be provided above the door on both the interior and exterior sides of each powered door.*

1133B.2.5.1 Door closer. *If the door has a closer, then the sweep period of the closer shall be adjusted so that from an open position of 70 degrees, the door will take at least 3 seconds to move to a point 3 inches (75 mm) from the latch, measured to the leading edge of the door.*

1133B.2.5.2 Hand-activated door opening hardware, handles, pulls, latches, locks, and other operating devices on accessible doors shall have a shape that is easy to grasp with one hand and does not require tight grasping, tight pinching or twisting of the wrist to operate. Hardware shall be centered between 30 inches (762 mm) and 44 inches (1118 mm) above the floor. Latching and locking doors that are hand-activated and which are in a path of travel shall be operable by lever-type hardware, panic bars, push-pull activating bars, U-shaped handles or other hardware designed to provide passage. Locked exit doors shall operate as above in egress direction.

1133B.2.6 Smooth surface. *The bottom 10 inches (254 mm) of all doors except automatic and sliding shall have a smooth, uninterrupted surface to allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition. Where narrow frame doors are used, a 10-inch (254 mm) high smooth panel shall be installed on the push side of the door, which will allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition.*

1133B.3 Corridors, hallways and exterior exit balconies.

1133B.3.1 Corridor and hallway widths. *Every corridor and hallway serving an occupant load of 10 or more shall not be less than 44 inches (1118 mm) in width. Corridors and hallways serving an occupant load of less than 10 shall not be less than 36 inches (914 mm) in width.*

1133B.3.2 Corridors and hallways over 200 feet (60 960 mm). *Corridors and hallways that are located on an accessible route and exceed 200 feet (60 960 mm) in length shall have a minimum clear width of 60 inches (1524 mm). If an accessible route has less than 60 inches (1524 mm) clear width, then passing spaces at least 60 inches by 60 inches (1524 mm by 1524 mm) shall be located at intervals of 200 feet (60 960 mm) maximum. A “T” intersection of two corridors or walks is an acceptable passing place.*

Exceptions:

1. *In existing buildings, when the enforcing agency determines that compliance with any building standard under this section would create an unreasonable hardship, an exception to such building standard shall be granted when equivalent facilitation is provided.*
2. *In existing buildings, the provisions of this section shall not apply when legal or physical constraints will not allow compliance with these building standards or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.*

1133B.4 Stairways. *Stairways shall conform to the provisions of this section.*

1133B.4.1 Handrails.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1133B.4.1.1 Required handrails. *Stairways shall have handrails on each side. Handrails shall be continuous along both sides of a stairway. Intermediate handrails shall be provided as required in Section 1012.8.*

1133B.4.2 Handrail configuration.

1133B.4.2.1 *The top of handrail gripping surface shall be mounted between 34 to 38 inches (864 to 965 mm) above the nosing of the treads.*

1133B.4.2.2 *Handrails shall extend a minimum of 12 inches (305 mm) beyond the top nosing and 12 inches (305 mm), plus the tread width, beyond the bottom nosing. At the top, the extension shall be parallel with the floor or ground surface. At the bottom, the handrail shall continue to slope for a distance of the width of one tread from the bottom riser; the remainder of the extension shall be horizontal. See Figures 11B-35 and 11B-37.*

Exceptions:

- 1. In new construction, the inside handrail on switchback or dogleg stairs shall always be continuous.*
- 2. In existing buildings and facilities, full extension of handrails at stairs shall not be required in alterations where such extensions would be hazardous or impossible due to plan configuration.*

1133B.4.2.3 *Ends shall be returned smoothly to floor, wall or post.*

1133B.4.2.4 *The orientation of at least one handrail shall be in the direction of the run of the stair and perpendicular to the direction of the stair nosing, and shall not reduce the minimum required width of the stairs.*

1133B.4.2.5 *Handrails projecting from a wall shall have a space of 1-½ inches (38 mm) between the wall and the handrail.*

Handrails may be located in a recess if the recess is a maximum of 3 inches (76 mm) deep and extends at least 18 inches (457 mm) above the top of the rail. Handrails shall not rotate in their fittings.

1133B.4.2.6 Handgrips. *The handgrip portion of handrails shall be not less than 1-¼ inches (32 mm) nor more than 1-½ inches (38 mm) in cross-sectional nominal dimension or the shape shall provide an equivalent gripping surface. The handgrip portion of handrails shall have a smooth surface with no sharp corners. Gripping surfaces (top or sides) shall be uninterrupted by newel posts, other construction elements or obstructions. Any wall or other surface adjacent to the handrail shall be free of sharp or abrasive elements. Edges shall have a minimum radius of ⅛ inch (3.2 mm).*

Exceptions:

- 1. In existing buildings when the enforcing agency determines that compliance with any requirement under Section 1133B.4.2 would create an unreasonable hardship, an exception to the requirement for persons with disabilities may be granted when equivalent facilitation is provided.*
- 2. These regulations shall not apply in existing buildings where legal or physical constraints will not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1133B.4.3 Tactile floor identification signs in stairways. Tactile floor identification signs that comply with Section 1117B.5 Item 1 shall be located at each floor level landing in all enclosed stairways in buildings two or more stories in height to identify the floor level. At exit discharge level, the sign shall include a raised five-pointed star located to the left of the identifying floor level. The outside diameter of the star shall be the same as the height of the raised characters.

1133B.4.4 Striping for the visually impaired. Interior stairs shall have the upper approach and lower tread marked by a stripe providing clear visual contrast. Exterior stairs shall have the upper approach and all treads marked by a stripe providing clear visual contrast.

The stripe shall be a minimum of 2 inches (50.8 mm) wide to a maximum of 4 inches (101.6 mm) wide placed parallel to, and not more than 1 inch (25.4 mm) from, the nose of the step or upper approach. The stripe shall extend the full width of the step or upper approach and shall be of a material that is at least as slip resistant as the other treads of the stair. A painted stripe shall be acceptable.

1133B.4.5 Stair treads, risers and nosing. Stair treads shall be no less than 11 inches (279 mm) deep, measured from riser to riser. Stair riser heights shall be 7 inches (187 mm) maximum and 4 inches (102 mm) minimum. On any given flight of stairs, all steps shall have uniform riser height and uniform tread widths.

1133B.4.5.1 Treads. All tread surfaces shall be slip resistant. Weather-exposed stairs and their approaches shall be designed so that water will not accumulate on the walking surfaces. Treads shall have smooth, rounded or beveled exposed edges.

1133B.4.5.2 Risers. Risers shall be solid and shall be vertical [see Figure 11B-35(a)] or sloped from the underside of the leading edge of the tread above at an angle not more than 30 degrees (0.52 rad) from the vertical [see Figure 11B-35(b)]. Open risers are not permitted.

Exceptions:

1. On exterior stairways, an opening of not more than ½ inch (12.7 mm) may be permitted between the base of the riser and the tread.
2. On exterior stairways, risers constructed of grating containing openings of not more than ½ inch (12.7 mm) may be permitted.

1133B.4.5.3 Nosing. The radius of curvature at the leading edge (nosing) of the tread shall be no greater than ½ inch (12.7 mm). Beveling of nosings shall not exceed ½ inch (12.7 mm). Nosings shall not project more than ¼ inches (31.8 mm) past the face of the riser below. Nosings that project beyond risers shall have the underside of the leading edge beveled at an angle not more than 30 degrees (0.52 rad) from the vertical (see Figure 11B-35(c)). The transition from the nosing to the riser shall be free of abrupt edges. All projections shall be of uniform size, including nosings at landings.

Exceptions:

1. In existing buildings there is no requirement to retroactively alter existing nosing projections of 1½ inches (38.1 mm) which were constructed in compliance with the building code in effect at the time of original construction.
2. In existing buildings, when the enforcing agency determines that compliance with any requirement under this section would create an unreasonable hardship, an exception to persons with disabilities requirements may be granted when equivalent facilitation is provided.
3. These regulations shall not apply to existing buildings when legal or physical constraints will not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1133B.5 Ramps.

1133B.5.1 General. Ramps shall conform to the provisions of this section. Any accessible route of travel shall be considered a ramp if its slope is greater than one unit vertical in 20 units horizontal (5-percent slope).

1133B.5.2 Width. Ramps shall have a minimum clear width of 48 inches (1219 mm), unless required to be wider by some other provision of this code. Ramps serving entrances to buildings where the ramp is the only exit discharge path and serves an occupant load of 300 or more shall have a minimum clear width of 60 inches (1524 mm). Ramps serving Group R occupancies may be 36 inches (914 mm) clear width when the occupant load is 50 or less.

1133B.5.3 Slope. The least possible slope shall be used for any ramp. The maximum slope of a ramp shall be one unit vertical in 12 units horizontal (8.33-percent slope). The maximum rise for any run shall be 30 inches (762 mm). Examples of ramp dimensions are as follows:

SLOPE	MAXIMUM RISE	MAXIMUM LENGTH
1:12	30 inches (762 mm)	30 feet (9144 mm)
1:13	30 inches (762 mm)	32.5 feet (9906 mm)
1:14	30 inches (762 mm)	35 feet (10668 mm)
1:15	30 inches (762 mm)	37.5 feet (11430 mm)
1:16	30 inches (762 mm)	40 feet (12192 mm)
1:17	30 inches (762 mm)	42.5 feet (12954 mm)
1:18	30 inches (762 mm)	45 feet (13716 mm)
1:19	30 inches (762 mm)	47.5 feet (14478 mm)

1133B.5.3.1 The cross slope of ramp surfaces shall be no greater than 1 unit vertical in 50 units horizontal (2-percent slope).

1133B.5.4 Landings. Level ramp landings shall be installed as follows:

1133B.5.4.1 Location of landings. Level ramp landings shall be provided at the top and bottom of each ramp. Intermediate landings shall be provided at intervals not exceeding 30 inches (762 mm) of vertical rise and at each change of direction. Landings are not considered in determining the maximum horizontal distance of each ramp. Landings shall be level as specified in the definition of "level area" in Section 1102B.

1133B.5.4.2 Size of top and bottom landings. Top landings shall be not less than 60 inches (1524 mm) wide and shall have a length of not less than 60 inches (1524 mm) in the direction of ramp run. Landings at the bottom of ramps shall have a dimension in the direction of ramp run of not less than 72 inches (1829 mm).

1133B.5.4.3 Doors at ramp landings. Doors at ramp landings shall comply with the maneuvering clearance requirements of Section 1133B.2.4.2, and the requirements of Section 1133B.5.4.4.

1133B.5.4.4 Encroachment of doors at ramp landings. Doors in any position shall not reduce the minimum dimension of the ramp landing to less than 42 inches (1067 mm) and shall not reduce the required width by more than 3 inches (76 mm) when fully open. See Figure 11B-39(b).

1133B.5.4.5 Landing width. At bottom and intermediate landings, the width shall be at least the same as required for the ramps.

1133B.5.4.6 Change of direction. Intermediate and bottom landings at a change of direction in excess of 30 degrees shall have a dimension in the direction of ramp run of not less than 72 inches (1829 mm) to accommodate the handrail extension.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1133B.5.4.7 Other intermediate landings. Other intermediate landings shall have a dimension in the direction of ramp run of not less than 60 inches (1524 mm).

1133B.5.4.8 For existing ramps or ramps not covered by Section 1133B.5.4.1, landings shall be provided as set forth in Section 1133B.5.4.1.

1133B.5.4.9 Hazards. Required ramps shall have a curb at least 2 inches (51 mm) high, or a wheel guide rail 2 to 4 inches (51 to 102 mm) high on each side of the ramp landing that has a vertical drop exceeding 4 inches (102 mm) and that is not bounded by a wall or fence.

1133B.5.5 Handrails for ramps.

1133B.5.5.1 Handrails are required on ramps that provide access if slope exceeds one unit vertical in 20 units horizontal (5-percent slope), except that at exterior door landings, handrails are not required on ramps less than 6 inches (152 mm) rise or 72 inches (1829 mm) in length. Handrails shall be placed on each side of each ramp, shall be continuous the full length of the ramp, shall be 34 to 38 inches (864 to 965 mm) above the ramp surface to the top of the handrails, shall extend a minimum of 1 foot (305 mm) beyond the top and bottom of the ramp and shall be parallel with the floor or ground surface. The inside handrail on switchback or dogleg ramps shall always be continuous. Handrails may project into the required clear width a distance of 3-½ inches (89 mm) maximum from each side of a ramp at the handrail height. The ends of handrails shall be either rounded or returned smoothly to floor, wall or post. Handrails projecting from a wall shall have a space of 1-½ inches (38 mm) between the wall and the handrail. Handrails may be located in a recess if the recess is a maximum of 3 inches (76 mm) deep and extends at least 18 inches (457 mm) above the top of the rail. The grip portion shall not be less than 1-¼ inches (32 mm) nor more than 1-½ inches (38 mm) in cross-sectional nominal dimension or the shape shall provide an equivalent gripping surface, and all surfaces shall be smooth with no sharp corners. Handrails shall not rotate within their fittings. Any wall or other surface adjacent to the handrail shall be free of sharp or abrasive elements. Edges shall have a minimum radius of 1/8 inch (3 mm).

Exceptions:

1. Handrails at ramps immediately adjacent to fixed seating in assembly areas are not required.
2. Curb ramps do not require handrails.

1133B.5.5.1.1 Ramp handrails. In existing buildings or facilities, where the extension of the handrail in the direction of the ramp run would create a hazard, the extension on the handrail may be turned 90 degrees to the run of the ramp.

1133B.5.6 . Guide curbs and wheel guide rails. Where the ramp surface is not bounded by a wall, guide curbs in compliance with Section 1133B.5.6.1 or wheel guide rails in compliance with Section 1133B.5.6.2, shall be provided.

Where handrails or guards are attached to the ramp surface with posts or similar elements, provide guide curbs in compliance with Section 1133B.5.6.1 or wheel guide rails in compliance with Section 1133B.5.6.2.

To prevent wheel entrapment, guide curbs or wheel guide rails shall provide a continuous and uninterrupted barrier along the length of the ramp.

1133B.5.6.1 A guide curb a minimum of 2 inches (51 mm) in height above the ramp surface.

1133B.5.6.2 A wheel guide rail centered 3 inches (76 mm) plus or minus 1 inch (25 mm) above the ramp surface.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1133B.5.7 Guards. Ramps more than 30 inches (762 mm) above the adjacent ground shall be provided with guards that comply with Section 1013. Such guards shall be continuous from the top of the ramp to the bottom of the ramp.

1133B.5.8 Outdoor ramps. Outdoor ramps and their approaches shall be designed so that water will not accumulate on walking surfaces.

1133B.6 Aisles.

1133B.6.1 General. Every portion of every building in which are installed seats, tables, merchandise, equipment or similar materials shall be provided with aisles leading to an exit.

1133B.6.2 Width. Every aisle shall not be less than 36 inches (914 mm) wide if serving only one side, and not less than 44 inches (1118 mm) wide if serving both sides. In addition, aisles shall comply with Figure 11B-5E(a) and (b) for circulation around obstructions.

1133B.7 Walks and Sidewalks.

1133B.7.1 Continuous surface. Walks and sidewalks subject to these regulations shall have a continuous common surface, not interrupted by steps or by abrupt changes in level exceeding ½ inch (12.7 mm) (see Section 1133B.7.4), and shall be a minimum of 48 inches (1219 mm) in width. If a walk or sidewalk has less than 60 inch (1525 mm) clear width, then passing spaces at least 60 inches by 60 inches (1525 mm by 1525 mm) shall be located at reasonable intervals not to exceed 200 feet (61 m). A T-intersection is an acceptable passing place. Surfaces shall be slip-resistant as follows:

Exception: When, because of right-of-way restrictions, natural barriers or other existing conditions, the enforcing agency determines that compliance with the 48-inch (1219 mm) clear sidewalk width would create an unreasonable hardship, the clear width may be reduced to 36 inches (914 mm).

1133B.7.1.1 Slopes less than 6 percent. Surfaces with a slope of less than 6-percent slope shall be at least as slip-resistant as that described as a medium salted finish.

1133B.7.1.2 Slopes 6 percent or greater. Surfaces with a slope of 6-percent slope shall be slip-resistant.

1133B.7.1.3 Surface cross slopes. Surface cross slopes shall not exceed one unit vertical in 50 units horizontal (2-percent slope).

1133B.7.2 Gratings. Walks, sidewalks and pedestrian ways shall be free of gratings whenever possible. For gratings located in the surface of any of these areas, grid openings in gratings shall be limited to ½ inch (12.7 mm) in the direction of traffic flow.

Exceptions:

1. Where the enforcing agency determines that compliance with this section would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.
2. This section shall not apply in those conditions where, due to legal or physical constraints, the site of the project will not allow compliance with these building standards or equivalent facilitation without creating an unreasonable hardship. See Section 1.9.1.5.

1133B.7.3 Five percent gradient. When the slope in the direction of travel of any walk exceeds 1 unit vertical in 20 units horizontal (5-percent slope), it shall comply with the provisions of Section 1133B.5.

1133B.7.4 Changes in level. Changes in level shall comply with Section 1124B.2.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1133B.7.5 Level areas. *All walks with continuous gradients shall have level areas at least 5 feet (1524 mm) in length at intervals of 400 feet (121 920 mm) maximum.*

1133B.8 Hazards.

1133B.8.1 Warning curbs. *Abrupt changes in level, except between a walk or sidewalk and an adjacent street or driveway, exceeding 4 inches (102 mm) in a vertical dimension, such as at planters or fountains located in or adjacent to walks, sidewalks or other pedestrian ways, shall be identified by curbs projecting at least 6 inches (152 mm) in height above the walk or sidewalk surface to warn the blind of a potential drop off.*

When a guard or handrail is provided, no curb is required when a guide rail is provided centered 3 inches (76 mm) plus or minus 1 inch (25 mm) above the surface of the walk or sidewalk, the walk is 5 percent or less gradient or no adjacent hazard exists.

1133B.8.2 Overhanging obstructions. *Any obstruction that overhangs a pedestrian's way shall be a minimum of 80 inches (2032 mm) above the walking surface as measured from the bottom of the obstruction. Where a guy support is used parallel to a path of travel, including, but not limited to sidewalks, a guy brace, sidewalk guy or similar device shall be used to prevent an overhanging obstruction as defined (see Figure 11B-28).*

Hazards such as drop-offs adjacent to walk ways or overhanging obstructions can be dangerous to persons with sight problems. This section addresses these situations.

1133B.8.3 Detectable warnings at transit boarding platforms. *See Section 1121B.3.1, Item 8(a).*

1133B.8.4 Detectable directional texture at boarding platforms. *See Section 1121B.3.1, Item 8(b).*

1133B.8.5 Detectable warnings at hazardous vehicular areas. *If a walk crosses or adjoins a vehicular way, and the walking surfaces are not separated by curbs, railings or other elements between the pedestrian areas and vehicular areas, the boundary between the areas shall be defined by a continuous detectable warning which is 36 inches (914 mm) wide, complying with Section 1121B.3.1 Item 8(a).*

Only approved DSA-AC detectable warning products and directional surfaces shall be installed as provided in the California Code of Regulations (CCR), Title 24, Part 1, Articles 2, 3 and 4. Refer to CCR Title 24, Part 12, Chapter 12-11A and B, for building and facility access specifications for product approval for detectable warning products and directional surfaces.

Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect-Access Compliance, for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

1133B.8.6 Protruding objects.

1133B.8.6.1 General. *Objects projecting from walls (for example, telephones) with their leading edges between 27 inches (686 mm) and 80 inches (2032 mm) above the finished floor shall protrude no more than 4 inches (102 mm) into walks, halls, corridors, passageways or aisles. Objects mounted with their leading edges at or below 27 inches (686 mm) above the finished floor may protrude any amount. Free-standing objects mounted on posts or pylons may overhang 12 inches (305 mm) maximum from 27 inches (686 mm) to 80 inches (2032 mm) above the ground or finished floor. Protruding objects shall not reduce the clear width of an accessible route or maneuvering space. See Figure 11B-7A.*

1133B.8.6.2 Head room. *Walks, halls, corridors, passageways, aisles or other circulation spaces shall have 80 inches (2032 mm) minimum clear head room. If vertical clearance of an area adjoining an accessible route is reduced to less than 80 inches (nominal dimension), a barrier to warn blind or*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

visually-impaired persons shall be provided. See Figures 11B-7A and 11B-7C.

1133B.8.6.3 Free-standing signs. *Wherever signs mounted on posts or pylons protrude from the posts or pylons and the bottom edge of the sign is at less than 80 inches (2032 mm) above the finished floor or ground level, the edges of such signs shall be rounded or eased and the corners shall have a minimum radius of 0.125 inches (3.2 mm).*

1133B.8.7 Detectable warnings at reflecting pools. *The edges of reflecting pools shall be protected by railings, walls, warning curbs or detectable warnings complying with Section 1121B.3.1, Item 8(a).*

Division IV – ACCESSIBILITY FOR EXISTING BUILDINGS

SECTION 1134B ACCESSIBILITY FOR EXISTING BUILDINGS

1134B.1 Scope. *The provisions of this division apply to renovation, structural repair, alteration and additions to existing buildings, including those identified as historic buildings. This division identifies minimum standards for removing architectural barriers, and providing and maintaining accessibility to existing buildings and their related facilities.*

No renovation, structural repair, alteration or addition shall be undertaken which decreases or has the effect of decreasing accessibility or usability of a building or facility below the requirements for new construction at the time of renovation, structural repair, alteration or addition.

1134B.2 General. *When alterations, structural repairs or additions are made to existing buildings or facilities, they shall comply with all provisions of Division I – New Buildings, except as modified by this division. These requirements shall apply only to the area of specific alteration, structural repair or addition and shall include those areas listed below:*

1134B.2.1 *A primary entrance to the building or facility and the primary path of travel to the specific area of alteration, structural repair or addition, and sanitary facilities, drinking fountains, signs and public telephones serving the area.*

Exceptions:

1. *When the total construction cost of alterations, structural repairs or additions does not exceed a valuation threshold of \$50,000, based on January 1981, “ENR US20 Cities” Average construction cost index of 3372.02 (Engineering News Record, McGraw Hill Publishing Company), and the enforcing agency finds that compliance with this code creates an unreasonable hardship, compliance shall be limited to the actual work of the project. The enforcing agency shall annually update the valuation threshold to a current amount based on the increase in the index since the last figure used. (For example, the January 2010 amount is \$128,410.86.) For purposes of this exception, an unreasonable hardship exists where the cost of providing an accessible entrance, path of travel, sanitary facilities, public phones and drinking fountains, is disproportionate to the cost of the project; that is, where it exceeds 20 percent of the cost of the project without these features. Where the cost of alterations necessary to make these features fully accessible is disproportionate, access shall be provided to the extent that it can be without incurring disproportionate cost. In choosing which accessible elements to provide, priority should be given to those elements that will provide the greatest access in the following order:*

1.1. An accessible entrance,

1.2. An accessible route to the altered area,

1.3. At least one accessible restroom for each sex,

1.4. Accessible telephones,

1.5. Accessible drinking fountains, and

1.6. When possible, additional accessible elements such as parking, storage and alarms.

The obligation to provide access may not be evaded by performing a series of small alterations to the area served by a single path of travel if those alterations could have been performed as a single undertaking. If an area has been altered

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

without providing an accessible path of travel to that area, and subsequent alterations of that area or a different area on the same path of travel are undertaken within three years of the original alteration, the total cost of alterations to the areas on that path of travel during the preceding three-year period shall be considered in determining whether the cost of making that path of travel accessible is disproportionate. Only alterations undertaken after January 26, 1992, shall be considered in determining if the cost of providing an accessible path of travel is disproportionate to the overall cost of the alterations.

2. *Certain types of privately funded, multistory buildings and facilities were formerly exempt from accessibility requirements above and below the first floor under this code, but as of the effective date of this regulation are no longer exempt due to more restrictive provisions in the federal Americans with Disabilities Act. In alteration projects involving buildings and facilities previously approved and built without elevators, areas above and below the ground floor are subject to the 20 percent disproportionality provisions described in Exception 1, above, even if the value of the project exceeds the valuation threshold in Exception 1. The types of buildings and facilities are:*

- 2.1. *Office buildings and passenger vehicle service stations of three stories or more and 3,000 or more square feet (279m²) per floor.*

- 2.2. *Offices of physicians and surgeons.*

- 2.3. *Shopping centers.*

- 2.4. *Other buildings and facilities three stories or more and 3,000 or more square feet (279 m²) per floor if a reasonable portion of services sought and used by the public is available on the accessible level.*

For the general privately funded multistory building exception applicable to new construction and alterations, see Section 1103B.1, Exception 2.

The elevator exception set forth in this section does not obviate or limit in any way the obligation to comply with the other accessibility requirements in this code. For example, floors above or below the accessible ground floor must meet the requirements of this section except for elevator service. If toilet or bathing facilities are provided on a level not served by an elevator, then toilet or bathing facilities must be provided on the accessible ground floor.

3. *Alterations, structural repairs or additions consisting of one or more of the following shall be limited to the actual work of the project:*

- 3.1. *Altering one building entrance to meet accessibility requirements.*

- 3.2. *Altering one existing toilet facility to meet accessibility requirements.*

- 3.3. *Altering existing elevators to meet accessibility requirements.*

- 3.4. *Altering existing steps to meet accessibility requirements.*

- 3.5. *Altering existing handrails to meet accessibility requirements.*

- 3.6. *Alteration solely for the purpose of barrier removal undertaken pursuant to the requirements of the Americans with Disabilities Act (Public Law 101-336, 28 C.F.R., Section 36.304) or the accessibility requirements of this code as those requirements or regulations now exist or are hereafter amended, including the following:*

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

- 3.6.1. *Installing ramps.*
 - 3.6.2. *Making curb cuts in sidewalks and entrance.*
 - 3.6.3. *Repositioning shelves.*
 - 3.6.4. *Rearranging tables, chairs, vending machines, display racks, and other furniture.*
 - 3.6.5. *Repositioning telephones.*
 - 3.6.6. *Adding raised markings on elevator control buttons.*
 - 3.6.7. *Installing flashing alarm lights.*
 - 3.6.8. *Widening doors.*
 - 3.6.9. *Installing offset hinges to widen doorways.*
 - 3.6.10. *Eliminating a turnstile or providing an alternative accessible path.*
 - 3.6.11. *Installing accessible door hardware.*
 - 3.6.12. *Installing grab bars in toilet stalls.*
 - 3.6.13. *Rearranging toilet partitions to increase maneuvering space.*
 - 3.6.14. *Insulating lavatory pipes under sinks to prevent burns.*
 - 3.6.15. *Installing a raised toilet seat.*
 - 3.6.16. *Installing a full-length bathroom mirror.*
 - 3.6.17. *Repositioning the paper towel dispenser in a bathroom.*
 - 3.6.18. *Creating designated accessible parking spaces.*
 - 3.6.19. *Installing an accessible paper cup dispenser at an existing inaccessible water fountain.*
 - 3.6.20. *Removing high-pile, low-density carpeting.*
 - 3.6.21. *Installing vehicle hand controls.*
 - 3.7. *Altering existing parking lots by resurfacing and/or restriping.*
4. *Projects which consist only of heating, ventilation, air conditioning, reroofing, electrical work not involving placement of switches and receptacles, cosmetic work that does not affect items regulated by this code, such as painting, equipment not considered to be a part of the architecture of the building or area, such as computer terminals, office equipment, etc., are not considered alteration projects for the purposes of accessibility for persons with disabilities and shall not be subject to this code unless they affect the usability of the building or facility. For the purposes of this section, the term "construction cost" does not include building permit fees or discretionary permit fees.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

The only purpose of this exception is to exclude projects from activating the provisions of this section. The exceptions are not intended to relieve projects from complying with other applicable provisions of this code (e.g., replacement of carpet does not activate the provisions of this section; however, it still must comply with Section 1124B.3).

1134B.2.2 *Where it is technically infeasible in the area of an alteration to make existing toilet facilities code compliant and to install separate toilet facilities for each sex, then the installation of at least one unisex toilet facility per floor being altered, located in the same area as existing toilet facilities, will be permitted. Such a facility shall meet the requirements of Section 1115B.3.2.*

1134B.2.3 *If alterations of single elements, when considered together, amount to an alteration of a room or space in a building or facility, the entire room or space shall be made accessible.*

SECTION 1135B HISTORIC PRESERVATION – SPECIAL STANDARDS OF ACCESSIBILITY FOR BUILDINGS WITH HISTORICAL SIGNIFICANCE

1135B.1 General. *Qualified historical buildings shall comply with the State Historical Building Code, Part 8, Title 24, of the California Code of Regulations.*

[FIGURES 11B-1A through 11B- 40D](#) *(link to separate document for 11B Figures)*

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 11C – STANDARDS FOR CARD READERS AT
GASOLINE FUEL-DISPENSING FACILITIES**

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter						X														
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				

**CHAPTER 11C
STANDARDS FOR CARD READERS AT GASOLINE
FUEL-DISPENSING FACILITIES**

**SECTION 1101C
CARD-READER DEVICES AT FUEL-DISPENSING EQUIPMENT**

1101C.1 General. Notwithstanding other requirements in the California Building Code, only the requirements and additional definitions in this section shall apply to card-reading devices in motor vehicle fuel facilities, except that administrative requirements which are found in Chapter 1 - California Administration Division I still apply.

For purposes of this section, the following definitions shall apply:

ACCESSIBLE. See Chapter 11A, Section 1107A.1-A and Chapter 11B, Section 1102B.

ACCESSIBLE ELEMENT. See Chapter 11B, Section 1102B.

ALTERNATE CARD READER shall be defined in this section as functionally equal card reader and control directly attached to or an integral part of the fuel dispenser in addition to the primary card reader which is an integral part of the dispenser.

FREE-STANDING PEDESTAL is a card-reading device which controls one or more remote fuel dispensers that have no card reader as an integral part of the fuel dispenser.

GRADE (Adjacent Ground Elevation). See Chapter 2, Section 202.

INTERNATIONAL SYMBOL OF ACCESSIBILITY. See Chapter 11A, Section 1107A.9-I and Chapter 11B, Section 1102B.

LEVEL ACCESSIBLE AREA, for the purposes of this section, shall mean a slope of not more than one unit vertical in 50 units horizontal (2-percent slope) in front of the dispensing device; however, the slope may extend to one unit vertical in 20 units horizontal (5-percent slope) where the enforcing authority determines that, due to unusual site conditions, the 2-percent slope is not obtainable.

LEVEL AREA. See Chapter 11A, Section 1107A.12-L and Chapter 11B, Section 1102B.

RECOMMEND. See Chapter 2, Section 202.

TYPE OF MOTOR FUEL shall mean gasoline, diesel, compressed natural gas, methanol, electricity or ethanol.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 1102C APPLICATION

This section shall apply to equipment located at the following facilities:

1. *New motor vehicle fuel facilities.*
2. *Existing motor vehicle fuel facilities built before the effective date of this section when:*
 - 1.1. *Remodeling or reconstruction includes removal and replacement of one or more islands and associated piping and tank(s); or*
 - 1.2. *Remodeling includes reconstruction or removal and replacement of fuel islands at facilities that provide free-standing pedestal card readers.*

SECTION 1103C NUMBER OF ACCESSIBLE CARD-READING DEVICES REQUIRED

Where only one card-reading device is installed for use with any type of motor fuel, it shall meet the required features of this section. When more than one card-reading location is available for a specific type of motor fuel, a minimum of two for that type shall have the accessible features of this section.

SECTION 1104C REQUIRED FEATURES

Card-reading devices at motor vehicle fuel facilities shall be accessible by complying with only the following:

1. *The highest operable part of each primary or alternate card reader shall be no more than 54 inches (1372 mm) measured from the base of the fuel dispenser. Where card readers are located on free-standing pedestals, the card-reading control function shall be no more than 54 inches (1372 mm) above an accessible level area which is served by an accessible route of travel.*

Exception: *If an enforcing agency requires that fuel dispensers or card-reading devices be placed in a manner where the card-reading device exceeds the requirements described herein, the provisions of Section 1104C do not apply. Any enforcing agency having jurisdiction over retail fueling facilities may not require islands or impose other regulations which conflict with this section, unless the agency documents and justifies the specific necessity for such a rule or ordinance and complies with the requirements of Health and Safety Code Section 18941.*

2. *An accessible route of travel shall be provided to the base of all fuel dispensers required to meet the provisions of this section. Such fuel dispensers shall be mounted on the accessible level area.*
3. *An accessible level area shall be provided which is minimally 30 inches by 48 inches (762 mm by 1219 mm) level and clear. This area shall be provided within 10 inches (254 mm) in plain view of the face of the controls and shall be unobstructed by any features, except pump nozzles and hoses, with the long side of this space parallel to and centered [plus or minus 9 inches (229 mm)] with the face of the card-reader controls. See Figures 11C-1 and 11C-2.*

[FIGURES 11C-1 AND 11C-2](#) (link to separate document for 11C Figures)

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 16 – STRUCTURAL DESIGN**

Adopting agency	BSC	SFM	HCD			DSA			OSHDP				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC	
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4									
Adopt entire chapter																					
Adopt entire chapter as amended (amended sections listed below)																					
Adopt only those sections that are listed below						X															
Chapter/Section																					
1607.7.2						X															

**CHAPTER 16
STRUCTURAL DESIGN**

**LIVE LOADS
SECTION 1607**

1607.7 Loads on handrails, guards, grab bars, shower seats, dressing room bench seats and vehicle barriers.

1607.7.2 Grab bars, shower seats and dressing room bench seats. Grab bars, shower seats and dressing room bench seat systems shall be designed to resist a single concentrated load of 250 pounds (1.11 kN) applied in any direction at any point. **[DSA-AC]** See Chapter 11A, Section 1127A.4, and Chapter 11B, Sections 1115B.7.2 and 1117B.8, for grab bars, shower seats and dressing room bench seats, as applicable.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 16A– STRUCTURAL DESIGN**

Adopting agency	BSC	SFM	HCD			DSA			OSHDP				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
1607A.7.2						X														

CHAPTER 16A

STRUCTURAL DESIGN

**SECTION 1607A
LIVE LOADS**

1607A.7 Loads on handrails, guards, grab bars, shower seats, dressing room bench seats, and vehicle barriers.

1607A.7.2 Grab bars, shower seats and dressing room bench seats. Grab bars, shower seats and dressing room bench seat systems shall be designed to resist a single concentrated load of 250 pounds (1.11 kN) applied in any direction at any point. **[DSA-AC]** See Chapter 11A, Section 1127A.4, and Chapter 11B, Sections 1115B.7.2 and 1117B.8, for grab bars, shower seats and dressing room bench seats, as applicable.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 27 – ELECTRICAL**

Adopting agency	BSC	SFM	HCD			DSA			OSHDP				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC	
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4									
Adopt entire chapter																					
Adopt entire chapter as amended (amended sections listed below)																					
Adopt only those sections that are listed below						X															
Chapter/Section																					
2702.2.5						X															
2702.2.6						X															

**CHAPTER 27
ELECTRICAL**

**SECTION 2702
EMERGENCY AND STANDBY POWER SYSTEMS**

2702.2 Where required.

2702.2.5 Accessible means of egress elevators. Standby power shall be provided for elevators that are part of an accessible means of egress in accordance with Section 1007.4.

2702.2.6 Accessible means of egress platform lifts. Standby power in accordance with this section or ASME A18.1 shall be provided for platform lifts that are part of an accessible means of egress in accordance with Section 1007.5.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 30 – ELEVATORS AND CONVEYING SYSTEMS**

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
3001.1						X														
3001.3						X														

**CHAPTER 30
ELEVATORS AND CONVEYING SYSTEMS**

**SECTION 3001
GENERAL**

3001.1 Scope. This chapter governs the design, construction, installation, alteration and repair of elevators and conveying systems and their components.

Exception: *[DSA-AC] For accessibility requirements for platform (wheelchair) lifts and elevators, see California Code of Regulations, Title 8 and Title 24, Part 2, Sections 1124A and 1116B.*

3001.3 Accessibility. Passenger elevators and platform (wheelchair) lifts required to be accessible by Chapters 11A or 11B shall conform to Chapter 11A for applications listed in Section 1.8.2.1.2 regulated by the Department of Housing and Community Development or Chapter 11B for applications listed in Section 1.9.1 regulated by the Division of the State Architect – Access Compliance.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 31 – SPECIAL CONSTRUCTION**

Adopting agency	BSC	SFM	HCD			DSA			OSHDP				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC	
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4									
Adopt entire chapter																					
Adopt entire chapter as amended (amended sections listed below)																					
Adopt only those sections that are listed below						X															
Chapter/Section																					
3104.2, Exception 2 only						X															

**SECTION 3104
PEDESTRIAN WALKWAYS AND TUNNELS**

3104.2 Separate structures. Connected buildings shall be considered to be separate structures.

Exceptions:

2. **[DSA-AC]** For purposes of *accessibility as required by Chapter 11A*, structurally connected buildings, *buildings connected by stairs, walkways, or roofs*, and buildings with multiple wings shall be considered one structure.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 31B – PUBLIC SWIMMING POOLS**

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC	
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4									
Adopt entire chapter																					
Adopt entire chapter as amended (amended sections listed below)																					
Adopt only those sections that are listed below						X															
Chapter/Section																					
3113B.1 w/Exception 4 only						X															

Division I - GENERAL

**SECTION 3113B
POOL DECKS**

3113B.1 General. *A minimum continuous and unobstructed 4-foot wide (1219 mm) slip-resistant, nonabrasive deck area of concrete or like material shall be provided flush with the top of the pool shell wall extending completely around the pool and the deck area shall further extend 4 feet (1219 mm) on both sides and rear of any diving board or slide and their appurtenances. The deck width shall be measured from the poolside edge of the coping lip.*

Exceptions:

1. *A deck at least 4 feet (1219 mm) in width shall extend around 50 percent or more of the perimeter of a spa pool. For spa pools that have their walls extending above the ground or floor level, the deck area requirement shall apply at the ground or floor level unless otherwise specified by the enforcing agency.*
2. *The deck width separating a spa pool from an adjacent pool shall not be less than 6 feet (1829 mm) wide.*
3. *The deck may be omitted from around a temporary training pool.*
4. **[DSA-AC]** *Any mechanism provided to assist persons with disabilities in gaining entry into the pool and in exiting from the pool shall comply with Chapter 11B, Section 1104B.4.3 Participation Areas.*

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 33 – SAFEGUARDS DURING CONSTRUCTION**

Adopting agency	BSC	SFM	HCD			DSA			OSHDP				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
3306.2						X														

**SECTION 3306
PROTECTION OF PEDESTRIANS**

3306.2 Walkways. A walkway shall be provided for pedestrian travel in front of every construction and demolition site unless the authority having jurisdiction authorizes the sidewalk to be fenced or close. Walkways shall be of sufficient width to accommodate the pedestrian traffic, but in no case shall they be less than 4 feet (1219 mm) in width. Walkways shall be provided with a durable walking surface. Walkways shall be accessible in accordance with *Chapters 11A or 11B* and shall be designed to support all imposed loads and in no case shall the design live load be less than 150 pounds per square foot (psf) (7.2kN/m²).

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 34 – EXISTING STRUCTURES**

Adopting agency	BSC	SFM	HCD			DSA			OSHDP				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
3401.1 (Last Paragraph only)						X														
3409 (1 st Paragraph)						X														

**SECTION 3401
GENERAL**

3401.1 Scope. The provisions of this chapter shall control the alteration, repair, addition and change of occupancy of existing structures, *including state-regulated structures in accordance with Section 3401.1 and 3401.1.2.*

Exceptions:

1. Existing bleachers, grandstands and folding and telescopic seating shall comply with ICC 300-02.

5. [HCD 2] ...

[DSA-AC] For applications listed in Section 1.9.1 regulated by the Division of the State Architect -- Access Compliance for accessibility requirements, see Chapter 11B, Section 1134B.

**SECTION 3409
HISTORIC BUILDINGS**

[DSA-AC] For applications listed in Section 1.9.1 regulated by the Division of the State Architect -- Access Compliance for Qualified Historical Buildings, see California Code of Regulations, Title 24, Part 8 (California Historical Building Code).

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**CALIFORNIA BUILDING CODE – MATRIX ADOPTION TABLE
CHAPTER 35 – REFERENCED STANDARDS**

Adopting agency	BSC	SFM	HCD			DSA			OSHDP				CSA	DPH	AGR	DWR	CEC	CA	SL	SLC
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4								
Adopt entire chapter																				
Adopt entire chapter as amended (amended sections listed below)																				
Adopt only those sections that are listed below						X														
Chapter/Section																				
ANSI						X														
ASME						X														
BHMA						X														
CPSC						X														
NFPA						X														

This chapter lists the standards that are referenced in various sections of this document. The standards are listed herein by the promulgating agency of the standard, the standard identification, the effective date and title, and the section or sections of this document that reference the standard. The application of the referenced standards shall be as specified in sections 101.5 and 101.7 and in *Section 1.1.5, 1.1.7 and 102.4.*

ANSI	American National Standards Institute 25 West 43 rd Street, Fourth Floor New York, NY 10036
Standard reference number	Title Referenced in code section number
S3.41	<i>American National Standard Specifications for Audible Emergency Evacuation Signal 907.5.2.1.3</i>

ASME	American Society of Mechanical Engineers Three Park Avenue New York, NY 10016-5990
Standard reference number	Title Referenced in code section number
A17.1/CSA B44--2007	Safety Code for Elevators and Escalators 907.3.3, 911.1.5, 1007.4, 1607.8.1, 1613.6.5, 3001.2, 3001.4, 3002.5, 3003.2, 3007.1, 3008.3, 3008.12, 3008.14.1, 3411.8.2
A18.1--2005	Safety Standard for Platform Lifts and Stairway Chairlifts 1116B.2.1, 2702.2.6, 3411.8.3

BHMA	Builders Hardware Manufacturers' Association 355 Lexington Avenue, 17 th Floor New York, NY 10017-6603
Standard reference number	Title Referenced in code section number
A 156.10--06	Power Operated Pedestrian Doors 1008.1.4.2, 1133B.2.3.2, 1133B.2.5
A 156.190--02	Standard for Power Assist and Low Energy Operated Doors. 1008.1.4.2, 1133B.2.3.2,1133B.2.5

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

CPSC	Consumer product Safety Commission 4330 East West Highway Bethesda, MD 20814-4408
Standard reference number	Referenced in code section number
16 CFR Part 1201 (1977)	Title Safety Standard for Architectural Glazing Material 2406.2, Table 2406.1(1) 2406.3.1, 2407.1, 2407.1.4.1, 2408.2.1, 2408.3, 2409.1, 2409.2, 2409.3.1

NFPA	National Fire Protection Association 1 Battery march Park Quincy, MA 02269-9101
Standard reference number	Referenced in code section number
72-10	Title National Fire Alarm Code, <i>as amended</i> * 901.6, 903.4.1, 904.3.5, 907.2, 907.2.5, 907.2.11, 907.2.13.2, 907.3, 907.3.3, 907.3.4, 907.5.2.1.2, 907.5.2.2, 907.6, 907.6.1, 907.6.5, 907.7, 907.7.1, 907.7.2, 911.1.5, 3006.5, 3007.6 *NFPA 72, Amended Sections as follows: 10.3.1 Equipment constructed and installed in conformity with this Code shall be listed for the purpose for which it is used. <i>Fire alarm systems and components shall be California State Fire Marshal approved and listed in accordance with California Code of Regulations, Title 19, Division 1.</i> 10.3.3 All devices and appliances that receive their power from the initiating device circuit or signaling line circuit of a control unit shall be <i>California State Fire Marshal</i> listed for use with the control unit. 10.6.1 <i>Where approved by the authority having jurisdiction</i> , ECS priority signals when evaluated by stakeholders through risk analysis in accordance with 24.4.2.2 shall be permitted to take precedence over all other signals. 14.4.7.1 Testing. Household fire alarm systems shall be tested <i>in accordance with the manufacturer's published instructions</i> according to the methods of Table 14.4.2.2. 17.15 Fire Extinguisher Monitoring Device. A fire extinguisher monitoring device shall indicate those conditions for a specific fire extinguisher required by <i>California Code of Regulations, Title 19, Division 1, Chapter 1, Section 574.2(c) and California Fire Code to a fire alarm control unit.</i> 23.4.2.2 (4) Where the vertically run conductors are contained in a 2-hour rated cable assembly, or enclosed (installed) in a 2-hour rated enclosure or a listed circuit integrity (C.I.) cable, which meets or exceeds a 2-hour fire resistive rating. 23.8.5.1.2 Where connected to a supervising station, fire alarm systems employing automatic fire detectors or waterflow detection devices shall include a manual fire alarm box to initiate a signal to the supervising station. Exception: Fire alarm systems dedicated to elevator recall control, supervisory service <i>and fire sprinkler monitoring.</i> 23.8.5.4.1 Systems equipped with alarm verification features shall be permitted under the following conditions: (1) The alarm verification feature is not initially enabled unless conditions or occupant activities that are expected to cause nuisance alarms are anticipated in the area that is protected by the smoke detectors. Enabling of the alarm verification feature shall be protected by password or limited access. (2) A smoke detector that is continuously subjected to a smoke concentration above alarm threshold does not delay the system functions of Sections 10.6 through 10.13, 23.8.1.1, or 21.2.1 by more than 30 seconds. (3) Actuation of an alarm-initiating device other than a smoke detector causes the system functions of 4.4.3, 6.8.1.1, or 6.16.2.1 without additional delay. (4) The current status of the alarm verification feature is shown on the record of completion (<i>see Figure 4.5.2.1, item 10</i>). (5) <i>Operation of a patient room smoke detector in I-2 and R-2.1 Occupancies shall not include an alarm verification feature.</i>

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

	<p>29.3.1 All devices, combinations of devices, and equipment to be installed in conformity with this chapter shall be approved or listed <i>by the California State Fire Marshal</i> for the purposes for which they are intended.</p> <p>29.5.2.1.1* Smoke and Heat Alarms. Unless exempted by applicable laws, codes, or standards, smoke or heat alarms used to provide a fire-warning function, and when two or more alarms are installed within a dwelling unit, suite of rooms, or similar area, shall be arranged so that the operation of any smoke or heat alarm causes all alarms within these locations to sound.</p> <p>29.7.2.1 <i>The alarm verification feature shall not be used for household fire warning equipment.</i></p> <p>29.7.5.7.1 <i>The alarm verification feature shall not be used for household fire warning equipment.</i></p>
--	---

HISTORY NOTE APPENDIX

**Building Regulations for the Division of the State Architect, Access Compliance
(Title 24, Part 2, California Code of Regulations)**

For prior history, see the History Note Appendix to the *California Building Code (CBC)*, 2010 Triennial Edition, effective January 1, 2011.

1. (BSC 02/09, DSA-AC 01/09, DSA-SS 02/09, HCD 01/09, OSHPD 05/09 & 07/09, SFM 03/09, DWR 01/09) Adoption by reference of the 2009 *International Building Code (IBC)* with necessary state amendments into the 2010 CBC and repeal of the 2006 Edition of the IBC, effective on January 1, 2011.

2010 CALIFORNIA ELECTRICAL CODE

California Code of Regulations - Title 24, Part 3

Based on 2008 National Electrical Code

Effective Date: January 1, 2011

ARTICLE 89 CALIFORNIA MATRIX ADOPTION TABLE

ARTICLE 89 – GENERAL CODE PROVISIONS

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				DPH	
			1	1/AC	2	AC	SS	SS/CC	1	2	3	4		
Adopt Entire Article														
Adopt Entire Article as amended (amended sections listed below)														
Adopt only those articles / sections that are listed below						X								
Article/Section														
89.109.1						X								

**CALIFORNIA ARTICLE 89
GENERAL CODE PROVISIONS**

**SECTION 89.109
DIVISION OF THE STATE ARCHITECT**

89.109.1 DSA–AC – Division of the State Architect-Access Compliance.

Note: For applications listed in Section 1.9.1 of the California Building Code, regulated by the Division of the State Architect - Access Compliance see California Code of Regulations, Title 24, Part 2 (California Building Code), Chapter 1 (Division I California Administration) under authority cited by Government Code Section 4450 and in reference cited by Government Code Sections 4450, through 4461, 12955.1 and Health and Safety Code Sections 18949.1, 19952 through 19959.

CHAPTER 4 CALIFORNIA MATRIX ADOPTION TABLE

CHAPTER 4 – EQUIPMENT FOR GENERAL USE

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				DPH	
			1	1/AC	2	AC	SS	SS/CC	1	2	3	4		
Adopt Entire Article														
Adopt Entire Chapter as amended (amended sections listed below)						X								
Adopt only those articles / sections that are listed below														
Article/Section														
404 FPN						X								
406 FPN						X								

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

**ARTICLE 404
Switches**

Note: For applications listed in Section 1.9.1 of the California Building Code, regulated by the Division of the State Architect - Access Compliance see California Code of Regulations, Title 24, Part 2 (California Building Code), California Chapter 1 (Division 1 California Administration) under authority cited by Government Code Section 4450 and in reference cited by Government Code Sections 4450, through 4461, 12955.1 and Health and Safety Code Section 18949.1, 19952 through 19959.

**ARTICLE 406
Receptacles, Cord Connectors, and Attachment Plugs (Caps)**

Note: For applications listed in Section 1.9.1 of the California Building Code, regulated by the Division of the State Architect - Access Compliance see California Code of Regulations, Title 24, Part 2 (California Building Code), California Chapter 1 (Division 1 California Administration) under authority cited by Government Code Section 4450 and in reference cited by Government Code Sections 4450, through 4461, 12955.1 and Health and Safety Code Section 18949.1, 19952 through 19959.

CHAPTER 7 CALIFORNIA MATRIX ADOPTION TABLE

CHAPTER 7 – SPECIAL CONDITIONS

Adopting agency	BSC	SFM	HCD			DSA			OSHPD				DPH	
			1	1/AC	2	AC	SS	SS/CC	1	2	3	4		
Adopt Entire Article														
Adopt Entire Chapter as amended (amended sections listed below)														
Adopt only those articles / sections that are listed below														
Article/Section 760 FPN						X								

**ARTICLE 760
Fire Alarm Systems**

Note: For applications listed in Section 1.9.1 of the California Building Code, regulated by the Division of the State Architect - Access Compliance see California Code of Regulations, Title 24, Part 2 (California Building Code), California Chapter 1 (Division 1 California Administration) under authority cited by Government Code Section 4450 and in reference cited by Government Code Sections 4450, through 4461, 12955.1 and Health and Safety Code Section 18949.1, 19952 through 19959.

HISTORY NOTE APPENDIX

Electrical Regulations for the Division of the State Architect, Access Compliance (Title 24, Part 3, California Code of Regulations)

Notes

For prior history, see the History Note appendix to the *California Electrical Code*, 2007 Triennial Edition, effective January 1, 2008.

1. (BSC 01/08, SFM 05/08, HCD 01/08, DSA-SS 01/08, OSHPD 01/08, DSA AC 05/09) Adoption by reference of the 2008 *National Electric Code (NEC)* with necessary state amendments and repeal of the 2005 edition of the NEC; effective on January 1, 2011.

2010 CALIFORNIA PLUMBING CODE

California Code of Regulations - Title 24, Part 5

Based on 2009 Uniform Plumbing Code

Effective Date: January 1, 2011

**CALIFORNIA PLUMBING CODE – MATRIX ADOPTION TABLE
CHAPTER 1 – ADMINISTRATION**

Adopting agency	BSC	SFM	HCD			DSA			OSHDPD				CSA	DPH	AGR	DWR	CA	
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4						
Adopt entire chapter																		
Adopt Entire Chapter as amended (amended sections listed below)																		
Adopt only those sections that are listed below						X												
Chapter/Section																		
1.9.0						X												
1.9.1						X												

**DIVISION I
CALIFORNIA ADMINISTRATION**

1.9.0 Division of the State Architect

1.9.1 Division of the State Architect—Access Compliance.

Note: For applications listed in Section 1.9.1 of the California Building Code, regulated by the Division of the State Architect - Access Compliance see California Code of Regulations, Title 24, Part 2 (California Building Code), California Chapter 1 (Division I California Administration) under authority cited by Government Code Section 4450 and in reference cited by Government Code Sections 4450 through 4461, 12955.1 and Health and Safety Code Sections 18949.1, 19952 through 19959.

**CALIFORNIA PLUMBING CODE – MATRIX ADOPTION TABLE
CHAPTER 4 – PLUMBING FIXTURES AND FIXTURE FITTINGS**

Adopting agency	BSC	SFM	HCD			DSA			OSHDPD				CSA	DPH	AGR	DWR	CEC	CA
			1	2	1/AC	AC	SS	SS/CC	1	2	3	4						
Adopt Entire Chapter																		
Adopt Entire Chapter as amended (amended sections listed below)																		
Adopt only those sections that are listed below						X												
Chapter/Section																		
Note Under Title						X												
412.1.1						X												
Table 4-1 (Footnote 18)						X												

Note: In addition the requirements of this chapter, which provide access to, or egress from buildings or facilities where accessibility is required for applications listed in Section 1.9.1 of the California Building Code, regulated by

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

the Division of the State Architect - Access Compliance shall also comply with Chapter 11A for public housing and Chapter 11B for public accommodations under authority cited by Gov. Code §4450 through 4461, 12955.1 and H&SC §18949.1, 19952 through 19959.

412.0 Minimum Number of Required Fixtures.

412.1 Fixture Count.

412.1.1 [DSA-AC] *Effective January 1, 1990, in new construction and those existing facilities which occupancy type are listed in Tables 4-1 and 4-4 for public use, which apply for permit to undertake construction, structural alterations, repairs or improvement which exceed 50 percent of the square footage of the entire facility, shall install water closets, urinals, lavatories and drinking fountains as stipulated in Tables 4-1 and 4-4 for public use. Community and/or municipal parks with a bleacher capacity not exceeding 500 seats shall be exempt from the requirements of this section and Tables 4-1 and 4-4. Each bathroom shall comply with Part 2, Chapters 11A and 11B of the California Building Code.*

**TABLE 4-1
MINIMUM PLUMBING FACILITIES**

1st sentence only

Each building shall be provided with sanitary facilities, including provisions for persons with disabilities as prescribed by the Department Having Jurisdiction ¹⁸ ...

3^d sentence only

For requirements for persons with disabilities, Chapter 11A or 11B of the California Building Code, shall be used. ...

Footnote 18 only

[DSA-AC] *In accordance with Sections 1.8.7 and 301.2, the Authority Having Jurisdiction may approve alternative design criteria when determining the minimum number of plumbing fixtures.*

HISTORY NOTE APPENDIX

**Plumbing Regulations for the Division of the State Architect, Access Compliance
(Title 24, Part 5, California Code of Regulations)**

For prior history, see the History Note Appendix to the *California Plumbing Code (CPC)* 2007 Triennial Edition effective January 1, 2011.

1. (BSC 05/09, DSA-AC 03/09, DSA-SS 04/09, HCD 03/09, OSHPD 02/09, SFM 02/09) Adoption by reference of the 2009 *Uniform Plumbing Code (UPC)* with necessary state amendments and repeal of the 2006 edition of the UPC. Effective on January 1, 2011.

2010 CALIFORNIA HISTORICAL BUILDING CODE

California Code of Regulations - Title 24, Part 8

Effective Date: January 1, 2011

CHAPTER 8-1

ADMINISTRATION

Note. The *California Historical Building Code*, Part 8 of Title 24, governs for all qualified historical buildings or properties in the State of California.

SECTION 8-101

TITLE, PURPOSE AND INTENT

8-101.1 Title. These regulations shall be known as the *California Historical Building Code* and will be referred to herein as "the CHBC."

8-101.2 Purpose. The purpose of the CHBC is to provide regulations for the preservation, restoration, rehabilitation, relocation or reconstruction, of buildings or properties designated as qualified historical buildings or properties (Chapter 8-2). The CHBC is intended to provide solutions for the preservation of qualified historical buildings or properties, to promote sustainability, to provide access for persons with disabilities, to provide a cost-effective approach to preservation, and to provide for the reasonable safety of the occupants or users. The CHBC requires enforcing agencies to accept solutions that are reasonably equivalent to the regular code (as defined in Chapter 8-2) when dealing with qualified historical buildings or properties.

8-101.3 Intent. The intent of the CHBC is to facilitate the preservation and continuing use of qualified historical buildings or properties while providing reasonable safety for the building occupants and access for people with disabilities.

SECTION 8-102

APPLICATION

8-102.1 Application. The CHBC is applicable to all issues regarding building code compliance for qualified historical buildings or properties. The CHBC may be used in conjunction with the regular code to provide solutions to facilitate the preservation of qualified historical buildings or properties. The CHBC shall be used by any agency with jurisdiction and whenever compliance with the code is required for qualified historical buildings or properties.

1. The state or local enforcing agency, shall apply the provisions of the CHBC in permitting repairs, alterations, and additions necessary for the preservation, restoration, reconstruction, rehabilitation, relocation or continued use of a qualified historical building or property when so elected by the private property owner.
2. **State agencies.** All state agencies shall apply the provisions of in the CHBC in permitting repairs, alterations, and additions necessary for the preservation, restoration, rehabilitation, safety, relocation, reconstruction, or continued use of qualified historical buildings or properties.

8-102.1.1 Additions, alterations and repairs. It is the intent of the CHBC to allow non-historical expansion or addition to a qualified historical building or property provided: non-historical additions shall conform to the requirements of the regular code. See Chapter 8-2.

8-102.1.2 Relocation. Relocated qualified historical buildings or properties shall be sited to comply with the regular code or with the solutions listed in the CHBC. Nonhistorical new construction related to relocation shall comply with regular code. Reconstruction and restoration related to relocation is permitted to comply with the provisions in the CHBC.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-102.1.3 Change of occupancy. For change of use or occupancy, see Chapter 8-3, Use and Occupancy.

8-102.1.4 Continued use. Qualified historical buildings or properties may have their existing use or occupancy continued if such use or occupancy conformed to the code or to the standards of construction in effect at the time of construction, and such use or occupancy does not constitute a distinct hazard to life safety as defined in this code the CHBC.

8-102.1.5 Unsafe buildings or properties. When a qualified historical building or property is determined to be unsafe as defined in the regular code, the requirements of the CHBC are applicable to the work necessary to correct the unsafe conditions. Work to remediate the buildings or properties need only address the correction of the unsafe conditions, and it shall not be required to bring the entire qualified historical building or property into compliance with regular code.

8-102.1.6 Additional work. Qualified historical buildings and or properties shall not be subject to additional work required by the regular code, regulation or ordinance beyond that required to completing complete the work undertaken. Certain exceptions for access accessibility and for distinct hazards exist by mandate and may require specific action, within the parameters of the CHBC.

SECTION 8-103 ORGANIZATION AND ENFORCEMENT

8-103.1 Authority. The state or local enforcing agency, pursuant to authority provided under Section 18954 of the Health and Safety Code, shall administer and enforce the provisions of the CHBC in permitting repairs, alterations, and additions necessary for the preservation, restoration, reconstruction, rehabilitation, relocation or continued use of a qualified historical building or property.

8-103.2 State enforcement. All state agencies pursuant to authority provided under Section 18954 and Section 18961 of the Health and Safety Code shall administer and enforce the CHBC with respect to qualified historical buildings or properties under their respective jurisdiction.

8-103.3 Liability. Prevailing law regarding immunity of building officials is unaffected by the use and enforcement of the CHBC.

SECTION 8-104 REVIEW AND APPEALS

8-104.1 State Historical Building Safety Board (SHBSB). In order to provide for interpretation of the provisions of the CHBC and to hear appeals, the SHBSB shall act as an appeal and review body to state and local agencies and any affected party.

8-104.2 SHBSB review. When a proposed design, material or method of construction is being considered by the enforcing agency, the agency chief, the building official or the local board of appeals may file a written request for opinion to the SHBSB for its consideration, advice or findings. In considering such request, the SHBSB may seek the advice of other appropriate private or public boards, individuals, or state or local agencies. The SHBSB shall, after considering all of the facts presented, including any recommendation of other appropriate boards, agencies or other parties, determine if, for the purpose intended, the proposal is reasonably equivalent to that allowed by these regulations in proposed design, material or method of construction, and it shall transmit such findings and its decision to the enforcing agency for its application. The Board may recover the costs of such reviews and shall report the decision in printed form, copied to the California Building Standards Commission.

8-104.2.1 State agencies. All state agencies with ownership of, or that act on behalf of state agency owners of qualified historical buildings or properties, shall consult and obtain SHBSB review prior to taking action or making decisions or appeals that affect qualified historical buildings or properties, per section 18961 of Health and Safety Code.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-104.2.2 Imminent threat. Where an emergency is declared and a qualified historical building or property is declared an imminent threat to life and safety, the state agency assessing such a threat shall consult with the SHBSB before any demolition is undertaken, per section 18961 of Health and Safety Code.

8-104.3 SHBC appeals. If any local agency administering and enforcing the CHBC or any person adversely affected by any regulation, rule, omission, interpretation, decision, or practice of the agency enforcing the CHBC wishes to appeal the issue for resolution to the SHBSB, either of these parties may appeal directly to the Board. The Board may accept the appeal only if it determines that issues involved are of statewide significance. The Board may recover the costs of such reviews and shall make available copies of decisions in printed form at cost, copied to the California Building Standards Commission.

8-104.4 Local agency fees. Local agencies, when actively involved in the appeal, may also charge affected persons reasonable fees not to exceed the cost of obtaining reviews and appeals from the Board.

SECTION 8-105 CONSTRUCTION METHODS AND MATERIALS

8-105.1 Repairs. Repairs to any portion of a qualified historical building or property may be made in-kind with historical materials and the use of original or existing historical methods of construction, subject to conditions of the CHBC. (See Chapter 8-8.)

8-105.2 Solutions to the *California Historical Building Code*. Solutions provided in the CHBC, or any other acceptable regulation or methodology of design or construction and used in whole or in part, with the regular code, or with any combination of the regular code and the CHBC, shall be allowed. The CHBC does not preclude the use of any proposed alternative or method of design or construction not specifically prescribed or otherwise allowed by these regulations. Any alternative may be submitted for evaluation to the appropriate enforcing agency for review and acceptance. The enforcing agency may request that sufficient evidence or proof be submitted to substantiate any claims that may be made regarding such solutions. Any alternative offered in lieu of that prescribed or allowed in the CHBC shall be reasonably equivalent in quality, strength, effectiveness, durability and safety to that of the CHBC.

SECTION 8-106 SHBSB RULINGS

8-106.1 General. Rulings of the SHBSB (i.e. formal appeals, case decisions, code interpretations and administrative resolutions, etc.) that are issues of statewide application are required to be submitted to the California Building Standards Commission in printed form. These rulings may be used to provide guidance for similar cases or issues.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

CHAPTER 8-2 DEFINITIONS

SECTION 8-201 DEFINITIONS

For the purpose of the CHBC, certain terms and phrases, words, and their derivatives shall be construed as specified in this chapter. Additional definitions and/or terms may appear in the various other chapters relative to terms or phrases primarily applicable thereto. Any reference to “authority having jurisdiction” does not necessarily preclude the appellate process of Section 8-104.3.

ADDITION. A non-historical extension or increase in floor area or height of a building or property.

ALTERATION. A modification to a qualified historical building or property that affects the usability of the building or property, or part thereof. Alterations include, but are not limited to, remodeling, renovation, rehabilitation, reconstruction, historical restoration, changes or rearrangement of the structural parts or elements, and changes or rearrangements in the plan configuration of walls and full-height partitions.

BUILDING STANDARD. Any guideline, regulation or code that may be applied to a qualified historical building or property.

CHARACTER-DEFINING FEATURE. Those visual aspects and physical elements that comprise the appearance of an a historical building, or property, and that are significant to its historical, architectural and cultural values, including the overall shape of the historical building or property, its materials, craftsmanship, decorative details, interior spaces and features, as well as the various aspects of its site and environment.

CULTURAL RESOURCE. Building, site, property, object, or district evaluated as having significance in pre-history or history.

DISTINCT HAZARD. Any clear and evident condition that exists as an immediate danger to the safety of the occupants or the public right of way. Conditions that do not meet the requirements of current regular codes and ordinances do *not*, of themselves, constitute a distinct hazard. Section 8-104.3, SHBC appeals, remains applicable.

ENFORCING AGENCY. Authority Having Jurisdiction, Local Agency with Jurisdiction, agency. An entity with the responsibility for regulating, enforcing, reviewing or otherwise that exerts control of or administration over the process of granting permits, approvals, decisions, variances, appeals for qualified historical buildings or properties.

EXIT LADDER DEVICE. An exit ladder device is a permanently installed, fixed, folding, retractable, or hinged ladder intended for use as a means of emergency egress from areas of the second or third stories. Unless approved specifically for a longer length, the ladder shall be limited to 25 feet (7620 mm) in length. Exit ladders are permitted where the area served by the ladder has an occupant load of less than 10 persons.

FIRE HAZARD. Any condition which increases, or may contribute to an increase in the hazard or menace of fire to a greater degree than customarily recognized by the authority having jurisdiction, or any condition or act which could obstruct, delay, hinder or interfere with the operations of firefighting personnel or the egress of occupants in the event of fire. Section 8-104.3 SHBC Appeals remain applicable.

HISTORICAL FABRIC OR MATERIALS. Original and later-added historically significant construction materials, architectural finishes or elements in a particular pattern or configuration which form a qualified historical property, as determined by the authority having jurisdiction.

HISTORICAL SIGNIFICANCE. Importance for which a property has been evaluated and found to be historical, as determined by the authority having jurisdiction.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

IMMINENT THREAT. Any condition within or affecting a qualified historical building or property which, in the opinion of the authority having jurisdiction, would qualify a building or property as dangerous to the extent that the life, health, property or safety of the public, its occupants or those performing necessary repair, stabilization or shoring work are in immediate peril due to conditions affecting the building or property. Potential hazards to persons using, or improvements within, the right-of-way may not be construed to be “imminent threats” solely for that reason if the hazard can be mitigated by shoring, stabilization, barricades or temporary fences.

INTEGRITY. Authenticity of a building or property’s historical identity, evidenced by the survival of physical characteristics that existed during the property’s historical or prehistorical period of significance.

LIFE SAFETY EVALUATION. An evaluation of the life-safety hazards of a qualified historical building or property based on procedures similar to those contained in NFPA 909, *Standard for the Protection of Cultural Resources, Appendix B, Fire Risk Assessment in Heritage Premises*.

LIFE SAFETY HAZARD. See Distinct Hazard.

PERIOD OF SIGNIFICANCE. The period of time when a qualified historical building or property was associated with important events, activities, or persons, or attained the characteristics for its listing or registration.

PRESERVATION. The act or process of applying measures necessary to sustain the existing form, integrity, and materials of a qualified historical building or property. Work, including preliminary measures to protect and stabilize the property, generally focuses upon the ongoing maintenance and repair of historical materials and features rather than extensive replacement and new construction. New exterior additions are not within the scope of this treatment; however, the limited and sensitive upgrading of mechanical, electrical, and plumbing systems and other code-related work to make properties functional is appropriate within a preservation project.

QUALIFIED HISTORICAL BUILDING OR PROPERTY. As defined in Health and Safety Code Section 18955 as “Qualified Historical Building or Property.” Any building, site, object, place, location, district or collection of structures, and their associated sites, deemed of importance to the history, architecture, or culture of an area by an appropriate local, state or federal governmental jurisdiction. This shall include historical buildings or properties on, or determined eligible for, national, state or local qualified historical registers or inventories, such as the National Register of Historic Places, California Register of Historical Resources, State Historical Landmarks, State Points of Historical Interest, and city or county registers, inventories or surveys of historical or architecturally significant sites, places or landmarks.

RECONSTRUCTION. The act or process of depicting, by means of new construction, the form, features, and detailing of a nonsurviving site, landscape, building, property or object for the purpose of replicating its appearance at a specific period of time.

REGULAR CODE. The adopted regulations that govern the design and construction or alteration of nonhistorical buildings and properties within the jurisdiction of the enforcing agency.

REHABILITATION. The act or process of making possible a compatible use for qualified historical building or property through repair, alterations, and additions while preserving those portions or features which convey its historical, cultural, or architectural values.

RELOCATION. The act or process of moving any qualified historical building or property or a portion of a qualified historical building or property to a new site, or a different location on the same site

REPAIR. Renewal, reconstruction, or renovation of any portion of an existing property, site or building for the purpose of its continued use.

RESTORATION. The act or process of accurately depicting the form, features, and character of a qualified building or property as it appeared at a particular period of time by the means of the removal of features from other periods in its history and reconstruction of missing features from the restoration period. The limited and sensitive upgrading of mechanical, electrical, and plumbing systems and other code-required work to make properties functional is appropriate within a restoration project.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

STRUCTURE. That which is built or constructed, an edifice or building of any kind, or any piece of work artificially built up or composed of parts joined together in some definite manner.

TREATMENT. An act of work to carry out preservation, restoration, stabilization, rehabilitation, or reconstruction.

CHAPTER 8-3
USE AND OCCUPANCY

SECTION 8-301
PURPOSE AND SCOPE

8-301.1 Purpose. The purpose of the CHBC is to provide alternative regulations for the determination of occupancy classifications and conditions of use for buildings or structures designated as qualified historical buildings or properties.

8-301.2 Scope. Every qualified historical building or property for which a permit or approval has been requested shall be classified prior to permit issuance according to its use or the character of its occupancy in accordance with regular code and applicable provisions of this chapter.

SECTION 8-302
GENERAL

8-302.1 Existing use. The use or character of occupancy of a qualified historical building or property, or portion thereof, shall be permitted to continue in use regardless of any period of time in which it may have remained unoccupied, or in other uses, provided such building or property otherwise conforms to all applicable requirements of the CHBC.

8-302.2 Change in occupancy. The use or character of the occupancy of a qualified historical building or property may be changed from or returned to its historical use or character provided the qualified historical building or property conforms to the requirements applicable to the new use or character of occupancy as set forth in the CHBC. Such change in occupancy shall not mandate conformance with new construction requirements as set forth in regular code.

8-302.3 Occupancy separations. Required occupancy separations of more than one hour may be reduced to one-hour fire-resistive construction with all openings protected by not less than three-fourths-hour fire-resistive assemblies of the self-closing or automatic-closing type when the building is provided with an approved automatic sprinkler system throughout the entire building in accordance with section 8-410.4. Doors equipped with automatic-closing devices shall be of a type which will function upon activation of a device which responds to products of combustion other than heat.

Required occupancy separations of one hour may be omitted when the building is provided with an approved automatic sprinkler system throughout.

8-302.4 Maximum floor area. Regardless of the use or character of occupancy, the area of a one-story qualified historical building or property may have, but shall not exceed, a floor area of 15,000 square feet (1393.5 m²) unless such an increase is otherwise permitted in regular code. Multistory qualified historical buildings (including basements and cellars) shall be in accordance with regular code requirements

Exception: Historical buildings may be unlimited in floor area without fire-resistive area separation walls:

1. When provided with an approved automatic sprinkler, or
2. Residential occupancies, of two stories or less when provided with a complete fire alarm and annunciation system and where the exiting system conforms to regular code.

8-302.5 Maximum height. The maximum height and number of stories of a qualified historical building or property shall not be limited because of construction type, provided such height or number of stories does not exceed that of its historical design.

8-302.5.1 High-rise buildings. Occupancies B, F-1, F-2 or S in high rise buildings with floors located more than 75 feet above the lowest floor level having building access, may be permitted with only the stories over 75 feet provided with an automatic fire sprinkler system if:

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

1. The building construction type and the exits conform to regular code and
2. A complete building fire alarm and annunciation system is installed and,
3. A fire barrier is provided between the sprinklered and nonsprinklered floors

8-302.6 Fire-resistive construction. See Chapter 8-4.

8-302.7 Light and ventilation. Existing provisions for light and ventilation which do not, in the opinion of the enforcing agency, constitute a safety hazard may remain. See Section 8-303.6 for residential requirements. See Section 8-503 for Escape or Rescue Windows and Doors

SECTION 8-303 RESIDENTIAL OCCUPANCIES

8-303.1 Purpose. The purpose of this section is to provide regulations for those buildings designated as qualified historical buildings or properties and classified as occupancies. The CHBC requires enforcing agencies to accept any reasonably equivalent to regular code when dealing with qualified historical buildings and properties

8-303.2 Intent. The intent of the CHBC is to preserve the integrity of qualified historical buildings and properties while maintaining a reasonable degree of protection of life, health and safety for the occupants.

8-303.3 Application and scope. The provisions of this section shall apply to all qualified historical buildings used for human habitation. Those dwelling units intended only for display, or public use with no residential use involved, need not comply with the requirements of this section

8-303.4 Fire escapes. See Chapter 8-5.

8-303.5 Room dimensions. Rooms used for sleeping purposes may contain a minimum of 50 square feet (4.6 m²) floor area, provided there is maintained an average ceiling height of 7 feet (2134 mm). Other habitable rooms need only be of adequate size to be functional for the purpose intended.

8-303.6 Light and ventilation. Windows in habitable rooms shall have an area of 6 percent of the floor area, or 6 square feet (0.56 m²), whichever is greater. Windows in sleeping rooms shall be openable (See Section 8-503). Residential occupancies need not be provided with electrical lighting.

8-303.7 Alteration and repair. The alteration and repair of qualified historical buildings or properties may permit the replacement, retention and extension of original materials and the continued use of original methods of construction provided a life-safety hazard is not created or continued. Alterations and repairs shall be consistent with the CHBC.

The amount of alterations and repairs is not limited provided there is no nonhistorical increase in floor area, volume, or size of the building or property.

8-303.8 Exiting. See Chapter 8-5.

CHAPTER 8-4
FIRE PROTECTION

SECTION 8-401
PURPOSE, INTENT AND SCOPE

8-401.1 Purpose. The purpose of this chapter is to provide for fire protection of qualified historical buildings or properties. The CHBC requires enforcing agencies to accept any reasonably equivalent to the regular code when dealing with qualified historical buildings or properties.

8-401.2 Intent. The intent of the CHBC is to preserve the integrity of qualified historical buildings or properties while maintaining a reasonable degree of fire protection based primarily on the life safety of the occupants and firefighting personnel

8-401.3 Scope. This chapter shall apply when required by the provisions of Section 8-102.

SECTION 8-402
FIRE-RESISTIVE CONSTRUCTION

8-402.1 Exterior wall construction. The fire resistance requirement for existing exterior walls and existing opening protection may be satisfied when an automatic sprinkler system designed for exposure protection is installed per the CHBC. The automatic sprinklers may be installed on the exterior with at least one sprinkler located over each opening required to be protected. Additional sprinklers shall also be distributed along combustible walls under the roof lines that do not meet the fire-resistive requirement due to relationship to property lines as required by regular code. Such sprinkler systems may be connected to the domestic water supply on the supply-main side of the building shut-off valve. A shut-off valve may be installed for the sprinkler system provided it is locked in an open position

8-402.2 One-hour construction. Upgrading an existing qualified historical building or property to one-hour fire-resistive construction and one-hour fire resistive corridors shall not be required regardless of construction or occupancy when one of the following is provided:

1. An automatic sprinkler system throughout. See Section 8-410.2 for automatic sprinkler systems.
2. An approved life-safety evaluation.
3. Other alternative measures as approved by the enforcing agency.

8-402.3 Openings in fire-rated systems. Historical glazing materials and solid wood unrated doors in interior walls required to have one-hour fire rating may be approved when operable windows and doors are provided with appropriate smoke seals and when the area affected is provided with an automatic sprinkler system. See Section 8-410 for automatic sprinkler systems.

SECTION 8-403
INTERIOR FINISH MATERIALS

New nonhistorical interior wall and ceiling finish shall conform to the provisions of the regular code. Existing nonconforming materials used for wood lath and plaster walls, see Section 8-404.

Exception: When an approved automatic sprinkler system is provided throughout the building, existing finishes shall be approved.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 8-404 WOOD LATH AND PLASTER

Wood lath and plaster walls may be considered in accordance with codes, standards, and listings published prior to 1943 whereby a wood stud wall assembly with gypsum or lime plaster on hand split or sawn wooden lath obtains a one-half-hour fire-resistive rating. This rating may be increased for interior walls to as much as one hour by filling the wall with mineral fiber or glass fiber.

SECTION 8-405 OCCUPANCY SEPARATION

See Chapter 8-3.

SECTION 8-406 MAXIMUM FLOOR AREA

See Chapter 8-3.

SECTION 8-407 VERTICAL SHAFTS

Vertical shafts need not be enclosed when such shafts are blocked at every floor level by the installation of not less than 2 full inches (51 mm) of solid wood or equivalent construction installed so as to prevent the initial passage of smoke and flame. Automatic sprinkler systems or other solutions may be considered on a case-by-case basis, in lieu of enclosure of vertical shafts and stairwells.

SECTION 8-408 ROOF COVERING

Existing or original roofing materials may be repaired or reconstructed subject to the following requirements:

1. The original or historical roofing system shall be detailed or modified as necessary in order to be capable of providing shelter while preserving the historical materials and appearance of the roof.
2. Wooden roof materials may be utilized where fire resistance is required provided they are treated with fire-retardant treatments to achieve a Class "B" roof covering rating. Wood roofing in state designated Urban Wildland and High Fire Zones shall be permitted when installed in class "A" assemblies.
3. Jurisdictions that prohibit wood roofing materials for application as roof coverings and roof assemblies shall submit documentation for the adoption. Express Terms, statement of reasons and minutes of the action by the adopting authority Health and Safety Code, Section 18959(f).

SECTION 8-409 FIRE ALARM SYSTEMS

Every qualified historical building or property shall be provided with fire alarm systems as required for the use or occupancy by regular code or other approved alternative.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 8-410 AUTOMATIC SPRINKLER SYSTEMS

8-410.1 Every qualified historical building or property which cannot be made to conform to the construction requirements specified in the regular code for the occupancy or use, and which constitutes a distinct fire hazard, (for definition of “distinct hazard”, see Chapter 8-2), shall be deemed to be in compliance if provided with an automatic sprinkler system, or a life-safety system or other technologies as approved by the enforcing agency. (“Automatic” is defined in regular code. Sprinkler System is defined in this section.)

8-410.2 When required by the CHBC, an automatic sprinkler systems is defined by the following standards (for nonhazardous occupancies).

1. Buildings of four stories or less; NFPA 13R, 2002 edition.
2. For floors above the fourth, NFPA 13, 2002 SFM amended edition.
3. Buildings with floors above 75 feet, NFPA 13, 2002 edition.
4. When the building is free standing or with property line separation, two floors and 1500 sf per floor or less, NFPA 13D, 2002 edition.
5. For exterior wall and opening protection. As required by this section.

Exception: When the automatic sprinkler systems are used to reach compliance using this code, in three or more occasions, the system shall be NFPA Standard 13D shall be increased to NFPA 13R Standard, or NFPA 13R standard shall be increased to NFPA 13 standard.

8-410.3 Automatic sprinkler systems shall not be used to substitute for or act as an alternate to the required number of exits from any facility. (See Chapter 8-5 for exiting requirements.)

8-410.4 An automatic sprinkler system shall be provided in all detention facilities.

SECTION 8-411 OTHER TECHNOLOGIES

Fire alarm systems, smoke and heat detection systems, occupant notification and annunciation systems, smoke control systems and fire modeling, timed egress analysis and modeling, as well as other engineering methods and technologies may be accepted by the enforcing agency to address areas of non-conformance.

SECTION 8-412 HIGH-RISE BUILDINGS

Qualified historical buildings having floors for human occupancy located more than 75 feet above the lowest floor level having building access shall conform to the provisions of the regular code for existing high-rise buildings as amended by the CHBC.

CHAPTER 8-5
MEANS OF EGRESS

SECTION 8-501
PURPOSE, INTENT AND SCOPE

8-501.1 Purpose. The purpose of this chapter is to establish minimum means of egress regulations for qualified historical buildings or properties. The CHBC requires enforcing agencies to accept reasonably equivalent alternatives to the means of egress requirements in the regular code.

8-501.2 Intent. The intent of these regulations to provide an adequate means of egress.

8-501.3 Scope. Every qualified historical building or portion thereof shall be provided with exists as required the CHBC when required by the provisions of Section 8-102.

SECTION 8-502
GENERAL

8-502.1 General. The enforcing agency shall grant reasonable exceptions to the specific provisions of applicable egress regulations where such exceptions will not adversely affect life safety.

8-502.2 Existing door openings and corridor widths of less than dimensions required by regular code shall be permitted where there is sufficient width and height for the occupants to pass through the opening or traverse the exit.

8-502.3 Stairs. Existing stairs having risers and treads, or width at variance with the regular code are allowed if determined by the enforcing agency to not constitute a distinct hazard. Handrails with nonconforming grip size or extensions are allowed if determined by the enforcing agency to not constitute a distinct hazard.

8-502.4 Main entry doors. The front or main entry doors need not be re-hung to swing in the direction of exit travel, provided other means or conditions of exiting, as necessary to serve the total occupant load, are provided.

8-502.5 Existing fire escapes. Existing previously approved fire escapes and fire escape ladders shall be acceptable as on one of the required means of egress, provided they extend to the ground and are easily negotiated, adequately signed, and in good working order. Access shall be by an opening having a minimum width of 29 inches (737mm) when open with a sill be no more than 30 inches (762 mm) above the adjacent floor, landing, or approved step.

8-502.6 New fire escapes and fire escape ladders. New fire escapes and fire escape ladders which comply with this section shall be acceptable as one of the required means of egress. New fire escapes and new fire escape ladders shall comply with the following:

1. Access from a corridor shall not be through an intervening room.
2. All openings within 10 feet (3048 mm) shall be protected by three-fourths-hour fire assemblies. When located within a recess or vestibule, adjacent enclosure walls shall be of not less than one-hour fire-resistive construction.
3. Egress from the building shall be by a clear opening having a minimum dimension of not less than 29 inches (737 mm). Such openings shall be openable from the inside without the use of a key or special knowledge or effort. The sill of an opening giving access shall not be more than 30 inches (737mm) above the floor, step or landing of the building or balcony.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

4. Fire escape stairways and balconies shall support the dead load plus a live load of not less than 100 pounds per square foot (4.79 kN/ m²) and shall be provided with a top and intermediate handrail on each side. The pitch of the stairway shall not exceed 72 degrees with a minimum width of 18 inches (457 mm). Treads shall not be less than 4 inches (102 mm) in width and the rise between treads shall not exceed 10 inches (254 mm). All stair and balcony railings shall support a horizontal force of not less than 50 pounds per lineal foot (729.5 N/m²) of railing.
5. Balconies shall not be less than 44 inches (1118 mm) in width with no floor opening other than the stairway opening greater than 5/8 inch in width. Stairway openings in such balconies shall not be less than 22 inches by 44 inches (559 by 1118 mm). The balustrade of each balcony shall not be less than 36 inches (914 mm) high with not more than 9 inches (287 mm) between balusters.
6. Fire escapes shall extend to the roof or provide an approved gooseneck ladder between the top floor landing and the roof when serving buildings four or more stories in height having roofs with less than 4 units vertical in 12 units horizontal (33.3 percent slope). Fire escape ladders shall be designed and connected to the building to withstand a horizontal force of 100 pounds (445 N) placed anywhere on the rung. All ladders shall be at least 15 inches (381 mm) wide, located within 12 inches (305 mm) of the building. Ladder rungs shall be ¾ inch (19.1 mm) in diameter and shall be located 12 inches (305 mm) on center. Openings for roof access ladders through cornices and similar projections shall have minimum dimensions of 30 inches by 33 inches (762 by 838 mm).

The length of fire escapes and exit ladder devices shall be limited to that approved by the building official based on products listed by a recognized testing laboratory.

7. The lowest balcony shall not be more than 18 feet (5486 mm) from the ground. Fire escapes shall extend to the ground or be provided with counterbalanced stairs reaching to the ground.
8. Fire escapes shall not take the place of stairways required by the codes under which the building was constructed.
9. Fire escapes shall be kept clear and unobstructed at all times and maintained in good working order.

SECTION 8-503 ESCAPE OR RESCUE WINDOWS AND DOORS

Basements in dwelling units and every sleeping room below the fourth floor shall have at least one openable window or door approved for emergency escape which shall open directly into a public street, public way, yard or exit court. Escape or rescue windows or doors shall have a minimum clear area of 3.3 square feet (0.31 m²) and a minimum width or height dimension of 18 inches (457 mm) and be operable from the inside to provide a full, clear opening without the use of special tools.

SECTION 8-504 RAILINGS AND GUARDRAILS

The height of railings and guard railings and the spacing of balusters may continue in their qualified historical height and spacing unless a distinct hazard has been identified or created by a change in use or occupancy.

**CHAPTER 8-6
ACCESSIBILITY**

**SECTION 8-601
PURPOSE, INTENT AND SCOPE**

8-601.1 Purpose. The purpose of the CHBC is to provide alternative regulations to facilitate access and use by people with disabilities to and throughout facilities designated as qualified historical buildings or properties. These regulations require enforcing agencies to accept alternatives to regular code when dealing with qualified historical buildings or properties.

8-602.2 Intent The intent of this chapter to preserve the integrity of qualified historical buildings and properties while providing access to and use by people with disabilities.

8-601.3 Scope. The CHBC shall apply to every qualified historical building or property that is required to provide access to people with disabilities.

1. Provisions of this chapter do not apply to new construction or reconstruction/replicas of historical buildings.
2. Where provisions of this chapter apply to alteration of qualified historical buildings or properties, alteration is defined in *California Building Code* (CBC), Chapter 2, Definitions and Abbreviations. 202 – A. Alter or Alteration.

8-601.4 General application. The provisions in the CHBC apply to local, state and federal governments (Title II entities); alteration of commercial facilities and places of public accommodation (Title III entities); and barrier removal in commercial facilities and places of public accommodation (Title III entities). Except as noted in this chapter.

**SECTION 8-602
BASIC PROVISIONS**

8-602.1 Regular code. The regular code for access for people with disabilities (Title 24, Part 2, Vol.1, Chapter 11B) shall be applied to qualified historical buildings or properties unless strict compliance with the regular code will threaten or destroy the historical significance or character-defining features of the building or property.

8-602.2 Alternative provisions. If the historical significance or character-defining features are threatened, alternative provisions for access may be applied pursuant to this chapter provided the following conditions are met:

1. These provisions shall be applied only on an item-by-item or case-by-case basis.
2. Documentation is provided, including meeting minutes or letters, stating the reasons for the application of the alternative provisions. Such documentation shall be retained in the permanent file of the enforcing agency.

**SECTION 8-603
ALTERNATIVES**

8-603.1 Alternative minimum standards. The alternative minimum standards for alterations of qualified historical buildings or facilities are contained in Section 4.1.7(3) of ADA Standards for Accessible Design, as incorporated and set forth in federal regulation 28 C.F.R Pt. 36.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-603.2 Entry. These alternatives do not allow exceptions for the requirement of level landings in front of doors, except as provided in Section 8-603.4.

1. Access to any entrance used by the general public and no further than 200 feet (60 960 mm) from the primary entrance.
2. Access at any entrance not used by general public but open and unlocked with directional signs at the primary entrance and as close as possible to, but no further than 200 feet (60 960 mm) from, the primary entrance.
3. The accessible entrance shall have a notification system. Where security is a problem, remote monitoring may be used.

8.603.3 Doors. Alternatives listed in order of priority are:

1. Single-leaf door which provides a minimum 30 inches (762 mm) of clear opening.
2. Single-leaf door which provides a minimum 29½ inches (749mm) clear opening
3. Double door, one leaf of which provides a minimum 29½ inches (749mm) clear opening.
4. Double doors operable with a power-assist device to provide a minimum 29½ inches (749mm) clear opening when both doors are in the open position.

8-603.4 Power-assisted doors. Power-assisted door or doors may be considered an equivalent alternative to level landings, strikeside clearance and door-opening forces required by regular code.

8-603.5 Toilet rooms. In lieu of separate-gender toilet facilities as required in the regular code, an accessible unisex toilet may be designated.

8-603.6 Exterior and interior ramps and lifts. Alternatives listed in order of priority are:

1. A lift or a ramp of greater than standard slope but no greater than 1:10, for horizontal distances not to exceed 5 feet (1525 mm). Signs shall be posted at upper and lower levels to indicate steepness of the slope.
2. Access by ramps of 1:6 slope for horizontal distance not to exceed 13 inches (330 mm). Signs shall be posted at upper and lower levels to indicate steepness of the slope.

SECTION 8-604 EQUIVALENT FACILITATION

Use of other designs and technologies, or deviation from particular technical and scoping requirements, are permitted if the application of the alternative provisions contained in Section 8-603 would threaten or destroy the qualified historical significance or character-defining features of the historical building or property.

1. Such alternatives shall be applied only on an item-by-item or case-by-case basis.
2. Access provided by experiences, services, functions, materials and resources through methods including, but not limited to, maps, plans, videos, virtual reality, and related equipment, at accessible levels. The alternative design and/or technologies used will provide substantially equivalent or greater accessibility to, and usability of, the facility.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

3. The official charged with the enforcement of the standards shall document the reasons for the application of the design and/or technologies and their effect on the historical significance or character-defining features. Such documentation shall be in accordance with Section 8-602.2, Item 2, and shall include the opinion and comments of state or local accessibility officials, and the opinion and comments of representative local groups of people with disabilities. Such documentation shall be retained in the permanent file of the enforcing agency. Copies of the required documentation should be available at the facility upon request.

Note: For commercial facilities and places of public accommodation (Title III entities).

Equivalent facilitation for an element of a building or property when applied as a waiver of an ADA accessibility requirement will not be entitled to the Federal Department of Justice certification of this code as rebuttable evidence of compliance for that element.

CHAPTER 8-7
STRUCTURAL REGULATIONS

SECTION 8-701
PURPOSE, INTENT AND SCOPE

8-701.1 Purpose. The purpose of the CHBC is to provide alternative regulations for the structural safety of buildings designated as qualified historical buildings or properties. The CHBC requires enforcing agencies to accept any reasonably equivalent alternatives to regular code when dealing with qualified historical buildings or properties.

8-701.2 Intent. The intent of the CHBC is to encourage the preservation of qualified historical buildings or properties while providing a reasonable level of structural safety for occupants and the public at large through the application of the CHBC.

8-701.3 Application. The alternative structural regulations provided by Section 8-705 are to be applied in conjunction with regular code whenever a structural upgrade or reconstruction is undertaken for qualified historical buildings or properties.

SECTION 8-702
GENERAL

8-702.1 The CHBC shall not be construed to allow the enforcing agency to approve or permit a lower level of safety of structural design and construction than that which is reasonably equivalent to the regular code provisions in occupancies which are critical to the safety and welfare of the public at large, including, but not limited to, public and private schools, hospitals, municipal police and fire stations and essential services facilities.

8-702.2 Nothing in these regulations shall prevent voluntary and partial seismic upgrades when it is demonstrated that such upgrades will improve life safety and when a full upgrade would not otherwise be required.

SECTION 8-703
STRUCTURAL SURVEY

8-703.1 Scope. When a structure, or portion of a structure is to be evaluated for structural capacity under the CHBC, it shall be surveyed for structural conditions by an architect or engineer knowledgeable in historical structures. The survey shall evaluate deterioration or signs of distress. The survey shall determine the details of the structural framing and the system for resistance of gravity and lateral loads. Details, reinforcement and anchorage of structural systems and veneers shall be determined and documented where these members are relied on for seismic resistance.

8-703.2 The results of the survey shall be utilized for evaluating the structural capacity and for designing modifications to the structural system to reach compliance with this code.

8-703.3 Historical records. Past qualified historical records of the structure or similar structures may be used in the evaluation, including the effects of subsequent alterations.

SECTION 8-704
NONHISTORICAL ADDITIONS AND NONHISTORICAL ALTERATIONS

8-704.1 New nonhistorical additions and nonhistorical alterations which are structurally separated from an existing historical structure shall comply with regular code requirements.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-704.2 New nonhistorical additions which impose vertical or lateral loads on an existing structure shall not be permitted unless the affected part of the supporting structure is evaluated and strengthened, if necessary, to meet regular code requirements.

Note: For use of archaic materials, see Chapter 8-8.

SECTION 8-705 STRUCTURAL REGULATIONS

8-705.1 Gravity loads. The capacity of the structure to resist gravity loads shall be evaluated and the structure strengthened as necessary. The evaluation shall include all parts of the load path. Where no distress is evident, and a complete load path is present, the structure may be assumed adequate by having withstood the test of time if anticipated dead and live loads will not exceed those historically present.

8-705.2 Wind and seismic loads. The ability of the structure to resist wind and seismic loads shall be evaluated. The evaluation shall be based on the requirements of Section 8-706.

8-705.2.1 Any unsafe conditions in the lateral-load-resisting system shall be corrected, or alternative resistance shall be provided. Additional resistance shall be provided to meet the minimum requirements of this code.

8-705.2.2 The architect or engineer shall consider additional measures with minimal loss of, and impact to historical materials which will reduce damage and needed repairs in future earthquakes to better preserve the historical structure in perpetuity. These additional measures shall be presented to the owner for consideration as part of the rehabilitation or restoration.

SECTION 8-706 LATERAL LOAD REGULATIONS

8-706.1 Lateral loads. The forces used to evaluate the structure for resistance to wind and seismic loads need not exceed 0.75 times the seismic forces prescribed by the 1995 Edition of the *California Building Code* (CBC). The seismic forces may be computed based on the R_w values tabulated in the regular code for similar lateral-force-resisting-systems. All deviations of the detailing provisions of the lateral-force-resisting systems shall be evaluated for stability and the ability to maintain load-carrying capacity at increased lateral loads.

Unreinforced masonry bearing wall buildings shall comply with Appendix Chapter 1 of the *Uniform Code for Building Conservation*[™] (UCBC[™]), 1994 edition, and as modified by this code. Reasonably equivalent standards may be used on a case-by-case basis when approved by the authority having jurisdiction.

8-706.2 Existing building performance. The seismic resistance may be based upon the ultimate capacity of the structure to perform giving due consideration to ductility and reserve strength of the lateral-force resisting-system and materials while maintaining a reasonable factor of safety. Broad judgment may be exercised regarding the strength and performance of materials not recognized by regular code requirements. (See Chapter 8-8, Archaic Materials and Methods of Construction.)

8-706.2.1 All structural materials or members that do not comply with detailing and proportioning requirements of the regular code shall be evaluated for potential seismic performance and the consequence of non-compliance. All members which might fail and lead to possible collapse, or threaten life-safety, when subjected to seismic demands in excess of those prescribed in Section 8-706.1, shall be judged unacceptable and appropriate structural strengthening shall be developed. Anchorages for veneers and decorative ornamentation shall be included in this evaluation.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-706.3 Load path. A complete and continuous load path, including connections, from every part or portion of the structure to the ground shall be provided for the required forces. It shall be verified that the structure is adequately tied together to perform as a unit when subjected to earthquake forces.

8-706.4 Parapets. Parapets and exterior decoration shall be investigated for conformance with regular code requirements for anchorage and ability to resist prescribed seismic forces.

An exception to regular code requirements shall be permitted for those parapets and decorations which are judged not to be a hazard to life safety.

8-706.5 Nonstructural features. Nonstructural features of historical structure, such as exterior veneer, cornices and decorations, which might fall and create a life-safety hazard in an earthquake, shall be investigated. Their ability to resist seismic forces shall be verified, or the feature shall be strengthened.

8-706.5.1 Partitions and ceilings of corridors and stairways serving an occupant load of 30 or more shall be investigated to determine their ability to remain in place when the building is subjected to earthquake forces.

CHAPTER 8-8
ARCHAIC MATERIALS AND METHODS OF CONSTRUCTION

SECTION 8-801
PURPOSE, INTENT AND SCOPE

8-801.1 Purpose. The purpose of the CHBC is to provide regulations for the use of historical methods and materials of construction that are at variance with regular code requirements or are not otherwise codified, in buildings or structures designated as qualified historical buildings or properties. The CHBC requires enforcing agencies to accept any reasonably equivalent alternatives to regular code when dealing with qualified historical buildings or properties.

8-801.2 Intent. It is the intent of the CHBC to provide for the use of historical methods and materials of construction that are at variance with specific code requirements or are not otherwise codified.

8-801.3 Scope. Any construction type or material that is, or was, part of the historical fabric of a structure, is covered by this chapter. Archaic materials and methods of construction present in a historical structure may remain or be reinstalled or be installed with new materials of the same class to match existing conditions.

SECTION 8-802
GENERAL ENGINEERING APPROACHES

Allowable stresses or ultimate strengths for archaic materials shall be assigned based upon similar conventional codified materials, or on tests as hereinafter indicated. The archaic materials and methods of construction shall be thoroughly investigated for their details of construction in accordance with Section 8-703. Testing shall be performed when applicable to evaluate existing conditions. The architect or structural engineer in responsible charge of the project shall assign allowable stresses or ultimate strength values to archaic materials. Such assigned allowable stresses, or ultimate strength values, shall not be greater than those provided for in the following sections without adequate testing, and shall be subject to the concurrence of the enforcing agency.

SECTION 8-803
NON-STRUCTURAL ARCHAIC MATERIALS

Where non-structural historical materials exist in uses which do not meet the requirements of the regular code, their continued use is allowed by this code, provided that any public health and life-safety hazards are mitigated subject to the concurrence of the enforcing agency.

SECTION 8-804
ALLOWABLE CONDITIONS FOR SPECIFIC MATERIALS

Archaic materials which exist and are to remain in historical structures shall be evaluated for their condition and for loads required by this code. The structural survey required in Section 8-703 of this code shall document existing conditions, reinforcement, anchorage, deterioration and other factors pertinent to establishing allowable stresses and adequacy of the archaic materials. The remaining portion of this chapter provides additional specific requirements for commonly encountered archaic materials.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 8-805 MASONRY

For adobe, see Section 8-806.

8-805.1 Existing solid masonry. Existing solid masonry walls of any type, except adobe, may be allowed, without testing, a maximum value of nine pounds per square inch (62.1 kPa) in shear where there is a qualifying statement by the architect or engineer that an inspection has been made, that mortar joints are filled and that both brick and mortar are reasonably good. The allowable shear stress above applies to unreinforced masonry, except adobe, where the maximum ratio of unsupported height or length to thickness does not exceed 12, and where minimum quality mortar is used or exists. Wall height or length is measured to supporting or resisting elements that are at least twice as stiff as the tributary wall. Stiffness is based on the gross section. Allowable shear stress may be increased by the addition of 10 percent of the axial direct stress due to the weight of the wall directly above. Higher quality mortar may provide a greater shear value and shall be tested in accordance with UBC Standard 21-6.

8-805.2 Stone masonry.

8-805.2.1 Solid-backed stone masonry. Stone masonry solidly backed with brick masonry shall be treated as solid brick masonry as described in Section 8-805.1 and in the UCBC, provided representative testing and inspection verifies solid collar joints between stone and brick and that a reasonable number of stones lap with the brick wythes as headers or that steel anchors are present. Solid stone masonry where the wythes of stone effectively overlap to provide the equivalent header courses may also be treated as solid brick masonry.

8-805.2.2 Independent wythe stone masonry. Stone masonry with independent face wythes may be treated as solid brick masonry as described in Section 805.1 and the UCBC, provided representative testing and inspection verify that the core is essentially solid in the masonry wall and that steel ties are epoxied in drilled holes between outer stone wythes at floors, roof and at not-to-exceed 4 feet (1219 mm) on center in each direction, between floors and roof.

8-805.2.3 Testing of stone masonry. Testing of stone masonry shall be similar to UBC Standard 21-6, except that representative stones which are not interlocked shall be pulled outward from the wall and shear area appropriately calculated after the test.

8-805.3 Reconstructed walls. Totally reconstructed walls utilizing original brick or masonry, constructed similar to original, shall be constructed in accordance with regular code. Repairs or infills may be constructed in a similar manner to the original walls without conforming to regular code.

SECTION 8-806 ADOBE

8-806.1 General. Unburned clay masonry may be constructed, reconstructed, stabilized, or rehabilitated subject to this chapter. Alternate approaches which provide an equivalent or greater level of safety may be used, subject to the concurrence of the enforcing agency.

8-806.2 Protection. Provisions shall be made to protect adobe structures from moisture and deterioration. The unreinforced adobe shall be maintained in reasonably good condition. Particular attention shall be given to moisture content of adobe walls. Unmaintained or unstabilized walls or ruins shall be evaluated for safety based on their condition and stability. Additional safety measures may be required subject to the concurrence of the enforcing agency.

8-806.3 Requirements. Unreinforced new or existing adobe walls shall meet the requirements. Existing sod or rammed earth walls shall be considered similar to the extent these provisions apply. Where existing dimensions do not meet these conditions, additional strengthening measures may be required.

1. One-story adobe load-bearing walls shall not exceed a height-to-thickness ratio of 6.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

2. Two-story adobe buildings or structures' height-to-thickness wall ratio shall not exceed 5 at the ground floor and 6 at the second floor, and shall be measured at floor-to-floor height when the second floor and attic ceiling/roof are connected to the wall as described below.
3. Non-load-bearing adobe partitions and gable end walls shall be evaluated for stability and anchored against out-of-plane failure.
4. A bond beam or equivalent structural element shall be provided at the top of all adobe walls, and for two-story buildings at the second floor. The size and configuration of the bond beam shall be designed in each case to meet the requirements of the existing conditions and provide an effective brace for the wall, to tie the building together and connect the wall to the floor or roof.

8-806.4 Repair or reconstruction. Repair or reconstruction of wall area may utilize un-stabilized brick or adobe masonry designed to be compatible with the constituents of the existing adobe materials.

8-806.5 Shear values. Existing adobe may be allowed a maximum value of four pounds per square inch (27.6 kPa) for shear, with no increase for lateral forces.

8-806.6 Mortar. Mortar may be of the same soil composition as that used in the existing wall, or in new walls as necessary to be compatible with the adobe brick.

SECTION 8-807 WOOD

8-807.1 Existing wood diaphragms or walls. Existing wood diaphragms or walls of straight or diagonal sheathing shall be assigned shear resistance values appropriate with the fasteners and materials functioning in conjunction with the sheathing. The structural survey shall determine fastener details and spacings and verify a load path through floor construction. Shear values of Tables 8-8-A and 8-8-B.

8-807.2 Wood lath and plaster. Wood lath and plaster walls and ceilings may be utilized using the shear values referenced in Section 8-807.1.

8-807.3 Existing wood framing. Existing wood framing members may be assigned allowable stresses consistent with codes in effect at the time of construction. Existing or new replacement wood framing may be of archaic types originally used if properly researched, such as balloon and single wall. Wood joints such as dovetail and mortise and tenon types may be used structurally, provided they are well made. Lumber selected for use and type need not bear grade marks, and greater or lesser species such as low-level pine and fir, boxwood and indigenous hardwoods and other variations may be used for specific conditions where they were or would have been used.

Wood fasteners such as square or cut nails may be used with a maximum increase of 50 percent over wire nails for shear.

SECTION 8-808 CONCRETE

8-808.1 Materials. Natural cement concrete, unreinforced rubble concrete, and similar materials may be utilized wherever that material is used historically. Concrete of low strength and with less reinforcement than required by the regular code may remain in place. The architect or engineer shall assign appropriate values of strength based on testing of samples of the materials. Bond and development lengths shall be determined based on historical information or tests.

8-808.2 Detailing. The architect or engineer shall carefully evaluate all detailing provisions of the regular code which are not met and shall consider the implications of these variations on the ultimate performance of the structure, giving due consideration to ductility and reserve strength.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

SECTION 8-809 STEEL AND IRON

The hand-built, untested use of wrought or black iron, the use of cast iron or grey iron, and the myriad of joining methods that are not specifically allowed by code may be used wherever applicable and wherever they have proven their worth under the considerable span of years involved with most qualified historical structures. Uplift capacity should be evaluated and strengthened where necessary. Fixed conditions or mid-height lateral loads on cast iron columns that could cause failure should be taken into account. Existing structural wrought, forged steel or grey iron may be assigned the maximum working stress prevalent at the time of original construction.

SECTION 8-810 HOLLOW CLAY TILE

The historical performance of hollow clay tile in past earthquakes shall be carefully considered in evaluating walls of hollow clay tile construction. Hollow clay tile bearing walls shall be evaluated and strengthened as appropriate for lateral loads and their ability to maintain support of gravity loads. Suitable protective measures shall be provided to prevent blockage of exit stairways, stairway enclosures, exit ways and public ways as a result of an earthquake.

SECTION 8-811 VENEERS

8-811.1 Terra cotta and stone. Terra cotta, cast stone and natural stone veneers shall be investigated for the presence of suitable anchorage. Steel anchors shall be investigated for deterioration or corrosion. New or supplemental anchorage shall be provided as appropriate.

8-811.2 Anchorage. Brick veneer with mechanical anchorage at spacings greater than required by regular code may remain provided the anchorages have not corroded. Nail strength in withdrawal in wood sheathing may be utilized to its capacity in accordance with code values.

SECTION 8-812 GLASS AND GLAZING

8-812.1 Glazing subject to human impact. Historical glazing material located in areas subject to human impact may be approved subject to the concurrence of the enforcing agency when alternative protective measures are provided. These measures may include, but not be limited to, additional glazing panels, protective film, protective guards or systems, and devices or signs which would provide adequate public safety.

8-812.2 Glazing in fire-rated systems. See Section 8-402.3.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Table 8-8A ALLOWABLE VALUES FOR EXISTING MATERIALS

EXISTING MATERIALS OR CONFIGURATIONS OF MATERIALS ¹	ALLOWABLE VALUES
	x14.594 for N/m
<p>1. Horizontal diaphragms²</p> <p style="margin-left: 20px;">1.1. Roofs with straight sheathing and roofing applied directly to the sheathing</p> <p style="margin-left: 20px;">1.2. Roofs with diagonal sheathing and roofing applied directly to the sheathing</p> <p style="margin-left: 20px;">1.3. Floors with straight tongue-and-groove sheathing</p> <p style="margin-left: 20px;">1.4. Floors with straight sheathing and finished wood flooring with board edges offset or perpendicular</p> <p style="margin-left: 20px;">1.5. Floors with diagonal sheathing and finished</p>	<p>100 lbs. Per foot for seismic shear</p> <p>250 lbs. Per foot for seismic shear</p> <p>100 lbs. Per foot for seismic shear</p> <p>500 lbs. Per foot for seismic shear</p> <p>600 lbs. Per foot for seismic shear</p>
<p>2. Crosswalls^{2,3}</p> <p style="margin-left: 20px;">2.1 Plaster on wood or metal lath</p> <p style="margin-left: 20px;">2.2 Plaster on gypsum lath</p> <p style="margin-left: 20px;">2.3 Gypsum wallboard, unblocked edges</p> <p style="margin-left: 20px;">2.4 Gypsum wallboard, blocked edges</p>	<p>Per side: 200 lbs. Per foot for seismic shear</p> <p>175 lbs. Per foot for seismic shear</p> <p>75 lbs. Per foot for seismic shear</p> <p>125 lbs. Per foot for seismic shear</p>
<p>Existing footings, wood framing, structural steel and reinforced steel</p> <p style="margin-left: 20px;">3.1 Plain concrete footings</p> <p style="margin-left: 20px;">3.2 Douglas fir wood</p> <p style="margin-left: 20px;">3.2 Reinforcing steel</p> <p style="margin-left: 20px;">3.4 Structural steel</p>	<p>$f'_c = 1,500$ psi (10.34 MPa) unless otherwise shown by tests⁴</p> <p>Allowable stress same as D.F. No. 1⁴</p> <p>$f_t = 18,000$ lbs. Per square inch (124.1 M/mm²) maximum</p> <p>$f_t = 200,00$ lbs. Per square inch (137.9 N/mm²) maximum⁴</p>

¹Material must be sound and in good condition.

²A one-third increase in allowable stress is not allowed.

³Shear values of these materials may be combined, except the total combined value shall not exceed 300 pounds per foot (4380 N/m).

⁴Stresses given may be increased for combinations of loads as specified in the regular code.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

Table 8-8B
ALLOWABLE VALUES OF NEW MATERIALS USED IN CONNECTION WITH EXISTING CONSTRUCTION

NEW MATERIALS OR CONFIGURATIONS OF MATERIALS	ALLOWABLE VALUES ¹
<p>1. Horizontal diaphragms²</p> <p>Plywood sheathing nailed directly over existing straight sheathing with ends of plywood sheets bearing on joists or rafters and edges of plywood located on center of individual sheathing boards</p> <p>Plywood sheathing nailed directly over existing diagonal sheathing with ends of plywood sheets bearing on joists or rafters</p> <p>1.3 Plywood sheathing nailed directly over existing straight or diagonal sheathing with ends of plywood sheets bearing on joists or rafters with edges of plywood located over new blocking and nailed to provide a minimum nail penetration into framing and blocking of 1-inch (41 mm)</p>	<p>225 lbs. Per foot (3283 N/m)</p> <p>375 lbs. Per foot (5473 N/m)</p> <p>75 percent of the values specified in the regular code</p>
<p>Shear walls: (general procedure)</p> <p>Plywood sheathing applied directly over wood studs. No value shall be given to plywood applied over existing plaster or wood sheathing</p>	<p>100 percent of the value specified in the regular code for shear walls</p>
<p>3. Crosswalls: (special procedure only)</p> <p>Plywood sheathing applied directly over wood studs. No value shall be given to plywood applied over existing plaster or wood sheathing</p> <p>Drywall or plaster applied directly over wood studs</p> <p>Drywall or plaster applied to sheathing over existing wood studs</p>	<p>133 percent of the value specified in the regular code for shear walls</p> <p>100 percent of the values in the regular code</p> <p>The values specified in the regular code reduced as noted.³ (UBC Table 25-I, Footnote 1)</p>
<p>4. Tension bolts</p> <p>Bolts extending entirely through unreinforced masonry walls secured with bearing plates on far side of a three-wythe-minimum wall with at least 30 square inches (19 350 mm²) of area^{4,5}</p> <p>Bolts extending to the exterior face of the wall with a 2½-inch (63.5 mm) round plate under the head and drilled at an angle of 22½ degrees to the horizontal, installed as specified for shear bolts^{4,5,7}</p>	<p>1,800 lbs. (8006 N) per bolt⁶</p> <p>900 lbs. (4003 N) per bolt for two-wythe walls⁶</p> <p>1,200 lbs. (5338 N) per bolt</p>
<p>5. Shear bolts</p> <p>Bolts embedded a minimum of 8 inches (203 mm) into unreinforced masonry walls and centered in a 2½-inch diameter (63.5 mm) hole filled with dry-pack or nonshrink grout. Through bolts with first 8 inches (203 mm) as noted above and embedded bolts as noted in Item^{4,25,7}</p>	<p>½ inch (12.7 mm) diameter = 350 lbs. (1557 N)⁶</p> <p>5/8 inch (15.9 mm) diameter = 500 lbs. (2224 N)⁶</p> <p>¾ inch (19 mm) diameter = 750 lbs. (3336 N)⁶</p>
<p>6. Infilled walls</p> <p>Reinforced masonry infilled openings in existing unreinforced masonry walls. Provide keys or dowels to match reinforcing</p>	<p>Same as values specified for unreinforced masonry walls</p>
<p>7. Reinforced masonry</p> <p>Masonry piers and walls reinforced per the regular code</p>	<p>Same as values specified in the regular code</p>

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

<p>8. Reinforced concrete</p> <p>Concrete footings, walls and piers reinforced as specified in the regular code and designed for tributary loads</p>	<p>Same values as specified in the regular code⁸</p>
--	---

¹A one-third increase in allowable stress is not allowed, except as noted.

²Values and limitations are for nailed plywood. Higher values may be used for other fastening systems such as wood screws or staples when approved by the enforcing authority.

³In addition to existing sheathing value.

⁴Bolts to be ½-inch (12.7 mm) minimum diameter.

⁵Drilling for bolts and dowels shall be done with an electric rotary drill. Impact tools shall not be used for drilling holes or tightening anchors and shear bolt nuts.

⁶Other bolt sizes, values and installation methods may be used provided a testing program is conducted in accordance with regular code standards. Bolt spacing shall not exceed 6 feet. (1830 mm) on center and shall not be less than 12 inches (305 mm) on center.

⁷Embedded bolts to be tested as specified in regular code standards.

⁸Stresses given may be increased for combinations of loads as specified in the regular code

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

CHAPTER 8-9 MECHANICAL, PLUMBING AND ELECTRICAL REQUIREMENTS

SECTION 8-901 PURPOSE, INTENT AND SCOPE

8-901.1 Purpose. The purpose of the CHBC is to provide regulations for the mechanical, plumbing and electrical systems of buildings designated as qualified historical buildings or properties. The CHBC requires enforcing agencies to accept any reasonable equivalent solutions to regular code when dealing with qualified historical buildings or properties.

8-901.2 Intent. The intent of the CHBC is to preserve the integrity of qualified historical buildings or properties while providing a reasonable level of protection from fire, health, and life-safety hazards (hereinafter referred to as safety hazards) for the building occupants.

8-901.3 Scope. The CHBC shall be applied in conjunction with the regular code whenever compliance with the regular code is required for qualified historical buildings or properties.

8-901.4 Safety hazard. No person shall permit any safety hazard to exist on premises under their control, or fail to take immediate action to abate such hazard. Existing systems which constitute a safety hazard when operational may remain in place provided they are completely and permanently rendered inoperative. Safety hazards created by inoperative systems shall not be permitted to exist. Requirements of the regular code concerning general regulations shall be complied with, except that the enforcing agency shall accept solutions which do not cause a safety hazard.

8-901.5 Energy conservation. Qualified historical buildings or properties covered by this part are exempted from compliance with energy conservation standards. When new nonhistorical lighting and space conditioning system components, devices, appliances and equipment are installed, they shall comply with the requirements of Title 24 Part 6, *The California Energy Code*, except where the historical significance or character-defining features are threatened.

SECTION 8-902 MECHANICAL

8-902.1 General. Mechanical systems shall comply with the regular code unless otherwise modified by this chapter.

8-902.1.1 The provisions of the CHBC shall apply to the acceptance, location, installation, alteration, repair, relocation, replacement or addition of any heating, ventilating, air conditioning, domestic incinerators, kilns or miscellaneous heat-producing appliances or equipment within or attached to a historical building.

8-902.1.2 Existing systems which do not, in the opinion of the enforcing agency, constitute a safety hazard may remain in use.

8-902.1.3 The enforcing agency may approve any alternative to the CHBC which would achieve equivalent life safety.

8-902.2 Heating facilities. All dwelling-type occupancies covered under this chapter shall be provided with heating facilities. Wood-burning or pellet stoves or fireplaces may be acceptable as heating facilities.

8-902.3 Fuel oil piping and tanks. Fuel oil piping and tanks shall comply with regular code requirements except that the enforcing agency may waive such requirements where the lack of compliance does not create a safety or environmental hazard.

8-902.4 Heat-producing and cooling equipment. Heat-producing and cooling equipment shall comply with regular code requirements, governing equipment safety, except that the enforcing agency may accept alternatives which do not create a safety hazard.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-902.5 Combustion air.

8-902.5.1 All fuel-burning appliances and equipment shall be provided a sufficient supply of air for proper fuel combustion, ventilation, and draft hood dilution.

8-902.5.2 The enforcing agency may require operational tests for combustion air systems which do not comply with applicable requirements of the regular code.

8-902.6 Venting of appliances.

8-902.6.1 Every appliance required to be vented shall be connected to an approved venting system. Venting systems shall develop a positive flow adequate to convey all combustion products to the outside atmosphere.

8-902.6.2 Masonry chimneys in structurally sound condition may remain in use for all fuel-burning appliances provided the flue is evaluated and documentation provided that the masonry and grout are in good condition. Terra cotta chimneys and Type C metallic vents installed in concealed spaces shall not remain in use unless otherwise mitigated and approved on a case-by-case basis.

8-902.6.3 The enforcing agency may require operational tests for venting systems which do not comply with applicable requirements of the regular code.

8-902.7 Ducts.

8-902.7.1 New ducts shall be constructed and installed in accordance with applicable requirements of the regular code.

8-902.7.2 Existing duct systems which do not comply with applicable requirements of the regular code and do not, in the opinion of the enforcing agency, constitute a safety or health hazard may remain in use.

8-902.8 Ventilating systems.

8-902.8.1 Ventilating systems shall be installed so that no safety hazard is created.

8-902.8.2 Grease hoods and grease hood exhaust systems shall be furnished and installed in accordance with applicable requirements of the regular code. Existing systems which are altered shall comply with the regular code.

8-902.9 Miscellaneous equipment requirements.

8-902.9.1 The following appliances and equipment shall be installed so that no safety hazard is created: warm air furnaces, space heating equipment, vented decorative appliances, floor furnaces, vented wall furnaces, unit heaters, room heaters, absorption units, refrigeration equipment, duct furnaces, infrared radiant heaters, domestic incinerators, miscellaneous heat-producing appliances and water heaters.

8-902.9.2 Storage-type water heaters shall be equipped with a temperature-and pressure-relief valve in accordance with applicable requirements of the regular code.

SECTION 8-903 PLUMBING

8-903.1 General. Plumbing systems shall comply with the regular code unless otherwise noted.

8-903.1.1 The provisions of the CHBC shall apply to the acceptance, location, installation, alteration, repair, relocation, replacement or addition of any plumbing system or equipment within or attached to a historical building.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-903.1.2 Existing systems which do not, in the opinion of the enforcing agency, constitute a safety hazard may remain in use.

8-903.1.3 The enforcing agency may approve any alternative to these regulations which achieves equivalent life safety.

8-903.2 Residential occupancies.

8-903.2.1 Where toilet facilities are provided, alternative sewage disposal methods may be acceptable if approved by the local health department. In hotels, where private facilities are not provided, water closets at the ratio of one for each 15 rooms may be acceptable.

8-903.2.2 Toilet facilities are not required to be on the same floor or in the same building as sleeping rooms. Water-flush toilets may be located in a building immediately adjacent to the sleeping rooms. When alternative Sewage disposal methods are utilized, they shall be located a minimum distance from the sleeping rooms or other locations as approved by the local health department.

8-903.2.3 Kitchen sinks shall be provided in all kitchens. The sink and counter top may be of any smooth non-absorbent finish which can be maintained in a sanitary condition.

8-903.2.4 Hand washing facilities shall be provided for each dwelling unit and each hotel guest room. A basin and pitcher may be acceptable as adequate hand washing facilities.

8-903.2.5 Hot or cold running water is not required for each plumbing fixture, provided a sufficient amount of water is supplied to permit the fixture's normal operation.

8-903.2.6 Bathtubs and lavatories with filler spouts less than 1-inch (25.4mm) above the fixture rim may remain in use provided there is an acceptable overflow below the rim.

8-903.2.7 Original or salvage water closets, urinals and flushometer valves shall be permitted in qualified historical buildings or properties. Historically accurate reproduction, nonlow-consumption water closets, urinals, and flushometer valves, shall be permitted except where historically accurate fixtures that comply with the regular code are available.

8-903.3 Materials. New nonhistorical materials shall comply with the regular code requirements. The enforcing agency shall accept alternative materials which do not create a safety hazard where their use is necessary to maintain the historical integrity of the building.

8-903.4 Drainage and vent systems. Plumbing fixtures shall be connected to an adequate drainage and vent system. The enforcing agency may require operational tests for drainage and vent systems which do not comply with applicable requirements of the regular code. Vent terminations may be installed in any location which, in the opinion of the enforcing agency, does not create a safety hazard.

8-903.5 Indirect and special wastes. Indirect and special waste systems shall be installed so that no safety hazard is created. Chemical or industrial liquid wastes which may detrimentally affect the sanitary sewer system shall be pretreated to render them safe prior to discharge.

8-903.6 Traps and interceptors. Traps and interceptors shall comply with the regular code requirements except that the enforcing agency shall accept solutions which do not increase the safety hazard. Properly maintained "S" and drum traps may remain in use.

8-903.7 Joints and connections.

8-903.7.1 Joints and connections in new plumbing systems shall comply with applicable requirements of the regular code.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-903.7.2 Joints and connections in existing or restored systems may be of any type that does not create a safety hazard.

8-903.8 Water distribution. Plumbing fixtures shall be connected to an adequate water distribution system. The enforcing agency may require operational tests for water distribution systems which do not comply with applicable requirements of regular code. Prohibited (unlawful) connections and cross connections shall not be permitted.

8-903.9 Building sewers and private sewage disposal systems. New building sewers and new private sewage disposal systems shall comply with applicable requirements of the regular code.

8-903.10 Fuel-gas piping. Fuel-gas piping shall comply with the regular code requirements except that the enforcing agency shall accept solutions which do not increase the safety hazard.

SECTION 8-904 ELECTRICAL

8-904.1 General. Electrical systems shall comply with the regular code unless otherwise permitted by this code, or approved by the authority having jurisdiction.

8-904.1.1 The provisions of the CHBC shall apply to the acceptance, location, installation, alteration, repair, relocation, replacement or addition of any electrical system or portion thereof, the premise wiring, or equipment fixed in place as related to restoration within or attached to a qualified historical building or property.

8-904.1.2 Existing systems, wiring methods and electrical equipment which do not, in the opinion of the enforcing agency, constitute a safety hazard may remain in use.

8-904.1.3 The enforcing agency may approve any alternative to the CHBC which achieves equivalent safety.

8-904.1.4 Archaic methods that do not appear in present codes may remain and may be extended if, in the opinion of the enforcing agency, they constitute a safe installation.

8-904.2 Wiring methods.

8-904.2.1 Where existing branch circuits do not include an equipment grounding conductor and, in the opinion of the enforcing agency, it is impracticable to connect an equipment grounding conductor to the grounding electrode system, receptacle convenience outlets may remain the nongrounding type.

8-904.2.2 Ground fault circuit interrupter (GFCI) protected receptacles shall be installed where replacements are made at receptacle outlets that are required to be so protected by the regular code in effect at the time of replacement. Metallic face plates shall either be grounded to the grounded metal outlet box or be grounded to the grounding-type device when used with devices supplied by branch circuits without equipment grounding conductors.

8-904.2.3 Grounding-type receptacles shall not be used without a grounding means in an existing receptacle outlet unless GFCI protected. Existing nongrounding receptacles shall be permitted to be replaced with nongrounding or grounding-type receptacles where supplied through a ground fault circuit interrupter.

8-904.2.4 Extensions of existing branch circuits without equipment grounding conductors shall be permitted to supply grounding-type devices only when the equipment grounding conductor of the new extension is grounded to any accessible point on the grounding electrode system.

8-904.2.5 Receptacle outlet spacing and other related distance requirements shall be waived or modified if determined to be impractical by the enforcing agency.

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

8-904.2.6 For the replacement of lighting fixtures on an existing non-grounded lighting outlet, or when extending an existing non-grounding lighting outlet, the following shall apply:

1. The exposed conductive parts of lighting fixtures shall be connected to any acceptable point on the grounding electrode system, or
2. The lighting fixtures shall be made of insulating material and shall have no exposed conductive parts.

Exception: Lighting fixtures mounted on electrically non-conductive ceilings or walls where located not less than either 8 feet (2438mm) vertically or five 5 feet (1524mm) horizontally from grounded surfaces.

8-904.2.7 Lighting load calculations for services and feeders may be based on actual loads as installed in lieu of the "watts per square foot" method.

8-904.2.8 Determination of existing loads may be based on maximum demand recordings in lieu of calculations provided all of the following are met:

1. Recordings are provided by the serving agency.
2. The maximum demand data is available for a one-year period.

Exception: If maximum demand data for one-year period is not available, the maximum demand data shall be permitted to be based on the actual amperes continuously recorded over a minimum 30-day period by a recording ammeter connected to the highest loaded phase of the feeder or service. The recording should reflect the maximum demand when the building or space is occupied and include the measured or calculated load at the peak time of the year, including the larger of the heating or cooling equipment load.

3. There has been no change in occupancy or character of load during the previous 12 months.
4. The anticipated load will not change, or the existing demand load at 125 percent plus the new load does not exceed the ampacity of the feeder or rating of the service.

CHAPTER 8-10
QUALIFIED HISTORICAL DISTRICTS, SITES AND OPEN SPACES

SECTION 8-1001
PURPOSE AND SCOPE

8-1001.1. Purpose. The purpose of this chapter is to provide regulations for the preservation, rehabilitation, restoration and reconstruction of associated qualified historical features of qualified historical buildings, properties or districts (as defined in Chapter 8-2), and for which Chapters 8-3 through 8-9 of the CHBC may not apply.

8-1001.2. Scope. This Chapter applies to the associated qualified historical features of qualified historical buildings or properties and such as historic districts that are beyond the buildings themselves which include, but are not limited to natural features and designed site and landscape plans with natural and man-made landscape elements that support their function and aesthetics. This may include, but will not be limited to:

1. Site plan layout configurations and relationships (pedestrian, equestrian and vehicular site circulation, topographical grades and drainage, and use areas).
2. Landscape elements (plant materials, site properties, structures other than the qualified historical buildings, bridges and their associated properties ,structures, lighting, water features, art ornamentation, and pedestrian, equestrian and vehicular surfaces).
3. Functional elements (utility placement, erosion control and environmental mitigation measures).

SECTION 8-1002
APPLICATION

8-1002.1 The CHBC shall apply to all sites and districts and their features associated with qualified historical buildings or qualified historical districts as outlined in 8-1001.2 Scope.

8-1002.2 Where the application of regular code may impact the associated features of qualified historical properties beyond their footprints, by work performed secondarily, those impacts shall also be covered by the CHBC.

8-1002.3 This Chapter shall be applied for all issues regarding code compliance or other standard or regulation as they affect the purpose of this Chapter.

8-1002.4 The application of any code or building standard shall not un-duly restrict the use of a qualified historical building or property that is otherwise permitted pursuant to Chapter 8-3 and the intent of the *State Historical Building Code*, Section 18956.

SECTION 8-1003
SITE RELATIONSHIPS

The relationship between a building or property structure and its site, or the associated features of a district (including qualified historical landscape), site, objects and their features are critical components that may be one of the criteria for these buildings and properties to be qualified under the CHBC. The CHBC recognizes the importance of these relationships. This Chapter shall be used to provide context sensitive solutions for treatment of qualified historical buildings, properties, district or their associated qualified historical features, or when work to be performed secondarily impacts the associated qualified historical features of a qualified historical building or property.

APPENDIX A

CHAPTER 8-1

When modification must be made to qualified historical buildings or properties, the CHBC is intended to work in conjunction with the United States Secretary of Interior Standards for the Treatment of Historic Properties with Guidelines for Preserving, Rehabilitating, Restoring and Reconstructing Historic Buildings and the Secretary of Interior’s Standards Guidelines for the Treatment of Historic Properties with Guidelines for the Treatment of Cultural Landscapes.

CHAPTER 8-6

TABLE 1 -- PROVISION APPLICABILITY

	Title II Public Entities	Title III Private Entities	Title III Barrier Removal
<p>SECTION 8-601 PURPOSE, INTENT, SCOPE</p> <p>8-601.1 Purpose. The purpose of the CHBC is to provide alternative regulations to facilitate access and use by people with disabilities to and throughout facilities designated as qualified historical buildings or properties. These regulations require enforcing agencies to accept alternatives to regular code when dealing with qualified historical buildings or properties.</p> <p>8-602.2 Intent The intent of this chapter to preserve the integrity of qualified historical buildings and properties while providing access to and use by people with disabilities.</p> <p>8-601.3 Scope. The CHBC shall apply to every qualified historical building or property that is required to provide access to people with disabilities.</p> <ol style="list-style-type: none"> Provisions of this chapter do not apply to new construction or reconstruction/replicas of historical buildings. Where provisions of this chapter apply to alteration of qualified historical buildings or properties, alteration is defined in <i>California Building Code</i> (CBC), Chapter 2, Definitions and Abbreviations. 202 – A. Alter or Alteration. <p>8-601.4 General application. The provisions in the CHBC apply to local, state and federal governments (Title II entities); alteration of commercial facilities and places of public accommodation (Title III entities); and barrier removal in commercial facilities and places of public accommodation (Title III entities). Except as noted in this chapter.</p>	Applies	Applies	Applies
<p>SECTION 8-602 — BASIC PROVISIONS</p> <p>8-602.1 Regular code. The regular code for access for people with disabilities (Title 24, Part 2, Vol.1, Chapter 11B) shall be applied to qualified historical buildings or properties unless strict compliance with the regular code will threaten or destroy the historical significance or character-defining features of the building or property.</p>	Applies	Applies	Applies
<p>8-602.2 Alternative provisions. If the historical significance or character-defining features are threatened, alternative provisions for access may be applied pursuant to this chapter provided the following conditions are met:</p> <ol style="list-style-type: none"> These provisions shall be applied only on an item-by-item or case-by-case basis. Documentation is provided, including meeting minutes or letters, stating the reasons for the application of the alternative provisions. Such documentation shall be retained in the permanent file of the enforcing agency. 			

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

TABLE 1 -- PROVISION APPLICABILITY -- continued

	Title II Public Entities	Title III Private Entities	Title III Barrier Removal
SECTION 8-603 — ALTERNATIVES	Applies	Applies	Applies
<p>8-603.1 Alternative minimum standards. The alternative minimum standards for alterations of qualified historical buildings or facilities are contained in Section 4.1.7(3) of ADA Standards for Accessible Design, as incorporated and set forth in federal regulation 28 C.F.R Pt. 36.</p>	Applies	Applies	Applies
<p>8-603.2 Entry. These alternatives do not allow exceptions for the requirement of level landings in front of doors, except as provided in Section 8-603.4.</p> <ol style="list-style-type: none"> 1. Access to any entrance used by the general public and no further than 200 feet (60 960 mm) from the primary entrance. 2. Access at any entrance not used by general public but open and unlocked with directional signs at the primary entrance and as close as possible to, but no further than 200 feet (60 960 mm) from, the primary entrance. 3. The accessible entrance shall have a notification system. Where security is a problem, remote monitoring may be used. 	Applies	Applies	Applies
<p>6.603.3 Doors. Alternatives listed in order of priority are:</p> <ol style="list-style-type: none"> 1. Single-leaf door which provides a minimum 30 inches (762 mm) of clear opening. 2. Single-leaf door which provides a minimum 29½ inches (749mm) clear opening 3. Double door, one leaf of which provides a minimum 29½ inches (749mm) clear opening. 4. Double doors operable with a power-assist device to provide a minimum 29½ inches (749mm) clear opening when both doors are in the open position. 	Does not apply	Does not apply	Applies
<p>8-603.4 Power-assisted doors. Power-assisted door or doors may be considered an equivalent alternative to level landings, strikeside clearance and door-opening forces required by regular code.</p>	Applies	Applies	Applies
<p>8-603.5 Toilet rooms. In lieu of separate-gender toilet facilities as required in the regular code, an accessible unisex toilet may be designated.</p>	Applies	Applies	Applies

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

TABLE 1 -- PROVISION APPLICABILITY -- continued

	Title II Public Entities	Title III Private Entities	Title III Barrier Removal
<p>8-603.6 Exterior and interior ramps and lifts. Alternatives listed in order of priority are:</p> <ol style="list-style-type: none"> 1. A lift or a ramp of greater than standard slope but no greater than 1:10, for horizontal distances not to exceed 5 feet (1525 mm). Signs shall be posted at upper and lower levels to indicate steepness of the slope. 2. Access by ramps of 1:6 slope for horizontal distance not to exceed 13 inches (330 mm). Signs shall be posted at upper and lower levels to indicate steepness of the slope. 	Applies	Applies	Applies
<p style="text-align: center;">SECTION 8-604 — EQUIVALENT FACILITATION</p> <p>Use of other designs and technologies, or deviation from particular technical and scoping requirements, are permitted if the application of the alternative provisions contained in Section 8-603 would threaten or destroy the qualified historical significance or character-defining features of the historical building or property.</p> <ol style="list-style-type: none"> 1. Such alternatives shall be applied only on an item-by-item or case-by-case basis. 2. Access provided by experiences, services, functions, materials and resources through methods including, but not limited to, maps, plans, videos, virtual reality, and related equipment, at accessible levels. The alternative design and/or technologies used will provide substantially equivalent or greater accessibility to, and usability of, the facility. 3. The official charged with the enforcement of the standards shall document the reasons for the application of the design and/or technologies and their effect on the historical significance or character-defining features. Such documentation shall be in accordance with Section 8-602.2, Item 2, and shall include the opinion and comments of state or local accessibility officials, and the opinion and comments of representative local groups of people with disabilities. Such documentation shall be retained in the permanent file of the enforcing agency. Copies of the required documentation should be available at the facility upon request. <p>Note: For commercial facilities and places of public accommodation (Title III entities).</p> <p>Equivalent facilitation for an element of a building or property when applied as a waiver of an ADA accessibility requirement will not be entitled to the Federal Department of Justice certification of this code as rebuttable evidence of compliance for that element.</p>		<p style="text-align: center;">Waivers</p> <p>If a builder applies for a waiver of an ADA accessibility requirement for an element of a building, he or she will not be entitled to certification's rebuttable evidence of compliance for that element. This limitation on the certification determination should be noted in any publication of Chapter 8-6 if certification is granted.</p>	Applies

Notes: The regular code for Chapter 8-6 is contained in Title 24, Part 2, Vol.1, Chapter 11, which contain standards for new construction. Provisions of this chapter may be used in conjunction with all other provisions of the regular code and ADA regulations.

HISTORY NOTE APPENDIX

Historical Regulations for the Division of the State Architect, Access Compliance (Title 24, Part 8, California Code of Regulations)

For prior history, see History Note Appendix to the California Historical Building Code, 2001 Triennial Edition, effective November 1, 2002.

1. The 2007 Triennial Edition of the *California Historical Building Code*, was approved by the California Building Standards Commission on January 29, 2007. The California Building Standards Commission established January 1, 2008, as the effective date.
2. Editorial correction to Chapter 8-8, Section 8-812, Tables 8-8A and 8-8B. Include missing tales in 2007 annual code adoption supplement.

2010 CALIFORNIA REFERENCED STANDARDS CODE

California Code of Regulations - Title 24, Part 12

Effective Date: January 1, 2011

Chapters 12-11A and 12-11B

BUILDING AND FACILITY ACCESS SPECIFICATIONS

Detectable warning products and directional surfaces installed after January 1, 2001, shall be evaluated by an independent entity, selected by the Department of General Services, Division of the State Architect-Access Compliance for all occupancies, including transportation and other outdoor environments, except that when products and surfaces are for use in residential housing evaluation shall be in consultation with the Department of Housing and Community Development. See Government Code Section 4460.

DETECTABLE WARNINGS

Sections 12-11A.201 and 12-11B.201

“Nominal” means that pre-manufactured detectable warnings or devices used to create the detectable warning in place shall comply with required dimensions within ± 0.020 -inch for dome height, top diameter and bottom diameter and 0.050-inch for dome spacing.

PRODUCT APPROVAL FOR DETECTABLE WARNING PRODUCTS AND DIRECTIONAL SURFACES

SCOPE

Sections 12-11A.202 and 12-11B.202

These requirements and test methods apply to detectable warning products and directional surfaces.

DETECTABLE WARNING PRODUCTS

Sections 12-11A.203 and 12-11B.203

Must comply with the California Code of Regulations, Title 24.

DIRECTIONAL SURFACES

Sections 12-11A.204 and 12-11B.204

Must comply with the California Code of Regulations, Title 24.

INDEPENDENT ENTITY

Sections 12-11A.205 and 12-11B.205

Evaluation by an independent entity to confirm the prescriptive and performance standard of detectable warning products or directional surfaces installed after January 1, 2001. An independent entity is a not-for-profit product safety testing and certification organization, dedicated to testing for public safety. An independent entity would operate for the testing, certification and quality assessment of products, systems and services.

TWO-YEAR APPROVAL

Sections 12-11A.206 and 12-11B.206

Detectable warning products and directional surfaces are to be recertified every two years without exception or waiver.

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL

FEE

Sections 12-11A.207 and 12-11B.207

The Division of the State Architect Access Compliance may impose a fee on manufacturer's of the specified products, to cover the cost of detectable warning products and directional surfaces.

DISABILITY ACCESS ACCOUNT

Sections 12-11A.208 and 12-11B.208

The fees received from manufacturers will be placed in the Disability Access Account.

DETECTABLE WARNING PRODUCTS AND DIRECTIONAL SURFACES

Sections 12-11A.209 and 12-11B.209

Detectable Warning Products and Directional Surfaces must ensure consistency and uniformity:

- a) Shape,
- b) Color fastness,
- c) Conformation,
- d) Sound-on-cane acoustic quality,
- e) Resilience, and
- f) Attachment will not degrade significantly for at least five years.

SIGNIFICANT DEGRADATION

Sections 12-11A.210 and 12-11B.210

Significant degradation means that the product maintains at least 90 percent of its approved design characteristics.

SELECTION OF INDEPENDENT ENTITY

Sections 12-11A.211 and 12-11B.211

The independent entity selected by the Division of the State Architect Access Compliance shall be recognized as having appropriate expertise in determining whether products comply with the California Code of Regulations, Title 24.

Authority: Government Code Sections 4450, 4460 and Health & Safety Code Section 18949.1.

Reference: Government Code Section 4460.

HISTORY NOTE APPENDIX

Referenced Standards for the Division of the State Architect, Access Compliance (Title 24, Part 12, California Code of Regulations)

For prior code history, see the History Note Appendix to the 2007 Triennial Edition of the California Referenced Standards Code (CRSC), effective January 1, 2008.

1. SFM 07-09 – Amendments to the 2010 *California Referenced Standards Code (CRSC)*, California Code of Regulations (CCR) Title 24, Part 12. Effective on January 1, 2011.


CHAPTER 11A FIGURES

TABLE OF CONTENTS

DIVISION VII – FIGURES

11A-1A	INTERNATIONAL ACCESSIBILITY SYMBOL
11A-1B	OVERHANGING OBSTRUCTION
11A-1C	WIDTH OF ACCESSIBLE ROUTE
11A-1D	WHEELCHAIR TURNING SPACE
11A-1E	MINIMUM CLEAR WIDTH FOR SINGLE WHEELCHAIR
11A-1F	MINIMUM CLEAR WIDTH FOR TWO WHEELCHAIRS
11A-1G	MINIMUM CLEAR FLOOR SPACE FOR WHEELCHAIRS
11A-1H	MINIMUM CLEAR FLOOR SPACE FOR WHEELCHAIRS
11A-1I	FORWARD REACH
11A-1J	SIDE REACH
11A-1K	MINIMUM CLEARANCES FOR SEATING AND TABLE
11A-1L	CORRIDOR OVER 200 FEET
11A-2A	DOUBLE PARKING STALLS
11A-2B	SINGLE PARKING STALLS
11A-2C	DIAGONAL PARKING STALLS
11A-3A	CURB DETAILS
11A-3B	CURB DETAIL
11A-3C	CURB DETAIL
11A-3D	CURB DETAIL
11A-3E	CURB DETAIL
11A-3F	CURB DETAIL
11A-3G	CURB DETAIL
11A-3H	CURB DETAIL
11A-3I	CURB DETAIL
11A-3J	CURB DETAIL
11A-3K	CURB DETAIL
11A-3L	CURB SECTIONS
11A-3M	RETURNED CURB STYLE
11A-3N	TRUNCATED DOMES
11A-3	(RESERVED)
11A-5A	RAMPS AND SIDEWALKS
11A-6A	WARNING STRIPING AND HANDRAIL EXTENSIONS
11A-6B	STAIR HANDRAILS
11A-6C	RAMP DIMENSIONS
11A-6D	RAMP LANDING AND DOORWAY
11A-6E	STAIR HANDRAILS
11A-7A	MINIMUM DIMENSIONS OF ELEVATOR CARS

11A-7B	ELEVATOR CONTROL PANEL
11A-7C	HOISTWAY AND ELEVATOR ENTRANCES
11A-7D	GRAPH OF TIMING EQUATION
11A-8A	FRONT APPROACHES – SWINGING DOORS
11A-8B	HINGE SIDE APPROACHES – SWINGING DOORS
11A-8C	LATCH SIDE APPROACHES – SWINGING DOORS
11A-8D	FRONT APPROACH – SLIDING DOORS AND FOLDING DOORS
11A-8E	SLIDE-SIDE APPROACH – SLIDING DOORS AND FOLDING DOORS
11A-8F	LATCH-SIDE APPROACH – SLIDING DOORS AND FOLDING DOORS
11A-8G	VESTIBULE
11A-8H	VESTIBULE
11A-8I	THRESHOLDS
11A-8J	PLATFORM AT SECONDARY EXTERIOR DOOR
11A-8K	RAMP AT SECONDARY EXTERIOR DOOR
11A-9A	MULTIPLE-ACCOMMODATION TOILET FACILITY
11A-9B	
11A-9C	GRAB BAR SECTION
11A-9D	KNEE CLEARANCE
11A-9E	CLEAR FLOOR SPACE AT BATHTUBS
11A-9F	GRAB BARS AT BATHTUBS
11A-9G	
11A-9H	ROLL-IN SHOWER
11A-9I	ROLL-IN SHOWER
11A-9J	OPEN SHOWER
11A-9K	ALTERNATIVE ROLL-IN
11A-9L	SHOWER WITH WATER CLOSET
11A-9M	WING WALL OR CABINET AT WATER CLOSET
11A-10A	KITCHEN SPECIFICATIONS
11A-11A	WATER FOUNTAINS
11A-11B	MOUNTING HEIGHTS AND CLEARANCES FOR TELEPHONES
11A-11C	INTERNATIONAL TTY SYMBOL
11A-11D	VOLUME CONTROL TELEPHONES
11A-11E	INTERNATIONAL SYMBOL OF ACCESS FOR HEARING LOSS




(a) SYMBOL PROPORTIONS



(b) DISPLAY CONDITIONS


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-1A—INTERNATIONAL ACCESSIBILITY SYMBOL




THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11A-1B—OVERHANGING OBSTRUCTION




(a) 90° TURN



(d) TURNS AROUND AN OBSTRUCTION



(c) CHANGE IN LEVEL



(d) CHANGE IN LEVEL

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11A-1C—WIDTH OF ACCESSIBLE ROUTE




FIGURE 11A-1E—MINIMUM CLEAR WIDTH FOR SINGLE WHEELCHAIR






FIGURE 11A-1F—MINIMUM CLEAR WIDTH FOR TWO WHEELCHAIRS




(a) 60 INCHES DIAMETER SPACE




(b) T-SHAPED SPACE FOR 180° TURNS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11A-1D—WHEELCHAIR TURNING SPACE



PARALLEL APPROACH




CLEAR FLOOR SPACE




FORWARD APPROACH

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11A-1G—MINIMUM CLEAR FLOOR SPACE FOR WHEELCHAIRS



(a) CLEAR FLOOR SPACE IN ALCOVES




NOTE : IF X > 24 INCHES, THEN AN ADDITIONAL MANEUVERING CLEARANCE OF 6 INCHES SHALL BE PROVIDED AS SHOWN.

NOTE : IF X > 15 INCHES, THEN AN ADDITIONAL MANEUVERING CLEARANCE OF 12 INCHES SHALL BE PROVIDED AS SHOWN.


(b) ADDITIONAL MANEUVERING CLEARANCE FOR ALCOVES

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11A-1H—MINIMUM CLEAR FLOOR SPACE FOR WHEELCHAIRS



(a) HIGH FORWARD REACH LIMIT




NOTE :
 X SHALL BE LESS THAN OR EQUAL TO 25 INCHES Z SHALL BE GREATER THAN OR EQUAL TO X. WHEN X IS LESS THAN 20 INCHES, THEN Y SHALL BE 48 INCHES MAXIMUM. WHEN X IS 20 TO 25 INCHES, THEN Y SHALL BE 44 INCHES MAXIMUM.


(b) MAXIMUM FORWARD REACH OVER AN OBSTRUCTION

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION


FIGURE 11A-11—FORWARD REACH



(a) CLEAR FLOOR SPACE PARALLEL APPROACH




(b) HIGH AND LOW SIDE REACH LIMITS




(c) MAXIMUM SIDE REACH OVER OBSTRUCTION

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11A-1J—SIDE REACH




← ACCESSIBLE PATH OF TRAVEL →




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS, AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11A-1K—MINIMUM CLEARANCES FOR SEATING AND TABLE




MINIMUM CORRIDOR WIDTH



MINIMUM WIDTH FOR
CORRIDORS OVER 200




PASSING ALCOVES FOR CORRIDORS OVER
200' IN LIEU OF 60" MIN. WIDTH



THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS
OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID
FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-1L—CORRIDOR OVER 200 FEET (60 960 mm)



THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS, AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-2A—DOUBLE PARKING STALLS




FIGURE 11A-2B—SINGLE PARKING STALLS







FIGURE 11A-2C—DIAGONAL PARKING STALLS



SECTION A-A

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11A-3A—CURB DETAILS



SEE FIGURE 11B-19A

THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-3B—CURB DETAIL



SECTION B-B

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-3C—CURB DETAIL




FIGURE 11A-3D—CURB DETAIL




FIGURE 11A-3E—CURB DETAIL

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.




FIGURE 11A-3F—CURB DETAIL
SIDEWALK LESS THAN 60" WIDE




FIGURE 11A-3G—CURB DETAIL

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.




FIGURE 11A-3H—CURB DETAIL




FIGURE 11A-3I—CURB DETAIL

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.






FIGURE 11A-3J—CURB DETAIL




GROOVING DETAIL

FIGURE 11A-3K—CURB DETAIL

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.




SECTION A-A



SECTION B-B

DEPRESS ENTIRE SIDEWALK AS REQUIRED



SECTION C-C


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-3L—CURB SECTIONS


FIGURE 11A-3M - RETURNED CURB STYLE (See Figure 11B-21)

FIGURE 11A-3N - TRUNCATED DOMES (See Figure 11B-23A)

FIGURE 11A-3—(RESERVED)




(a) SIDEWALK OBSTRUCTIONS



(b) GUIDE RAIL

GUIDE RAIL DETAIL





(c) WHEEL GUIDE

WHEEL GUIDE DETAIL


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-5A—RAMPS AND SIDEWALKS




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-6A—WARNING STRIPING AND HANDRAIL EXTENSIONS




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-6B—STAIR HANDRAILS




(a) STRAIGHT RAMP RUN




(b) RAMP WITH TURNING PLATFORM

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-6C—RAMP DIMENSIONS




(a) RAMP WITH INTERMEDIATE SWITCH BACK PLATFORM



(b) RAMP LANDING AT DOORWAY


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-6D—RAMP LANDING AND DOORWAY




NOTE : INNER HANDRAIL AT LANDINGS OF STAIRS THAT DOUBLE BACK OR IMMEDIATELY TURN SHALL BE CONTINUOUS AND SHALL NOT EXTEND INTO LANDING OR PATH OF TRAVEL.

X : EXTENSION OF HANDRAIL SHALL BE EQUAL TO THE TREAD WIDTH PLUS 12 INCHES.




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-6E—STAIR HANDRAILS




(a) SIDE OPENING DOOR




(b) CENTER OPENING DOOR

THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11A-7A—MINIMUM DIMENSIONS OF ELEVATOR CARS




(a) ELEVATOR CONTROL PANEL DETAIL



(b) MAXIMUM INSTALLATION HEIGHTS ABOVE CAB FLOOR


THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-7B—ELEVATOR CONTROL PANEL



NOTE:
 THE AUTOMATIC DOOR REOPENING DEVICE IS ACTIVATED IF AN OBJECT PASSES THROUGH EITHER LINE A OR LINE B. LINE A AND LINE B REPRESENT THE VERTICAL LOCATION OF THE DOOR REOPENING DEVICE NOT REQUIRING CONTACT.

FIGURE 11A-7C—HOISTWAY AND ELEVATOR ENTRANCES



THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-7D—GRAPH OF TIMING EQUATION




FIGURE 11A-8A—FRONT APPROACHES - SWINGING DOORS




FIGURE 11A-8B—HINGE SIDE APPROACHES - SWINGING DOORS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

LEVEL MANEUVERING CLEARANCE AT DOORS




FIGURE 11A-8C—LATCH SIDE APPROACHES - SWINGING DOORS




FIGURE 11A-8D—FRONT APPROACH - SLIDING DOORS AND FOLDING DOORS




FIGURE 11A-8E—SLIDE-SIDE APPROACH - SLIDING DOORS AND FOLDING DOORS






FIGURE 11A-8F—LATCH-SIDE APPROACH - SLIDING DOORS AND FOLDING DOORS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

LEVEL MANEUVERING CLEARANCE AT DOORS (Continued)



(a) DOOR IN SERIES




(b) BOTH DOORS OPEN OUT


(SERVING OTHER THAN A REQUIRED EXIT STAIRWAY)

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-8G—VESTIBULE




(a) DOORS AT ADJACENT WALLS



(b) DOORS AT OPPOSITE WALLS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-8H—VESTIBULE
(SERVING OTHER THAN A REQUIRED EXIT STAIRWAY)



THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-8I—THRESHOLDS

*Platform of approved materials to raise
floor level of balcony.*

(Platform required for final inspection)




FIGURE 11A-8J – PLATFORM AT SECONDARY EXTERIOR DOOR






FIGURE 11A-8K – RAMP AT SECONDARY EXTERIOR DOOR




THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11A-9A—MULTIPLE-ACCOMMODATION TOILET FACILITY



SINGLE-ACCOMMODATION TOILET FACILITY




ACCESSIBLE WATER CLOSET COMPARTMENT
WITHIN A MULTIPLE-ACCOMMODATION TOILET FACILITY



SIDE ELEVATION

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION


FIGURE 11A-9B



SECTION THROUGH TYPICAL GRAB BAR


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11A-9C—GRAB BAR SECTION



SIDE ELEVATION


*Note: If a minimum 9 inches height of toe clearance is provided, a maximum of 6 inches of the 48 inches of clear floor space required at the fixture may extend into the toe space.



PLAN VIEW


THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-9D—KNEE CLEARANCE




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-9E—CLEAR FLOOR SPACE AT BATHTUBS



(a) WITH SEAT IN TUB




(b) WITH SEAT AT HEAD OF TUB

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-9F—GRAB BARS AT BATHTUBS




(a) WATER CLOSET IN ADAPTABLE BATHROOMS



NOTE: THE AREA OUTLINED IN DASHED LINES REPRESENT LOCATIONS FOR FUTURE INSTALLATION OF GRAB BARS FOR TYP. FIXTURE CONFIGURATIONS

(b) LOCATION OF GRAB BAR REINFORCEMENTS FOR ADAPTABLE BATHTUBS



NOTE: THE AREA OUTLINED IN DASHED LINES REPRESENT LOCATION FOR FUTURE INSTALLATION OF GRAB BARS

(a) LOCATION OF GRAB BAR REINFORCEMENTS FOR ADAPTABLE SHOWERS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-9G






FIGURE 11A-9H—ROLL-IN SHOWER




PERSPECTIVE OF ROLL-IN SHOWER—B
42" x 48" CALIFORNIA SIZE




ROLL-IN SHOWER—B
42" x 48" CALIFORNIA SIZE

FIGURE 11A-9I —ROLL-IN SHOWER




PLAN



ELEVATION

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11A-9J—OPEN SHOWER



THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11A-9K—ALTERNATIVE ROLL-IN




FIGURE 11A-9L – SHOWER WITH WATER CLOSET






FIGURE 11A-9M – WING WALL OR CABINET AT WATER CLOSET




TYPICAL KITCHEN



"U" SHAPED KITCHEN


- (1) 30-inch wide counter top space for sink installation with removable base cabinet and finish flooring beneath sink
- (2) 30-inch wide counter top workspace
- (3) 30-inch by 48-inch clear space adjacent to range or cooktop to allow parallel approach
- (4) 30-inch by 48-inch either parallel approach at oven, dishwasher, trash compactor or refrigerator

FIGURE 11A-10A—KITCHEN SPECIFICATIONS




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION


FIGURE 11A-11A—WATER FOUNTAINS



(a) SIDE REACH ARRANGEMENT



(b) FULL HEIGHT ENCLOSURE



(c) FORWARD REACH ARRANGEMENT

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11A-11B—MOUNTING HEIGHTS AND CLEARANCES FOR TELEPHONES



FIGURE 11A-11C— INTERNATIONAL TTY SYMBOL



FIGURE 11A-11D— VOLUME CONTROL TELEPHONES



FIGURE 11A-11E— INTERNATIONAL SYMBOL OF ACCESS FOR HEARING LOSS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


CHAPTER 11B FIGURES

TABLE OF CONTENTS


FIGURES 11B – 1A THROUGH 11B – 40D

11B-1A	
11B-1B	MULTIPLE ACCOMMODATION TOILET FACILITY
11B-1C	TYPICAL GRAB BAR SECTION
11B-1D	KNEE CLEARANCE
11B-1E	MULTIPLE-ACCOMMODATION TOILET FACILITY
11B-2A	SHOWER STALLS
11B-2B	SHOWER STALLS (Cont)
11B-2C	SHOWER STALLS (Cont)
11B-2D	SHOWER STALLS
11B-3A	DRINKING FOUNTAINS
11B-3B	DRINKING FOUNTAINS
11B-4	MOUNTING HEIGHTS AND CLEARANCES FOR TELEPHONES
11B-5A	MINIMUM CLEAR FLOOR SPACE FOR WHEELCHAIRS
11B-5B	DOOR WIDTH
11B-5C	FORWARD REACH
11B-5D	SIDE REACH
11B-5E	WIDTH OF ACCESSIBLE ROUTE
11B-5F	ATM REACH RANGE LIMITS
11B-6	INTERNATIONAL ACCESSIBILITY SYMBOL
11B-7A	PROTRUDING OBJECTS
11B-7B	OBJECTS MOUNTED ON POSTS OR PYLONS
11B-7C	OVERHANGING AND OVERHEAD HAZARDS
11B-7D	PROTECTION AROUND WALL-MOUNTED OBJECTS
11B-7E	
11B-8	CLEAR FLOOR SPACE AT BATHTUBS
11B-9	GRAB BARS AT BATHTUBS
11B-10	MINIMUM CLEAR WIDTH FOR SINGLE WHEELCHAIR
11B-11	MINIMUM CLEAR WIDTH FOR TWO WHEELCHAIRS
11B-12	WHEELCHAIR TURNING SPACE
11B-13	MINIMUM CLEARANCES FOR SEATING AND TABLE
11B-14A	INTERNATIONAL TTY SYMBOL
11B-14B	VOLUME CONTROL TELEPHONES
11B-14C	INTERNATIONAL SYMBOL OF ACCESS FOR HEARING LOSS
11B-15	SPACE REQUIREMENTS FOR WHEELCHAIR SEATING
11B-16	FOOD SERVICE LINES
11B-17	TABLEWARE AREAS


11B-18A	DOUBLE PARKING STALLS
11B-18B	SINGLE PARKING STALLS
11B-18C	DIAGONAL PARKING STALLS
11B-19A	CURB DETAILS
11B-19B	CURB DETAIL
11B-19C	CURB DETAIL
11B-20A	CURB DETAIL
11B-20B	CURB DETAIL
11B-20C	CURB DETAIL
11B-20D	CURB DETAIL
11B-20E	CURB SECTIONS
11B-21	RETURNED CURB STYLE
11B-22	CURB RAMPS AT MARKED CROSSING
11B-23A	TRUNCATED DOMES
11B-23B	DIRECTIONAL BARS
11B-24	ACCESS AISLE AT PASSENGER LOADING ZONES
11B-25	OBSTRUCTIONS
11B-26A	LEVEL MANEUVERING CLEARANCE AT DOORS (Continued)
11B-26B	LEVEL MANEUVERING CLEARANCE AT DOORS
11B-26C	LEVEL MANEUVERING CLEARANCE AT DOORS (Cont)
11B-27	RAMPS AND SIDEWALKS
11B-28	OVERHANGING OBSTRUCTION
11B-29	DOOR CONSTRUCTION
11B-30	VESTIBULE
11B-31	VESTIBULE
11B-32	THRESHOLDS
11B-33	CLEAR DOOR WIDTH AND DEPTH
11B-34	CORRIDOR OVER 200 FEET
11B-35	WARNING STRIPING AND HANDRAIL EXTENSIONS
11B-36	STAIR HANDRAILS
11B-37	STAIR HANDRAILS
11B-38	RAMP DIMENSIONS
11B-39	RAMP LANDING AND DOORWAY
11B-40	CLEANER AIR SYMBOL
11B-40A	MINIMUM DIMENSIONS OF ELEVATOR CARS
11B-40B	ELEVATOR CONTROL PANEL
11B-40C	HOISTWAY AND ELEVATOR ENTRANCES
11B-40D	GRAPH OF TIMING EQUATION




SINGLE-ACCOMMODATION TOILET FACILITY



ACCESSIBLE WATER CLOSET COMPARTMENT WITHIN A MULTIPLE-ACCOMMODATION TOILET FACILITY



SIDE WALL ELEVATION




REAR WALL ELEVATION

* REAR GRAB BAR ALLOWED AT 36" A.F.F. AT TANK-TYPE TOILET


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-1A




THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-1B—MULTIPLE-ACCOMMODATION TOILET FACILITY




THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-1C—TYPICAL GRAB BAR SECTION




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11B-1D—KNEE CLEARANCE




(a) CLEARANCES AT WATER CLOSET




**(b) CLEARANCES AT WATER CLOSET
IN COMPARTMENT WITH OUT-SWINGING
END-OPENING DOOR**



**(c) CLEARANCES AT WATER CLOSET
IN COMPARTMENT WITH IN-SWINGING
END-OPENING DOOR**




**(d) CLEARANCES AT WATER CLOSET
IN COMPARTMENT WITH OUT-SWINGING
SIDE-OPENING DOOR**




**(e) CLEARANCES AT WATER CLOSET
IN COMPARTMENT WITH IN-SWINGING
SIDE-OPENING DOOR**

**NOTE: SEE SECTION 1115B.3.1, ITEM 4.5 FOR COMPARTMENT
DOOR MANEUVERING SPACE REQUIREMENTS**

FIGURE 11B-1E - CLEARANCES AT WATER CLOSETS




(a) 60" MINIMUM X 30" MINIMUM ROLL-IN SHOWER




(b) ELEVATION - 60" MINIMUM X 30" MINIMUM ROLL-IN SHOWER

FIGURE 11B-2A - SHOWER STALLS



(a) 60" MINIMUM X 36" ALTERNATE ROLL-IN SHOWER



(b) ELEVATION - 60" MINIMUM X 36" ALTERNATE ROLL-IN SHOWER

FIGURE 11B-2B - SHOWER STALLS (CONT)







FIGURE 11B-2D - SHOWER SEAT



(b) NONALCOVE WING WALL INSTALLATION




(a) ALCOVE INSTALLATION




(c) NONALCOVE SOLID WING WALL INSTALLATION

FIGURE 11B-3A - DRINKING FOUNTAINS



* EQUIPMENT PERMITTED IN SHADED AREA

SPOUT HEIGHT AND KNEE CLEARANCE
AT DRINKING FOUNTAINS




CLEAR FLOOR SPACE
AT DRINKING FOUNTAIN ALCOVES

NOTES:


AT ALCOVES DEEPER THAN 24"
ADDITIONAL 6" MANEUVERING
CLEARANCE IS REQUIRED.
SEE CBC 1118B.4, ITEM 2.

AT "HI-LOW" TYPE FOUNTAINS,
CENTER THE 30" BY 48" CLEAR
FLOOR SPACE ON THE "LOW"
FOUNTAIN FIXTURE




CLEAR FLOOR SPACE
AT "HI-LOW" DRINKING FOUNTAIN ALCOVES

FIGURE 11B-3B - DRINKING FOUNTAINS




SIDE REACH POSSIBLE




FORWARD REACH REQUIRED

* HEIGHT TO HIGHEST OPERABLE PARTS WHICH ARE ESSENTIAL TO BASIC OPERATION OF TELEPHONE.

FIGURE 11B-4 - MOUNTING HEIGHTS AND CLEARANCES FOR TELEPHONES




(a) CLEAR FLOOR SPACE IN ALCOVES



NOTE: IF X > 24 INCHES, THEN AN ADDITIONAL MANEUVERING CLEARANCE OF 6 INCHES SHALL BE PROVIDED AS SHOWN.

NOTE: IF X > 15 INCHES, THEN AN ADDITIONAL MANEUVERING CLEARANCE OF 12 INCHES SHALL BE PROVIDED AS SHOWN.

(b) ADDITIONAL MANEUVERING CLEARANCE FOR ALCOVES




(c) CLEAR FLOOR SPACE

(d) FORWARD APPROACH

(e) PARALLEL APPROACH


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-5A—MINIMUM CLEAR FLOOR SPACE FOR WHEELCHAIRS




CLEAR OPENINGS MUST BE BETWEEN THE DOOR IN ITS 90° OPENING POSITION AND THE FACE OF THE STOP

(a) SINGLE DOOR



CLEAR OPENINGS FOR TWO LEAF DOORS MUST BE BETWEEN EITHER DOOR IN ITS 90° OPEN POSITION AND THE EDGE OF THE OTHER DOOR.

(b) DOUBLE DOOR




AN ADULT SIZE WHEELCHAIR AVERAGES 27 INCHES IN WIDTH. THE REQUIRED 32 INCH CLEAR OPENING ALLOWS 2 - 1/2 INCHES ON EACH SIDE FOR HANDS.


(c) PASSAGE CLEARANCE

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-5B—DOOR WIDTH



(a) HIGH FORWARD REACH LIMIT




NOTE :
 X SHALL BE LESS THAN OR EQUAL TO 25 INCHES Z SHALL BE GREATER THAN OR EQUAL TO X. WHEN X IS LESS THAN 20 INCHES, THEN Y SHALL BE 48 INCHES MAXIMUM. WHEN X IS 20 TO 25 INCHES, THEN Y SHALL BE 44 INCHES MAXIMUM.


(b) MAXIMUM FORWARD REACH OVER AN OBSTRUCTION

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION


FIGURE 11B-5C—FORWARD REACH




(a) CLEAR FLOOR SPACE PARALLEL APPROACH




(b) HIGH AND LOW SIDE REACH LIMITS



(c) MAXIMUM SIDE REACH OVER OBSTRUCTION




(d) SHELVES




(e) CLOSETS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION


FIGURE 11B-5D—SIDE REACH




(a) 90 ° TURN



(b) TURNS AROUND AN OBSTRUCTION




(c) CHANGE IN LEVEL



(d) CHANGE IN LEVEL

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-5E—WIDTH OF ACCESSIBLE ROUTE




(d) ATM REACH RANGE LIMITS

**CORRESPONDING REACH HEIGHTS
FOR GIVEN DEPTHS:**

WHEN D = 10"	OR LESS,	H = 54" MAX.
WHEN D = 11"	,	H = 53.5" MAX.
WHEN D = 12"	,	H = 53.0" MAX.
WHEN D = 13"	,	H = 52.5" MAX.
WHEN D = 14"	,	H = 51.5" MAX.
WHEN D = 15"	,	H = 51.0" MAX.
WHEN D = 16"	,	H = 50.5" MAX.
WHEN D = 17"	,	H = 50.0" MAX.
WHEN D = 18"	,	H = 49.5" MAX.
WHEN D = 19"	,	H = 49.0" MAX.
WHEN D = 20"	,	H = 48.5" MAX.
WHEN D = 21"	,	H = 47.5" MAX.
WHEN D = 22"	,	H = 47.0" MAX.
WHEN D = 23"	,	H = 46.5" MAX.
WHEN D = 24"	,	H = 46.0" MAX.

THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-5F—ATM REACH RANGE LIMITS




(a) SYMBOL PROPORTIONS




(b) DISPLAY CONDITIONS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-6—INTERNATIONAL ACCESSIBILITY SYMBOL




WALKING PARALLEL TO A WALL




WALKING PERPENDICULAR TO WALL

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-7A—PROTRUDING OBJECTS




PLAN




ELEVATION

FIGURE 11B-7B - OBJECTS MOUNTED ON POSTS OR PYLONS




FREE-STANDING OVERHANGING OBJECTS



OVERHEAD HAZARDS



FIGURE 11B-7C - OVERHANGING AND OVERHEAD HAZARDS




PLAN

EXAMPLE OF PROTECTION AROUND WALL-MOUNTED OBJECTS AND MEASUREMENTS OF CLEAR WIDTHS

FIGURE 11B-7D - PROTECTION AROUND WALL-MOUNTED OBJECTS




(a) GRATE ORIENTATION TO PATH OF TRAVEL




(b) CARPET PILE THICKNESS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11B-7E



(a) WITH SEAT IN TUB




(b) WITH SEAT IN TUB




(c) WITH SEAT AT HEAD OF TUB

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-8—CLEAR FLOOR SPACE AT BATHTUBS



(a) WITH SEAT IN TUB



(b) WITH SEAT AT HEAD OF TUB

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-9—GRAB BARS AT BATHTUBS




FIGURE 11B-10—MINIMUM CLEAR WIDTH FOR SINGLE WHEELCHAIR






FIGURE 11B-11—MINIMUM CLEAR WIDTH FOR TWO WHEELCHAIRS




(a) 60 INCHES DIAMETER SPACE



(b) T-SHAPED SPACE FOR 180° TURNS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-12—WHEELCHAIR TURNING SPACE



THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-13—MINIMUM CLEARANCES FOR SEATING AND TABLE




FIGURE 11B-14A— INTERNATIONAL TTY SYMBOL





FIGURE 11B-14B— VOLUME CONTROL TELEPHONES




FIGURE 11B-14C— INTERNATIONAL SYMBOL OF ACCESS FOR HEARING LOSS

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.



(a) FORWARD OR REAR ACCESS



(b) SIDE ACCESS

NOTE:
EACH INDIVIDUAL SEATING POSITION HAS AN
EGRESS ROUTE WHICH DOES NOT CROSS
THROUGH OTHER SEATING POSITIONS.

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS
OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID
FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-15—SPACE REQUIREMENTS FOR WHEELCHAIR SEATING






FIGURE 11B-16—FOOD SERVICE LINES



THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-17—TABLEWARE AREAS



THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-18A - DOUBLE PARKING STALLS







FIGURE 11B-18B - SINGLE PARKING STALLS



THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-18C - DIAGONAL PARKING STALLS




SECTION A-A

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-19A—CURB DETAILS


FOR DETECTABLE WARNING
REQUIREMENTS AT CURB RAMPS,
SEE SECTION 1127B.5, ITEM 7




SEE FIGURE 11B-19A

THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF
THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR
BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-19B—CURB DETAIL



CASE A




CASE B

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-20A—CURB DETAIL—CASES A AND B


FOR DETECTABLE WARNING
REQUIREMENTS AT CURB RAMP,
SEE SECTION 1127B.5, ITEM 7



CASE C

SIDEWALK LESS THAN 60" WIDE

FOR DETECTABLE WARNING
REQUIREMENTS AT CURB RAMP,
SEE SECTION 1127B.5, ITEM 7




CASE D

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS
OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID
FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-20B—CURB DETAIL—CASES C AND D


FOR DETECTABLE WARNING REQUIREMENTS AT CURB RAMPs, SEE SECTION 1127B.5, ITEM 7

SEE SEC. 1127B.5, ITEM 6



CASE E


FOR DETECTABLE WARNING REQUIREMENTS AT CURB RAMPs, SEE SECTION 1127B.5, ITEM 7




CASE F

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-20C—CURB DETAIL—CASES E AND F



CASE G




GROOVING DETAIL


CASE H

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11B-20D—CURB DETAIL—CASES G AND H




MEASUREMENT OF CURB RAMP SLOPES



SECTION A-A




SECTION B-B
DEPRESS ENTIRE SIDEWALK AS REQUIRED




SECTION C-C

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-20E—CURB SECTIONS




(a)



(b)


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-21—RETURNED CURB STYLE




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-22—CURB RAMPS AT MARKED CROSSING




(a) TRUNCATED DOME SPACING




(b) TRUNCATED DOME SECTION A-A

FIGURE 11B-23A - TRUNCATED DOMES




TYPICAL PLAN



TYPICAL SECTION A-A


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-23B—DIRECTIONAL BARS




THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-24—ACCESS AISLE AT PASSENGER LOADING ZONES



THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11B-25—OBSTRUCTIONS



* NOTE: ALL DOORS IN ALCOVES SHALL COMPLY WITH THE CLEARANCES FOR FRONT APPROACHES.

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-26A—LEVEL MANEUVERING CLEARANCE AT DOORS (Continued)




*
NOTE:
48" MINIMUM IF DOOR
HAS A CLOSER

(c) LATCH APPROACH


* NOTE: ALL DOORS IN ALCOVES SHALL COMPLY WITH THE CLEARANCES FOR FRONT APPROACHES.

THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11B-26B—LEVEL MANEUVERING CLEARANCE AT DOORS




(d) FRONT APPROACH
SLIDING DOORS




(g) FRONT APPROACH
FOLDING DOORS




(e) SLIDE SIDE APPROACH
SLIDING DOORS



(h) SLIDE SIDE APPROACH
FOLDING DOORS




(f) LATCH SIDE APPROACH
SLIDING DOORS




(i) LATCH SIDE APPROACH
FOLDING DOORS

NOTE: ALL DOORS IN ALCOVES SHALL COMPLY WITH THE CLEARANCES FOR FRONT APPROACHES.


FIGURE 11B-26C - LEVEL MANEUVERING CLEARANCE AT DOORS (CONT)




(a) SIDEWALK OBSTRUCTIONS




(b) HANDRAIL AND GUIDE RAIL



GUIDE RAIL DETAIL




(c) GUIDE CURB




GUIDE CURB DETAIL

FIGURE 11B-27 - RAMPS AND SIDEWALKS




THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-28—OVERHANGING OBSTRUCTION




THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-29—DOOR CONSTRUCTION



(a) DOOR IN SERIES




(b) BOTH DOORS OPEN OUT


(SERVING OTHER THAN A REQUIRED EXIT STAIRWAY)

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-30—VESTIBULE





(a) DOORS AT ADJACENT WALLS



(b) DOORS AT OPPOSITE WALLS


THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

**FIGURE 11B-31—VESTIBULE
(SERVING OTHER THAN A REQUIRED EXIT STAIRWAY)**




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11B-32—THRESHOLDS



(a) PULL SIDE (INTERIOR DOOR)




(b) SLIDING DOOR




(c) FOLDING DOOR

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11B-33—CLEAR DOOR WIDTH AND DEPTH




(a) MINIMUM CORRIDOR WIDTH



(b) MINIMUM WIDTH FOR
CORRIDORS OVER 200'





(c) PASSING ALCOVES FOR CORRIDORS OVER
200' IN LIEU OF 60" MIN. WIDTH




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-34—CORRIDOR OVER 200 FEET (60 960 mm)




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-35 - WARNING STRIPING AND HANDRAIL EXTENSIONS




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-36—STAIR HANDRAILS




NOTE: INNER HANDRAIL AT LANDINGS OF STAIRS THAT DOUBLE BACK OR IMMEDIATELY TURN SHALL BE CONTINUOUS AND SHALL NOT EXTEND INTO LANDING OR ACCESSIBLE ROUTE OF TRAVEL

X = EXTENSION OF HANDRAIL SHALL BE EQUAL TO THE TREAD WIDTH PLUS 12 INCHES MINIMUM




THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-37 - STAIR HANDRAILS




(a) STRAIGHT RAMP RUN




(b) RAMP WITH TURNING LANDING

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-38—RAMP DIMENSIONS



(a) RAMP WITH INTERMEDIATE SWITCH BACK LANDING



(b) RAMP LANDING AT DOORWAY

THESE DIAGRAMS ILLUSTRATE THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND ARE INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.


FIGURE 11B-39—RAMP LANDING AND DOORWAY



Cleaner Air


FIGURE 11B-40-CLEANER AIR SYMBOL

* ALTERNATE LOCATION
OF PANEL WITH SIDE-
OPENING DOOR



(a) SIDE OPENING DOOR



* ALTERNATE LOCATION
OF PANEL WITH CENTER-
OPENING DOOR



(b) CENTER OPENING DOOR


THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS
OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID
FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-40A—MINIMUM DIMENSIONS OF ELEVATOR CARS




THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION.

FIGURE 11B-40B—ELEVATOR CONTROL PANEL



NOTE:
 THE AUTOMATIC DOOR REOPENING DEVICE IS ACTIVATED IF AN OBJECT PASSES THROUGH EITHER LINE A OR LINE B. LINE A AND LINE B REPRESENT THE VERTICAL LOCATION OF THE DOOR REOPENING DEVICE NOT REQUIRING CONTACT.

FIGURE 11B-40C - HOISTWAY AND ELEVATOR ENTRANCES



THIS DIAGRAM ILLUSTRATES THE SPECIFIC REQUIREMENTS OF THESE REGULATIONS AND IS INTENDED ONLY AS AN AID FOR BUILDING DESIGN AND CONSTRUCTION

FIGURE 11B-40D - GRAPH OF TIMING EQUATION

CHAPTER 11C FIGURES

TABLE OF CONTENTS

FIGURES 11C-1 AND 11C-2

11C-1	CARD READER MOUNTED IN FUEL DISPENSERS
11C-2	CARD READERS LOCATED ON THE FREE-STANDING PEDESTALS




FIGURE 11C-1—CARD READERS MOUNTED IN FUEL DISPENSERS




FIGURE 11C-2—CARD READERS LOCATED ON FREE-STANDING PEDESTALS

DSA Access Compliance Policies

DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL POLICIES

Introduction

Section 3 – Policies: The policies indicated in this manual address those aspects of DSA’s plan and construction review program that are not clearly addressed by code. These policies are applicable to projects within the jurisdiction of DSA.

DSA Access Compliance Policy Index

Policies are numbered sequentially within the original year of issue. Example: "94-10" is the tenth policy issued in 1994. Missing numbers indicate policies that are not access-related.

Policy Number	Status/Title of Policy
94-01	Superseded by 96-01 Application of Existing Building Requirements in Seismic Upgrade of Unreinforced Masonry Buildings, Repair of Earthquake Damage, or Emergency Retrofit for Seismic Safety, Etc.
94-02	<i>Formally Deleted 2/10/96</i> Accessibility Requirements for Emergency Portable Classrooms at School Sites with Seismic Damage at El Camino Senior High School
94-03	<i>Formally Deleted 8/10/95</i> Accessibility Requirements for Emergency Portable Classrooms at School Sites with Seismic Damage
94-04	<i>Formally Deleted 10/01/98</i> Accessibility Requirements for Projection Booths or Rooms in Non-Teaching Accommodations
<u>94-05</u>	Revised 8/25/05 Accessibility at Exit-Only Doors
<u>94-10</u>	Revised 8/25/05 Resurfacing, Restriping, and Alterations of Parking Lots
94-13	<i>Formally Deleted 8/25/05</i> Accessibility Requirements for Seismic Safety Enhancement and Repair at School Sites with Damage
94-15	<i>Formally Deleted 4/01/98</i> Recommended Dimensions for Accessibility in Toilet Facilities for Children
94-16	<i>Formally Deleted 8/25/05</i> Portable Classrooms: Existing Handrails on Existing Relocated Portables
94-18	<i>Formally Deleted 8/25/05</i> Ramp Landing Clearances at Doors
<u>94-22</u>	Revised 8/25/05 Reconstruction After Fire Damage
95-01	<i>Superseded by DSA IR A-10 11/16/05</i> Public School Alteration Projects (Under \$20,000)

Policy Number	Status/Title of Policy
95-02	<i>Formally Deleted 8/25/05</i> Single Room Occupancy – Hotels
95-05	<i>Formally Deleted 8/25/05</i> Residential Elevators in Commercial Buildings
95-06	<i>Formally Deleted 8/25/05</i> Home Business Accessibility (DSA Jurisdictional Only)
95-07	<i>Formally Deleted 8/25/05</i> Seismic Upgrade in Hospitals
95-08	<i>Formally Deleted 8/25/05</i> Counters – Food Preparation Facilities
<u>95-09</u>	Revised 8/25/05 Accessible Seating at Fixed Counters
95-10	Superseded by 96-01 DSA Seismic Policy on Seismic Upgrade Projects
<u>96-01</u>	Revised 8/25/05 Seismic Upgrade Projects
96-04	<i>Formally Deleted 8/25/05</i> Elevator Call Button-Mounting Height
96-05	<i>Formally Deleted 3/31/00</i> Modernization Program
96-06	<i>Formally Deleted 8/25/05</i> Fire Repair Construction
96-08	<i>Formally Deleted 1/01/00</i> Equivalent Facilitation
96-09	<i>Formally Deleted 1/21/00</i> Alternate Methods
<u>96-10</u>	Revised 12/30/96 Handrails at Steps
<u>97-01</u>	Revised 8/25/05 Unisex Toilet Rooms

Policy Number	Status/Title of Policy
<u>97-02</u>	Revised 4/05/00 Permit Extensions
<u>97-03</u>	Revised 6/05/97 Interim Disabled Access Guidelines for Electrical Vehicle Charging Stations
97-04	<i>Formally Deleted 8/25/05</i> Engineered Wood Product at Playground Equipment
97-05	<i>Formally Deleted 8/25/05</i> Detectable Warning Domes at Curb Cuts Required by Federal Law to be Flushed at the Lip
<u>97-06</u>	Revised 4/05/00 Parking Ticket Dispensers
97-07	<i>Formally Deleted 8/25/05</i> Manufactured Ramps for Relocatable Buildings
97-11	<i>Formally Deleted 8/25/05</i> Over-the-Counter Approvals for Existing Restrooms
97-12	<i>Formally Deleted 8/25/05</i> Access Code Adoption to the Metric System
98-01	<i>Formally Deleted 8/25/05</i> Special Access (Wheelchair) Lifts
98-02	<i>Formally Deleted 6/15/09</i> Two-Story Relocatable Classrooms Project
98-03	<i>Formally Deleted 9/11/02</i> Modernization Program
<u>98-04</u>	Revised 4/05/00 Accessibility Requirements in Group I Occupancies
<u>98-05</u>	Revised 3/16/00 Folding Bleachers Accessible Seats
98-06	<i>Formally Deleted 8/25/05</i> Signs
<u>98-07</u>	Revised 8/25/08 Assembly Seating

Policy

Number Status/Title of Policy

98-08 *Formally Deleted 1/12/00*
Window Hardware

99-01 Revised 3/10/00
Special Education Relocatable Classrooms

99-02 **Playgrounds (Being Revised)**

99-03 *Formally Deleted 10/1/99*
No Title

99-05 *Formally Deleted 8/25/05*
Application for Unreasonable Hardship Exception

99-06 *Formally Deleted 8/25/05*
Residential Care Facility

99-07 *Formally Deleted 8/25/05*
Toilet Paper Dispensers at Accessible Stalls

99-08 Revised 1/01/00
Door Stops and Other Floor-Mounted Obstructions

99-09 *Formally Deleted 10/01/99*
Waivers

99-09.1 Supersedes 99-09
Waivers

00-01 Revised 8/25/05
Self-Evaluation and Transition Plan

00-02 *Formally Deleted 8/25/05*
Acceptance of Construction Documents Policy

ACCESSIBILITY AT EXIT-ONLY DOORS

94-05

Reference: 2001 California Building Code Sections 1114B.2.1, 1133B.1.1.1.1
& 1134B.2

Effective 3-1-94
Revised 8-25-05

This policy is applicable to projects under Division of the State Architect, Access Compliance (DSA/AC) jurisdiction only; this authority encompasses state-funded buildings, facilities and universities, as well as publicly funded elementary schools, secondary schools, and community colleges. Local authorities may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation or defining acceptable parameters when enforcing the California Building Standards Code. [Reference California Government Code Section 4451(f)]

Issue: California Building Code (CBC) Section 1114B.2.1 states: “In buildings or portions of buildings required to be accessible, accessible means of egress shall be provided in the same number as required for exits by Chapter 10.” CBC Section 1133B.1.1.1.1 states: “All entrances and exterior ground floor exit doors to buildings and facilities shall be made accessible to persons with disabilities.” Exit-only doors (doors without entry hardware) are not specifically mentioned.

Resolution: In new construction, all entrances and ground floor exit doors shall be made accessible for persons with disabilities. Exit-only doors (doors without entry hardware) are required to be accessible and *egressible* in the direction of egress for people with disabilities, with the following three (3) exceptions:

1. Exits are not required to be accessible when an area for evacuation assistance is provided. Areas of evacuation assistance are not required in buildings or facilities having a supervised automatic sprinkler system.
2. Exterior ground-floor exits serving smoke-proof enclosures, stairwells, and exit doors servicing stairs only, need not be made accessible.
3. Exits in excess of those required and which are more than 24 inches (610 mm) above grade are not required to be accessible. These doors shall have signs warning that they are not accessible.

In existing buildings, when provisions of CBC Section 1134B.2 apply, there are no requirements for an *egressible* route other than the primary entrance.

RESURFACING, RESTRIPING, AND ALTERATIONS OF PARKING LOTS

94-10

Reference: California Government Code Section 4451(c)

Effective 6-13-94
Revised 8-25-05

This policy is applicable to projects under Division of the State Architect, Access Compliance (DSA/AC) jurisdiction only; this authority encompasses state-funded buildings, facilities and universities, as well as publicly funded elementary schools, secondary schools, and community colleges. Local authorities may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation or defining acceptable parameters when enforcing the California Building Standards Code. [Reference California Government Code Section 4451(f)]

Issue: Construction approvals are sometimes not required when existing parking lots undergo resurfacing, restriping, and alterations. When approvals are not required, there may be some confusion about whether compliance with California Building Code accessibility regulations is required. California Government Code Section 4451(c) states in part: “With respect to buildings, structures, sidewalks, curbs, and related facilities not requiring a building permit, building standards published in the California Building Standards Code relating to access for persons with disabilities and other regulations adopted pursuant to Section 4450, and in effect at the time construction is commenced shall be applicable.”

Resolution: When construction approvals are not required for resurfacing, restriping, or alterations of parking lots, compliance with the California Building Code is required and accessible parking shall be provided. Building standards in effect at the time construction begins shall be applicable for resurfacing, restriping, or alterations of parking lots.

RECONSTRUCTION AFTER FIRE DAMAGE

94-22

Reference: 2001 California Building Code Sections 1134B.2
Americans with Disabilities Act Title III Regulation, 28 CFR Part 36,
Section 36.402(b)

Effective 11-4-94
Revised 8-25-05

This policy is applicable to projects under Division of the State Architect, Access Compliance (DSA/AC) jurisdiction only; this authority encompasses state-funded buildings, facilities and universities, as well as publicly funded elementary schools, secondary schools, and community colleges. Local authorities may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation or defining acceptable parameters when enforcing the California Building Standards Code. [Reference California Government Code Section 4451(f)]

Issue: In the past, reconstruction work after fire damage was often limited to “as built” replacement of materials as required by the codes in effect at the time of the original construction. However, current federal ADA Standards and California Building Code regulations may require the scope of work to extend outside the fire damage area to provide required accessible features.

Americans with Disabilities Act (ADA), Title III Regulation, 28 CFR Part 36, Section 36.402(b) defines an alteration as “a change to a place of public accommodation or a commercial facility that affects or could affect the usability of the building or facility or any part thereof”. The term alteration includes remodeling, renovation, rehabilitation, reconstruction, historic restoration, changes or rearrangement in structural parts or elements, and changes or rearrangement in the plan configuration of walls and full-height partitions. A US Department of Justice interpretation dated August 26, 1998, indicates reconstruction after a fire is considered an “alteration”.

When alterations, structural repairs or additions are made to existing buildings or facilities, California Building Code Section 1134B.2 indicates that projects shall comply with all applicable accessibility regulations. These regulations apply to the area of specific alteration, structural repair or addition, as well as, the primary entrance to the building or facility and the primary path of travel to the specific area of alteration, structural repair or addition including sanitary facilities, drinking fountains, signs, and public telephones serving the area.

Resolution: This interpretation emphasizes the provisions of current federal and state regulations as they apply to reconstruction work after fire damage. Reconstruction after a fire is considered an alteration, and such alteration work shall comply with all applicable accessibility regulations. On projects under DSA jurisdiction: (1) reconstruction work in the specific area of fire damage shall comply with all applicable accessibility regulations for new construction, and (2) the obligation to provide an accessible primary entrance to the building or facility and primary path of travel to the specific area of alteration, including sanitary facilities, drinking fountains, signs, and public telephones shall be met.

The Office of Public School Construction, which approves funding for fire damage reconstruction projects at state funded facilities, has been made aware that they must fund these additional project requirements. Also, school district officials should be aware that insurance policies generally cover only the fire damage areas and additional project funding may be necessary to complete all required work.

ACCESSIBLE SEATING AT FIXED COUNTERS

95-09

Reference: 2001 California Building Code Sections 1104B.5 item 4, 1122B.4 & 1134B.2

Effective 10-31-95

Revised 8-25-05

This policy is applicable to projects under Division of the State Architect, Access Compliance (DSA/AC) jurisdiction only; this authority encompasses state-funded buildings, facilities and universities, as well as publicly funded elementary schools, secondary schools, and community colleges. Local authorities may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation or defining acceptable parameters when enforcing the California Building Standards Code. [Reference California Government Code Section 4451(f)]

Issue: At fixed counters exceeding 34 inches (864 mm) in height, when food or drink is served for consumption by customers seated on stools or standing at the counter, table service at accessible tables within the same area had been an acceptable alternative to providing accessible seating at the fixed counter. As of April 1, 1994, providing table service instead of accessible seating at a fixed counter is no longer an option in California. California Building Code (CBC) Section 1104B.5 item 4 indicates that each dining, banquet and bar area shall have one wheelchair seating space for each 20 seats, with at least one minimum wheelchair seating space per functional area. In addition, required accessible seating areas shall be integrated with general seating areas to avoid having one area specifically *highlighted* as the area for persons with disabilities. Where fixed counters are provided for the public, CBC Section 1122B.4 indicates that at least 5 percent, but never less than one, of each type of station shall be located at a section of counter that is at least 36 inches (914 mm) long. However, seating for one at a lowered section of counter does not provide the disabled person with an equal opportunity to sit shoulder-to-shoulder with others and converse. Federal accessibility guidelines require that where food or drink is served at fixed counters exceeding 34 inches (864 mm) in height, an accessible portion of counter 60 inches (1524 mm) in length minimum be provided.

Resolution: At dining, banquet, and bar facilities, accessible seating spaces shall be integrated with general seating to avoid having one area specifically *highlighted* as the area for persons with disabilities. At fixed counters exceeding 34 inches (864 mm) in height, where food or drink is served for consumption by customers seated on stools or standing at the counter, the DSA encourages and will accept designs that indicate accessible portions of counters designed to accommodate more than one person, allowing disabled persons an equal opportunity to converse with others.

Under the provisions of CBC 1134B.2, when it is determined that compliance with accessibility regulations in existing buildings or facilities would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided. An example of equivalent facilitation would be to provide an accessible counter or bar with similar architecture, casework, ambience and service, in close proximity to the existing counter or bar, which will accommodate several people. Some existing buildings or facilities have historic significance which may allow use of the State Historical Building Code. Projects will be evaluated by the DSA on a case-by-case basis to ensure both accessibility and an equitable environment are provided to the maximum extent feasible.

SEISMIC UPGRADE PROJECTS

96-01

Reference: 2001 California Building Code Section 1134B.2
California Office of the Attorney General, Legal Opinion No. 94-1109

Effective 1-18-96
Revised 8-25-05

This policy is applicable to projects under Division of the State Architect, Access Compliance (DSA/AC) jurisdiction only; this authority encompasses state-funded buildings, facilities and universities, as well as publicly funded elementary schools, secondary schools, and community colleges. Local authorities may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation or defining acceptable parameters when enforcing the California Building Standards Code. [Reference California Government Code Section 4451(f)]

Issue: In Legal Opinion No. 94-1109, dated May 10, 1995, the Attorney General for the State of California concluded that seismic strengthening work in an existing building constitutes a “building alteration, structural repair or addition” for purposes of providing access to the building for disabled persons.

When alterations, structural repairs, or additions are made to existing buildings or facilities, California Building Code (CBC) Section 1134B.2 indicates that projects shall comply with all applicable accessibility regulations for new construction. These requirements apply to the area of specific alteration, structural repair or addition, as well as, the primary entrance to the building or facility and the primary path of travel to the specific area of alteration, structural repair or addition including sanitary facilities, drinking fountains, signs, and public telephones serving the area.

In seismic strengthening or upgrade projects, the scope of work often includes the entire building or facility; therefore, it may be difficult to determine the area of specific alteration for the purposes of applying CBC Section 1134B.2.

Resolution: When seismic strengthening or upgrade work occurs in existing buildings or facilities, the entire building or facility is enhanced. Although, there may not be a specific area of alteration, the requirement of CBC Section 1134B.2 to provide access to the building or facility for persons with disabilities is applicable.

In existing buildings or facilities under DSA jurisdiction, if seismic strengthening or upgrade work does not alter the primary use or function of the building or facility and/or does not alter the design of specific rooms or spaces, then the requirement for an accessible path of travel to the area of specific alteration does not apply. However, the requirement to provide an accessible primary entrance, sanitary facilities, drinking fountains, signs, and public telephones, as well as, an accessible path of travel connecting these elements shall be met.

In existing buildings or facilities under DSA jurisdiction, when the primary use or function of the building or facility and/or the design of specific rooms or spaces are altered, the seismic strengthening or upgrade work shall comply with all applicable accessibility regulations for new construction. In addition, the obligation to provide an accessible primary entrance to the building or facility and primary path of travel to the specific area of alteration, including sanitary facilities, drinking fountains, signs, and public telephones serving the area shall be met.

Any work done in conjunction with the seismic strengthening or upgrade project, such as alterations or additions to the building or facility, shall comply with all applicable accessibility regulations.

Handrails at Steps

96-10

Effective 2-13-96
Revised 12-30-96

This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f)] of the California Code of Regulations.

Issue: The definition of 'Stairway' is:

STAIRWAY. Two or more risers shall constitute a stairway.

Since handrails are required by code for 'stairways', it appears that there is no requirement for single steps. Model code does not address accessibility at single step conditions.

Resolution: The Division of the State Architect, (DSA/AC), must review any and all work which effects accessibility for path of travel, functional areas, outdoor gates, fences, outdoor surfaces, landscaping, and grading. Government Code 4450 requires compliance with the Americans with Disabilities Act Accessibility Guidelines until minimum standards are adopted. Therefore, in order to meet State legislative mandates to approve plans meeting the intent of Gov. Code 4450, DSA/AC does require handrails at single step conditions where path of travel to new work is required to be accessible.

Approving Authority:



Michael J. Mankin, AIA
Manager, Access Compliance Program

UNISEX TOILET ROOMS

97-01

Reference: 2001 California Building Code Sections 1115B.1, 1115B.2, 1115B.7.2,
1134B.2.1 & 1134B.2.2

Effective 1-17-97
Revised 8-25-05

This policy is applicable to projects under Division of the State Architect, Access Compliance (DSA/AC) jurisdiction only; this authority encompasses state-funded buildings, facilities and universities, as well as publicly funded elementary schools, secondary schools, and community colleges. Local authorities may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation or defining acceptable parameters when enforcing the California Building Standards Code. [Reference California Government Code Section 4451(f)]

Issue: California Building Code (CBC) Section 1115B.2 indicates that where separate toilet rooms are provided for nondisabled persons of each sex, then separate toilet rooms shall be provided for persons with disabilities of each sex also. However, CBC Section 1134B.2.2 indicates that in existing buildings where it is technically infeasible in an area of alteration to make existing restroom facilities code compliant and to install separate toilet rooms for each sex, then the installation of at least one unisex toilet room per floor being altered will be permitted. The unisex toilet room must be located in the same area as the existing restroom facilities.

When alterations, structural repairs or additions are made to existing buildings or facilities, CBC Section 1134B.2 indicates that restroom facilities serving the specific area of alteration shall comply with all provisions for new buildings, unless the exceptions contained within that section are utilized. The exception to CBC Section 1115B.1 indicates that in existing buildings or facilities, when the enforcing agency determines that compliance with the building standards would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided. When equivalent facilitation is used, a fully accessible unisex toilet room provides greater usability for disabled persons than a pair of partially accessible single-sex toilet rooms. The unisex toilet room must be located within a reasonable distance of accessible areas.

Resolution: In existing buildings or facilities, unisex toilet rooms will be permitted where it is determined that full code compliance is technically infeasible in an area of alteration per CBC Section 1134B.2.2. Under the provisions of CBC Section 1134B.2.1, when it is determined that compliance with accessibility regulations in existing buildings or facilities would create an unreasonable hardship, an exception may be granted when a unisex toilet room is provided as equivalent facilitation. The unisex toilet rooms shall be located on the same floor and in the same area as the existing inaccessible restroom facilities, and shall meet the requirements of CBC Section 1115B.7.2.

Unisex toilet rooms benefit people who use opposite sex personal care assistants. For this reason, it is recommended to install unisex toilet rooms in new buildings and facilities in addition to a pair of separate accessible toilet rooms. However, unisex toilet rooms may not be utilized in place of separate accessible toilet rooms for each sex in new construction.

Note: California labor codes may require separate toilet rooms for each sex when there are five or more employees serving a business.

Permit Extensions

97-02

Effective 4-29-97

Revised 4-5-00

This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f)] of the California Code of Regulations.

Issue: Some projects under the jurisdiction of Access Compliance have been approved in the past and are eligible for extensions. Certain projects were approved prior to implementation of the Americans with Disabilities Act regulations. Those remodel projects permitted before January 26, 1992, and those new projects submitted prior to January 26, 1993, were permitted prior to implementation of federal regulations relating to accessibility. Essentially, the US Department of Justice has indicated to DSA that those projects are “grandfathered in”, and do not have to meet ADA requirements.

Access Compliance incorporated more restrictive federal accessibility requirements into the State Building Code through rulemaking changes effective April 1, 1994. Projects submitted after this date may be allowed extensions without code upgrades.

Some projects were submitted and approved by DSA in the window period between implementation of federal regulations and enforcement effective dates for DSA “new ADA language.” This window period may include projects that were plan reviewed to higher federal standards as a courtesy to the architect, yet were not enforceable by DSA/AC under state law. Some architects did not want to comply with higher federal standards and chose to be responsible for those unenforceable issues.

Resolution: Existing projects submitted to Access Compliance during a window period beginning from January 26, 1992, or if new construction, January 26, 1993, and ending April 1, 1994, need to be examined by Access Compliance plan checkers to verify compliance with higher federal standards now in effect before extensions to the permit may be granted. Most projects were approved to the higher standards of either state or federal law, however, now must be required to change to incorporate ADA standards. DSA/AC has no authority to continue permit extensions on these projects contrary to the intent of state law that now requires ADA minimums.

Approving Authority:



Michael J. Mankin, AIA
Manager, Access Compliance Program

Interim Disabled Access Guidelines for Electrical Vehicle Charging Stations

97-03

Effective 4-30-97
Revised 6-5-97

This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f)] of the California Code of Regulations.

Issue: In state funded projects with electrical vehicle, charging stations must be accessible. Electric Vehicles are being slowly introduced to the consumer market over the next three years as a result of an agreement between auto makers and the State of California. The zero emission vehicles as well as the equipment to charge them are continuing to develop and change at a rapid pace. Yet to successfully serve new electric vehicle customers, public charging is essential. Public charging sites that are developed now are likely to see significant technology changes before electric vehicles are fully commercialized. Based on a rule adopted by the California Air Resources Board, beginning in 2003, 10% of vehicles sold in California must be zero emission.

Public charging stations will be installed in public places such as shopping centers, parking lots and garages of companies or municipalities. They are provided as a convenient charging location for Electric Vehicle owners while they work or shop. Full charging of an Electric Vehicle takes between two to three hours.

Resolution: Representatives of the Division of State Architect, California Electric Transportation Coalition, Edison EV, The California Building Officials, Department of Rehabilitation and members of the disabled community have held meetings for the purpose of developing interim guidelines to address the issue of disabled access to these charging stations. The following guidelines have been developed and agreed upon by the these organizations:

ARE EV CHARGING STATIONS REQUIRED TO BE ACCESSIBLE?

Yes. EV Charging Stations are required to be accessible because they offer a service to the general public. When EV charging is coupled with regular parking, the EV charging is considered the primary service. (See Item V for further discussions.)

WHAT PERCENTAGE OF THE EV CHARGING STATIONS MUST BE MADE ACCESSIBLE?

The following table shall be used in determining the required number of accessible charging stations:

# of charging stations provided at a site	# of accessible charging stations required
1 to 25	1
50	2
51 to 75	3

WHAT PERCENTAGE OF THE EV CHARGING STATIONS MUST BE MADE ACCESSIBLE?

The following table shall be used in determining the required number of accessible charging stations:

# of charging stations provided at a site	# of accessible charging stations required
76 to 100	4

WHAT SPECIFICATIONS MUST THE ACCESSIBLE EV CHARGING STATION COMPLY WITH?

- a. A 9 foot wide space by 18 feet deep space is required. An access aisle of 5 feet on the passenger side is required. One in every eight accessible charging stations, but not less than one, shall be van accessible with a 8 foot access aisle.
- b. The accessible EV charging station and its access aisle need not be striped or provided with signage as required for an accessible parking space. An information sign must be posted which reads, "Parking for EV Charging Only; This Space Designed for Disabled Access; Use Last."

MUST ACCESSIBLE EV CHARGING STATIONS BE RESERVED EXCLUSIVELY FOR THE USE OF PERSONS WITH DISABILITIES?

No. The primary function of these stations is the charging of Electric Vehicles. Parking is not intended to be the primary use of the charging station.

ARE THERE ANY RESTRICTIONS RELATIVE TO THE LOCATION OF THE ACCESSIBLE EV CHARGING STATIONS?

For installations associated with new construction, the accessible charging station must be located in close proximity to a major facility, public way or a major path of travel on the site. Note: 200 feet is the maximum distance recommended. However, the charging stations need not be provided immediately adjacent to the major facilities since, again, the primary purpose of the stations is to provide the charging as a service, and parking is not intended to be the primary use of the stations.

For installations at existing sites, the accessible charging station need not be located in close proximity to other services at the site.

IS AN ACCESSIBLE PATH OF TRAVEL REQUIRED FROM THE ACCESSIBLE EV CHARGING STATION TO OTHER SERVICES PROVIDED AT THE SITE?

Yes, for installations associated with new construction. As for other facilities on the site, an accessible path of travel is required between facilities.

For installation at an existing site, an accessible path of travel is required to the extent that the cost of providing such path does not exceed 20% of the cost of the EV equipment and installation of all EV charging stations at the site, when such valuation does not exceed the threshold amount referenced in Exception 1 of Section 1134 of Title 24. The accessible path of travel shall connect to a major facility, public way or major path of travel on the site.

WHAT SPECIFICATIONS MUST THE CHARGING EQUIPMENT MEET?

The charging equipment must meet all applicable reach range provisions of Section 1118B of Title 24. A clear path of travel measuring 36 inches in clear width to the charging equipment is required.

DOES THE INSTALLATION OF CHARGING STATIONS AT AN EXISTING SITE TRIGGER PATH OF TRAVEL IMPROVEMENTS SUCH AS PRIMARY ENTRANCE TO OTHER FACILITIES, RESTROOMS, TELEPHONES, OR DRINKING FOUNTAINS?

No, unless the above features are located in the parking lot, are accessed directly from the parking lot and designed for use with the parking lot.

HOW DOES THE THREE-YEAR VALUATION ACCUMULATION APPLY TO THESE INSTALLATIONS?

The valuation of other improvements at the site over the last three years need not be added to the cost of the installation to determine application of the exception referenced in item VI above. The cost of installation of other EV charging stations at the site over a three-year period must be used in determining compliance with the exception.

Approving Authority:



Michael J. Mankin, AIA
Manager, Access Compliance Program

Parking Ticket Dispensers

97-06

Effective 12-23-97
Revised 4-5-00

This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f) of the California Code of Regulations.

Issue: This interim policy requires parking areas controlled by ticket dispensers to include accessible parking spaces for persons with disabilities outside the controlled area so that these inaccessible dispensers do not create an architectural barrier.

The California Vehicle Code Section 22511.5 allows any person with a disability, displaying distinguishing placards or special plates, to park in any zone that is restricted in the length of time parking is permitted, and metered parking, such as those restricted by ticket dispensers to allow such persons to park without paying any fees. While most people with disabilities would rather pay the fee in order to be treated equally, it may be necessary to consider this issue in conjunction with developing a solution for a related issue in providing additional uncontrolled parking. DSA is not intending to prevent parking facilities from charging a fee in spite of metered parking being exempted from the fee in statute. While existing parking facilities are somewhat limited with the situation they have, they must programmatically provide solutions that make it possible for persons with disabilities to park without the need to retrieve a ticket from a ticket dispenser. Intercom systems that could call an attendant to raise the gate, or to remotely raise the gate, would seem to be a reasonable programmatic solution.

Such dispensers are architectural barriers to quadriplegics, some amputees and other persons with reach-range limitations. As a rule, programmatic solutions may not withstand the test of time, and architectural barriers must be solved by architectural solutions. Until regulations are developed, DSA is adopting an interim policy consistent with the vehicle code and the regulations cited below, which provide a solution to these architectural barriers.

Resolution: To be consistent with Vehicle Code Section 22511.5 and Government Code Section 4450, and especially Section 101.2 of Part 2 of the California Building Code, Title 24, it is necessary to plan review and approve parking facilities which provide at least one accessible van stall outside the restricted area in new construction, and in existing facilities, DSA will require adequate signage indicating a programmatic solution if there is not accessible parking equally available within 200 feet in a nearby facility.

Approving Authority:



Michael J. Mankin, AIA
Manager, Access Compliance Program

Accessibility Requirements In Group I Occupancies

98-04

Effective 10-15-98

Revised 4-5-00

This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f)] of the California Code of Regulations.

Issue: The general accessibility requirements usually apply throughout a facility, and occupancy enhancements often add specificity. However, for Group I Occupancies, scoping reductions reduce the total number of required accessible patient bedrooms and related toilets.

Resolution: The general application of accessibility requirements for new buildings or renovations, structural repairs, alterations and additions to existing buildings are found in CCR title 24, Part 2, Chapter 11B (California Building Code), Section 1103B.1. Occupancy modifications and/or enhancements, found in subsequent sections, prescribe more detailed requirements for specific applications.

The specific applications for accessibility for Group I Occupancies (Hospitals, Skilled Nursing and Intermediate-Care Facilities) are found in Sections 1109B.1 through 1109B.8., Section 1109B.3, subsections 1 through 3, state that the total number of patient bedrooms and associated toilet rooms that must be accessible for Long-term-care (Skilled Nursing and Intermediate Care) facilities are 50 percent, 10 percent for General-purpose hospital (Acute Care) facilities, and Rehabilitation facilities must have 100 percent accessible patient bedrooms. Specificity is also given in the various sections of 1109B pertaining to requirements for the facility entrance, diagnostic and treatment areas, waiting areas, offices and sanitary facilities, offices and suites, and all public-use and common-use areas. The requirements found in Section 1114B.1 are to be applied to all of these areas.

The special requirements of Section 1114B.1 need not be applied to those patient bedrooms and associated toilet rooms beyond the percentage of rooms required in Section 1109B.3. To place these requirements on **all** patient rooms and/or associated toilet rooms would in essence be requiring 100 percent patient bedroom accessibility. This is clearly not the intent or specific percentages, as a modification or enhancement to patient bedroom accessibility requirements would not have been given.

The total number of accessible patient bedrooms is to be applied facility-wide, not necessarily by unit or by floor. However, care must be exercised to have a reasonable disbursement of accessible patient bedrooms throughout the facility.

Because of other code provisions, it appears that reasonable access or accommodation is generally provided to all patient bedrooms. The doors are 3'-1-" or 4'-0" wide to provide the minimum 44" clear exit width required by Section 1019.2. This width is greater than the 32"

minimum required for accessibility. Doors are usually easy to open because closures are not required for patient bedrooms, even when located off a rated exit corridor, per Section 1019.3. The doors are usually left in an open position when occupied to allow better supervision by nursing staff and cubicle curtains surrounding the bed(s) usually provide privacy.

Approving Authority:

A handwritten signature in black ink, appearing to read "M. Mankin". The signature is fluid and cursive, with a large loop at the end.

Michael J. Mankin, AIA
Manager, Access Compliance Program

Folding Bleachers Accessible Seats

98-05

Effective 12-1-98
Revised 3-16-00

This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f)] of the California Code of Regulations.

Issue: The California Building Code (CBC) calls for providing accessible seating areas for persons with disabilities in stadiums, multi-purpose rooms, and gymnasiums.

Section: 1104B.3.5 / 3103A (b) 2.A (iii)d. Placement of wheelchair locations.

Wheelchair areas shall be an integral part of any fixed seating plan, and shall be arranged so as to provide persons with disabilities a choice of admission prices and lines of sight comparable to those for members of the general public. Each wheelchair area shall adjoin an accessible route, which shall also serve as a means of egress in case of emergency. At least one companion fixed seat shall be provided next to each wheelchair seat locations. When the seating capacity exceeds 300, wheelchair spaces shall be provided in more than one location in addition to complying with Section 1104B.3.3/3103A (b) 2.A (iii).

Folding bleachers are a fixed foldable seating system and the wheelchair spaces are usually provided by a cut back in the first rows. Integrated companion fixed seats cannot be obtained in most designs.

Resolution: Until more specific regulations are adopted for foldable bleachers, projects will be accepted which have the following features:

1. Next to each wheelchair space a 60-centimeters (24-inches) by 120 centimeters (48 inches) clear space will be provided for each companion seating area, with signage identifying it on the companion seat.
2. Wheelchair spaces will be identified by the International Symbol of Accessibility on the floor or on the front of the lowest bleacher row in front of space.
3. The number of wheelchair accessible seats shall be dispersed equally for each side (home and visitors) and shall not be clustered into one location for each side.

Approving Authority:



Michael J. Mankin, AIA
Manager, Access Compliance Program

ASSEMBLY SEATING

98-07

Reference: 2001 California Building Code Sections 1104B.3.1 through 1104B.3.8

Effective 12-31-98

Revised 8-25-05

This policy is applicable to projects under Division of the State Architect, Access Compliance (DSA/AC) jurisdiction only; this authority encompasses state-funded buildings, facilities and universities, as well as publicly funded elementary schools, secondary schools, and community colleges. Local authorities may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation or defining acceptable parameters when enforcing the California Building Standards Code. [Reference California Government Code Section 4451(f)]

Issue: The California Building Code (CBC) Section 1104B.3 contains provisions related to accessible seating in auditoriums, assembly halls, theaters and related facilities, including requirements for wheelchair seating areas, companion seating, transfer (aisle) seating, and semi-ambulant seating. It is unclear whether these types of required seating can be combined with one another or are mutually exclusive of each other.

Resolution: This interpretation emphasizes the provisions of current federal and state regulations as they apply to accessible seating in assembly areas. The DSA encourages and will accept construction documents that indicate the following at assembly seating areas:

1. Wheelchair seating areas are provided as shown in Table 11B-1. Wheelchair seating areas are an integral part of the seating plan, so that people using wheelchairs are not isolated from other spectators or their friends and family. These seats shall comply with CBC Section 1104B.3.1 through 1104B.3.7.
2. A companion seat is provided next to each wheelchair seating location. The companion seat is a conventional seat that accommodates a friend or companion. These seats shall comply with CBC Section 1104B.3.5.
3. Transfer (aisle) seating is provided in addition to wheelchair seating locations. At least one percent (but not less than one) of all fixed seats in all seating areas are aisle seats with no armrest, or with removable or folding armrest, on the aisle side. These seats accommodate wheelchair users who wish to transfer to existing seating during an event when fixed seating is provided. These seats shall comply with CBC Section 1104B.3.4, item 1.
4. Semi-ambulant seating is provided in addition to the spaces provided for wheelchair users. At least one percent (but no fewer than two) of all fixed seats in all seating areas provide 24 inches clear leg room from the front edge of the seat to the nearest obstruction or to the seat immediately in front. Semi-ambulant seating is located on an accessible route, and specifically on an aisle without steps. These seats accommodate people who have a mobility disability but who are not wheelchair users. These seats shall comply with CBC Section 1104B.3.8.

Special Education Relocatable Classrooms

99-01

Effective 1-31-99
Revised 3-10-00

This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f)] of the California Code of Regulations.

Issue: Title 24, Part 2, the California Building Code (CBC) requires public accommodations to be accessible and available on an accessible route with equal facility. Special education trailers for persons with disabilities are at times placed inappropriately in remote corners of the site, somewhat distant from the main buildings of the school facility. Often these sites are placed in a fenced-off area separate from the main playground areas of the school. Recently, case law has indicated that separate, highlighted, accessible features are discriminatory, and that the intent of statutes is to provide integration and dispersal of accessible features. Special education relocatable buildings must be provided as an integrated part of the school facility according to the U.S. Department of Education, Office of Civil Rights, and may not be fenced-off as a separate facility. If these buildings are being fenced-off in order to avoid application of the Field Act, the effect is discriminatory and is unacceptable.

Resolution: Special education relocatable classrooms shall be placed within 200 feet of the main building(s) and may not be fenced-off from the rest of the school site.

Approving Authority:



Michael J. Mankin, AIA
Manager, Access Compliance Program

Playgrounds

99-02

Effective 7-1-99


This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f)] of the California Code of Regulations.

Issue: Participation areas are required to be accessible by Section 1104B.4.3 of Part 2, Title 24, California Code of Regulations. Playgrounds are required to be accessible by this section and by the Americans with Disabilities Act. However, the California Building Standards Code does not provide specificity by indicating on an item by item basis which particular features are required. Additionally, federal agencies are concerned that California playgrounds are often not in strict compliance with Section 504 of the Rehabilitation Act of 1973, which requires play areas, which when viewed in their entirety, to be accessible by teachers, parents and children with disabilities in the most integrated setting.

The Federal Access Board has developed play setting recommendations for new construction, but these well developed accessibility guidelines are not yet adopted by the US Department of Justice for incorporation into the ADA accessibility guidelines. Playgrounds are required to be accessible to persons with disabilities as part of an ongoing obligation under Title II of the Americans with Disability Act. As a separate issue, the California Building standards Code "triggers" the requirements for accessibility in alterations, additions or in new construction when it occurs.

Resolution: Until specific requirements are adopted by the US Department of Justice and incorporated into the State Building Standards Code, DSA/AC will not take issue with playground plans which have been developed consistent with the accessibility guidelines for the Play Setting Subcommittee issued by the Access Board. Generally, playground equipment shall be reviewed during the plan check as part of the review process, and in some cases where the design and type of equipment has not been determined, deferred approvals shall be accepted prior to close out of the project. An accessible route will be required to one of each type of feature available in playground equipment, with engineered wood, properly installed and maintained, roll-out mats, or rubber surfaces deemed to be accessible surfaces. Raised features must be available at grade or by transfer points which lead to elevated areas by way of stepped platforms. All features at grade level must also be accessible, and arrange of play features must be provided (at least one of each type). Related to this policy see the Play Setting Subcommittee Guidelines used as a current standard for this environment.

Approving Authority:



Michael J. Mankin, AIA
Manager, Access Compliance Program

Door Stops and other Floor-Mounted Obstructions

99-08

Effective 12-1-99
Revised 1-1-00

This policy is applicable to projects under DSA jurisdiction only. DSA's Access Compliance jurisdiction encompasses state-funded buildings, facilities and universities, as well as publicly-funded elementary schools, secondary schools, and community colleges. Local jurisdictions may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation, or defining acceptable parameters as necessary in enforcing the existing California Building Standards Code as allowed under Government Code Section 4451(f)] of the California Code of Regulations.

Issue: California Government Code 4452 and Title 24, Part 2 require public accommodations to be accessible and available on an accessible route with equal facility. To assure that the path of travel is free of hazards, care must be taken in the design and placement of walking-surface or wall-mounted components.

Resolution: Floor-mounted door stops and similar obstructions are allowed to be installed at a maximum of four inches from the face of the wall or partition. Refer to Title 24, Section 1133B.8.6, for protruding objects.

Approving Authority:



Michael J. Mankin, AIA
Manager, Access Compliance Program

SELF-EVALUATION AND TRANSITION PLAN

00-01

Reference: 2001 California Government Code Section 4450, et seq
Americans with Disabilities Act Title II Regulation, 28 CFR Part 35,
Section 35.105 & 35.150

Effective 4-1-00
Revised 8-25-05

This policy is applicable to projects under Division of the State Architect, Access Compliance (DSA/AC) jurisdiction only; this authority encompasses state-funded buildings, facilities and universities, as well as publicly funded elementary schools, secondary schools, and community colleges. Local authorities may or may not adopt similar methods of administering current code requirements, determining equivalent facilitation or defining acceptable parameters when enforcing the California Building Standards Code. [Reference California Government Code Section 4451(f)]

Issue: All facilities under Division of the State Architect (DSA) jurisdiction must meet the provisions of California Government Code Section 4450, as well as, the federal Americans with Disabilities Act (ADA). The ADA Title II Regulation, 28 CFR Part 35, requires public entities to evaluate its current services, policies and practices to ensure persons with disabilities are protected from discrimination on the basis of disability. The ADA Title II Regulation, 28 CFR Part 35, Section 35.150 requires public entities to develop a transition plan for making the necessary structural changes to facilities in order to achieve program accessibility.

Resolution: The DSA completed and published the *Five Phases of Access Compliance* flow chart in April 2004. This document leads State agencies through the Self-Evaluation and Transition Plan process to evaluate program and facility accessibility. It is also an ideal tool to determine the accessibility of a facility prior to relocation. The flow chart can be found on the DSA website at http://www.documents.dgs.ca.gov/dsa/pubs/5phases_accesscompliance.pdf.

END OF POLICY MANUAL

DSA Access Compliance Interpretations of Regulations (IRs)

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL INTERPRETATIONS OF REGULATIONS

Introduction

Section 4 – Interpretations of Regulations (IRs): The Interpretations of Regulations shown in this section are intended for use by DSA staff and as a resource for design professionals to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. The IRs typically indicate acceptable methods of achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

DSA Access Compliance Interpretations of Regulations

IR#	Title	Date
IR 11B-1	Visual Alarms in Classrooms	01-01-11(r)
IR 11B-2	Beveled Lip at Curb Ramps	01-01-11(r)
IR 11B-3	Detectable Warnings at Curb Ramps	01-01-11(r)
IR 11B-4	Detectable Warnings	11-18-11(r)
IR 11B-5	Effort to Operate Exterior Doors	<i>Formally Deleted</i>
IR 11B-6	Mechanical Only Projects Exempt From Accessibility Review	01-01-11(r)
IR 11B-7	Requirements for Accessible Parking Spaces	01-01-11(r)
IR 11B-8	Use of Predetermined Construction Tolerance Guidelines for Accessibility	01-01-11(r)

VISUAL ALARMS IN CLASSROOMS

IR 11B-1

References:

2001 California Building Code, Sections 1114B.2.4 and 3505.1 Sec. 4-4.5
Americans with Disabilities Act Standards for Accessible Design 4.1.1(1) and 4.1.3(14)
California Government Code, Section 4451(d)

Revised 01-01-11
Revised 11-01-07
Issued 01-26-05

Discipline: Access Compliance

This Interpretation of Regulations (IR) is intended for use by the Division of the State Architect (DSA) staff, and as a resource for design professionals, to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. This IR indicates an acceptable method for achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

This IR is reviewed on a regular basis and is subject to revision at any time. Please check the DSA web site for currently effective IRs. Only IRs listed in the document at <http://www.dgs.ca.gov/dsa/Resources/IRManual.aspx> at the time of plan submittal to DSA are considered applicable.

Purpose: This interpretation clarifies acceptable design and installation requirements for fire alarm systems installed in new buildings containing classrooms for projects under Division of the State Architect (DSA) jurisdiction, which includes state-funded buildings and facilities, State of California public elementary and secondary schools (grades K-12), community colleges, and universities. (In the 2007 CBC this issue is addressed in Section 907.9.1.1.) (In the 2010 CBC this issue is addressed in Section 907.5.2.3.1.)

General: Unlike audible alarms, visual alarms are typically located within the space they serve so the signal is visible to the occupants of the space. The Americans with Disabilities Act Standards for Accessible Design, Section 4.1.3(14) indicates that when emergency warning systems are provided, they shall include both audible and visual alarms. Since classrooms in newly constructed buildings are required to be accessible by Section 4.1.1(1), where audible alarm coverage is provided, the emergency warning system shall also provide visual alarm coverage.

Design Requirements: Per California Government Code 4451(d), until such building standards are published in the California Building Standards Code that meet or exceed the requirements of the Federal Americans with Disabilities Act, specifically in this case the Americans with Disabilities Act Standards for Accessible Design, Section 4.1.3(14), effective March 1, 2005, DSA will accept construction documents for new construction (new buildings) that indicate visual fire alarm coverage for all classrooms¹ that are provided with audible fire alarm coverage.

¹ United States Architectural and Transportation Barriers Compliance Board: ADAAG Manual, A guide to the Americans with Disabilities Act Accessibility Guidelines, July 1998, p. 98, Visual Alarms (4.28.3); Technical Bulletin: Visual Alarms, August, 2003,
<http://www.access-board.gov/adaag/about/bulletins/alarms.htm>
or
<http://www.access-board.gov/adaag/about/bulletins/pdf/alarms.pdf>

BEVELED LIP AT CURB RAMPS

IR 11B-2

References:

2001 California Building Code, Sections 1127B.5 Items 3 & 5, and
1117A.4.5 (prior to the 10/12/06 Supplement, effective 5/2/07).
California Government Code, Sections 4451(d) & (f)
Americans with Disabilities Act Standards for Accessible Design, Section 4.7.2

Revised 01-01-11
Revised 11-01-07
Issued 01-26-05
See IR 11B-3

Discipline: Access Compliance

This Interpretation of Regulations (IR) is intended for use by the Division of the State Architect (DSA) staff, and as a resource for design professionals, to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. This IR indicates an acceptable method for achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

This IR is reviewed on a regular basis and is subject to revision at any time. Please check the DSA web site for currently effective IRs. Only IRs listed in the document at <http://www.dgs.ca.gov/dsa/Resources/IRManual.aspx> at the time of plan submittal to DSA are considered applicable.

Purpose: This interpretation clarifies acceptable design and installation requirements for curb ramps under Division of the State Architect (DSA) jurisdiction, which includes state-funded buildings and facilities, State of California public elementary and secondary schools (grades K-12), community colleges, and universities. (In the 2007 and 2010 CBC this issue has been addressed by removing the requirement for a beveled lip at curb ramps.)

General: California Building Code (CBC) Section 1127B.5 Item 3 states: "Transitions from ramps to walks, gutters, or streets shall be flush and free of abrupt changes, except that curb ramps shall comply with Item 5...." CBC Section 1127B.5 Item 5 states: "The lower end of each curb ramp shall have a 1/2 inch (13 mm) lip beveled at 45 degrees as a detectable way-finding edge for persons with visual impairment."

However, the Americans with Disabilities Act Standards for Accessible Design Section 4.7.2 does not allow a beveled lip at the lower end of a curb ramp and states: "Transitions from ramps to walks, gutters, or streets shall be flush and free of abrupt changes."

Design Requirements: Per California Government Code 4451(d), until such building standards are published in the California Building Standards Code that meet or exceed the requirements of the federal Americans with Disabilities Act, and specifically in this case the Americans with Disabilities Act Standards for Accessible Design Section 4.7.2, the DSA will accept curb ramp designs which indicate that the lower end of each curb ramp is flush and free of abrupt changes, without a beveled lip. All such curb ramp designs shall incorporate a detectable warning surface (truncated domes) as indicated in other sections of the CBC, and Access Compliance IR 11B-3.

Note: The October 12, 2006 Supplement to the 2001 CBC removed from Chapter 11A the requirement for a beveled lip at curb ramps.

DETECTABLE WARNINGS AT CURB RAMPS

IR 11B-3

References:

2001 California Building Code, Sections 1127B.5 Item 8 and
1117A.4.7 (prior to the 10/12/06 Supplement, effective 5/2/07).
California Government Code, Section 4451(d)
Americans with Disabilities Act Standards for Accessible Design, Section 4.7.7

Revised 01-01-11
Revised 11-01-07
Issued 01-26-05

See IR 11B-2 and 11B-4

Discipline: Access Compliance

This Interpretation of Regulations (IR) is intended for use by the Division of the State Architect (DSA) staff, and as a resource for design professionals, to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. This IR indicates an acceptable method for achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

This IR is reviewed on a regular basis and is subject to revision at any time. Please check the DSA web site for currently effective IRs. Only IRs listed in the document at <http://www.dgs.ca.gov/dsa/Resources/IRManual.aspx> at the time of plan submittal to DSA are considered applicable.

Purpose: This interpretation clarifies acceptable design and installation requirements of detectable warnings at curb ramps under Division of the State Architect (DSA) jurisdiction, which includes state funded buildings and facilities, State of California public elementary and secondary schools (grades K-12), community colleges, and universities. (In the 2007 and 2010 CBC this issue has been addressed in Section 1127B.5 Item 7).

General: California Building Code Sections 1127B.5 Item 8 and 1117A.4.7 state “a curb ramp shall have a detectable warning....when the ramp slope is less than 1 unit vertical to 15 units horizontal (6.7% slope).”

However, the Americans with Disabilities Act Standards for Accessible Design Section 4.7.7 indicates that curb ramps shall have a detectable warning surface without regard to the slope of the ramp.

Design Requirements: Per California Government Code 4451(d), until such building standards are published in the California Building Standards Code that meet or exceed the requirements of the federal Americans with Disabilities Act, and specifically in this case the Americans with Disabilities Act Standards for Accessible Design Section 4.7.7, the DSA will accept curb ramp designs which indicate detectable warnings at curb ramps regardless of slope.

DETECTABLE WARNINGS

IR 11B-4

References:

2001 California Building Code (CBC), Sections 1117A.4.5, 1127B.5 Item 8,
1133B.8.3, and 1133B.8.5
2007/2010 CBC, Sections 1112A.9, 1121B.3.1 Item 8(a), 1127B.5 Item 7,
1133B.8.5 and Figure 11B-23A
California Government Code, Sections 4451(d) & (f)

Revised 11-18-11
Revised 11-01-07
Issued 01-26-05
See IR 11B-3



Discipline: Access Compliance

This Interpretation of Regulations (IR) is intended for use by the Division of the State Architect (DSA) staff, and as a resource for design professionals, to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. This IR indicates an acceptable method for achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

This IR is reviewed on a regular basis and is subject to revision at any time. Please check the DSA web site for currently effective IRs. Only IRs listed in the document at <http://www.dgs.ca.gov/dsa/Resources/IRManual.aspx> at the time of plan submittal to DSA are considered applicable.

Purpose: This interpretation clarifies acceptable alternative design and installation requirements for detectable warnings under Division of the State Architect (DSA) jurisdiction, which includes state funded buildings and facilities, State of California public elementary and secondary schools (grades K-12), community colleges, and universities. (In the 2010 California Building Code, item 1 below has been addressed by removing the requirement for a “staggered” pattern from Section 1121B.3.1 Item 8(a) and revising Figure 11B-23A consistently.)

General: The California Building Code indicates technical criteria for detectable warning surfaces (truncated domes). The technical criteria include dome pattern, dome spacing and dimensional placement.

The U.S. Access Board develops the minimum design standards for complying with the ADA, and has also developed and considered detailed research studies regarding pedestrians and the use of detectable warning surfaces. Under the Access Board, the Public Rights-of-Way Access Advisory Committee was established in 1999 to develop additional ADAAG provisions. The advisory committee reached agreement on recommended accessibility standards for new and altered public rights-of-way covered by the ADA. The standards proposed by the committee were presented in a report titled *Building a True Community*. The draft guidelines issued by the Access Board, consistent with the advisory committee's recommendations, include revised technical criteria for detectable warnings.

The U.S. Department of Transportation (USDOT) is a designated agency responsible for enforcing the standards and implementing regulations of the ADA Title II (State and Local Government Services). The Federal Highway Administration (FHWA), under the USDOT, is the enforcement authority for overseeing pedestrian discrimination issues under the Title II implementing regulations. Both FHWA and the Access Board are encouraging the use of the new technical criteria for detectable warnings over the original ADA design standard.

Acceptable Alternative Designs: The Division of the State Architect (DSA) recognizes the federal research effort and that the new technical criteria provide substantially equivalent or greater access and usability as modified and specifically indicated below.

Regarding the dome pattern and dome spacing for detectable warnings, the DSA will accept, as an acceptable alternative design, detectable warning surfaces that comply with all of the following:

1. Pattern: Detectable warnings consisting of a surface with truncated domes that are aligned in a square grid (in-line) pattern.
2. Dome Spacing: Truncated domes aligned in a square grid (in-line) pattern shall have a center-to-center spacing of 1.67 inches (42.4 mm) to 2.35 inches (59.7 mm).

In addition to the above criteria regarding detectable warning design, the DSA will accept, as an acceptable alternative design, dimensional placement of detectable warning surfaces at curb ramps that comply with the following criteria:

3. Dimensional Placement at Curb Ramps: The detectable warning surface shall extend 36 inches (914.4 mm) minimum in the direction of travel for the full width of the curb ramp. For curb ramps, also see IR 11B-2 and 11B-3.

**MECHANICAL ONLY PROJECTS
EXEMPT FROM ACCESSIBILITY REVIEW**

IR 11B-6

References:
California Building Code, Section 1134B.2.1, Exception 4

Revised 01-01-11
Issued 02-04-08

Discipline: Access Compliance

This Interpretation of Regulations (IR) is intended for use by the Division of the State Architect (DSA) staff, and as a resource for design professionals, to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. This IR indicates an acceptable method for achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

This IR is reviewed on a regular basis and is subject to revision at any time. Please check the DSA web site for currently effective IRs. Only IRs listed in the document at <http://www.dgs.ca.gov/dsa/Resources/IRManual.aspx> at the time of plan submittal to DSA are considered applicable.

Purpose: The purpose of this Interpretation of Regulations (IR) is to clarify that *mechanical only* projects do not require DSA Access Compliance review.

Discussion: *Mechanical only* means projects where all work is undertaken solely for the purpose of heating, ventilation or air conditioning (HVAC). California Building Code (CBC) Section 1134B.2 indicates that all existing buildings and facilities, when alterations, structural repairs or additions are made to such buildings or facilities, shall comply with all provisions of Division I, New Buildings.

However, the building code also states that for existing buildings, projects which consist *only* of HVAC are not considered alteration projects for the purposes of accessibility for persons with disabilities and are not subject to the accessibility provisions of the code.

DSA Access Compliance considers structural work that is required solely for the purpose of performing the mechanical work to be incidental to the mechanical project which is exempt work per CBC Section 1134B.2.1, Exception 4.

Exemption from DSA Access Compliance Review: Mechanical only projects are exempt by accessibility code provisions and do not require DSA Access Compliance review or approval. This includes mechanical only projects that contain incidental structural upgrades required solely for the purpose of performing mechanical only work. It should be noted that compliance with the building code is still required (i.e. the height of thermostats shall be installed 48" above the finish floor to the operating handle).

REQUIREMENTS FOR ACCESSIBLE PARKING SPACES

IR 11B-7

References:

2007/2010 California Building Code, Sections 1129B.3 and 1129B.4,
Figures 11B-18A, 11B-18B and 11B-18C

Revised 01-01-11
Revised 08-01-09
Issued 07-15-08

Discipline: Access Compliance

This Interpretation of Regulations (IR) is intended for use by the Division of the State Architect (DSA) staff, and as a resource for design professionals, to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. This IR indicates an acceptable method for achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

This IR is reviewed on a regular basis and is subject to revision at any time. Please check the DSA web site for currently effective IRs. Only IRs listed in the document at <http://www.dgs.ca.gov/dsa/Resources/IRManual.aspx> at the time of plan submittal to DSA are considered applicable.

Purpose: The purpose of this Interpretation of Regulations (IR) is to clarify requirements for accessible parking.

Background: On October 10, 2007 the Governor of California approved Assembly Bill (A.B.) 1531 (2007). A.B. 1531 does the following:

- Amends the requirements for signage and striping at accessible parking spaces,
- Directs that the initial regulations to implement these provisions shall be adopted as emergency regulations,
- Provides that the adoption of these regulations shall be considered by the Department of General Services (DGS) to be an emergency necessary for the immediate preservation of the public peace, health and safety, or general welfare.

On May 21, 2008 the California Building Standards Commission approved amended regulations proposed by DGS implementing A.B. 1531. The amended regulations became effective July 1, 2008 and on January 1, 2009 were published in the 2007 California Building Code, Sections 1129B.3 and 1129B.4, and Figures 11B-18A, 11B-18B and 11B-18C.

Scope: The amended regulations apply to all new construction projects and alterations to existing buildings and facilities covered by California Building Code, Chapter 11B. Construction documents submitted to DSA for review and approval on or after July 1, 2008 must indicate compliance with the amended regulations.

1. Signage Requirements: The amended regulations indicate that the signage at accessible parking spaces shall include "Minimum Fine \$250" below the International Symbol of Accessibility as either an additional sign or additional language. This fine posting requirement is in addition to other signage regulations contained in the California Building Code for accessible parking spaces.

2. Striping Requirements: The revised regulations indicate that the accessible parking space striping shall be as follows:

- The border (perimeter) of the loading and unloading access aisle shall be painted blue.
- The hatching within the loading and unloading access aisle shall be painted a suitable contrasting color to the parking space at 3'-0" maximum on center. Blue or white paint is preferred.

The amended regulations for the border and hatching at the loading and unloading access aisle are in addition to other requirements indicated in the California Building Code for accessible parking spaces.

The requirement that the hatching at the loading and unloading access aisle be a suitable contrasting color to the parking space is intended to ensure that the hatching is visually distinct from the background to which it is applied, and thus can be more easily seen. As hatching is generally recognized as a no-parking area, this difference in contrast assists drivers in providing a conspicuous visual deterrent to parking in the loading and unloading access aisle.

3. Acceptable Designs: Asphalt is often the parking surface material used at accessible parking spaces. Asphalt is generally considered to be fairly dark in appearance. In order to provide a suitable contrasting color at the hatched area of the loading and unloading access aisle, a light color hatching must be used at locations where asphalt is the parking surface material. Although white paint is preferred (and traditionally the color most often used), its use is not mandatory under the CBC.

In order to provide a suitable contrast at the hatching of the loading and unloading access aisle in locations where light concrete is used as the parking surface material (such as at concrete parking garages), a dark color hatching must be used. Although blue paint is preferred, its use is not mandatory under the CBC

**USE OF PREDETERMINED CONSTRUCTION
TOLERANCE GUIDELINES FOR ACCESSIBILITY**

IR 11B-8

References: 2007/2010 California Building Code, Section 1101B.5

Revised 01-01-11
Issued 11-19-09

Discipline: Access Compliance

This Interpretation of Regulations (IR) is intended for use by the Division of the State Architect (DSA) staff, and as a resource for design professionals, to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA. This IR indicates an acceptable method for achieving compliance with applicable codes and regulations, although other methods proposed by design professionals may be considered by DSA.

This IR is reviewed on a regular basis and is subject to revision at any time. Please check the DSA web site for currently effective IRs. Only IRs listed in the document at <http://www.dgs.ca.gov/dsa/Resources/IRManual.aspx> at the time of plan submittal to DSA are considered applicable.

Purpose: This Interpretation of Regulation clarifies DSA's position regarding the use of construction tolerance guidelines related to accessibility provisions contained in the California Building Code.

Background: Often, the subject of construction tolerance arises with regard to provisions for accessibility as indicated in California Building Code Section 1101B.5. Requests have been received for DSA to predetermine guidelines for what is considered an acceptable construction tolerance for various architectural components.

1. LEGAL ISSUES: According to the California Attorney General's office, developing guidelines for construction tolerances *"...unnecessarily encourages contractors and others to deviate from the access regulations found in the California Building Code..."*¹

The California Attorney General's office also indicated *"we are concerned that local building officials and members of the general public, when they consult Construction Tolerance Guidelines,...may assume that they have been adopted by a state agency and therefore, have the force of state law, which they do not. Such reliance, in our view, may result in violations of the California Building Code and, possibly, litigation against local building officials and/or property owners."*¹

Separately, a United States District Court case discussed the term "conventional building industry tolerances" as follows:

*"What is an acceptable 'dimensional tolerance' obviously will vary, depending in part upon the purpose for the standard and the technological capacity to closely adhere to the target dimensions."*²

2. REGULATORY BUILT-IN TOLERANCES: California Building Code Section 1101B.5 indicates all dimensions are subject to conventional industry tolerances except where the requirement is stated as a range with specific minimum and maximum end points. Where a California Building Code requirement states a specified range, such as in Section 1133B.4.2.1 where handrails must be installed between 34 inches and 38 inches above the nosing, the regulation itself already provides an adequate tolerance and therefore no further tolerance outside of the range at either limit is permitted. In such cases, the technological capacity to achieve literal compliance with the dimensional requirements is quite easy to accomplish.

3. MINIMUMS, MAXIMUMS AND SPECIFYING AT THE LIMIT: Where an element is to be installed at the minimum or maximum permitted dimension, such as "48 inches maximum", it is not good practice to specify 48 inches, although it is allowed. Rather, it would be good practice to specify a dimension less than the required maximum (or more than the required minimum) by the amount of the *expected* field or manufacturing tolerance and not to state any tolerance in conjunction with the specified dimension.

In other words, dimensions noted in accessibility provisions as "maximum" or "minimum" should not be considered dimensions for design, because they represent the absolute limits of a requirement. To be sure that field tolerances result in usable construction, notes and dimensions in construction documents should identify and incorporate *expected* tolerances so that a required dimensional range is not exceeded by the addition of a finish material or a variation in construction practice, to the maximum extent feasible.

Specifying dimensions for design in the manner described above will better ensure that facilities and elements accomplish the level of accessibility intended by the requirements. It will also more often produce an end result of strict and literal compliance with the stated requirements and eliminate enforcement difficulties and issues that might otherwise arise.

On the other hand, by voluntarily choosing to specify the exact maximum limit or the exact minimum limit of a requirement for design, field construction based on such specification may unnecessarily fail to achieve the compliance that is required. In such cases the failure is not necessarily a consequence of field tolerance, but rather it is a result of the decision to design at the very edge of the prescribed limit.

4. ABSOLUTE DIMENSIONS: In the few cases where absolute dimensions are indicated, the application of construction tolerances is most likely to be influenced. In construction, the technological capacity to achieve an exact and precise placement of an architectural element in some cases can be quite difficult. In addition, the technological capacity to place one particular architectural element at a specific distance may not be the same for a different architectural element. For instance, consider the requirement that water closets (toilets) be an absolute 18" from the adjacent wall to the centerline. Variations in wall finish thicknesses or structural members could easily influence the final constructed condition, especially in concrete slab construction.

In such water closet installations, it would not be unusual to see minor ½" deviations (17½" to 18½") based on these field conditions. Therefore, it is reasonable to assume that at least some minor deviation from absolute dimensions could be expected for water closets.

In recent projects however, water closet centerline dimensions in newly constructed toilet rooms for adults measured as much as 21" and as little as 15" from the adjacent wall. In both cases the amount of variation equaled or even exceeded the entire thickness of the combined wall finishes. Under analysis, it was clear that the lack of care and coordination exercised in the planned placement of the wall, the rough plumbing, and the wall finish was the cause of the deviation, rather than any field condition or manufacturing variant.

While acceptance of a ½" water closet centerline variance may be allowed as a DSA jurisdictional building code approval, it should be noted that such acceptance may not necessarily have effect or provide immunity under a judicial review.

5. ESTABLISHING TOLERANCE GUIDELINES: In conclusion, establishing predetermined construction tolerances guidelines related to the requirements for accessibility contained in the California Building Code is inappropriate.

As previously stated, the California Attorney General's office has indicated that construction tolerance guidelines *"may wrongfully be viewed by some to have the effect of law"*¹ and *"unnecessarily encourages contractors and others to deviate from the access regulations contained in the California Building Code."*¹

The use of predetermined construction tolerance guidelines allows a blanket acceptance of departures from the building code requirements with no analysis as to the reason the use of a tolerance is either justified or warranted. As a result, the guidelines are then arbitrarily substituted for building code requirements, without taking into account the specific facts of each circumstance.

It is preferred that construction tolerance acceptance be on a case-by-case basis, with the degree of departure from the literal requirements coupled with the specific reason that the requirement was unable to be achieved as the basis to be utilized for analysis. Many times when questions arise regarding tolerances, it is often found after analysis that neither field conditions nor manufacturing variables contributed to the deviation, but rather there was simply a lack of proper planning or coordination. Inadequate planning and coordination are not justifications for the use of construction tolerances.



Endnotes

¹ Letter from the State of California Department of Justice to the Orange Empire Chapter of the International Conference of Building Officials dated August 22, 2002.

² Independent Living Resources v. Oregon Arena Corporation

DSA Access Compliance Official Comments (Checklists)

**DSA – 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL
OFFICIAL COMMENTS (CHECKLISTS)**

Introduction

Section 5 – Official Comments (Checklists): This section contains a collection of 25 subject-specific checklists covering a variety of accessibility topics which may be applicable to construction projects typically submitted to DSA. We have attempted to include relevant citations of accessibility requirements from the CBC and the ADA Standards for Accessible Design. The checklists are intended for use by DSA staff and as a resource for design professionals to promote more uniform statewide criteria for plan review and construction inspection of projects within the jurisdiction of DSA.

CHECKLIST TABLE OF CONTENTS

1	General Requirements
2	Site Requirements
3	Accessible Route of Travel
4	Accessible Parking, Passenger Loading, and Bus Stops
5	Curb Ramps and Pedestrian Crossings
6	Walks and Sidewalks
7	Accessible Ramps
8	Doors and Gates
9	Corridors, Hallways, and Vestibules
10	Stairs and Steps
11	Accessible Means of Egress
12	Elevators and Platform (Wheelchair) Lifts
13	Public Telephones
14	Drinking Fountains
15	Sanitary Facilities
16	Alarms
17	Signage and Way-Finding
18	Assembly Use Areas
19	Business and Mercantile Use Areas
20	Educational Use Areas
21	Institutional Use Areas
22	Residential Use Areas
23	Other Use Areas
24	Qualified Historical Buildings
25	Specifications

COMMONLY USED ABBREVIATIONS

ADA	Americans with Disabilities Act	PD	Project Designer
ADA Stds	ADA Standards for Accessible Design as adopted by the US Department of Justice	PRC	California Public Resources Code
ADAAG	Americans with Disabilities Act Accessibility Guidelines	PTD	Paper towel dispenser
AFF	Above finished floor	Qty	Quantity
ANSI	American National Standards Institute	REF	Reference
ASME	American Society of Mechanical Engineers	req.	Requirement
ASTM	American Society for Testing and Materials	RO	DSA Regional Office
BHMA	Builders Hardware Manufacturers Association	ROM	Regional Office Manager
CA	California	SD	Soap dispenser
CBC	California Building Code	sec.	Second (1/60 minute)
CBSC Part 1	California Building Standards Administrative Code	Sec.	Section
CBSC	California Building Standards Code or Title 24 of the California Code of Regulations	sf	Square foot
CC	California Civil Code	SFM	California State Fire Marshal
CCR	California Code of Regulations	tbd	To be determined
CEC	California Electrical Code	Tbl.	Table
CESCC	California Elevator Safety Construction Code	Title 24	Title 24 of the CCR
CFC	California Fire Code	UFAS	Uniform Federal Accessibility Standards
CFR	Code of Federal Regulations	USAB	United States Access Board
CHBC	California Historical Building Code	USDOJ	U.S. Department of Justice
cl	Center line	u.o.n.	Unless otherwise noted
CMC	California Mechanical Code	VC	California Vehicle Code
CPC	California Plumbing Code	WC	Water closet
CRSC	California Reference Standards Code	Y	Yes
D.A.	Designated accessible	28 CFR 35	DOJ's Rule for ADA Title II
Dept.	Department	28 CFR 36	DOJ's Rule for ADA Title III
DF	Drinking fountain		
DGS	Department of General Services		
Dims	Dimension, measurement		
DSA	Division of the State Architect		
DSA-AC	DSA Access Compliance Program		
Fig.	Figure		
GC	California Government Code		
H&SC	California Health and Safety Code		
HQ	Headquarters		
IBC	International Building Code		
incl.	Including		
ISA	International Symbol of Accessibility		
IR	Interpretation of Regulations		
Lab	Laboratory		
Lav	Lavatory		
lbs.	Pound		
If	Linear foot		
max	Maximum		
min	Minimum		
MOD	Modernization project		
MOU	Memorandum of understanding		
N	No		
N/A	Not applicable		
NFPA	National Fire Protection Association		
NT	Non-typical		
o.c.	On center		
		'	Foot
		"	Inch
		%	Percent
		<	Less than
		>	More than
		≤	Less than or equal
		≥	More than or equal

1

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 1. GENERAL REQUIREMENTS

GENERAL SUBMITTAL NOTES

- Plans and specifications shall be sufficient to show extent of work and shall be complete at the time of submittal. Plans that are incomplete will not be reviewed and DSA will issue a notification letter to the PD and the school district. A construction document set may be considered for rejection by DSA for any of the following reasons:
 1. Excessive coordination errors (no more than ten per project). Civil, architectural, structural, mechanical, plumbing, landscaping, and electrical plans and specifications should be coordinated to match.
 2. Excessive, incompletely dimensioned details from site plan, floor plans, and interior elevations.
 3. Absence of coordinated signage schedule indicating the location and mounting height of signs.
 4. Absence of accessible parking plans and details indicating dimensioned clearances, slopes, transitions between materials, signage, and parking ratios.
 5. Modernization project site plans on which no path of travel is indicated to accessible toilets and area of new work.
 6. Incomplete plan set as indicated on the index sheet.
 7. Lacking application, check, plans or specifications.
 8. Assembly rooms without seating plans and details, no accessible seating locations with companion seating, or non-equitable lines of sight (includes stadiums and bleachers).
 9. Doors without all required clearances fully dimensioned.
 10. Missing details for ramps, curb cuts, transitions, elevators, stairs, lifts, thresholds, or cross slopes.
 11. Absence of dimensioned restroom plans enlarged to 1/4 inch scale and interior elevations with fixture locations and accessory mounting heights.
 12. Incomplete door schedule lacking:
 - Size of doors
 - Hardware groups
 - Threshold details referenced
 - Signage coordination (details referenced and copy)
 13. Assembly room plans which do not indicate assistive listening devices, as required, with signage.
- Reviewer will review all items related to accessibility, provided by project designer (PD), in specifications and in plans, including floor plans, elevations, sections, and details, to make sure all construction work is accessible. For DSA policies, practices and procedures, go to the DSA website at: www.dgs.ca.gov/dsa/
- Reviewer will review preliminary design meeting notes (prepared and submitted by PD).

CBSC Part 1, 4-317(b)2

Information on plans and specifications

DSA Plan Check Procedures

DSA Plan Check Procedures

1

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 1. GENERAL REQUIREMENTS

GENERAL PLAN REVIEWER NOTES

G.1	Provide the following for this element or area: 1. Enlarged Plans 2. Sections 3. Elevations 4. Details	CBSC Part 1 4-317(b)	Plans
G.2	Coordinate element(s) in architectural, structural, mechanical, plumbing, or electrical drawings (plans, sections, elevations, or details) with the one shown in this area.	CBSC Part 1 4-317(b)	Plans
G.3	Provide all sheets, sections, elevations, and details as indicated in plans.	CBSC Part 1 4-317(b)	Plans
G.4	Coordinate element(s) with specifications.	CBSC Part 1 4-317(b)	Plans
G.5	Indicate scale on drawing.	CBSC Part 1 4-317(b)	Plans
G.6	Provide missing dimension(s).	CBSC Part 1 4-317(b)	Plans
G.7	Update old code citation with current one.	CBSC Part 1 4-317(b)	Plans
G.8	Typical (applies to all similar situations in this project).	CBSC Part 1 4-317(b)	Plans
G.9	Provide absolute dimensions, not a range, in construction documents.	CBSC Part 1 4-317(b)	Plans
G.10	Provide enlarged plan or detail, showing all relevant dimensions to clearly indicate how accessibility requirements are met.	CBSC Part 1 4-317(b)	Plans
G.11	Delete the term "handicap" and/or "H/C". Use "accessible", "ACC" for accessible, or "D.A." for disabled access(ibility) instead.	Appendix B to 28 CFR 35.104 & VC §22511.9	Definitions Disabled person sign
G.12	Identified work, element, furniture, equipment, or layout, even though labeled NIC or provided by the owner, is integral to access compliance of this submittal. Specify dimensions and locations of work or element.	CBSC Part 1 4-317(b)	Plans
G.13	In new construction, additions, and in areas of alteration, full compliance must be provided.	CBSC Part 1 4-317(b)	Plans
G.14	PD may consider submitting a written application for unreasonable hardship to DSA and providing equivalent facilitation.	CBC 202 CBC 1102B	Definitions Definitions
G.15	Shown equivalent facilitation does not provide equal or greater accessibility and protection, as provided under federal law.	CBC 1102B & GC §4451(f)	Definitions Access to public buildings
G.16	Bring manufacturer cut-sheets or product sample of specified element to back check.	DSA Plan Check Procedures	

1

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 1. GENERAL REQUIREMENTS

GENERAL REQUIREMENTS

1.1 State and federal rules require, as do the statutes, that newly constructed facilities be readily accessible to and usable by individuals with disabilities. The phrase "readily accessible to and usable by individuals with disabilities" is a term that, in slightly varied formulations, has been used in the Architectural Barriers Act of 1968, the Fair Housing Act, the regulations implementing section 504 of the Rehabilitation Act of 1973, California's Government Code, and current accessibility standards. It means, with respect to a facility or a portion of a facility, that it can be approached, entered, and used by individuals with disabilities (including mobility, sensory, and cognitive impairments) easily and conveniently. A facility that is constructed to meet the requirements of the rules' accessibility standards will be considered readily accessible and usable with respect to construction. To the extent that a particular type or element of a facility is not specifically addressed by the standards, the language of this section is the safest guide.

GC §4450 & Appendix B of 28 CFR Part 36

Access to public buildings

1.2 Show list of all current codes, regulations, and adopted standards, which apply for the project:

CBSC Part 1 4-317(b)

Plans

Applicable State Codes as of January 1, 2011

- 2010 Building Standards Administrative Code, Part 1, CBSC
- 2010 California Building Code (CBC), Part 2, CBSC (2009 IBC & California Amendments)
- 2010 California Electrical Code (CEC), Part 3, CBSC (2008 National Electrical Code & California Amendments)
- 2010 California Mechanical Code (CMC), Part 4, CBSC (2009 Uniform Mechanical Code & California Amendments)
- 2010 California Plumbing Code (CPC), Part 5, CBSC (2009 Uniform Plumbing Code & California Amendments)
- 2010 California Energy Code, Part 6, CBSC
- 2010 California Historical Building Code, Part 8, CBSC
- 2010 California Fire Code, Part 9, CBSC (2009 International Fire Code & California Amendments)
- 2010 California Referenced Standards, Part 12, CBSC
- Title 8 C.C.R., Ch. 4, Sub-Ch. 6 – Elevator Safety Orders
- Title 19 C.C.R., Public Safety, SFM Regulations

List of Federal Codes and Standards (if applicable)

- Americans with Disabilities Act (ADA), Title II or Title III
- For Title II: Uniform Federal Accessibility Standards (UFAS) or ADA Standards for Accessible Design (Appendix A of 28 CFR Part 36).
- For Title III: ADA Standards for Accessible Design (Appendix A of 28 CFR Part 36)

28 CFR 35.151(c)

28 CFR 36.406

NOTE:
Title II applies to projects funded and/or used by state and local government services. Title III covers public accommodations and commercial facilities. Depending on the use and funding, both titles may apply to a project.

1

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 1. GENERAL REQUIREMENTS

Partial List of Applicable Referenced Standards

- NFPA 13, Installation of Sprinkler Systems, 2010 Edition
- NFPA 72, National Fire Alarm Code (CA Amended) 2010 Edition (see UL Standard 1971 for "Visual Devices")
- Reference code section for NFPA Standards-CBC (SFM) Chapter 35.
- ASME A17.1/CSA B44-2007
- ASME A18.1-2005
- ASTM F 1487-98 Standard Consumer Safety Performance Specification for Playground Equipment for Public Use.
- ASTM F 1951-99 Standard Specification for Determination of Accessibility of Surface Systems Under and Around Playground Equipment.
- ASTM F 1292-99 Standard Specification for Impact Attenuation of Surface Systems Under and Around Playground Equipment.
- BHMA A156.10-2006 American National Standard for Power Operated Pedestrian Doors
- BHMA A156.19-2002 American National Standard for Power Assist and Low Energy Power Operated Doors

1.3 Provide list of code analysis data: construction type, area square footage, occupancy classification, occupancy load, and fire sprinklers, if applicable.

CBSC Part 1, 4-317

Plans, specs and other data

1.4 Describe the scope of work covered under this application. Identify the area, category, and type of project.

1.5 In order to clarify the scope of work, describe the relationship of this application with previous or upcoming projects at the same site and provide DSA application numbers for all buildings, paths of travel, parking, passenger loading zones, sanitary facilities, drinking fountains, signage, and public telephones on this site (e.g., increments, phases, ADA Transition Plan efforts, etc).

CBSC Part 1 4-317(b)

CATEGORIES OF PROJECTS:

- New construction
- Alteration w/o state funds
- Alteration w/ state funds
- Additions
- Relocatables
- HCD relocatables
- ADA-barrier removal
- Fire damage projects
- Historical properties
- MOU projects
- Housing
- Class size reduction
- Other

1.6 Due to the difficulty of anticipating every unsatisfactory condition that might exist in connection with the existing facility where alteration work is proposed, the following clause or one of similar meaning must be included in the specifications or in the general notes:

CBSC Part 1, 4-317

The intent of the drawings and specifications is to modify the facility for accessibility in accordance with Title 24, California Code of Regulations. Should any conditions develop not covered by the contract documents such that the finished work will not comply with said Title 24, California Code of Regulations, a change order detailing and specifying the required work shall be submitted to and approved by DSA-AC before proceeding with the work.

1.7 Indicate whether the facility is a qualified historical building and provide details showing whether the alteration is using alternatives in compliance with California State Historical Building Code (see Checklist 24).

CBC 1135B.1 CBSC Part 8, Ch 8-6

Historical preservation – General CA Historical Building Code

1

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 1. GENERAL REQUIREMENTS

1.8 Stamp or license of design professional is missing or expired, renew and stamp plans for back check.

CBSC Part 1 4-316(c)

Assumption of responsibility

1.9 For new construction projects: provide full accessibility to all areas of facilities or portions of facilities, including exterior routes of travel and all floors, including split levels, platforms, podiums, sunken areas, balconies, roof gardens, and mezzanines. Modify scoping of the project accordingly and indicate clearly on drawings how this requirement is being met.

GC §4450
CBC 1103B.1 &
CBC 1127B.1

Access to public buildings
Building accessibility - General
Exterior routes of travel

EXCEPTIONS:

- a. Floors or portions of floors not customarily occupied, including, but not limited to, non-occupiable or employee spaces accessed only by ladders, catwalks, crawl spaces, very narrow passageways, or freight (non-passenger) elevators, and frequented only by service personnel for repair or maintenance purposes, including, but not limited to, elevator pits and elevator penthouses, piping and equipment catwalks, and machinery rooms.

28 CFR 35.130(b)(4): A public entity may not, in determining the site or location of a facility, make selections –

- (i) That have the effect of excluding individuals with disabilities from, denying them the benefits of, or otherwise subjecting them to discrimination; or
- (ii) That have the purpose or effect of defeating or substantially impairing the accomplishment of the objectives of the service, program, or activity with respect to individuals with disabilities.

1.10 For alteration, renovation, structural repair, or addition projects: provide full accessibility within the area of specific alteration. All proposed work must comply fully with the requirements for new construction (see Item 1.9, including exception). Scoping of the project shall be shown clearly on drawings indicating how this requirement is being met.

GC §4450
CBC 1134B.2

Access to public buildings
Accessibility for existing buildings

1.11 In alteration, renovation, structural repair, or addition projects, the following elements, serving the specific area of alteration must be made accessible:

CBC 1134B.2.1

Accessibility for existing buildings

- 1. A primary entrance to the building, facility, or exterior area that is being altered.
- 2. A primary path of travel to the specific area of alteration, including: a path of travel from the site entry point (at the public right-of-way) that is closest to public transportation stops; a path of travel from on-site transportation stops; designated accessible parking; a path of travel from designated accessible parking; and identifying and directional signage.
- 3. Sanitary facilities serving the area.
- 4. Drinking fountains serving the area.
- 5. Signage.
- 6. Public telephones serving the area.

DEFINITIONS:

ALTERATION OR ALTER: Any change, addition, or modification in construction or occupancy or structural repair or change in primary function to an existing structure made by, on behalf of, or for the use of a public accommodation or commercial facility.

ADDITION: An extension, expansion or increase in floor area or height of a building, facility or structure.

1

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 1. GENERAL REQUIREMENTS

1.12 Modify scoping of the project and all related drawings to indicate clearly how scoping requirements are being met.

EXCEPTIONS:

a. Alteration Projects below the Cost Cap:

When the total construction cost of alterations is less than \$132,536.28 (in 2011), and DSA finds that full compliance creates an unreasonable hardship, and equivalent facilitation is provided, compliance shall be limited to the actual alteration work.

An unreasonable hardship exists where the cost of providing an accessible entrance, path of travel, sanitary facilities, public phones and drinking fountains, exceeds 20% of the cost of the project without these features. In such a case, access must be provided to the extent that it can be without incurring disproportionate cost (up to 20%).

PD must apply for unreasonable hardship in writing and provide construction history for this site for the previous three years, and construction cost documentation.

When scoping the project, priority should be given to those elements that will provide the greatest access in the following order:

1. An accessible entrance.
2. An accessible path of travel to the altered area.
3. At least one accessible restroom of each type for each sex serving the area of alteration.
4. Accessible telephones.
5. Accessible drinking fountains.
6. Additional accessible elements.

b. Barrier Removal Projects

Alterations that are limited to the removal of architectural barriers are not subject to the accessibility requirements in CBC 1134B.2.1. Exception 3 of Section 1134B.2.1 is not intended to relieve projects from complying with all applicable provisions within the specific area of alteration.

c. Other Alteration Projects

Alteration projects that consist only of heating, ventilation, air conditioning; re-roofing; electrical work not involving placement of switches and receptacles; cosmetic work (e.g. painting, carpeting) that does not affect items regulated by the CBSC, etc. are not considered alterations for the purpose of accessibility and are not subject to the accessibility requirements in CBC 1134B.2.1.

Exception 4 of CBC 1134B.2.1 is not intended to relieve projects from complying with other applicable provisions of the CBC (e.g., replacement of carpet does not activate the

CBSC Part 1 4-317(b)

CBC 1134B.2.1

CBC 202 & GC §4451(f)

CBC 1134B.2.1 - Exception 3

CBC 1134B.2.1 - Exception 4

Plans

Accessibility for existing buildings Exception 1

NOTE:
Exception (a) is based on the January ENR Index and will be updated annually (January). See <http://www.dgs.ca.gov/dsa/Programs/progAccess/threshold.aspx>

Definitions
Access to public buildings

Accessibility for existing buildings

NOTE:
Exception (b) does not apply to facilities for which construction started after January 26, 1992.

Accessibility for existing buildings

1

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 1. GENERAL REQUIREMENTS

provisions of this section; however, the new carpet still must comply with CBC 1124B.3).

PD must provide information related to applicable accessibility requirements for all planned elements and features in the specific area of alteration.

d. Alteration Projects with Department of Education (CDE) or Office of Public School Construction (OPSC) Funding

Alteration projects that are wholly or in part funded by CDE or OPSC, and which consist only of heating, ventilation, air conditioning; re-roofing; electrical work not involving placement of switches and receptacles; cosmetic work (e.g. painting, carpeting) that does not affect items regulated by the CBSC, etc. are not considered alterations for the purpose of accessibility and are not subject to the accessibility requirements in CBC 1134B.2.1.

However, OPSC makes an additional 3% of funding available for Access and Fire-Life-Safety beyond the building envelope, plus provides an allocation for required elevators.

Scoping of the project and all drawings shall indicate clearly how this requirement is met. Provide cost documentation.

CBC 1134B.2.1 - Exception 4

Accessibility for existing buildings

CBSC Part 1 4-317(b) &

Plans

1.13 Special requirements for school modernization projects:

1. Provide information related to the project consistent with the district's ADA Transition Plan for the facilities.
2. If elevators are required by DSA in writing at preliminary phase, partial funding for elevator can be granted by OPSC, in addition to the basic funding package.
3. Alteration projects under \$35,623.28 (in 2009) need not be submitted to DSA, however, all work must be code-compliant. Also, projects between \$35,623.28 and \$142,493.12 may not require DSA review when specific conditions are met.

CBSC Part 1 4-317(b)

Plans

CBSC Part 1, 4-308
4-308
CBSC Part 1 4-309
DSA-IR A-10

Reconstruction or alterations not in excess of \$25,000 in cost
Reconstruction or alterations in excess of \$25,000 in cost
Reconstruction and alteration projects – Exemption from DSA approval

NOTE: Cost threshold is based on the January ENR Index and will be updated annually.

1.14 Provide the following note on drawings for projects that include deferred approval items for access related equipment or elements: "Installation of deferred approval items shall not be started until contractor's drawings, specifications and engineering calculations for the actual systems to be installed have been accepted and signed by the Architect or Structural Engineer and approved by DSA."

CBSC Part 1 4-317(b)

Plans

1.15 Charter schools must submit plans to DSA for approval.

CBC 1.9.1.4

Enforcing agency

2

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings/ Comments / Notes / & Examples

Check List 2. SITE REQUIREMENTS

2.1 New construction: All proposed site work, including choice of location, site development and grading, must be designed to provide access to all new building entrances and exterior ground-floor exits, access to normal routes, and where necessary to provide access, shall incorporate ramps, curb ramps, etc. When more than one building or facility is located on a site, an accessible route of travel shall be provided between all buildings and accessible site facilities. The accessible route of travel shall be the most practical direct route between accessible building entrances, accessible site facilities and the accessible entrance to the site. Where more than one route of travel is provided, all routes shall be accessible.

EXCEPTION:

Where DSA determines that compliance with this requirement would create an unreasonable hardship because of topography, natural barriers, etc., an exception may be granted when equivalent facilitation is provided through the use of other methods and materials.

2.2 Alterations, structural repairs or additions: All proposed work must comply fully with the requirements for new construction (see Checklist Item 2.1).

EXCEPTIONS:

a. Where DSA determines that compliance with this requirement would create an unreasonable hardship because of topography, natural barriers, etc., an exception may be granted when equivalent facilitation is provided through the use of other methods and materials.

b. The requirements do not apply in those conditions where DSA determines that, due to legal or physical constraints, the site of the project would not allow compliance with this requirement or equivalent facilitation without creating an unreasonable hardship.

2.3 The site is an important part of a building or facility, and the PD must ensure that buildings or facilities can be approached and entered easily and conveniently. Site plans shall meet the following requirements:

1. Use larger scale to more clearly show relevant elements.
2. Change graphic layout and/or line weights and types to better represent access compliance.
3. Provide names and/or designations for all existing buildings.
4. Provide and indicate DSA application numbers for all existing buildings affected by project scope. Alterations are not permitted to previously uncertified construction.

CBC 1134B.2

CBC 1.9.1.4 & CBC 1127B.1

CBSC Part 1 4-317(b)

28 CFR 35.130(b)(4): A public entity may not, in determining the site or location of a facility, make selections –

- (i) That have the effect of excluding individuals with disabilities from, denying them the benefits of, or otherwise subjecting them to discrimination; or
- (ii) That have the purpose or effect of defeating or substantially impairing the accomplishment of the objectives of the service, program, or activity with respect to individuals with disabilities.

General

Enforcing agency
Exterior routes of travel - General

NOTE:
Jurisdictional findings and determinations are subject to an internal DSA appeals process.

Plans

NOTE:
Call DSA's Regional Office Supervisor for information on the certification process of existing buildings without a DSA application number.

2

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings/ Comments / Notes /
& Examples

Check List 2. SITE REQUIREMENTS

2.4 Indicate the following infrastructure on site plan:

1. Location of all sanitary facilities on site.

- A. Identify all sanitary facilities that are part of the project and provide DSA application number for existing sanitary facilities that were previously upgraded.
- B. Identify all existing sanitary facilities.
- C. Identify type of use (men's, women's, or unisex; single or multi-accommodation; employee, public, student, kindergarten, or visitor).
- D. Prior to back check, PD must field verify and indicate on plans compliance status with current standards of sanitary facilities serving the areas of construction. Fully compliant sanitary facilities should be identified as "accessible". Identified barriers that do not comply with current standards must be removed under this application or PD must file for unreasonable hardship.

2. Location of all on-site and associated off-site parking and passenger drop-off and loading zones.

- A. Provide parking ratio for all parking, indicating number of regular, accessible, van-accessible, and total spaces. Calculate each lot/area separately.
- B. Identify type of use (regular, accessible, or van-accessible; employees, students, or visitors), and provide DSA application number for existing parking and passenger loading zones that were previously upgraded.
- C. Identify all accessible parking spaces and passenger loading zones that are part of the project.
- D. Indicate 5' min wide access aisles adjacent to each accessible parking stall and 8' min wide access aisles on the passenger side of all van accessible parking stalls.
- E. Indicate location of accessible parking stall and "Tow-away" signage.
- F. Prior to back check, PD must field verify and indicate on plans compliance status with current standards of accessible parking and passenger loading zones serving the areas of construction. Fully compliant accessible parking and passenger loading zones should be identified as "accessible". Identified barriers that do not comply with current standards must be removed under this application or PD must file for unreasonable hardship.

3. Location of all drinking fountains on site.

- A. Identify all drinking fountains that are part of the project and provide DSA application numbers for existing drinking fountains that were previously upgraded.
- B. Identify all existing drinking fountains.

CBSC Part 1
4-317(b)
CBC 1115B

CBC 1134B.2.1,
CBSC, Part 1,
4-316(e) &
CBC 202

CBC 1129B &
CBC 1131B

CBC 1134B.2.1,
CBSC, Part 1,
4-316(e) &
CBC 202

CBC 1117B.1 &
CBSC Part 1
4-317(b)

Plans

Bathing and toilet facilities

Existing buildings
Designation of Responsibilities

Unreasonable hardship

Accessible parking required
Passenger drop-off and loading
zones

Existing buildings
Designation of Responsibilities

Unreasonable hardship

Drinking fountains
Plans

2

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings/ Comments / Notes /
& Examples

Check List 2. SITE REQUIREMENTS

<p>C. Identify type of use (single, multi, or hi-low unit; adult or children's height).</p> <p>D. Prior to back check, PD must field verify and indicate on plans compliance status with current standards of drinking fountains serving the areas of construction. Fully compliant drinking fountains should be identified as "accessible". Identified barriers that do not comply with current standards must be removed under this application or PD must file for unreasonable hardship.</p>	<p>CBC 1134B.2.1, CBSC, Part 1, 4-316(e) & CBC 202</p>	<p>Existing buildings Designation of Responsibilities</p> <p>Unreasonable hardship</p>
<p>4. Location of all public telephones.</p> <p>A. Identify all public telephones that are part of the project.</p> <p>B. Identify all existing public telephones and provide DSA application numbers for existing public telephones that were previously upgraded.</p> <p>C. Prior to back check, PD must field verify and indicate on plans compliance status with current standards of public telephones serving the areas of construction. Fully compliant public telephones should be identified as "accessible". Identified barriers that do not comply with current standards must be removed under this application or PD must file for unreasonable hardship.</p>	<p>CBC 1117B.2 & CBSC Part 1 4-317(b)</p>	<p>Telephones Plans</p> <p>Existing buildings Designation of Responsibilities</p> <p>Unreasonable hardship</p>
<p>5. Location of all ramps.</p> <p>A. Identify type of ramp (exterior, interior, covered ramp; curb ramp, built-up curb ramp).</p> <p>B. Identify all ramps that are part of the project and provide DSA application number for all ramps that were previously upgraded.</p> <p>C. Identify all existing ramps and indicate length, width, landings and slope.</p> <p>D. Indicate any slopes in the accessible route of travel that exceed 1:20 (5%) with an arrow, starting at the top of the ramp run and ending at the bottom of the ramp run.</p> <p>E. Prior to back check, PD must field verify and indicate on plans compliance status with current standards of all ramps serving the areas of construction. Fully compliant ramps should be identified as "accessible". Identified barriers that do not comply with current standards must be removed under this application or PD must file for unreasonable hardship.</p>	<p>CBC 1127B.5, 1133B.5 & CBSC Part 1 4-317(b)</p>	<p>Curb Ramps Ramps Plans</p> <p>Existing buildings Designation of Responsibilities</p> <p>Unreasonable hardship</p>
<p>6. Location of all stairs.</p> <p>A. Identify type of stairs (exterior, interior, covered stairs).</p> <p>B. Identify all stairs that are part of the project.</p> <p>C. Identify all existing stairs and provide DSA application numbers for all stairs that were previously upgraded.</p> <p>D. Indicate stairs or steps with arrow and label with direction. Specify details where applicable.</p>	<p>CBC 1133B.4 & CBSC Part 1 4-317(b)</p>	<p>Stairways Plans</p>

2

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings/ Comments / Notes /
& Examples

Check List 2. SITE REQUIREMENTS

<p>7. Location of all elevators and lifts.</p> <p>A. Identify type and provide DSA application number for all elevators or lifts that were previously upgraded.</p> <p>B. Identify all elevators or lifts that are part of the project.</p> <p>C. Prior to back check, PD must field verify and indicate on plans compliance status with current standards of elevators and lifts serving the areas of construction. Fully compliant elevators and lifts should be identified as "accessible". Identified barriers that do not comply with current standards must be removed under this application or PD must file for unreasonable hardship.</p>	<p>CBC 1116B & CBSC Part 1 4-317(b)</p> <p>CBC 1134B.2.1, CBSC, Part 1, 4-316(e) & CBC 202</p>	<p>Elevators and platform (wheelchair) lifts Plans</p> <p>Existing buildings Designation of Responsibilities</p> <p>Unreasonable hardship</p>
<p>2.5 Clearly delineate all accessible paths of travel by a dashed or dotted line (- · - ·) on site plans. See Checklist 3 for additional accessible routes of travel requirements.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>2.6 Provide the following note on site plan: Accessible path of travel as indicated on plan is a barrier-free access route without any abrupt level changes exceeding 1/2" if beveled at 1:2 max slope, or vertical level changes not exceeding 1/4" max, and at least 48" in width. Surface is stable, firm, and slip resistant. Cross slope does not exceed 2% and slope in the direction of travel is less than 5%, unless otherwise indicated. Accessible path of travel shall be maintained free of overhanging obstructions to 80" minimum, and protruding objects greater than 4" projection from wall and above 27" and less than 80". Architect shall verify that there are no barriers in the path of travel.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>2.7 Coordinate civil drawings with architectural drawings.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>2.8 Provide relevant spot elevations along the accessible route of travel on site plan. At a minimum, show elevations at:</p> <ol style="list-style-type: none"> 1. Interior finished floor of buildings. 2. Exterior entrance door landings. 3. Along sloped walks in intervals of 100 ft max. 4. Site entry points. 5. Ramp landings (top, bottom, intermediate). 6. Curb ramps (top, bottom). 7. Elevator landings. 8. Accessible parking and passenger drop-off zones. 9. Drinking fountains. 10. Exterior side of counters. 	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>2.9 Specify all surface materials (existing and new) along and adjacent to the accessible route of travel. Separate different surface areas by lines.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>

2

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings/ Comments / Notes / & Examples

Check List 2. SITE REQUIREMENTS

2.10 Identify all level changes between materials which exceed 1/4" vertical or 1/2" (if beveled at 1:2) in height along and adjacent to the accessible route of travel.


CBC 1133B.7.4 & CBSC Part 1 4-317(b)

Changes in level Plans

2.11 Indicate all ground floor entries/exits that are required to be accessible.

CBSC Part 1 4-317(b)


Plans



2.12 Indicate all existing and proposed curb cuts or curb ramps that are in the accessible route of travel. If new, specify details. If existing, indicate conditions (slope, width, landings) to show compliance status. Below are two acceptable examples.

CBSC Part 1 4-317(b) & CBC 1127B.5

Plans Curb ramps



2.13 Indicate warning curbs and tactile/visual indicators and specify detail.

CBC 1133B.8

Hazards

2.14 Where gates are within the accessible route of travel, indicate how gate will be used: Specify lever hardware and smooth surface at bottom 10" of gate (e.g. kick plate).

CBC 1133B.1.1.1.4

Gates

1. If gate is used as exit only, it must comply with exit door requirements (panic hardware and exit signs may be required to coordinate with Fire & Life Safety).

CBC 1008.2

Gates

2. In existing facilities, if an existing gate is used as entrance and exit, it must comply with exit door and general door requirements (panic hardware and exit signs may be required to coordinate with Fire & Life Safety). Specify door schedule number and detail (landings, hardware, kick-plate, strike edge clearance, clear opening).

CBC 1133B.1.1.1.4 & CBC 1008.2

Gates Gates

2.15 Indicate locations of all exterior directional signs and specify detail.

CBC 1127B.3

Exterior routes of travel - Signs

2.16 Provide enlarged plan of required element or area containing site requirement(s) in 1/4" scale.

CBSC Part 1 4-317(b)

Plans

3

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 3. ACCESSIBLE ROUTE OF TRAVEL

- 3.1** For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1** and **Checklist 2**.
- 3.2** The accessible route of travel must, to the maximum extent feasible, coincide with the route for the general public.
- 3.3** Indicate the accessible route of travel (dashed or dotted line) from and to the following areas (if necessary, modify scoping of the project accordingly and indicate clearly on drawings how this requirement is met):
1. From public transportation stops and cross walks in the public rights-of-way serving the area adjacent to a site entry point.
 2. From all appropriate site entry points that serve pedestrians (e.g., public transportation stops, cross walks, etc.) to the area of new construction or alteration, starting at the property line.
 3. From accessible parking serving the area to the area of new construction or alteration.
 4. From passenger drop-off and loading zones to the area of new construction or alteration.
 5. From visitor arrival or sign-in points to the area of new construction or alteration.
 6. From accessible restrooms serving the area to the area of new construction or alteration.
 7. From drinking fountains serving the area to the area of new construction or alteration.
 8. From public telephones serving the area to the area of new construction or alteration.
 9. From and to elevators serving the site's accessible route.
 10. From exterior activity areas serving the area (e.g., plazas, playgrounds, vista points, etc.) to the area of new construction or alteration.
 11. From all other essential function areas serving the area to the area of new construction or alteration.
 12. Between all areas of new construction or alteration.
- 3.4** Indicate width of accessible route of travel at this location:
1. 48" min for walks and sidewalks. See Checklist 6 for exceptions and additional requirements.
 2. 48" min for curb ramps. See Checklist 5 for exceptions and additional requirements.

CBC 1114B.1.2

CBSC Part 1
4-317(b)

CBC 202 &
CA Streets and
Highways Code
§5610

CBC 1133B.7.1
CBC 1005

CBC 1127B.5 #2

Accessible route of travel

Plans

Definitions – Path of Travel
For code, see: www.leginfo.ca.gov

NOTE:
The PD must clearly demonstrate and document an effort in requesting that the entity having authority (or control) over the public right-of-way (such as a city or a county) provide the necessary improvements / alterations needed to comply with accessibility. If such request is denied by the entity having authority (or control) over the public right-of-way, that denial must be documented and entered into the DSA project file.

Continuous surface
Egress width

Width of curb ramps

3

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 3. ACCESSIBLE ROUTE OF TRAVEL

- 3. 48" min for ramps, or 60" min if serving an occupancy load of ≥300 and the entrance ramp is the only exit discharge path from a building. See Checklist 7 for exceptions and additional requirements.
- 4. 36" min for corridors, hallways, and exterior exit balconies if serving an occupancy load of <10, or 44" min if serving an occupancy load of 10 or more. See Checklist 9 for exceptions and additional requirements.
- 5. For corridors, hallways, and exterior exit balconies exceeding 200' in length, provide 60" min clear width or 60"x60" passing spaces at intervals of 200' maximum. A T-shaped intersection of two 36" min width corridors is an acceptable alternate passing space. See Checklist 9 for
- 6.
- 7. 44" min within a multi-accommodation toilet room to and from accessible compartments.
- 8. 36" min within a single-accommodation toilet room except at doors. If a person in a wheelchair must make a turn around an obstruction, the min clear width of the accessible route shall be as shown in CBC Figure 11B-5E.
- 9. 36" min at aisles serving one side only.
- 10. 44" min at aisles serving both sides.

CBC 1133B.5.2

Entrance and special occupancy

CBC 1133B.3.1 & CBC 1133B.3.2

Corridor and hallway widths
Corridors and hallways over 200'

CBC 1133B.3.2

Corridors and hallways over 200 feet

CBC 1115B.3.1 #4.5

Multiple accommodation toilet facilities

CBC 1115B.3.2 #4


Single-accommodation toilet facilities

CBC 1133B.6.2

Aisles - Width

CBC 1133B.6.2

Aisles - Width



For turns around an obstruction, see 3.6.

NOTE:
Chapter 10 may require 44" min aisle width in B and M occupancies, and in assembly occupancies without fixed seating, where seats, tables, furnishings, displays, and similar fixtures or equipment are located on both sides of the aisle.

- 3.5 Doors (in any position) shall not reduce the required width of a corridor or hallway by more than 50%.

CBC 1005.2

Egress Width – Door Encroachment

3


Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 3. ACCESSIBLE ROUTE OF TRAVEL

- 3.6** Provide and indicate the following dimensions when the accessible route changes direction or turns around an obstruction:
1. 90 degree turns can be made from a 36" wide passageway into another 36" passageway if the depth of the obstruction is 48" or greater on the inside dimensions of the turn.
 2. U-turns around an obstruction less than 48" wide can be made if the passageway width is 42" min and the base of the U-turn space is 48" min wide.



EXCEPTIONS: At doors.

- 3.7** Provide and indicate the following properties for the accessible route of travel:
1. Accessible route surface must be slip-resistant, stable, and firm.
 2. On surfaces with slopes up to 6%, provide equivalent of medium salted finish.
 3. On surfaces with slopes equal to or greater than 6%, provide slip-resistant finish.
 4. Outdoor stairs, ramps and landings shall be designed so water will not accumulate on their surfaces.
- 3.8** All entrances and ground floor exits must be accessible.
- EXCEPTIONS:
- a. Exterior ground-floor exits serving smoke-proof enclosures, stairwells and exit doors servicing stairs only.
 - b. Exits in excess of those required by Chapter 10, and which are more than 24 inches above grade. Such doors shall have a visual sign which indicates, by means of an arrow and/or text, the location of the nearest accessible exit. The warning sign shall comply with Section 1117B.5 and be mounted at a location so steps do not need to be retraced.

CBC 1118B.1

Wheelchair passage width

CBC 1118B.1

Wheelchair passage width

CBC 1118B.1

Wheelchair passage width

***NOTE:**
If occupancy load is 10 or more, the min width of all * dimensions must be increased to 44" min.

CBC 1133B.7.1
CBC 1124B.1

Continuous surface
Ground and floor surfaces

CBC 1133B.7.1.1

Slopes less than 6 percent

CBC 1133B.7.1.2

Slopes 6 percent or greater

CBC 1133B.4.5.1
CBC 1133B.5.8

Treads
Outdoor ramps

CBC 1133B.1.1.1.1

Entrances

3

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 3. ACCESSIBLE ROUTE OF TRAVEL

<p>c. In existing buildings where the enforcing agency determines that compliance with the building standards of this section would create an unreasonable hardship, an exception shall be granted when equivalent facilitation is provided. Equivalent facilitation would require at least one entrance to be accessible to and usable by persons with disabilities.</p>		<p>NOTE: Jurisdictional findings and determinations are subject to an internal DSA appeals process.</p>
<p>d. In existing buildings when legal or physical constraints will not allow compliance or equivalent facilitation without creating an unreasonable hardship.</p>		
<p>3.9 In existing buildings and facilities, a service entrance can not be the only accessible entrance unless it is the only entrance to a building or facility.</p>	<p>1133B.1.1.1.5</p>	<p>Service entrances</p>
<p>3.10 Indicate on plans all entrances and ground floor exits that are required to be accessible (either by extending the accessible route of travel line into the building or by a symbol (e.g., ►). Provide strike edge and landing dimensions for each entrance on plan or provide the following general note on plan:</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<ul style="list-style-type: none"> ▪ All exterior entrances and exits identified with a triangular symbol (►) on this plan are accessible and comply with CBC 1133B.1.1, including: 		
<p>A. 32" clear opening</p>	<p>CBC 1133B.1.1.1.1</p>	<p>Entrances</p>
<p>B. Required strike edge clearance at pull side of door (24" for front and latch, 36" for hinge approach)</p>	<p>CBC 1133B.2.4.2</p>	<p>Maneuvering clearances at doors</p>
<p>C. Level landings (2% max)</p>	<p>CBC 1133B.2.4.2</p>	<p>Maneuvering clearances at doors</p>
<p>D. Accessible threshold, hardware, closer, kick-plate</p>	<p>CBC 1133B.2.4.1 CBC 1133B.2.5.1 CBC 1133B.2.5.2 CBC 1133B.2.6</p>	<p>Thresholds Door closer Hardware Smooth surface</p>
<p>E. ISA on exterior side of entrance</p>	<p>CBC 1117B.5.8.1.2</p>	<p>Entrance signs</p>
<p>F. Tactile exit signage on interior side of exit door, as required</p>	<p>CBC 1011.3</p>	<p>Tactile exit signs</p>
<p>G. Outline of canopy, awning, or roof</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>3.11 Vertical change in the accessible route cannot exceed 1/4". Provide curb ramp, ramp, elevator, platform lift, or remove element at this location, or provide equally convenient, alternative accessible route.</p>	<p>CBC 1124B.2 CBC 1133B.7.4</p>	<p>Changes in level Changes in level</p>
<p>3.12 Level change in the accessible route between 1/4" and 1/2" must be beveled at 1:2 max slope. Changes in level greater than 1/2" shall be accomplished by means of a curb ramp, ramp, elevator, platform lift, or provide equally convenient, alternative accessible route.</p>	<p>CBC 1124B.2 & CBC 1133B.7.4</p>	<p>Changes in level Changes in level</p> <p>NOTE: Thresholds over 1/2" must be mitigated by a ramp/sloped walk.</p>

3

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 3. ACCESSIBLE ROUTE OF TRAVEL

3.13 If level change between pedestrian area and adjacent surface exceeds 30" in height, specify and provide detail for guard (42" AFF).

CBC 1013.1

Guards – Where required

3.14 Indicate condition of level change between pedestrian area and adjacent surface. If drop exceeds 1/4" in height, specify and provide one of the following details:

CBSC Part 1 4-317(b)

Plans


- 1. Abrupt vertical drops between 1/4" and 4".
- 2. 6" high warning curb if vertical drop exceeds 4".

CBC 1133B.8.1

Warning curbs

EXCEPTIONS:

- a. Between a walk or sidewalk and a street or driveway.
- b. If adjacent grade is higher than pedestrian way.
- c. If cane-detectable handrails, guards, or wheel-guides are provided.



3.15 Identify location of all gratings within the accessible route and provide cut sheet of gratings for back check review.

CBC 1124B.4 & CBC 1133B.7.2

Gratings
Gratings

Walks, sidewalks and pedestrian ways shall be free of gratings whenever possible. Grate openings cannot exceed 1/2" in the direction of travel. Gratings with elongated opening must be placed with the long dimension perpendicular to the dominant direction of traffic flow.

EXCEPTIONS:

- a. In alteration projects, when DSA finds unreasonable hardship and when equivalent facilitation is provided.
- b. Where, due to legal or physical constraints, the site of the project will not allow compliance with this requirement or equivalent facilitation without creating an unreasonable hardship.

CBSC Part 1 4-317(b)

Plans

NOTE:
Jurisdictional findings and determinations for exception (b) are subject to an internal DSA appeals process.

3

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 3. ACCESSIBLE ROUTE OF TRAVEL

3.16 Wall mounted objects with the bottom edge between 27" and 80" AFF shall protrude no more than 4" into the pedestrian circulation area.


CBC 1133B.8.6.1

Protruding objects - General

3.17 Post or pylon-mounted objects with a bottom edge between 27" and 80" above the ground may overhang no more than 12".

CBC 1133B.8.6.1

Protruding objects - General



3.18 Handrail extension shall not project into the accessible route of travel or create a hazard.

CBC 1133B.8.6.1
CBC 1133B.4.2.2
CBC 1133B.5.5.1.1

Protruding objects - General
Stair Handrails
Ramp Handrails

3.19 Accessible route of travel at parking stalls shall not compel a person with a disability to wheel or walk behind parking spaces other than that person's own accessible parking space.

CBC 1129B.3 #3

Arrangement of parking spaces

3.20 For large sites and complicated accessible routes of travel, provide directional signs, indicating the direction to accessible parking, buildings, or outside facilities. Signs should be designed to facilitate reading by persons with impaired vision. Background contrast and character proportion is critical.

CBC 1117B.5
CBC 1127B.3

Signs and identification
Signs

3.21 Provide detectable warnings at transit boarding platforms.

CBC 1121B.3.1 #8(a)

Detectable warnings at transit
boarding platforms

3.22 Provide detectable directional texture (truncated bars) at transit boarding platforms.

CBC 1121B.3.1 #8(b)
CBC Fig. 11B-23B

Detectable directional texture at
boarding platforms
Directional bars

3.23 Provide a continuous band of detectable warning surface (36" deep) where a walk crosses or adjoins a vehicular way, and the walking surface is not separated from the hazardous vehicular way by curbs, railings or other elements.

CBC 1133B.8.5

Detectable warnings at hazardous
vehicular areas


3

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).


Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 3. ACCESSIBLE ROUTE OF TRAVEL



(a) TRUNCATED DOME SPACING



(b) TRUNCATED DOME SECTION A-A

3.24 If existing building elevators are being altered in order to be made accessible, no modifications are required to stairs that connect levels served by the accessible elevator.

CBC 1134B.2.1 #3.3
ADA Stds. 4.1.6(1)(d)

Accessibility for existing buildings -
General
Accessible buildings - Alterations

4

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Heading / Comments / Notes & Examples

Check List 4. ACCESSIBLE PARKING, PASSENGER LOADING, AND BUS STOPS

4.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

ACCESSIBLE PARKING

4.2 Indicate location and layout of all accessible parking on site plan and connect dashed accessible route of travel to the access aisle.

4.3 Provide separate parking ratio for each parking lot on this site. Indicate name of lot, total number of stalls, van accessible stalls, and regular accessible stalls.

4.4 Provide enlarged plan in 1/4" scale representing the actual layout, including associated sidewalks, curb ramps, curb cuts, and location of water drains, for all accessible parking under this contract.

4.5 Provide the required number of accessible parking spaces for each lot (calculate each lot separately):

Total Parking in Lot	Required Accessible	Including Van Accessible
1-25 spaces	1 space(s)	1 space(s)
26-50	2	1
51-75	3	1
76-100	4	1
101-150	5	1
151-200	6	1
201-300	7	1
301-400	8	1
401-500	9	2
501-1,000	Two % of total	(1 in 8)
1,001 and over	Twenty plus one for each 100, or fraction thereof over 1,001	(1 in 8)

EXCEPTIONS:

- a. 10% of the total number of parking spaces at outpatient units and facilities shall be accessible.
- b. 20% of the total number of parking spaces at units and facilities that specialize in treatment or services for persons with mobility impairments shall be accessible.

4.6 One (1) of every eight (8) accessible spaces, but not less than one, is required to be van accessible.

4.7 Where provided, electrical vehicle charging stations shall be accessible as required.

CBC 1129B

CBSC Part 1 4-317(b)

CBSC Part 1 4-317(b)

CBSC Part 1 4-317(b)

CBC Table 11B-6

CBC 1129B.2 #1

CBC 1129B.2 #2

CBC 1129B.3 #2

DSA Policy 97-03

Accessible parking required

Plans

Plans

Plans

Spaces required

NOTE:
One (1) in every eight (8) accessible spaces, but not less than one (1), shall be van accessible. Van accessible parking spaces are "accessible spaces" and are not to be considered "in addition" to the number of accessible spaces required.

Medical care outpatient facilities – Outpatient units and facilities

Units and facilities that specialize in treatment or services for persons with mobility impairments

Parking space size - Van space(s)

Interim disabled access guidelines for electrical vehicle charging stations

4

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Heading / Comments / Notes
& Examples

Check List 4. ACCESSIBLE PARKING, PASSENGER LOADING, AND BUS STOPS

<p>4.8 Consider relocating accessible parking if necessary. Accessible parking spaces serving a particular building must be located on the shortest accessible route of travel from adjacent parking to an accessible entrance. Note that required stalls need not be provided in the particular lot. They may be provided in a different location if equivalent or greater accessibility is ensured, in terms of distance from an accessible entrance, user cost and convenience.</p>	<p>CBC 1129B.1</p>	<p>Accessible parking required – General</p>
<p>4.9 Where parking lots serve accessible entrances of several buildings or different areas on site, accessible parking spaces must be dispersed and located closest to the accessible route of travel.</p>	<p>CBC 1129B.1</p>	<p>Accessible parking required – General</p>
<p>4.10 Rearrange parking layout so that a person with a disability is not compelled to wheel or walk behind parking spaces other than that person's own accessible parking space.</p>	<p>CBC 1129B.3 #3</p>	<p>Arrangement of parking spaces</p>
<p>4.11 Typical parking detail(s) must match actual parking layout.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>4.12 Accessible parking stalls and access aisles - provide and indicate the following dimensions and elements on plans:</p> <ol style="list-style-type: none"> 1. 8' wide access aisles on the passenger side of each van accessible parking stall. 2. 5' wide access aisles on the passenger side of each accessible parking stall. Two adjacent accessible parking stalls may share a common access aisle. 3. 18' long parking stalls and access aisles. 4. Loading and unloading access aisles marked by a border painted blue. Within the blue border, hatched lines at 36 inches max on center painted a color contrasting with the parking surface, preferably blue or white. 5. 2% max slope in any direction at parking spaces and access aisles. 6. A 36" wide and 36" high International Symbol of Accessibility on pavement at rear of stall. 7. Post or wall mounted accessible parking stall signs: <ol style="list-style-type: none"> A. Signs must be located at the interior end of the accessible stall. Signs shall be located so they cannot be obscured by a vehicle parked in the space. B. Signs must be reflectorized, 70 square inch min, with a white ISA on blue background. C. An additional sign or additional language below the ISA must state, "Minimum Fine \$250". D. Van accessible spaces must have an additional sign or additional language below the ISA stating "Van Accessible". 	<p>CBC 1129B.3</p> <p>CBC 1129B.3 #2</p> <p>CBC 1129B.3 #1</p> <p>CBC 1129B.3 #1</p> <p>CBC 1129B.3 #1 CBC 1129B.3 #2</p> <p>CBC 1129B.3 #4</p> <p>CBC 1129B.4</p> <p>CBC 1129B.4 CBC 1133B.8.6.3</p>	<p>Parking space size</p> <p>Van space(s)</p> <p>Dimensions</p> <p>Dimensions</p> <p>Dimensions Van space(s)</p> <p>Slope of parking space</p> <p>Identification of parking spaces for off-street parking facilities</p> <p>Identification of parking spaces for off-street parking facilities Free-standing signs</p>

4

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Heading / Comments / Notes
& Examples

Check List 4. ACCESSIBLE PARKING, PASSENGER LOADING, AND BUS STOPS

<p>8. "Tow-away" signs:</p> <p>A. Post in a conspicuous place at each entrance to an off-street parking lot, or immediately adjacent to and visible from each designated stall.</p> <p>B. Sign must be 17" x 22" min, with letters 1" high min.</p> <p>C. Sign must state: "Unauthorized vehicles parked in designated accessible spaces not displaying distinguishing placards or special license plates issued for persons with disabilities will be towed away at the owner's expense. Towed vehicles may be reclaimed at _____ or by telephoning _____."</p> <p>D. PD to provide contact info on plans.</p>	<p>CBC 1129B.4</p>	<p>Identification of parking spaces for off-street parking facilities</p>
<p>9. A bumper or curb shall be provided if required to prevent encroachment of cars over the required width of adjacent walkways.</p>	<p>CBC 1129B.3 #3 ADA Stds. 4.6.3</p>	<p>Walks and sidewalks - Continuous surface</p>
<p>10. Provide the words "NO PARKING" in each access aisle, painted in 12" minimum high white letters.</p>	<p>CBC 1129B.3 #1 & 2</p>	<p>Dimensions and Van space(s)</p>
<p>11. Provide minimum vertical clearance of 98" at accessible parking spaces and along at least one vehicle access route to such spaces from site entrances and exits.</p>	<p>CBC 1129B.3 #5</p>	<p>Vertical clearance</p>
<p>4.13 Curb ramps with slopes greater than 2% cannot be located within the parking space or adjacent access aisle. Provide parallel or perpendicular curb ramp instead of built-up curb ramp or redesign parking layout (see Checklist 4, Fig. 4-A, 4-B & 4-C).</p>	<p>CBC 1129B.3 #3 ADA Stds. 4.6.3</p>	<p>Arrangement of parking space Parking spaces See figures at the end of this Checklist</p>
<p>4.14 Accessible route of travel to parking - provide and indicate the following dimensions and elements on plans:</p> <p>1. The access aisle must either be level with the adjacent accessible route or have a curb ramp. Provide spot elevations.</p> <p>2. Curb ramp opening must be located within the access aisle boundaries, not within the parking space boundaries.</p> <p>3. Top landing at curb ramp must be level and 48" deep min.</p> <p>4. Transitions from ramps to walks, gutters, or streets shall be flush and free of abrupt changes. (No 1/2" lip.)</p>	<p>CBSC Part 1 4-317(b)</p> <p>CBC 1129B.3 #3</p> <p>CBC 1127B.5 #4</p> <p>CBC 1127B.5 #3</p>	<p>Plans</p> <p>Arrangement of parking space</p> <p><u>NOTE:</u> Detectable warning surfaces are required on all curb ramps.</p> <p>Curb Ramps - Level landing</p> <p>Curb Ramps - Slope of curb ramp</p>
<p>4.15 Provide and indicate 98" min (8' - 2") vertical clearance at the van accessible parking stalls and at vehicle routes to and from these stalls.</p>	<p>ADA Stds. 4.6.5</p>	<p>Vertical Clearance</p>
<p>4.16 Provide and indicate a reasonable programmatic or architectural solution at parking areas controlled by ticket dispensers which may represent a barrier for persons with disabilities, particular those with reach range limitations. Examples of acceptable solutions include an accessible voice communication system and signage, or providing accessible parking spaces outside the controlled area.</p>	<p>DSA Policy 97-06 28 CFR 35.130(a)</p>	<p>Parking ticket dispensers</p>

4

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Heading / Comments / Notes
& Examples

Check List 4. ACCESSIBLE PARKING, PASSENGER LOADING, AND BUS STOPS

PARKING STRUCTURES

4.17 Provide and indicate 98" min (8' - 2") vertical clearance at the accessible parking stalls and at vehicle routes to and from these stalls.

EXCEPTIONS:

- a. Where DSA determines that compliance with building standards would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.
- b. In existing buildings where DSA determines that, due to legal or physical constraints, compliance with building standards or equivalent facilitation would create an unreasonable hardship.

4.18 In multi-story parking structures, provide accessible parking stalls on the following levels:

1. All floor levels that have accessible walks or ramps leading to the exterior.
2. All floor levels that have accessible walks (incl. skywalks) or ramps leading to adjacent buildings.
3. All floor levels that have additional benefits or amenities, such as electrical charging stations, better security, scenic views, or other public accommodations such as shops, telephones, smoking areas, long-term parking, etc.

4.19 Locate accessible parking closest to elevator, ramp or other accessible entrances.

4.20 When direct access is provided for pedestrians from a parking garage to a building, each direct entrance from the garage to the building must be accessible.

PASSENGER LOADING ZONES

4.21 Provision of valet parking does not eliminate any of the requirements for accessible parking (i.e. provide all features to allow self parking).

4.22 Where valet parking is provided, provide accessible passenger loading zone.

4.23 Indicate type, location, and layout of all passenger drop-off and loading zones on site plan.

4.24 Where provided, one passenger drop-off and loading zone must be made accessible. Connect dashed accessible route of travel to area.

CBC 1130B

CBC 1130B.1

CBC 1129B.1

CBC 1129B.1

CBC 1130B.2

CBC 1131B

CBC 1131B.3

CBC 1131B.3

CBSC Part 1
4-317(b)

CBC 1131B.2

Parking structures

NOTE:
Jurisdictional findings and determinations for exception (b) are subject to an internal DSA appeals process.

Accessible parking required –
General

Accessible parking required –
General

Parking structures

Passenger drop-off and loading
zones

Valet parking

Valet parking

Plans

Passenger loading zones

4

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Heading / Comments / Notes
& Examples

Check List 4. ACCESSIBLE PARKING, PASSENGER LOADING, AND BUS STOPS

<p>4.25 Provide enlarged plan in 1/4" scale representing the actual layout, including associated sidewalks and curb ramps, for all accessible passenger loading zones. Provide and indicate:</p> <ol style="list-style-type: none"> 1. 5' x 20' access aisle adjacent and parallel to the vehicle pull-up space. 2. Level access aisle and vehicle pull-up space (2% max in any direction). 3. Indicate a curb ramp if there is a curb between the access aisle and the vehicle pull-up space, or if there is a curb between the access aisle and the accessible route. 4. Vertical clearance of 114" min along at least one vehicle access route to such zones (from site entrances & exits). 5. Identifying signage with the ISA and stating "Passenger Loading Zone Only", in white on a dark blue background. 6. Detectable warning surface at blended transitions and curb ramps. 	<p>CBSC Part 1 4-317(b)</p> <p>CBC 1131B.2 #1</p> <p>CBC 1131B.2 #1</p> <p>CBC 1131B.2 #1</p> <p>CBC 1131B.2 #2</p> <p>CBC 1131B.2 #1</p> <p>CBC 1133B.8.5, ADA Stds. 4.29.5, & IRs 11B-2, 11B-3 & 11B-4</p>	<p>Plans</p> <p>Passenger loading zones – General</p> <p>Passenger loading zones – General</p> <p>Passenger loading zones - General</p> <p>Passenger loading zones – Vertical Clearance</p> <p>Accessible passenger loading zones</p> <p>Detectable Warnings at Hazardous Vehicular Areas</p>
<p>BUS STOPS</p>	<p>CBC 1121B.2</p>	<p>Bus stops and terminals</p>
<p>4.26 Where provided, bus stop(s) and pad(s) shall be accessible.</p>	<p>CBC 1121B.2</p>	<p>Bus stops and terminals</p>
<p>4.27 Indicate location and layout of all accessible bus stops on site plan and connect dashed accessible route to bus stop pad.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>4.28 Provide and indicate an 8' long by 5' wide bus stop pad (8' measured perpendicular to curb and 5' measured parallel to curb).</p>	<p>CBC 1121B.2.1</p>	<p>Bus stops and terminals – New construction</p>
<p>4.29 In new construction: provide a square curb surface between the pad and road or other detectable warning (provide detail).</p>	<p>CBC 1121B.2.1</p>	<p>Bus stops and terminals – New construction</p>
<p>4.30 The slope of the pad perpendicular to the roadway must not exceed 2%.</p>	<p>CBC 1121B.2.1</p>	<p>Bus stops and terminals – New construction</p>
<p>4.31 The slope of the pad parallel to the roadway must be the same as the roadway.</p>	<p>CBC 1121B.2.1</p>	<p>Bus stops and terminals – New construction</p>
<p>4.32 Provide 30" x 48" clear floor wheelchair space completely within bus stop shelter and connect space to bus stop pad and accessible route of travel.</p>	<p>CBC 1121B.2.1</p>	<p>Bus stops and terminals – New construction</p>
<p>ON STREET PARKING</p>		
<p>4.33 Additional information for on-street parking, see also Caltrans Standard Plans A90A and A90B.</p>	<p>Caltrans Std Plans</p>	<p>For Standard Plans, see: http://www.dot.ca.gov/hq/esc/oe/project_plans/HTM/06_plans_disclaim_US.htm</p>




Fig 4-A. Depressed Curb Ramp at Accessible Parking (Typical)





Fig 4-B. Curb Ramp at Accessible Parking



Ramp surface to be contrasting finish from adjacent walk.

Note that neither built-up curb ramp, nor sidewalk protrude into the required, perpendicular 18'x17' van space, or the 18'x14' regular space.

Fig 4-C. Built-up Curb Ramp at Accessible Angled Parking

5

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 5. CURB RAMPS AND PEDESTRIAN CROSSINGS

5.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

CURB RAMPS


5.2 Indicate location and layout of all curb ramps on site plan.

5.3 Typical curb ramp details must match actual layout. Provide dimensioned detail in 1/4" scale representing the actual layout, including associated sidewalks, for all accessible curb ramps under this contract.

5.4 Curb ramps cannot project into vehicular traffic lanes or into an accessible parking space or adjacent access aisle.

5.5 Indicate 48" min width exclusive of side flares.

5.6 Provide spot elevations at top and bottom of curb ramp and at relevant spots on sidewalk.



Sample Curb Ramp

5.7 Indicate curb ramp slope based on available length and elevation change. Use the least possible slope but never greater than the 8.3% max.

5.8 Indicate side flare slope (10% max, or 8.3% max if top landing is less than 48").

5.9 Indicate counter slope of adjoining gutters or road surface at the bottom of and immediately adjacent to the curb ramp (5% max for 48" in the direction of travel).

CBC 1127B.5

CBSC Part 1 4-317(b)

CBSC Part 1 4-317(b)

CBC 1127B.5 #1
CBC 1129B.3 #3

CBC 1127B.5 #2

CBSC Part 1 4-317(b)

Plans

Plans

Curb ramps - General
Parking space size - Arrangement of parking space

Width of curb ramps

Plans

DEFINITIONS:

CURB RAMP is a sloping pedestrian way, intended for pedestrian traffic, which provides access between a walk or sidewalk and a surface located above or below an adjacent curb face.

CURB CUT is an interruption of a curb at a pedestrian way, which separates surfaces that are substantially at the same elevation.

CBC 1127B.5 #3 & ADA Stds 4.7.2

CBC 1127B.5 #3
CBC 1127B.5 #4

CBC 1127B.5 #3
ADA Stds 4.7.2

Slope of curb ramps
Curb ramps - slope

Slope of curb ramps
Level landing

Slope of curb ramps
Slope

5


Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 5. CURB RAMPS AND PEDESTRIAN CROSSINGS

5.10 Provide and indicate detectable warning surface (i.e. truncated domes) at perpendicular curb ramp. Domes must extend the full width and length of the curb ramp, excluding the flares.



Perpendicular Curb Ramp


CBC 1127B.5 #7, DSA-IR 11B-3, DSA-IR 11B-4 & ADA Stds 4.7.7

Detectable warnings
Detectable warnings at curb ramps
Detectable warnings
Detectable warnings

NOTE:
DSA may approve a 36" long warning surface as equivalent to full width and length in accordance with IR 11B-4.

NOTE:
As of July 26, 2001, ADA Stds requires the provision of truncated domes on all curb ramps, regardless of slope.


5.11 Provide and indicate detectable warning surface (i.e. truncated domes) at parallel or combination curb ramp. Provide 36" wide band of detectable warning between pedestrian area and vehicular way.



Parallel Curb Ramp

CBC 1133B.8.5 & ADA Stds 4.29.5

Detectable warnings at hazardous vehicular areas



Combination Curb Ramp

5

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 5. CURB RAMPS AND PEDESTRIAN CROSSINGS

- 5.12** Indicate the following for detectable warning surfaces
1. Visual contrast with adjoining surfaces, either a light-on-dark or dark-on-light contrast.
 2. Staggered domes (diagonal grid) spaced 2.35" on center, or in-line domes (square grid) spaced 1.67" to 2.35" on center.

CBC 1127B.5 #7

Detectable warnings

CBC 1127B.5 #7
DSA-IR 11B-4

Detectable warnings
Detectable warnings

5.13 Detectable warnings shall be slip-resistant.

CBC 1127B.5 #7

Detectable warnings

5.14 Provide dimension on plan indicating that the 48" landing at the bottom of the curb ramp is fully contained within marked crossings.

CBC 1127B.5 #9,
CBC Fig. 11B-22(c) & (d),
ADA Stds 4.7.9 &
ADA Stds Fig. 15

Diagonal curb ramps
Curb ramps at marked crossings
Location at marked crossings
Curb ramps at marked crossings

5.15 Design to provide 48" min deep level top landing or slope flares at 8.3% max.

CBC 1127B.5 #4


Level landing

NOTE:
The length of a curb ramp (sloped 8.3%) at a regular sidewalk with 2% cross slope and 6" curb is 95".

5.16 Provide 12" wide grooved border around upper edges of curb ramp and flares to indicate transition from sidewalk to curb ramp.

CBC 1127B.5 #6

Border



Perpendicular Curb Ramp

5.17 Provide 12" wide grooved border as part of level walkway, not as part of sloped curb ramp and flares.

CBC 1127B.5 #6

Border

5.18 Indicate how finish of curb ramp and flared surfaces contrast with that of adjacent sidewalk.

CBC 1127B.5 #5

Finish

5

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation



Headings / Comments / Notes & Examples

Check List 5. CURB RAMPS AND PEDESTRIAN CROSSINGS

5.19 Provide and indicate 60" min wide bottom or intermediate landing at depressed or combination curb ramp.

CBC 1133B.5.4.7 & ADA Stds 4.8.4(2)

Other intermediate landings Landings



PEDESTRIAN CROSSINGS

5.20 At diagonal curb ramps, provide dimension on plan, indicating a 24" straight curb segment, perpendicular to the direction of the cross walks, on each side of the curb ramp.

CBC 1127B.5 #9, CBC Fig. 11B-22 & ADA Stds 4.7.10

Diagonal curb ramps
Curb ramps at marked crossings
Diagonal curb ramps

5.21 At diagonal curb ramps, there must be a 24" straight curb segment within the marked crossing.


CBC 1127B.5 #9

Diagonal curb ramps

5.22 Provide level cut through pedestrian island (median), or provide a crowned cut through sloped at 8.3% max with a 48" min long top landing.

ADA Stds 4.7.11 & ADA Stds Fig. 15 (a) & (b)

Islands
Curb ramps at marked crossings



5

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 5. CURB RAMPS AND PEDESTRIAN CROSSINGS

5.23 Provide and indicate a level 30" x 48" min clear space, centered and parallel to the pedestrian signal push button.

CBC 1118B.4 #1

Clear floor or ground space for wheelchairs - Size and approach

5.24 Indicate height of pedestrian signal push button (48" max).

CBC 1117B.5.9

Traffic-control devices

5.25 Provide and indicate the following at the pedestrian signal push button:

1. Activating force must be 5 lbs or less.
2. A textured horizontal yellow band 2" wide and encircling the pole, and a 1" wide dark border band above and below this yellow band.

CBC 1117B.6 #4

Controls and operating mechanisms - Operation

CBC 1117B.5.9


Traffic-control devices

BLENDED TRANSITIONS

5.26 Where a walk crosses or adjoins a vehicular way, and the walking surfaces are not separated by curbs, railings, or other elements between the pedestrian areas and vehicular areas, the boundary between the areas must be defined by a continuous, yellow, 36" wide detectable warning surface that differs from the adjoining walking surface in resiliency or sound on cane contact.

CBC 1133B.8.5 & ADA Stds 4.29.5

Detectable warnings at hazardous vehicular areas
Detectable warnings at hazardous vehicular areas



APPLICATION IN THE PUBLIC RIGHTS-OF-WAY

5.27 For acceptable designs for curb ramps, traffic islands, blended transitions, and detectable warnings in the public rights-of-way, see Caltrans Standard Plans A88A and A88B.

Caltrans Std Plans

For Standard Plans, see: http://www.dot.ca.gov/hq/esc/oe/project_plans/HTM/06_plans_disclaim_US.htm

5

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 5. CURB RAMPS AND PEDESTRIAN CROSSINGS

PEDESTRIAN OVERPASSES AND UNDERPASSES

5.28 Pedestrian ramps on pedestrian grade separations (overpasses and underpasses) must comply with the requirements for ramps.

EXCEPTIONS:

- a. When the grade differential of the walking surface of a pedestrian grade separation exceeds 14 feet due to required height clearance and grade conditions, and DSA finds that wheelchair accessibility or equivalent facilitation would create an unreasonable hardship, such accessibility need not be provided. However, the requirements in these regulations relating to other types of mobility shall be complied with.
- b. For existing facilities, this section shall not apply where, due to legal or physical constraints, the site of the project will not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship.

5.29 Provide and indicate level landings at pedestrian over- and underpasses:

- 1. At intervals not exceeding 30" of vertical rise, if slope is greater than 5%.
- 2. At intervals of 400' maximum if a continuous slope is between 2% and 5%.

CBC 1128B

Pedestrian grade separations (overpasses and underpasses)

NOTE:

Jurisdictional findings and determinations for exceptions (a) and (b) are subject to an internal DSA appeals process.

CBC 1133B.5.4.1

Location of landings

CBC 1133B.7.5

Level areas




Fig 5-A. Typical Pedestrian Crossing Layouts

Height of Curb Face	1:10 max. Flare Width at Curb	Ramp Run Length (Plan)*	Total Needed Sidewalk Width (incl. 4' Landing)
4" (10.2 cm)	40" (1.02 m)	63" (1.6 m)	111" (2.82 m)
5" (12.7 cm)	50" (1.27 m)	78" (1.98 m)	126" (3.2 m)
6" (15.2 cm)	60" (1.52 m)	95" (2.41 m)	143" (3.63 m)
7" (17.8 cm)	70" (1.78 m)	111" (2.82 m)	159" (4.04 m)
7.5" (19.0 cm)	75" (1.90 m)	118.5" (3.01 m)	166.5" (4.23 m)
8" (20.3 cm)	80" (2.03 m)	126" (3.2 m)	174" (4.42 m)

* For ramp sloping 8.3% on sidewalk with 2% cross slope




Fig 5-B. Sidewalk Width Requirement

6

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 6. WALKS AND SIDEWALKS

6.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

6.2 All walks and sidewalks must be accessible (i.e. those that are to be newly constructed or altered, or are part of the required accessible route of travel).

EXCEPTION:

In alteration projects, when DSA determines that compliance would create an unreasonable hardship, an exception may be granted when an equivalent alternative accessible path of travel is provided.

6.3 Provide and indicate enlarged detail of surface material transition at:

1. Any change in surface material.
2. Where new construction meets existing surface.

6.4 Vertical changes in level along the accessible route of travel cannot exceed 1/4". Level changes in the accessible route between 1/4" and 1/2" must be beveled at 1:2 max slope.

6.5 Provide and indicate continuous common surface material to be slip resistant, stable, and firm.

6.6 Provide and indicate width of walk or sidewalk at all locations.

1. 48" min width required.
2. Wheelchair turning space 60" min wherever a person using a wheelchair may have to make a 180 degree or greater turn to access elements or equipment (e.g., at doors, gates, tables and seating accommodations, dispensers, drinking fountains, mail boxes, telephones, etc.).
3. 60" min width if there are no passing spaces measuring 60" by 60" min located at reasonable intervals not to exceed 200'. A T-shaped space complying with CBC Figure 11B-12(b) is an acceptable passing space.

EXCEPTION:

When, because of right-of-way restrictions, natural barriers or other existing conditions, DSA determines that compliance with the 48" clear sidewalk width would create an unreasonable hardship, the clear width may be reduced to 36".

CBC 1114B.1.2

CBSC Part 1 4-317(b)

CBC 1133B.7.4
CBC 1124B.2

CBC 1133B.7.1 & CBC 1124B.1

CBC 1133B.7.1

CBC 1118B.3 & ADA Stds. 4.2.3

CBC 1133B.7.1
CBC Fig. 11B-12(b)
ADA Stds 4.3.4

CBC 1133B.7.1

Accessible route of travel

DEFINITIONS:

SIDEWALK is a surfaced pedestrian way contiguous to a street used by the public.

WALK is a surfaced pedestrian way not located contiguous to a street used by the public.

Plans

Changes in level
Changes in level

Continuous surface
Ground and floor surfaces


Continuous surface

Wheelchair turning space
Wheelchair turning space

Continuous surface
Passing space

NOTE:

Required sidewalk width must be measured exclusive of the curb.



6

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 6. WALKS AND SIDEWALKS

<p>6.7 Provide spot elevation and gradients to show how slope requirements are met.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>6.8 Slope perpendicular to the direction of travel (cross slope) shall not exceed 2%.</p>	<p>CBC 1133B.7.1.3 & ADA Stds. 4.3.7</p>	<p>Surface cross slopes Slope</p>
<p>6.9 At driveway, show how the 2% cross slope requirement is met. At a minimum, provide and indicate a 48" wide portion of the sidewalk to comply. Provide section through driveway.</p> <p>EXCEPTION: When, due to right-of-way restrictions, natural barriers or other existing conditions, DSA determines that compliance with the 48" clear sidewalk width would create an unreasonable hardship, the clear width may be reduced to 36".</p>	<p>CBSC Part 1 4-317(b) & CBC 1133B.7.1.3</p> <p>CBC 1133B.7.1</p>	<p>Plans Surface cross slopes</p> <p>Surface cross slopes</p>
<p>6.10 Slope exceeds 5% - provide curb ramp at this location. See Checklist 5 for requirements.</p>	<p>CBC 1127B.5</p>	<p>Ramps</p>
<p>6.11 Slope exceeds 5% - provide ramp at this location. See Checklist 7 for requirements.</p>	<p>CBC 1133B.5</p>	<p>Ramps</p>
<p>6.12 Provide a level resting area 5' in length at intervals of 400' maximum, or indicate that slope in the direction of travel is 2% or less by providing spot elevations.</p>	<p>CBC 1133B.7.5</p>	<p>Level areas</p>
<p>6.13 Provide a passing space, measuring 60" x 60" every 200' min, or indicate width of walk to be 60" or more.</p>	<p>CBC 1133B.7.1</p>	<p>Continuous surface</p>
<p>6.14 Provide level areas (2% max slope in any direction) at doors and gates.</p>	<p>CBC 1133B.2</p>	<p>Doors</p>
<p>6.15 Walks, sidewalks, and pedestrian ways shall be free of gratings whenever possible. See Checklist 3 for exceptions.</p>	<p>CBC 1133B.7.2</p>	<p>Gratings</p>
<p>6.16 Identify location of all gratings within the path of travel and provide cut sheet of gratings for back check review. If gratings are located in walking surfaces, then grate openings cannot exceed 1/2" in the direction of travel flow. Elongated openings should be placed perpendicular to the dominant direction of travel.</p>	<p>CBC 1124B.4 CBC 1133B.7.2 ADA Stds. 4.5.4</p>	<p>Ground/floor surfaces-Gratings Walks/Sidewalks-Gratings Gratings</p>
<p>6.17 If the level change between walk/sidewalk and adjacent surface exceeds 4" in height, provide detail and indicate a 6" warning curb or appropriate guide rails.</p>	<p>CBC 1133B.8.1</p>	<p>Warning curbs</p>
<p>6.18 If the level change between walk/sidewalk and adjacent surface exceeds 30" in height, provide detail and indicate guards (42" AFF).</p>	<p>CBC 1013</p>	<p>Guards</p>









Fig 6-A. Examples of Sidewalk Driveway Connections




Fig 6-B. Sidewalk Width

7

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 7. ACCESSIBLE RAMPS

7.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

RAMPS

CBC 1133B.5

7.2 Indicate location, layout, and slope of all ramps on site plan.

CBSC Part 1
4-317(b)

Plans

7.3 All ramps under this contract must be made accessible (i.e. those that are to be newly constructed or altered, or are part of the required path of travel).

CBC 1114B.1.2

Accessible route of travel

EXCEPTION: In alteration projects, when DSA finds unreasonable hardship and when an alternative accessible path of travel is provided.

7.4 Indicate compliance status of existing ramps in the path of travel (slope, width, landings, etc.).

CBSC Part 1
4-317(b)

Plans

7.5 Provide enlarged plan and sections (longitudinal and transversal) of ramp in 1/4" scale.

CBSC Part 1
4-317(b)

Plans

7.6 Typical ramp detail provided is not similar to actual layout. Modify to provide dimensioned detail in 1/4" scale representing the actual layout.

CBSC Part 1
4-317(b)

Plans

7.7 Indicate ramp slopes. Use least possible but never more than 8.3% max.

CBC 1133B.5.3
ADA Stds 4.8.2

Ramps – Slope
Ramps - Slope and rise

7.8 Slope perpendicular to the direction of travel (cross slope) must be 2% or less.

CBC 1133B.5.3.1

Slope

7.9 Provide spot elevations and ramp run dimensions at this location to show how slope requirements are met.

CBSC Part 1
4-317(b)

Plans

7.10 Ramp run cannot change direction between level landings.

CBC 1133B.5.4.1

Location of landings

7.11 Provide and indicate slip-resistant ramp surface.

CBC 1124B.1

Ground and floor surfaces –
general

7.12 Provide and indicate width of ramp at all locations.

1. 48" min required.

CBC 1133B.5.2

Ramps - width

2. 60" min if serving an occupancy load of ≥300 and the entrance ramp is the only exit discharge path from a building.

CBC 1133B.5.2

Ramps - width

7.13 Provide and indicate one of the following at ramps which are not bounded by a wall OR where handrails or guards are attached to the ramp surface with posts or similar elements.

CBC 1133B.5.6
ADA Stds. 4.1.7

Wheel guides
Edge protection

1. Guide curb 2" high minimum above ramp surface.

2. Wheel guide rail centered at 3" AFF (+/- 1") above ramp surface.

7

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 7. ACCESSIBLE RAMPS

Guide curbs or wheel guide rails shall provide a continuous and uninterrupted barrier along the length of the ramp.

RAMP LANDINGS

7.14 Provide and indicate dimension of top landing.

1. 60" x 60" min.
2. Level (2% max slope).

CBC 1133B.5.4

Landings

7.15 Provide and indicate dimension of bottom landing.

1. 72" long and as wide as the ramp, if no change in direction.
2. 72" long and 60" wide, if change in direction.
3. Level (2% max slope).

CBC 1133B.5.4.2

Size of top and bottom landings

CBC 1133B.5.4.1

Location of landings

CBC 1133B.5.4.2 &
CBC 1133B.5.4.5

Size of top and bottom landings
Landing width

ADA Stds 4.8.4(3)

Ramps – Landings

CBC 1133B.5.4.1

Location of landings

7.16 Provide and indicate dimension of intermediate landing.

1. 60" long and as wide as the ramp, if no change in direction.
2. 72" long and 60" wide, if change in direction.
3. Level (2% max slope).
4. Provide intermediate landing at each change in direction.

CBC 1133B.5.4.5 &
CBC 1133B.5.4.7

Landing width
Other intermediate landings

CBC 1133B.5.4.6 &
ADA Stds 4.8.4(3)

Change of direction
Ramps – Landings

CBC 1133B.5.4.1

Location of landings

CBC 1133B.5.4.1

Location of landings

7.17 Provide and indicate dimension of ramp landing at door or gate.

1. Doors at ramp landings shall comply with the maneuvering clearances of 1133B.2.4.2.
2. Doors in any position cannot reduce the minimum dimension of the landing to less than 42".
3. Fully opened doors cannot reduce the required width of the landing by more than 3".
4. Level (2% max slope).

CBC 1133B.2.4.2 &
CBC 1133B.5.4.3

Maneuvering clearances at doors
Doors at ramp landings

CBC 1133B.5.4.4

Encroachment of doors

CBC 1133B.5.4.4

Encroachment of doors

CBC 1133B.5.4.1

Location of landings


7

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 7. ACCESSIBLE RAMPS



- 7.18** Provide intermediate landings at intervals not exceeding 30" of vertical rise.
- 7.19** If ramps change direction at landings, the intermediate and bottom landings shall be a minimum of 60" wide.
- 7.20** Indicate how exterior ramps and landings are designed so that water will not accumulate on walking surface.
- 7.21** Provide enlarged detail, showing smooth transition between ramp runs, landings, and existing surfaces.

CBC 1133B.5.4.1
 ADA Stds 4.8.4(3)
 CBC 1133B.5.8
 CBSC Part 1 4-317(b)

Location of landings
 Landings
 Outdoor ramps
 Plans

HANDRAILS FOR RAMPS

- 7.22** Provide handrails on both sides of ramp.
 EXCEPTIONS:
 - a. Ramps at exterior door landings that rise less than 6" or have a projection of less than 72".
 - b. Curb ramps.
 - c. Ramps immediately adjacent to seating in assembly areas.
- 7.23** Handrails must be continuous the full length of the ramp run, plus extensions.
- 7.24** Inside handrails at switchback or dogleg ramps must be continuous.
- 7.25** Top of gripping surface must be between 34" and 38" AFF.

CBC 1133B.5.5.1, &
 CBC 1133B.5.5.1
 CBC 1133B.5.5.1
 CBC 1133B.5.5.1

Handrails for ramps
 Handrails for ramps
 Handrails for ramps

7

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation


Headings / Comments / Notes & Examples

Check List 7. ACCESSIBLE RAMPS

7.26 Extend handrail 12" beyond the top and bottom of the ramp run.


CBC 1133B.5.5.1 & ADA Stds 4.8.5(2)

Ramp handrails
Handrails



Not Acceptable

Handrail at landing does NOT extend 12 inches minimum in the direction of the ramp run.



Acceptable

Handrail at landing extends 12 inches minimum in the direction of the ramp run.

NOTE:
Top and bottom handrail extensions are important safety features for persons with mobility impairments and must extend in the direction of the ramp run to permit the intended use.

7.27 Handrail extension cannot extend into the required width of an adjacent route of travel. Relocate ramp or modify design.

CBC 1133B.8.6.1

Protruding objects - General

7.28 Handrail extensions must be parallel to landing surface.

CBC 1133B.5.5.1 &

Handrails

7.29 Provide cane detectable rail portion below 27" AFF if portion of rail that is more than 27" AFF protrudes more than 4" into a perpendicular running circulation path.


CBC 1133B.8.6.1

Protruding objects - General

7.30 Return ends of handrail extension to wall, floor or post.


CBC 1133B.5.5.1

Handrails for ramps



Hazardous

Handrail extension does not terminate safely to the wall, floor or post.



Compliant

Handrail extension end is returned to wall.

7.31 Indicate gripping portion of handrail to be 1-1/4" to 1-1/2" in cross-sectional nominal dimension or provide shape with equivalent gripping surface (i.e. 4" to 6-1/4" perimeter, and 2-1/4" max in any direction).

CBC 1133B.5.5.1

Handrails for ramps

NOTE:
When using industry standard round steel handrails (1-1/2" nominally dimensioned) DSA may approve an actual outside diameter of 1-7/8" max.

7


Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 7. ACCESSIBLE RAMPS

- 7.32** Provide and indicate 1-1/2" clearance from adjacent obstruction (wall or guard).
- 7.33** Recess to be 3" deep maximum with 18" min height, measured from the top of the handrail.



CBC 1133B.5.5.1 &

CBC 1133B.5.5.1

Handrails for ramps

Handrails for ramps

- 7.34** All gripping surfaces must be smooth, with no sharp edges, continuous, without interruption by newel posts, and other construction elements, or obstructions.
- 7.35** Handrails and adjacent walls or other surfaces shall be free of any sharp or abrasive elements. Edges shall have a minimum radius of 1/8".
- 7.36** Handrails may project into the required clear width a distance of 3-1/2" maximum from each side of a ramp at the handrail height.
- 7.37** Provide guards, 42" high, as a vertical barrier along the open edges of ramps, platform, or landings to prevent persons from falling off the open edge if drop exceeds 30".
- 7.38** Indicate that a sphere 4" in diameter cannot pass through any opening at guards (intermediate rails or an ornamental pattern).

CBC 1133B.5.5.1, ADA Stds 4.9.4(4) & ADA Stds 4.26

CBC 1133B.5.5.1

CBC 1133B.5.5.1

CBC 1013
CBC 1133B.5.7

CBC 1013.3

Handrails for ramps
Handrails
Handrails

Handrails for ramps

Handrails for ramps

Guards
Guards

Opening Limitations

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code
Citation

Headings / Comments / Notes
& Examples

(as applicable)

Check List 8. DOORS AND GATES

<p>8.1 For additional scoping requirements and exceptions see also applicable DSA-AC Checklist 1.</p>		
<p>8.2 Identify the following doors on plans and coordinate with numbers/characters in door schedule:</p> <ol style="list-style-type: none"> 1. All doors for new construction. 2. All doors that are being altered in existing buildings. 3. All doors in existing buildings that are in the accessible route of travel, including existing doors. 	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>8.3 Include all doors in door schedule.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>8.4 Provide the following information for each door in the door schedule:</p> <ol style="list-style-type: none"> 1. Door mark number/character. 2. Room name/number. 3. Width of door leaf or clear opening. 4. Reference to sheet and detail for new or existing door types. 5. Reference to sheet and detail for new or existing thresholds for exterior doors, and interior doors with special flooring transitions (gymnasium, rubber flooring, etc). 6. Reference to sheet and detail for required signage including: tactile/Braille exit signs, restroom signs, entrance signs, identifying room signs, directional signs, etc. 7. "Copy" of door signage. 8. Hardware group for new doors or existing doors that are being altered. 	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>8.5 Indicate either on plan or in schedule that existing door in the accessible route has accessible threshold, hardware, closer, and 10" smooth surface at bottom of push side (e.g. kick plate).</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>8.6 All entrances and ground floor exit doors must be made accessible.</p> <p>EXCEPTIONS:</p> <ol style="list-style-type: none"> a. Exterior ground floor exits serving smoke-proof enclosures, stairwells and exit doors servicing stairs only. b. Exits in excess of those required by Chapter 10, and which are more than 24" above grade. Such doors shall have visual signs which indicate, by means of an arrow and/or text, the location of the nearest accessible exit. The warning sign shall comply with Section 1117B.5.1, Item 2. c. In existing buildings, where DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided. Equivalent facilitation would require at least one entrance to be accessible. 	<p>CBC 1133B.1.1.1.1</p>	<p>Entrances</p>


Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code
Citation

Headings / Comments / Notes
& Examples

(as applicable)

Check List 8. DOORS AND GATES

<p>d. In existing buildings where DSA determines that, due to legal or physical constraints, compliance with the height requirement or equivalent facilitation would create an unreasonable hardship.</p>		<p>NOTE: Jurisdictional findings and determinations are subject to an internal DSA appeals process.</p>
<p>8.7 In existing buildings and facilities, a service entrance can not be the only accessible entrance unless it is the only entrance to a building or facility.</p>	<p>CBC 1133B.1.1.1.5</p>	<p>Services entrances</p>
<p>8.8 All doors on an accessible route of travel must be made accessible.</p>	<p>CBC 1114B.1.1</p>	<p>General</p>
<p>8.9 Revolving doors or turnstiles cannot be used as the only means of entrance and exit. Provide an accessible door adjacent, designed to facilitate the same use pattern.</p>	<p>CBC 1133B.2.3.3 CBC 1133B.2.3.4</p>	<p>Revolving doors Turnstiles, rails and pedestrian controls</p>
<p>8.10 Provide and indicate door leafs to be 3' - 0" min (4'-0" max) in width and 6' - 8" min in height.</p>	<p>CBC 1008.1.1 CBC 1133B.2.2</p>	<p>Size of doors Doors - Width and height</p>
<p>8.11 Hinged door must open at least 90°.</p>	<p>CBC 1133B.2.2</p>	<p>Hinged doors</p>
<p>8.12 Door must provide a clear opening of 32" when positioned at an angle of 90 degrees from the closed position (measured between the face of the door and the opposite stop).</p> <p>EXCEPTION: Doors not requiring full user passage, such as shallow closets (i.e., 24" or less in depth), may have the clear opening reduced to 20" minimum width.</p>	<p>CBC 1133B.2.2, & CBC 1133B.2.3</p>	<p>Doors - Width and height Hinged doors</p>
<p>8.13 In existing buildings, when an exit is not accessible, provide a sign to direct people to the nearest accessible means of egress. The sign shall comply with CBC Section 1117B.5 and be mounted at a location so steps do not need to be retraced.</p>	<p>CBC 1007.10 CBC 1117B.5 ADA Stds 4.1.6(1)(h)</p>	<p>Accessible means of egress – signage Signs Entrances</p>
<p>8.14 Provide clear opening width dimension.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>8.15 At double doors, with or without mullion, automatic or manual, indicate clear opening width of one of the doors to be 32" min.</p>	<p>CBC 1133B.2.3.1 CBC 1133B.2.3.2</p>	<p>Pair of doors Automatic Doors</p>
	<p>CBC 1133B.2.4</p>	<p>Floor level at doors</p>
<p>8.16 Provide and indicate a clear and level (2% slope) landing on each side of door.</p>	<p>CBC 1133B.2.4</p>	<p>Floor level at doors</p>
<p>8.17 Provide and indicate the following maneuvering clearances and level landings at door:</p>	<p>CBC Fig. 11B-26A & CBC Fig. 11B-26B</p>	<p>Level maneuvering clearances at doors</p>
<p>1. Front approach to pull side of door must have maneuvering space that extends 24" min at exterior doors (18" min at interior doors) beyond the latch side of the door and 60" min perpendicular to the doorway.</p>		

8

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code
Citation

Headings / Comments / Notes
& Examples

(as applicable)

Check List 8. DOORS AND GATES

- 2. Front approach to push side of door, equipped with closer and latch, must have maneuvering space that extends 12" min beyond the latch side of the door and 48" min perpendicular to the doorway.
- 3. Front approach to push side of door, not equipped with latch and closer, must have maneuvering space that is the same width as door opening and extends 48" min perpendicular to the doorway.
- 4. Hinge-side approach to pull side of door must have maneuvering space that extends 36" min beyond the latch side of the door and 60" min perpendicular to the doorway.
- 5. Hinge side approach to push side of door, equipped with latch and closer, must have maneuvering space of 54" min parallel to the doorway and 48" min perpendicular to the doorway.
- 6. Hinge-side approach to push side of door, not equipped with latch and closer, must have a maneuvering space of 54" min parallel to the doorway and 44" min perpendicular to the doorway.
- 7. Latch-side approach to pull side of door must have maneuvering space that extends 24" min beyond the latch side of the door and 60" min perpendicular to the doorway.
- 8. Latch-side approach to push side of door, with closers, must have maneuvering space that extends 24" min parallel to the doorway beyond the latch side of the door and 48" min perpendicular to the doorway.
- 9. Latch-side approach to push side of door, not equipped with closers, must have maneuvering space that extends 24" min parallel to the doorway beyond the latch side of the door and 44" min perpendicular to the doorway.

8.18 When a door is located in a recess or alcove and the plane of the doorway is offset 8" or more from any obstruction within 18", measured laterally on the latch side, the door shall be provided with maneuvering clearance for front approach.


CBC 1133B.2.4.5
CBC Fig. 11B-33(a)

Recessed doors
Clear door width and depth - Pull side

8.19 Level difference at landing/threshold transition between 1/4" and 1/2" must be beveled at 1:2.

CBC 1133B.2.4.1

Floor level at doors - Thresholds



8.20 Indicate level difference between top of threshold and door landing to be 1/2" max (if beveled at 1:2).

CBC 1133B.2.4.1

Floor level at doors - Thresholds

8.21 Indicate level difference between interior and exterior door landing to be 1/2" max (if beveled at 1:2).

CBC 1133B.2.4.1

Floor level at doors - Thresholds


Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples
(as applicable)

Check List 8. DOORS AND GATES

8.22 In existing projects, level differences at landing/threshold transitions greater than 1/2" shall be accomplished by means of ramps or sloped walking surfaces and must include required level landings.



CBC 1133B.2.4.1 & CBC 1133B.5.1

Floor level at doors - Thresholds
Ramps - General

NOTE:
Handrails are not required on ramps at exterior door landings with less than 6" rise and 72" in length (CBC 1133B.5.5.1, ADAAG 4.8.5).

8.23 Recessed doormats, grills, and carpets must be adequately anchored to prevent interference with wheelchair traffic.

CBC 1133B.1.1.1.3

Entrances - Recessed doormats

DOOR HARDWARE

8.24 If door closers are used, indicate maximum effort to operate doors either in drawings or specifications:

1. 5 lbf max for interior doors.
2. 5 lbf max for exterior doors.

CBC 1133B.2.5

Door opening force

EXCEPTION: When, at a single location, one of every 8 exterior door leaves, or fraction of 8, is a powered door, other exterior doors at the same location, serving the same interior space, may have a maximum opening force of 8.5 lbf. The powered leaf(s) shall be located closest to the accessible route.

CBC 1133B.2.5, Ex 2

Door opening force

8.25 At fire doors or rated doors provide the following note: "The Authority having Jurisdiction may increase the maximum effort to operate fire doors in order to achieve positive latching, but not exceeding 15 lbf maximum."

CBC 1133B.2.5

Door opening force

8.26 Push button to operate automatic or power-assisted door must be located in an accessible location that is adjacent to or part of the general accessible route of travel; visible and easily recognizable from the main approach; and so that the clear

CBC 1133B.2.5 Ex 2

Door opening force

8

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code
Citation

Headings / Comments / Notes
& Examples

(as applicable)

Check List 8. DOORS AND GATES

<p>floor or ground space in front of the button is outside any door swing.</p>		
<p>8.27 Indicate height of push button to operate power-assisted door to be between 15" and 48" AFF for forward approach / forward reach or between 9" and 54" AFF for parallel approach / side reach.</p>	<p>CBC 1117B.6 #3 CBC 1118B.5 CBC 1118B.6</p>	<p>Controls and operating mechanisms - Height Forward reach Side reach</p>
<p>8.28 Indicate mounting height of hand-activated door hardware, including all dead bolts, between 30" and 44" AFF (36" preferred).</p>	<p>CBC 1133B.2.5.2</p>	<p>Closer-effort to operate doors</p>
<p>8.29 Provide note or detail indicating floor-mounted doorstops and similar obstructions to be installed 4" max from the face of the wall or partition.</p>		
<p>8.30 Indicate smooth, uninterrupted surface at the bottom 10" of push side of door leaf.</p>	<p>CBC 1133B.2.6</p>	<p>Smooth surface</p>
<p>8.31 Provide a 10" high kick plate cover at the bottom of the push side of narrow frame doors.</p>	<p>CBC 1133B.2.6</p>	<p>Smooth surface</p>
<p>8.32 Provide a 10" high kick plate cover at the bottom of doors where hardware is surface-mounted (i.e. exposed rod for panic device).</p>	<p>CBC 1133B.2.6</p>	<p>Smooth surface</p>
<p>GATES</p>		
<p>8.33 All gates intended for pedestrian use, including ticket gates, must comply with all applicable requirements of doors (see items above).</p>	<p>CBC 1133B.1.1.1.4</p>	<p>Gates</p>
<p>8.34 Identify gate with a mark on plans and include in door schedule.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>8.35 Provide and indicate accessible operating hardware and 10" high smooth surface at bottom of gate.</p>	<p>CBC 1133B.2.5.2 CBC 1133B.2.6</p>	<p>Smooth surface</p>
<p>8.36 Gate on required exit path must comply with exit door and hardware requirements.</p>	<p>CBC 1133B.1.1.1.4</p>	<p>Gates</p>







Fig 8-A. Door Maneuvering Clearances and Landings




FRONT APPROACH
SLIDING DOORS




FRONT APPROACH
FOLDING DOORS




SLIDE SIDE APPROACH
SLIDING DOORS



SLIDE SIDE APPROACH
FOLDING DOORS



LATCH SIDE APPROACH
SLIDING DOORS



LATCH SIDE APPROACH
FOLDING DOORS

NOTE: ALL DOORS IN ALCOVES SHALL COMPLY WITH THE CLEARANCES FOR FRONT APPROACHES.

Fig 8-A. Door Maneuvering Clearances and Landings (cont.)

9

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 9. CORRIDORS, HALLWAYS, AND VESTIBULES

9.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

CORRIDORS, HALLWAYS, EXTERIOR EXIT BALCONIES

9.2 All corridors, hallways, and exterior exit balconies must be made accessible.

EXCEPTIONS:

- a. In existing buildings, when an area is not part of the planned alteration or part of the required path of travel to the area of alteration.
- b. Corridors, hallways, and exterior exit balconies on floors or portions of floors not customarily occupied, including non-occupiable or employee spaces accessed only by ladders, catwalks, crawl spaces, very narrow passageways, and frequented only by service personnel for repair or maintenance purposes, including, but not limited to, elevator pits and elevator penthouses, piping and equipment catwalks and machinery rooms.

9.3 Provide and indicate clear widths as follows:

1. 36" min if occupancy load is <10.
2. 44" min if occupancy load is 10 or more.
3. 60" min if corridor, hallway, or exterior exit balcony exceeds 200' in length without passing spaces, at least 60" x 60" at intervals of 200' maximum. A T-intersection of two corridors or walks is an acceptable passing space.

EXCEPTIONS:

- a. In existing buildings, where DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.
- b. In existing buildings where DSA determines that, due to legal or physical constraints, compliance with building standards requirements or equivalent facilitation would create an unreasonable hardship.

9.4 Corridor, hallway, or exterior exit balcony in Group E, Div. 1 occupancy (K-12 facilities), serving an occupancy load of 100 or more must be 72" min wide.

9.5 Corridor, hallway, or exterior exit balcony in Group E, Div. 1 occupancy (K-12 facilities), serving an occupancy load of less than 100 must be 44" min wide.

9.6 If corridor, hallway, or exterior exit balcony slopes more than 5%, indicate compliance with all requirements for ramps.

CBC 1133B.3

CBC 1114B.1.1,
CBC 1114B.1.2, &
CBC 1133B.3

CBC 1134B.2

CBC 1103B.1, Exc 1

CBC 1133B.3.1

CBC 1133B.3.1

CBC 1133B.3.2 &
ADA Stds 4.3.4

CBC 1017.2, Ex. 4 &
CBC 1014.5

CBC 1017.2 &
CBC 1014.5

CBC 1133B.5.1

Facility accessibility-general
Accessible route of travel
Corridors, hallways and exterior
exit balconies

(Existing buildings) General

Building accessibility - General

Corridor and hallway widths

Corridor and hallway widths

Corridors and hallways over 200'
Passing space

NOTE:
Jurisdictional findings and
determinations for exception b are
subject to an internal DSA appeals
process.

Corridor width
Egress balconies

Corridor width
Egress balconies

Ramps – General

9

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).


Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 9. CORRIDORS, HALLWAYS, AND VESTIBULES


9.7 Provide and indicate required maneuvering space at the following conditions:

1. When turning around an obstruction.



- 2. Wherever a person using a wheelchair may have to make a 180° turn.
- 3. At doors and gates.
- 4. To access elements or equipment.

9.8 Wall mounted object(s) with bottom edge(s) between 27" and 80" above the ground shall not protrude more than 4" into pedestrian circulation area.



9.9 Provide guards, 42" high, as a vertical barrier along the open edges of walking surfaces, mezzanines, industrial equipment platforms, stairways, ramps and landings to prevent persons from falling off the open edge if drop exceeds 30".

VESTIBULES

9.10 Indicate and provide 48" min between two hinged or pivoted doors plus the width of any door(s) swinging into the space.

9.11 Doors in series must swing either in the same direction or away from the space between the doors.

CBC Fig. 11B-5E (a) & (b)

CBC Fig 11B-12

CBC Fig 11B-26A & 11B-26B

CBC 1133B.8.6 & CBC Fig. 11B-7A

CBC 1013

CBC 1133B.2.4.4 & ADA Stds 4.13.7

CBC 1133B.2.4.4 & ADA Stds 4.13.7

Width of accessible route

NOTE:
* If occupancy load is 10 or more, the minimum width of all dimensions must be increased to 44" min.

Wheelchair turning space

Level maneuvering clearances at doors

Protruding objects

Guards

Two doors in series

Two doors in series

10

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 10. STAIRS AND STEPS

<p>10.1 A stair is a change in elevation, consisting of one or more risers.</p>	<p>CBC 1002</p>	<p>Definitions - Stair</p>
<p>10.2 All stairs, stairways, and steps must be accessible.</p> <p>EXCEPTIONS:</p> <p>a. In existing buildings, when stairs are not part of the planned alteration and compliant vertical access is provided through elevators, lifts or ramps, stairways need not be accessible.</p> <p>b. Stairs to floors or portions of floors not customarily occupied, including non-occupiable or employee spaces accessed only by ladders, catwalks, crawl spaces, very narrow passageways, and frequented only by service personnel for repair or maintenance purposes, including, but not limited to, elevator pits and elevator penthouses, piping and equipment catwalks and machinery rooms need not be accessible with the exception of stair striping.</p>	<p>CBC 1114B.1.1 CBC 1133B.4</p> <p>CBC 1134B.2.1 ADA Stds. 4.1.6(d)</p> <p>CBC 1103B.1, Exc 1</p>	<p>Facility accessibility - General Stairways</p> <p>Accessibility for existing buildings Accessible buildings - Alterations</p> <p>Building accessibility – General</p> <p><u>NOTE:</u> All vertical level changes, exceeding 1/4" in height (or 1/2" if beveled at 1:2), and within a pedestrian circulation area are considered stairs or steps, with the exception of curbs that border vehicular ways.</p>
<p>10.3 Stair treads and risers must comply with the following:</p> <ol style="list-style-type: none"> 1. Treads shall be no less than 11" deep. 2. Risers shall be 7" max and 4" min in height. 3. On a flight of stairs, all steps shall have uniform riser height and tread width. 4. Open risers are not permitted. 	<p>CBC 1133B.4.5</p>	<p>Stair treads, risers and nosing</p>
<p>EXCEPTIONS:</p> <p>a. On exterior stairways, an opening of not more than 1/2" may be permitted between the base of the riser and the tread.</p> <p>b. On exterior stairways, risers constructed of grating containing openings of not more than 1/2" may be permitted.</p>	<p>CBC 1133B.4.5.2</p>	<p>Risers</p>
<p>10.4 All tread surfaces shall be slip resistant. Weather-exposed stairs and their approaches shall be designed so that water will not accumulate on the walking surfaces. Treads shall have smooth, rounded or beveled exposed edges.</p>	<p>CBC 1133B.4.5.1</p>	<p>Treads</p>
<p>10.5 Risers shall be solid and shall be vertical or sloped from the underside of the leading edge of the tread above at an angle not more than 30 degrees from the vertical.</p>	<p>CBC 1133B.4.5.2</p>	<p>Risers</p>
<p>10.6 Stair nosing must comply with the following:</p> <ol style="list-style-type: none"> 1. 1/2" max radius of curvature at leading edge of tread. 	<p>CBC 1133B.4.5.3</p>	<p>Nosing</p>

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 10. STAIRS AND STEPS

<p>2. Nosings that project beyond risers must have the underside of the leading edge beveled at an angle not more than 30 degrees from the vertical.</p> <p>3. Maximum permitted projection of the nosing is 1-1/4".</p> <p>EXCEPTION: In existing buildings there is no requirement to retroactively alter existing nosing projections of 1-1/2" which were constructed in compliance with the building code in effect at the time of original construction.</p> <p>4. The transition from the nosing to the riser shall be free of abrupt edges.</p> <p>5. All projections shall be of uniform size, including nosings at landings.</p>		
<p>10.7 Provide detail of color contrasting striping at all stairs and steps within the pedestrian circulation area. Indicate the following:</p> <p>1. Upper approach and all treads of exterior stairs must have a stripe of contrasting color.</p> <p>2. Upper approach and lower tread of interior stairs must have a stripe of contrasting color.</p> <p>3. Contrasting color stripe to be 2" min to 4" max wide and be located 1" max from the front edge of the step or landing.</p> <p>4. The stripe shall be as slip resistant as the other treads of the stair and shall extend the full width of the step or upper approach. A painted stripe is acceptable.</p>	<p>CBC 1133B.4.4 CBC Fig. 11B-35</p>	<p>Striping for the visually impaired Warning striping and handrail extensions</p>
<p>10.8 Provide and indicate width of stairway to be 44" min, or 36" min if serving an occupancy load of <50.</p> <p>EXCEPTION: Stairways adjacent to or serving an area of refuge must be 48" min clear between handrails.</p>	<p>CBC 1009.1</p> <p>CBC 1007.3 ADA Stds. 4.3.11.3</p>	<p>Stairway width</p> <p>Exit stairways Areas of rescue assistance – Stairway width</p>
<p>10.9 Indicate top and bottom landing to slope no more than 2% in any direction and have a dimension in the direction of travel not less than the width of the stairway.</p> <p>EXCEPTIONS:</p> <p>a. Aisle stairs complying with CBC Section 1025.</p> <p>b. At straight stair runs the landing need not exceed 48".</p> <p>c. Provide additional space where landings serve as areas of refuge.</p>	<p>CBC 1009.5 CBC 1009.6.1</p> <p>CBC 1009.5, Ex. 1</p> <p>CBC 1009.5</p> <p>CBC 1007.6.1</p>	<p>Stairway landings Stairway walking surface</p> <p>Stairway landings</p> <p>Stairway landings</p> <p>Areas of refuge - size</p>

10

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 10. STAIRS AND STEPS

<p>d. Doors opening onto a landing shall not reduce the landing to less than one-half the required width. When fully open, the door shall not project more than 7 inches (178 mm) into a landing.</p>	<p>CBC 1009.5</p>	<p>Stairway landings</p>
<p>10.10 Increase stair landing dimensions to accommodate required maneuvering space for doors.</p>	<p>CBC 1133B.2.4.2</p>	<p>Maneuvering clearances at doors</p>
<p>10.11 Indicate clear headroom of 6' - 8" min at stairs and landings.</p>	<p>CBC 1009.2</p>	<p>Headroom</p>
<p>10.12 When staircase underside creates a hazardous overhead obstruction, provide cane-detectable barrier to warn blind or visually impaired.</p>	<p>CBC 1133B.8.6.2 & CBC Fig. 11B-7C</p>	<p>Head room</p>
<p>10.13 Provide and indicate location of tactile floor designation signs. See Checklist 17 for additional requirements.</p>	<p>CBC 1133B.4.3</p>	<p>Tactile floor designation signs in stairways</p>
<p>HANDRAILS FOR STAIRS</p>		
<p>10.14 Provide handrails on both sides of stairs.</p>	<p>CBC 1133B.4.1.1</p>	<p>Required handrails</p>
<p>EXCEPTIONS:</p>		
<p>a. Stairs located immediately adjacent to fixed seating in assembly areas.</p>	<p>CBC 1009.12</p>	<p>(Stairways) Handrails</p>
<p>b. In existing facilities where:</p> <ul style="list-style-type: none"> ▪ stairs are not within the specific area of alteration, and ▪ stairs are not part of the required path of travel. 	<p>CBC 1134B.2.1</p>	<p>Accessibility for existing buildings</p>
<p>10.15 Stairways shall have intermediate handrails located in such a manner that all portions of the stairway width required for egress capacity are within 30" of a handrail. On monumental stairs, handrails shall be located along the most direct path of egress travel.</p>	<p>CBC 1012.8</p>	<p>Intermediate handrails</p>
<p>10.16 Design to provide continuous handrails on the full length of the stair run.</p>	<p>CBC 1133B.4.1.1</p>	<p>Required handrails</p>
<p>10.17 Design to provide continuous inside handrails at intermediate landings.</p>	<p>CBC 1133B.4.2.2</p>	<p>Handrail configuration</p>
<p>10.18 Top of gripping surface of handrail must be between 34" and 38" AFF.</p>	<p>CBC 1133B.4.2.1</p>	<p>Handrail configuration</p>
<p>10.19 Indicate a specific height from front edge of nosing to top of handrail gripping surface.</p>	<p>CBSC Part 1, 4-317(b)</p>	<p>Plans</p>
<p>10.20 Extend handrail 12" beyond the top of the stair run and parallel to the landing surface (see Fig 10-A).</p>	<p>CBC 1133B.4.2.2 ADA Stds. Fig. 19(d)</p>	<p>Handrail configuration Stair Handrails - Extension at top of run</p>
<p>10.21 Extend handrail 12" plus the width of one tread beyond the bottom riser. The handrail must continue to slope for a distance of the width of one tread and the remainder of the extension must be parallel to the landing surface (see Fig 10-A).</p>	<p>CBC 1133B.4.2.2 ADA Stds. Fig. 19(c)</p>	<p>Handrail configuration Stair Handrails - Extension at bottom of run</p>

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 10. STAIRS AND STEPS

10.22 Handrail extension cannot extend into the required width of an adjacent route of travel or the required width of an exit discharge component.

CBC 1003.3.4

Clear width

10.23 Handrail extensions must meet the following requirements:

1. Handrail extensions must extend in the direction of the stair handrail.
2. Return ends of handrail extension to wall, floor or post.

CBC 1133B.4.2.2

Handrail configuration

CBC 1133B.4.2.3


EXCEPTIONS:

- a. In existing buildings, where DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.
- b. In existing buildings where DSA determines that, due to legal or physical constraints, compliance with building standards or equivalent facilitation would create an unreasonable hardship.

CBC 1133B.4.2.6.1
ADA Stds. 4.1.6(3)(b)

Stairways - Handrail configuration
Alterations - Stairs

NOTE:
Jurisdictional findings and determinations for exception (b) are subject to an internal DSA appeals process.



Hazardous

Handrail extension does not terminate safely to the wall, the floor, or newel.

Compliant

Handrail extension end is returned to wall.

NOTE:
Top and bottom handrail extensions are important safety features for people with balance problems and must therefore extend in the direction of the stair run.

10.24 Indicate gripping portion between 1-1/4" and 1-1/2" in cross-sectional nominal dimension or the shape shall provide an equivalent gripping surface (i.e. 4" to 6-1/4" perimeter, and 2-1/4" max in any direction).

CBC 1133B.4.2.6

Handgrips

NOTE:
When using industry standard steel handrails (nominally dimensioned) DSA may approve an actual outside diameter of 1-7/8" max.

10.25 All gripping surfaces and adjacent wall or other surface must be smooth with no sharp edges, and continuous, without interruption by newel posts, other construction elements, or obstructions. Edges shall have a minimum radius of 1/8".

CBC 1133B.4.2.6
ADA Stds. 4.9.4

Handgrips
Handrails

10.26 Provide and indicate 1-1/2" absolute clearance from adjacent obstruction (wall or guard).

CBC 1133B.4.2.5

Handrail configuration


Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 10. STAIRS AND STEPS

10.27 Recess to be 3" deep maximum with a minimum 18" height, measured from the top of the handrail.



CBC 1133B.4.2.5
CBC Fig. 11B-36

Stairways - Handrail configuration
Stair handrails

10.28 Provide guard, 42" min high, as a vertical barrier along the open edges of stairs, platform, or landings to prevent persons from falling off the open edge if drop exceeds 30".


CBC 1013.1
CBC 1013.2

Guards
Guards - Height

10.29 Indicate that a sphere 4" in diameter cannot pass through any opening at guards (intermediate rails or an ornamental pattern).

CBC 1013.3

Guards - Opening limitations



NOTE: INNER HANDRAIL AT LANDINGS OF STAIRS THAT DOUBLE BACK OR IMMEDIATELY TURN SHALL BE CONTINUOUS AND SHALL NOT EXTEND INTO LANDING OR PATH OF TRAVEL.

X: EXTENSION OF HANDRAIL SHALL BE EQUAL TO THE TREAD WIDTH PLUS 12 INCHES.





Fig 10-A. Requirements for Stairs and Stair Handrails

All dimensions are inches, u.o.n.

11

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 11. ACCESSIBLE MEANS OF EGRESS

11.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

ACCESSIBLE MEANS OF EGRESS

11.2 Indicate all accessible spaces are provided with not less than one accessible means of egress. Where more than one means of egress is required by Chapter 10 from any accessible space, indicate each accessible portion of the space is served by accessible means of egress in at least the same number as required by Section 1015.1 or 1019.1.

EXCEPTIONS:

- a. Accessible means of egress are not required in alterations to existing buildings.
- b. One accessible means of egress, consisting of an exit stairway, elevator or platform lift, is required from an accessible mezzanine level.
- c. In assembly spaces with sloped floors, one accessible means of egress is required from a space where the common path of egress travel of the accessible route for access to the wheelchair spaces meets the requirements of Section 1025.8.

11.3 Indicate each required accessible means of egress is continuous to a public way and consists of one or more of the following components:

1. Accessible routes, complying with Section 1114B.1.2
2. Stairways within vertical exit enclosures, complying with Sections 1007.3, 1020 and 1133B.4
3. Exterior exit stairways, complying with 1007.3, 1023 and 1133B.4
4. Elevators, complying with 1007.4 and 1116B.1
5. Platform (wheelchair) lifts, complying with Sections 1007.5 and 1116B.2
6. Horizontal exits, complying with Section 1021
7. Ramps, complying with 1010 and 1133B.5
8. Areas of refuge, complying with 1007.6

EXCEPTIONS:

- a. Where the exit discharge is not accessible, an exterior area for assisted rescue must be provided.
- b. Where the exit stairway is open to the exterior, the accessible means of egress shall include either an area of refuge or an exterior area for assisted rescue.

CBC 1007

Accessible means of egress

CBC 1007.1

Accessible means of egress required

CBC 1007.2

Continuity and components

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 11. ACCESSIBLE MEANS OF EGRESS

11.4 In buildings where a required accessible floor is four or more stories above or below a level of exit discharge, indicate that at least one required accessible means of egress is an elevator.

EXCEPTIONS:

- a. In buildings equipped throughout with an automatic sprinkler system, the elevator shall not be required on floors provided with a horizontal exit and located at or above the level of exit discharge.
- b. In buildings equipped throughout with an automatic sprinkler system, the elevator shall not be required on floors provided with a ramp.

CBC 1007.2.1

Elevators required

EXIT STAIRWAYS

CBC 1007.3

Exit stairways

11.5 Indicate an exit stairway provides a clear width of 48" min between handrails and either incorporates an area of refuge within an enlarged floor-level landing or can be accessed from either an area of refuge complying with Section 1007.6 or a horizontal exit.

CBC 1007.3

Exit stairways

EXCEPTIONS:

- a. Unenclosed exit stairways as permitted by Section 1020.1 are permitted to be considered part of an accessible means of egress.
- b. The area of refuge is not required at unenclosed exit stairways as permitted by Section 1020.1 in buildings or facilities that are equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1.
- c. The clear width of 48 inches between handrails is not required at exit stairways in building or facilities equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2.
- d. The clear width of 48 inches between handrails is not required for exit stairways accessed from a horizontal exit.
- e. Areas of refuge are not required at exit stairways serving open parking garages.

11

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 11. ACCESSIBLE MEANS OF EGRESS

ELEVATORS

- 11.6** Indicate an elevator complies with the emergency operation and signaling device requirements of ASME A17.1, Section 2.27. Indicate standby power is provided in accordance with Sections 2702 and 3003. Indicate the elevator can be accessed from either an area of refuge complying with Section 1007.6 or a horizontal exit.

EXCEPTION:

Elevators are not required to be accessed from an area of refuge or horizontal exit in open parking garages.

CBC 1007.4

Elevators

CBC 1007.4

Elevators

PLATFORM (WHEELCHAIR) LIFTS

- 11.7** Platform (wheelchair) lifts shall not serve as part of an accessible means of egress, except where allowed as part of a required accessible route in Section 1116B.2, items 1 through 4. Indicate standby power is provided in accordance with Section 2702.2.6 for platform lifts permitted to serve as part of a means of egress.

- 11.8** Platform lifts on an accessible means of egress shall not be installed in a fully enclosed hoistway.

CBC 1007.5

Platform lifts

CBC 1007.5

Platform lifts

CBC 1007.5.1

Openness

AREAS OF REFUGE

- 11.9** Indicate required area of refuge is accessible from the space it serves by an accessible means of egress.

- 11.10** Indicate the maximum travel distance from any accessible space to an area of refuge does not exceed the travel distance permitted for the occupancy in accordance with Section 1016.1.

- 11.11** Indicate that every required area of refuge has direct access to an enclosed stairway complying with Sections 1007.3 and 1020.1 or an elevator complying with Section 1007.4.

- 11.12** Where an elevator lobby is used as an area of refuge, indicate that the shaft and lobby comply with Section 1020.1.7 for smokeproof enclosures except where the elevators are in an area of refuge formed by a horizontal exit or smoke barrier.

- 11.13** Areas of refuge must adjoin an accessible route of travel.

- 11.14** Provide, and indicate on plan, at least two 30" x 48" minimum wheelchair spaces at each area of refuge.

- 11.15** The 30" x 48" wheelchair spaces cannot encroach on any required means of egress width, including door swings and required stair landing dimensions. Access to required wheelchair spaces cannot be obstructed by more than one adjoining wheelchair space.

CBC 1007.6

Areas of refuge

CBC 1007.6.1

Areas of refuge - Size

CBC 1007.6.1

Areas of refuge - Size

11

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 11. ACCESSIBLE MEANS OF EGRESS

<p>11.16 Provide at least one 30" x 48" space on each story for every 200 persons of calculated occupant load served by the area of refuge, but never less than two at each area of refuge.</p> <p>EXCEPTION: The building official may reduce the minimum number of 30" x 48" spaces to one for each area of refuge on floors where the occupant load is less than 200.</p>	<p>CBC 1007.6.1</p>	<p>Areas of refuge - Size</p>
<p>11.17 If applicable, indicate on cover sheet, plan, or in code analysis occupancy load for each story.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>11.18 Stairs adjacent to, or serving areas of refuge, shall provide 48" minimum clear width between handrails.</p>	<p>CBC 1007.3</p>	<p>Exit stairways</p>
<p>11.19 Provide a two-way emergency communication system with both visible and audible communication for use by the fire department or rescue crews at a central control point approved by the fire department. A button shall activate both a light at the primary entrance and a light in the area of evacuation assistance indicating that the request has been received.</p>	<p>CBC 1007.6.3 CBC 1007.6.3.1</p>	<p>Two-way communication Visible communication method</p>
<p>11.20 Indicate the location of operable parts on the two-way emergency communication system.</p>	<p>CBC 1007.6.3</p>	<p>Two-way communication</p>
<p>11.21 Provide a sign which states: "AREA OF REFUGE" complying with Section 1117B.5.1 #2, including the International Symbol of Accessibility. Where exit sign illumination is required, the area of refuge sign shall be illuminated. Additionally, tactile identification signage complying with Section 1117B.5.1 #1 shall be located adjacent to each door to an area of refuge.</p>	<p>CBC 1007.9 ADA Stds 4.3.11.5</p>	<p>Identification Identification</p>
<p>11.22 Provide a sign with instructions in each area of refuge, including directions for use of emergency communications system.</p>	<p>CBC 1007.6.4 ADA Stds 4.3.11.5</p>	<p>Instructions Identification</p>

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 12. ELEVATORS AND PLATFORM (WHEELCHAIR) LIFTS

12.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1.**

ELEVATORS

12.2 Provide automatic passenger elevator to serve each level (including floors, stories, split levels, platforms, podiums, sunken areas, balconies, roof gardens, and mezzanines) in a facility that is constructed by, on behalf of, or for the use of a public entity. If more than one elevator is provided, each passenger elevator shall comply with Section 1116B.

EXCEPTIONS:

- a. Floors or portions of floors not customarily occupied, including, but not limited to, non-occupiable or employee spaces accessed only by ladders, catwalks, crawl spaces, very narrow passageways or freight (non-passenger) elevators, and frequented only by service personnel for repair or maintenance purposes, including, but not limited to, elevator pits and elevator penthouses, piping and equipment catwalks and machinery rooms.
- b. When an existing theater is subdivided into more than one facility having upper levels not accessible by ramp or elevator, and DSA determines that full compliance with this code would create an unreasonable hardship, upper levels need not be made accessible, provided all facilities at grade are accessible and any event, showing of motion pictures or other activities made available to the public in all of the facilities are scheduled to ensure that all such functions are available to the public in the accessible facility.
- c. Ramps may be provided in lieu of elevators.
- d. Platform (wheelchair) lifts may be approved by DSA between levels in lieu of passenger elevators.
- e. In existing buildings, other than dining banquet and bar facilities, when DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.
- f. In existing dining, banquet and bar facilities, when DSA determines that compliance would create an unreasonable hardship, an exception may be granted provided that a minimum of 75 percent of the dining, banquet and bar is on a common level throughout or connected by ramps, passenger elevators or platform lifts, and provided that the same services and décor are provided in an accessible space usable by the general public and are not restricted to use by people with disabilities.

CBC 1116B.1

Elevators

CBC 1103B.1,
CBC 1114B.1.2,
CBC 1120B.1,
ADA Stds 4.1.3(5), &
28 CFR 35.151(a)&(b)

Building accessibility - Scope
Accessible route of travel
Floors within each story
Accessible buildings: New construction
New construction and alterations

DEFINITION:
Health & Safety Code §19955.3
MEZZANINE: An intermediate floor placed in any story or room. When the total area of any "mezzanine floor" exceeds 33.3% of the total floor area in that room, it shall be considered as constituting an additional "story".

CBC 1104B.3.1 Ex 2

Seating

CBC 1103B.1 &
ADA Stds 4.1.3(5) -
Exception 3

Building accessibility - Scope
Accessible buildings: New construction

CBC 1120B.1 Ex 1

Floors within each story

CBC 1120B.1 Ex 2

Floors within each story

12

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 12. ELEVATORS AND PLATFORM (WHEELCHAIR) LIFTS

g. In existing buildings, when legal or physical constraints would not allow compliance with this section or equivalent facilitation without creating an unreasonable hardship.	CBC 1120B.1 Ex 3	Floors within each story <u>NOTE:</u> Jurisdictional findings and determinations for exception (g) are subject to an internal DSA appeals process.
h. Private facilities that have less than three stories or less than 3,000 sq. ft. per story, unless the building is a shopping center, a shopping mall, the professional office of a health care provider, a terminal, depot or other station used for specified public transportation, or an airport passenger terminal.	CBC 1103B.1 Ex 2.2	Building accessibility - Scope <u>NOTE:</u> Exception (h) does not apply to privately funded facilities that are intended for use by a public entity.
12.3 Indicate elevators used as a component of an accessible means of egress comply with the emergency operation and signaling device requirements of ASME A17.1, Section 2.27; comply with the standby power requirements in Section 2702 and 3003; and can be accessed from either an area of refuge complying with Section 1007.6 or a horizontal exit. Also, see Checklist 11 – Accessible Means of Egress.	CBC 1007.4	Elevators
12.4 Indicate compliance of existing elevator and provide DSA application number.	CBSC Part 1 4-317(b)	Plans
12.5 Indicate location of all elevators on each site and floor plan with an appropriate symbol (X).	CBSC Part 1 4-317(b)	Plans
12.6 Where more than one elevator is provided, all elevators must be made accessible.	CBC 1103B.1 CBC 1114B.1.2	Building Accessibility – Scope Accessible route of travel
12.7 Freight elevators are not considered as meeting the accessibility requirements unless the only elevators provided are used as combination passenger and freight elevators for the public and employees.	CBC 1116B.1	Elevators
12.8 In existing buildings, where elevators are required by Section 1134B.2 or 1103B.1, if an escalator or stair is installed where none existed previously and major structural modifications are necessary for such installation, then a means of accessible vertical access via ramp, elevator or lift shall be provided.	1103B.1	Building Accessibility - Scope
12.9 In new construction of buildings where elevators are required, and which exceed 10,000 square feet on any floor, accessible means of vertical access shall be provided within 200 feet of each stairs and each escalator. EXCEPTION: Stairs used <u>solely</u> for emergency egress.	CBC 1103B.2	Distance to elevators
12.10 In existing buildings where elevators are required, and which exceed 10,000 square feet on any floor, and where newly constructed means of vertical access is provided via stairs or escalator, an accessible means of vertical access shall be provided within 200 feet of each new stairs or escalator. EXCEPTION: Stairs used <u>solely</u> for emergency egress.	CBC 1103B.2	Distance to elevators

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 12. ELEVATORS AND PLATFORM (WHEELCHAIR) LIFTS

- 12.11** Indicate height of centerline of hall call buttons in elevator lobby or hall to be 42" AFF.
- 12.12** Indicate call button to be 3/4" min in the smallest dimension, and to be raised 1/8 inch (plus or minus 1/32 inch) above the surrounding surface.
- 12.13** Indicate centerline of visual hall lantern fixtures to be a minimum 72" o.c. AFF, 2-1/2" min in the smallest dimension, and visible from the vicinity of the hall call button.
- 12.14** Provide and indicate raised character, with corresponding contracted (Grade 2) Braille below, floor designations to be 60" AFF to centerline on both jambs of each elevator.

CBC 1116B.1.10, CBC Fig. 11B-40C & ADA Stds 4.10.3

CBC 1116B.1.10 & ADA Stds 4.10.3

CBC 1116B.1.13, CBC Fig. 11B-40C & ADA Stds 4.10.4


CBC 1116B.1.14 & CBC Fig. 11B-40C

Hall call buttons
Hoistway and elevator entrances
Hall call buttons

Hall call buttons
Hall call buttons

Hall lantern
Hoistway and elevator entrances
Hall lanterns

Doorjamb marking
Hoistway and elevator entrances



- 12.15** Indicate clearance between the car platform sill and the edge of the hoistway landing to be no greater than 1-1/4".
- 12.16** Indicate clear door opening width to be 36" min.
- 12.17** Indicate height of door re-opening sensors at nominal 5" and 29" AFF.

CBC 1116B.1.2
ADA Stds 4.10.9

CBC 1116B.1.4

CBC 1116B.1.5

Operation and leveling

Door size

Door protective and reopening device

12


Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation


Headings / Comments / Notes & Examples

Check List 12. ELEVATORS AND PLATFORM (WHEELCHAIR) LIFTS

12.18 Indicate interior dimensions for elevator cab with 36" wide side-slide opening doors to be 68" min wide, and 54" min deep between the back wall and the elevator door, and 51" min deep between the back wall and the return panel. Indicate controls located at the side wall or at the front wall next to the door.



12.19 Indicate interior dimensions for elevator cab with 36" wide center-opening doors to be 80" min wide, and 54" min deep between the back wall and the elevator door, and 51" min deep between the back wall and the return panel. Indicate the controls located on a front wall.



12.20 Provide and indicate at least one (1) handrail at 32" AFF and 1-1/2" from the wall.

CBC 1116B.1.8, CBC Fig. 11B-40A(a)

Car inside
Minimum dimensions of elevator cars - Side opening doors

CBC 1116B.1.8 & CBC Fig. 11B-40A (b)

Car inside
Minimum dimensions of elevator cars - Center opening doors

NOTE:
DSA may approve other elevator configurations and dimensions if it is clearly shown that the floor area of the elevator car provides space for wheelchair users to enter the car, turn around, maneuver within reach of controls, and exit from the car.

CBC 1116B.1.11

Handrails

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 12. ELEVATORS AND PLATFORM (WHEELCHAIR) LIFTS

12.21 The highest operable part of a two-way emergency intercom system must be 48" max AFF. The device must be identified by a raised telephone symbol and corresponding Braille lettering located adjacent to the device. If the system uses a handset, the cord from the panel to the handset must be 29" min long. The car emergency signaling device cannot be limited to voice communication. If instructions for use are provided, essential information must be presented in both tactile and visual form.

CBC 1116B.1.8
ADA Stds 4.10.14

Car inside

12.22 Indicate centerlines of highest and lowest elevator floor buttons (inside car) to be within 35" and 48" AFF for front approach and 35" and 54" AFF for side approach.


CBC 1116B.1.8
CBC Fig. 11B-40B (b)

Car inside
Elevator control panel

12.23 Emergency controls, including the emergency stop and alarm, must be grouped in or adjacent to the bottom of the panel and must be 35" min AFF.

CBC 1116B.1.8 &
CBC Fig. 11B-40B (a)

Car inside
Elevator control panel - Elevator control panel detail



12.24 Indicate on an enlarged detail elevator car control buttons to be designated by:

CBC 1116B.1.9

Car controls

1. Car control buttons shall have a minimum dimension of 3/4" and shall be illuminated.
2. Car control buttons shall be raised 1/8" +/- 1/32" above the surrounding surface and shall have square shoulders.
3. Floors shall be designated by numbers, a min of 5/8" high and white on a black background, with standard alphabet characters or standard symbols immediately to the left of control buttons.
4. A contracted (Grade 2) Braille symbol, located immediately below the numeral, character or symbol.
5. A minimum clear space of 3/8" or other suitable means of separation shall be provided between rows of control buttons.

12

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 12. ELEVATORS AND PLATFORM (WHEELCHAIR) LIFTS

PLATFORM (WHEELCHAIR) LIFTS

**THIS PORTION OF THE CHECKLIST IS CURRENTLY
UNDER REVISION**

13

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Heading / Comments / Notes
& Examples

Check List 13. PUBLIC TELEPHONES

13.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

13.2 Indicate number and location of all public pay telephones, public closed circuit telephones, or other public telephones on each site and floor plan.

CBSC Part 1
4-317(b) &
CBC 1102B

Plans

Definitions

DEFINITION:

CLOSED CIRCUIT TELEPHONE:
A telephone with dedicated line(s) such as a house phone, courtesy phone or phone that must be used to gain entrance to a facility.

13.3 Indicate compliance status of all telephones included in this project (i.e. those that are to be newly constructed or altered, or part of the required path of travel) and provide DSA application number.

CBSC Part 1
4-317(b)

Plans

13.4 Indicate path of travel to accessible telephones (dashed line) and show 30" x 48" minimum clear floor space.

CBC 1117B.2.2 &
CBSC Part 1
4-317(b)

Clear ground floor space
Plans

13.5 Provide and indicate interior and exterior accessible public pay telephones, public closed circuit telephones, or other public telephones in compliance with the following table:

CBC 1117B.2.1 &
ADA Stds 4.1.3(17)(a)

Telephones
Public telephones

Number of each type of telephone provided on each floor	Minimum number of telephones required to comply with 1117B.2 (excluding TTY requirement).
1 or more single unit	At least 50 percent of telephone units per floor but not less than one.
1 bank	At least 50 percent of telephone units per bank but not less than one.
2 or more banks	At least 50 percent of telephone units per bank but not less than one. At least 1 telephone per floor shall meet the requirements for a forward reach telephone.

*A bank is two or more adjacent telephones.

13.6 Provide additional maneuvering space as required at alcoves (indicate dimensions).

CBC 1117B.2.4
CBC Fig. 11B-5A

Relationship of maneuvering clearances to wheelchair spaces
Minimum clear floor space for wheelchairs

13.7 Provide enlarged side and front elevation, indicating height of operable parts, knee clearance, and location of required signage.

CBC Fig. 11B-4

Mounting heights and clearances for telephones

13.8 Telephone enclosures that protrude into pedestrian circulation areas shall comply with 1133B.8.6.1.

CBC 1117B.2.7#4 &
CBC 1133B.8.6.1

Protruding telephone enclosures
Protruding objects - General

13.9 Provide and indicate provision of volume control at all accessible telephones (12 dBA min to 18 dBA max above normal). In addition, equip 25%, but never less than one, of all other public telephones with a volume control and disperse

CBC 1117B.2.8,

Telephone equipment for hearing impaired persons

13

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Heading / Comments / Notes
& Examples

Check List 13. PUBLIC TELEPHONES

them among all types of public telephones, including closed circuit telephones, throughout the building or facility.

<p>13.10 Provide and indicate at least one text telephone (TTY) where four or more public pay telephones are provided at the exterior and interior of a site and if at least one is in an interior location. The TTY must be located on the inside in a public use area.</p>	<p>CBC 1117B.2.9.1#1& ADA Stds 4.1.3(17)(c)(i)</p>	<p>Text telephones – Where required Public telephones</p>
<p>13.11 Provide and indicate a text telephone (TTY) where at least one interior public pay telephone is located in a facility that is a stadium or arena, a convention center, a hotel with a convention center, or a covered mall.</p>	<p>CBC 1117B.2.9.1 #2</p>	<p>Text telephones – Where required</p>
<p>13.12 Provide and indicate a text telephone (TTY) where at least one public pay telephone is located in or adjacent to a hospital emergency room, hospital recovery room, or hospital waiting room. One TTY shall be provided at each such location.</p>	<p>CBC 1117B.2.9.1 #3</p>	<p>Text telephones – Where required</p>
<p>13.13 Provide and indicate a text telephone (TTY) if alterations to an existing building or facility with less than four exterior or interior public pay telephones would increase the total number to four or more telephones with at least one in an interior location.</p>	<p>CBC 1117B.2.9.1 #4</p>	<p>Text telephones – Where required</p>
<p>13.14 Provide and indicate a text telephone (TTY) if alterations to one or more exterior or interior public pay telephones occur in an existing building or facility with four or more public telephones with at least one in an interior location.</p>	<p>CBC 1117B.2.9.1 #5</p>	<p>Text telephones – Where required</p>
<p>13.15 Provide and indicate a text telephone in facilities used by entities that provide emergency services, including 911 services.</p>	<p>28 CFR §35.162</p>	<p>Telephone emergency services</p>
<p>13.16 Provide and indicate shelf and electrical outlet for portable TTY.</p>	<p>CBC 1117B.2.9.2 #2</p>	<p>Text telephones - General</p>
<p>13.17 Provide and indicate the following signage at accessible telephones:</p>		
<p>1. ISA at all wheelchair accessible telephones.</p>	<p>CBC 1117B.5.8.1</p>	<p>International Symbol of Accessibility</p>
<p>2. Depiction of telephone handset with radiating sound waves at all telephones with volume controls.</p>	<p>CBC 1117B.2.8</p>	<p>Telephone equipment for hearing impaired persons</p>
<p>3. International TTY symbol at all text telephones.</p>	<p>CBC 1117B.2.9.3</p>	<p>Text telephones - Signage</p>
<p>4. Directional signage adjacent to all banks of telephones which do not contain a text telephone indicating the location of the nearest text telephone (TTY). Include the international TTY symbol. If a facility has no banks of telephones, the directional signage shall be provided at the entrance (e.g., in a building directory).</p>	<p>CBC 1117B.2.9.3</p>	<p>Text telephones - Signage</p>


13

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Heading / Comments / Notes
& Examples

Check List 13. PUBLIC TELEPHONES



5. Indicate location of signs to be high enough to be seen even when the telephone is in use. Size signs so that they can be seen from a distance.

13.18 In large projects with many telephone units or banks, provide ratio table, indicating total units, accessible units, volume control units, and TTY units for each floor/area.

13.19 Telephones shall have push button controls where service for such equipment is available.

13.20 The cord from the telephone to the handset shall be at least 29 inches long.

13.21 Telephone book, if provided, must be located at a position within reach range.

CBSC Part 1
4-317(b)

Plans

CBSC Part 1
4-317(b)

Plans

CBC 1117B.2.10 &
ADA Stds 4.31.6


Telephones - Controls
Telephones - Controls

CBC 1117B.2.11 &
ADA Stds 4.31.8


Telephones - Cord length
Telephones - Cord length

CBC 1117B.2.12 &
ADA Stds 4.31.7

Telephone books
Telephone books



SIDE REACH POSSIBLE



FORWARD REACH REQUIRED

* HEIGHT TO HIGHEST OPERABLE PARTS WHICH ARE ESSENTIAL TO BASIC OPERATION OF TELEPHONE.

Fig 13-A Telephone Approaches and Reach Ranges

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 14. DRINKING FOUNTAINS

<p>14.1 For additional scoping requirements and exceptions see also applicable DSA-AC Checklist 1.</p>		
<p>14.2 Indicate location and user type of all interior and exterior drinking fountains (DFs) on each site and floor plan.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>14.3 Indicate compliance status of all DFs included in this project (i.e. those that are to be newly constructed or altered, or part of the required path of travel) and provide DSA application number.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>14.4 Indicate the path of travel (dashed line) to accessible DFs and show a 30" x 48" min clear space.</p>	<p>ADA Stds 4.1.3(10)(b) CBSC Part 1 4-317(b)</p>	<p>Drinking fountains Plans</p>
<p>14.5 Provide and indicate "hi-low" combination DF in new construction where only one drinking fountain area is provided per floor.</p>	<p>CBC 1117B.1 #1</p>	<p>Accessible drinking fountains - General</p>
<p>14.6 Provide and indicate "hi-low" combination DF in alteration projects if DF is <u>part of the alteration</u> and where only one drinking fountain area is provided per floor.</p>	<p>CBC 1134B.2</p>	<p>Accessibility for existing buildings</p>
<p>14.7 Provide and indicate "hi-low" combination DF in alteration projects if DF <u>serves the area of alteration</u> and where only one drinking fountain area is provided per floor.</p>	<p>CBC 1134B.2.1</p>	<p>Accessibility for existing buildings</p>
<p>14.8 Where more than one DF is provided on a floor, indicate that 50% of those provided are to be accessible and located on an accessible route of travel.</p>	<p>CBC 1117B.1 #1</p>	<p>Accessible drinking fountains - General</p>
<p>14.9 When DFs are provided, indicate "hi-low" combination, or one wheelchair accessible DF and one DF at standard height within immediate proximity.</p>	<p>CBC 1117B.1 #1 & ADA Stds 4.1.3(10)(a)</p>	<p>Accessible drinking fountains - General Drinking fountains</p>
<p>14.10 Where a "hi-low" type fountain is provided, indicate the 30" x 48" clear floor space centered on the "low" fountain fixture.</p>	<p>CBC 1117B.1 #2</p>	<p>Clearances</p>
<p>14.11 All DFs must be located in alcoves, positioned completely between wing walls or otherwise positioned so as not to encroach into pedestrian ways.</p>	<p>CBC 1117B.1 #3 CBC Fig. 11B-3A</p>	<p>Alcoves Drinking fountains</p>
<p>14.12 Provide alcove dimensions: 1. 32" min wide and 18" min deep. 2. 36" min wide, if alcove is deeper than 24".</p>	<p>CBC 1117B.1 #3 CBC Fig. 11B-3A(a)</p>	<p>Alcoves Drinking fountains</p>
<p>14.13 If wing walls are provided, they must project out from the supporting wall at least as far as the DF to within 6" of the surface of the surface of the circulation path. There shall be 32" minimum clear between the wing walls.</p>	<p>CBC 1117B.1 #3 CBC Fig. 11B-3A(b&c)</p>	<p>Alcoves Drinking fountains</p>
<p>14.14 Provide and indicate the following clearances for wheelchair accessible DF on enlarged elevations and plan. Refer to checklist figure 14-B. 1. DF must be 18" - 19" deep and allow front approach.</p>	<p>CBC 1117B.1 #2</p>	<p>Clearances</p>

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 14. DRINKING FOUNTAINS

2.	Knee clearance must be 27" min AFF for a depth of 8" min, measured from the front edge of the DF.	CBC 1117B.1 #2	Clearances
3.	Toe clearance must be 9" min AFF and 17" min deep, measured from the front of the DF.	CBC 1117B.1 #2	Clearances
4.	DF activator must provide accessible operation and be within 6" of the front edge of the DF.	CBC 1117B.1 #4	Bubbler
5.	Indicate that the force required to activate controls can not exceed 5 lbf.	CBC 1117B.1 #4	Bubbler
6.	The bubbler outlet must be at 36" max AFF.	CBC 1117B.1 #4	Bubbler
7.	Indicate that the spout must provide a flow of water at least 4" high.	CBC 1117B.1 #5	Spout
8.	On DFs with round or oval bowls, the bubbler outlet must be located so that the flow of water is within 3" of the front edge of the DF.	CBC 1117B.1 #5	Spout
9.	On DFs with square bowls, the bubbler outlet must be within 6" of the front edge of the DF and provide a flow of water that is parallel with the front edge.	CBC 1117B.1 #4	Bubbler
14.15	DFs in facilities primarily used by children should be adjusted to meet their accessibility needs in accordance with the following suggested dimensions: 1. Knee clearance height must be 24" max AFF for elementary schools and 22" max AFF for kindergarten. 2. The bubbler outlet height must be 32" max AFF for elementary schools and 30" max AFF for kindergarten.	CBC 1115B.1.2 & CBC Table 1115B-1	Where used by children Suggested dimensions for children's use
14.16	DF details on architectural plans must correspond with site plan, plumbing plans, and/or specs.	CBSC Part 1 4-317(b)	Plans
14.17	Provide dimensioned detail representing the actual fixture, for all accessible DFs under this contract.	CBSC Part 1 4-317(b)	Plans
14.18	Bring manufacturer's DF cut sheets to back check.	CBSC Part 1 4-317(b)	Plans





Fig 14-A. Single Accessible Drinking Fountain



* EQUIPMENT PERMITTED IN SHADED AREA

Fig 14-B. Spout Height and Knee Clearance at Drinking Fountains






Fig 14-C. Side Elevation "Hi-Low"



NOTE:
 AT ALCOVES DEEPER THAN 24"
 ADDITIONAL 6" MANEUVERING
 CLEARANCE IS REQUIRED.
 SEE CBC 1118B.4, ITEM 2.

Fig 14-D. Clear Floor Space at Drinking Fountain Alcoves



NOTE:
 AT "HI-LOW" TYPE FOUNTAINS,
 CENTER THE 30" BY 48" CLEAR
 FLOOR SPACE ON THE "LOW"
 FOUNTAIN FIXTURE

Fig 14-E. Clear Floor Space at "Hi-Low" Drinking Fountain Alcoves

15

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 15. SANITARY FACILITIES

<p>15.1 For additional scoping requirements and exceptions see also applicable DSA-AC Checklist 1.</p>		
<p>15.2 Indicate location and DSA application number of all toilet and bathing facilities on site plan.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>15.3 All toilet and bathing facilities under this contract shall be on an accessible route and shall be made accessible (i.e. those that are to be newly constructed or altered, or part of the required path of travel).</p> <p>EXCEPTION:</p> <p>In alterations where accessibility is required to and in sanitary facilities serving the area of alteration, when DSA determines that compliance would create an unreasonable hardship, and when equivalent facilitation is provided.</p> <p>When equivalent facilitation is used, accessible sanitary facilities must be provided within a reasonable distance of accessible areas. Signage shall be provided at inaccessible sanitary facilities indicating the location of the nearest accessible sanitary facility.</p>	<p>CBC 1115B.1</p>	<p>Bathing and toilet facilities - General</p> <p><u>NOTE:</u> DSA generally does not determine hardship if the equivalent facilitation toilet facility provides only front transfer.</p>
<p>15.4 Where separate facilities are provided for persons of each sex, these facilities shall be accessible to persons with disabilities. Where unisex facilities are provided, these facilities shall be accessible to persons with disabilities.</p>	<p>CBC 1115B.1.1</p>	<p>Separate and unisex facilities</p> <p><u>NOTE:</u> Labor Code §2350 requires separate facilities within a reasonable distance when there are five or more employees.</p>
<p>15.5 In existing buildings or facilities, unisex toilet rooms will be permitted where it is determined that full code compliance is technically infeasible in an area of alteration.</p>	<p>DSA Policy 97-01</p>	<p>Unisex Toilet Rooms</p>
<p>15.6 Common-use accessible sanitary facilities shall be accessible directly from a corridor or from the exterior (not through an office, a classroom, or any assembly or performance area which disturbs the function of that room).</p>	<p>CBC 1114B.1.2 & ADA Stds 4.3</p>	<p>Accessible route of travel Accessible route</p>
<p>15.7 Door leading to sanitary facility must be accessible. Indicate door width, door maneuvering clearances and slope, and show 90° door swing on plan.</p>	<p>CBC 1115B.5 & CBC 1133B.2</p>	<p>Passageways Doors</p>
<p>15.8 At sanitary facility, door cannot swing into the clear floor space required for any fixture (i.e. front and side transfer spaces at accessible WC, spaces at accessible urinal and lavatory, and transfer spaces at accessible showers and bathtubs). Doors may swing into that portion of maneuvering space which does not overlap the fixture's required clear floor space.</p>	<p>CBC 1115B.3.1 #2 CBC 1115B.3.2 #2 CBC Fig 11B-1E</p>	<p>Multiple-accommodation toilet facilities Single-accommodation toilet facilities</p>
<p>15.9 Indicate 30" x 48" clear floor space on plan at accessible urinal, shower/bathtub, and at least one accessible lavatory.</p>	<p>CBC 1115B.4.2 #3 CBC 1115B.4.3 #3 CBC 1115B.4.5 #1 CBC Figs 11B-2A-C</p>	<p>Accessible urinals Accessible lavatories Accessible bathtubs Shower Stalls</p>

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 15. SANITARY FACILITIES

<p>15.10 Indicate wheelchair turning space on plan:</p> <ol style="list-style-type: none"> 1. 60" diameter circle or a T-shaped space for 180 turns in single accommodation toilet facility. 2. 60" diameter circle in multiple accommodation toilet facility. 3. 60" diameter circle or a T-shaped space for 180 turns in bathroom, bathing facility & shower room. 	<p>CBSC Part 1 4-317(b), & CBC 1115B.3.2 #1</p> <p>CBC 1115B.3.1 #1</p> <p>ADA Stds 4.23.3</p>	<p>Plans</p> <p>Wheelchair clearance</p> <p>Wheelchair clearance</p> <p>Clear floor space</p>
<p>15.11 Doors, other than the door to the accessible compartment, cannot swing into the wheelchair turning space by more than 12".</p>	<p>CBC 1115B.3.1 #1</p>	<p>Wheelchair clearance</p>
<p>15.12 In alterations, provide as-built dimensions pertinent to compliance status of this restroom.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>15.13 For restroom signage see Checklist 17.</p>		
<p>15.14 Coordinate plumbing drawings with architectural drawings.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>15.15 Coordinate all fixtures shown on fixture schedule with all plumbing fixtures shown on plumbing and architectural drawings.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>

WATER CLOSETS (WCs) AND COMPARTMENTS

<p>15.16 Compartment door to accessible fixture must comply with door maneuvering requirements, and in no case shall the space immediately outside of the water closet compartment door be less than 48" measured perpendicular to the compartment door in its closed position. Indicate strike edge clearance and landing depth (e.g., for front pull-side approach show 18" and 60" dimensions). See Checklist 8 for door requirements.</p>	<p>CBC 1115B.3.1 #4.5</p>	<p>Accessible water closet compartment</p>
<p>15.17 Provide and indicate the following for compartment door to accessible fixture:</p>	<p>CBC 1115B.3.1 #4</p>	<p>Accessible water closet compartment</p>
<p>1. Side entry stall door must have 34" clear opening.</p>	<p>CBC 1115B.3.1 #4.4</p>	<p>Accessible water closet compartment</p>
<p>2. Front entry stall door must have 32" clear opening.</p>	<p>CBC 1115B.3.1 #4.4</p>	<p>Accessible water closet compartment</p>
<p>3. Stall door must be self-closing, and have U-pulls on both sides. If provided, the locking mechanism must be accessible, not requiring grasping, pinching or turning of the wrist.</p>	<p>CBC 1115B.3.1 #4.5</p>	<p>Accessible water closet compartment</p>

15


Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 15. SANITARY FACILITIES

15.18 Front entry stall door must be located in front of the WC side transfer space – not in front of the WC – with a maximum stile width of 4 inches.



CBC 1115B.3.1 #4.3
ADA Stds Fig 30(a)

Accessible water closet compartment
Toilet stalls - Standard stall

15.19 In multiple-accommodation toilet rooms, provide and indicate a 44" min clear passageway to the accessible WC compartment, excluding door opening and door swings.

CBC 1115B.3.1 #4.5

Accessible water closet compartment

15.20 In accessible water closet compartments, provide and indicate clear floor space and maneuvering space consistent with Fig 15-C at the end of this checklist.

CBC Fig 11B-1E

Clearances at water closets

15.21 Indicate height of top of WC seat. Provide exact dimension, not a range, and coordinate with specifications and product cut sheet.

CBC 1115B.4.1 #4

Accessible water closets

15.22 Indicate WC flush valve to be on wide side of toilet area.

CBC 1115B.4.1 #5

Accessible water closets

15.23 In new construction and alterations, indicate 18" from centerline of WC to nearest sidewall.


CBC 1115B.4.1 #1

Accessible water closets

15.24 Indicate a 28" min wide clear dimension between the accessible WC (or tank) and any other fixture or a 32" min wide clear dimension to sidewall or partition that is located on the wide side.

CBC 1115B.4.1 #1

Accessible water closets



15.25 Indicate 42" min from centerline of WC to wall on wide side, or indicate total width of clear area to be 60" min (18" + 42") to allow side and front transfer use.

CBC 1115B.3.1 #4.1
ADA Stds Fig 28(c)

Accessible water closet compartment
Clear floor space at water closets

15.26 Provide one ambulatory accessible stall where six or more WCs are provided within a multiple-accommodation toilet room.

CBC 1115B.3.1 #5

Large toilet rooms

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 15. SANITARY FACILITIES

- 15.27** Provide and indicate the following at ambulatory accessible stall:
1. Stall must be 36" wide absolute.
 2. Stall length must provide 24" in front of the WC, and allow installation of grab bars on each side.
 3. Stall door with 32" clear opening.
 4. Stall door must be out-swinging, self-closing, have U-pulls on both sides and a locking mechanism that does not require grasping, pinching or turning of the wrist.
 5. Parallel grab bars on both sides of the WC, at least 42" long, with the front end positioned 24" from the WC.
 6. Accessible WC fixture and accessible toilet accessories.

CBC 1115B.3.1#5

Large toilet rooms

CBC 1115B.4.1 #3

Accessible water closets

CBC 1115B.4.1 #3

Accessible water closets

ADA Stds 4.22.4

Water Closets

GRAB BARS IN TOILET FACILITIES

- 15.28** Indicate height of grab bar to be 33" AFF.
EXCEPTION: Where a tank-type toilet is used which obstructs placement at 33" AFF, the back grab bar may be 36" max AFF.
- 15.29** At an accessible WC, indicate a 36" long back grab bar to extend 12" beyond the center of the WC toward the side wall, and 24" toward the open side.
- 15.30** At an accessible WC, indicate 42" min long side grab bar to extend 54" min beyond the back wall.
- 15.31** Indicate diameter of grab bars and coordinate with specs.
- 15.32** Indicate space between grab bar and adjacent wall to be 1-1/2" absolute.

CBC 1115B.4.1 #3

Accessible water closets

CBC 1115B.4.1 #3.2

Accessible water closets

CBC 1115B.4.1 #3.2

Accessible water closets

CBC 1115B.4.1 #3.1

Accessible water closets

CBC 1115B.7.1

Diameter or width

CBC 1115B.7.1

Diameter or width

ACCESSORIES

- 15.33** Indicate location and provide necessary dimensions for all toilet/bathroom dispensers/disposals/accessories (e.g., soap, paper towel, seat cover, feminine tissue, electric dryer, coat hooks, etc) on enlarged plans and elevations. Elements must be within reach range of user but cannot protrude into any required clear floor space.
- 15.34** Indicate toilet paper dispenser (TPD) located within 12" of the front edge of the WC, mounted below the grab bar, centered 19" min AFF, and 36" max to the far edge from the rear wall. TPDs that control delivery, or that do not permit continuous paper flow, shall not be used.

CBC 1115B.8

Accessories

CBC 1115B.8.4, CBC Fig. 11B-1A & ADA Stds 4.16.6

Toilet tissue dispensers
Side elevation
Water closets - Dispensers


15

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 15. SANITARY FACILITIES



- | | | |
|--|--|--|
| <p>15.35 Indicate projection of dispensers and disposals (e.g. toilet paper dispenser, feminine tissue disposal) in accessible and ambulatory accessible compartment. Provide recess for installation and coordinate elevations, notes and specs.</p> | <p>CBC 1115B.8.3</p> | <p>Towel, sanitary napkin, waste receptacles, dispensers & controls</p> |
| <p>15.36 If dispensers and disposals are N.I.C., indicate dimensions of recess or compliant projection.</p> | <p>CBSC Part 1
4-317(b)</p> | <p>Plans</p> |
| <p>15.37 Indicate height of operable parts, including coin slots of dispensers, disposal containers and other equipment (at least one of each type), to be 40" max AFF.</p> | <p>CBC 1115B.8.3</p> | <p>Towel, sanitary napkins, waste receptacles, dispensers & controls</p> |
| <p>15.38 If medicine cabinets are provided, indicate at least one with a usable shelf at 44" max AFF. Indicate 30" x 48" clear floor space in front of the medicine cabinet allowing a forward or parallel approach.</p> | <p>CBC 1115B.8.2</p> | <p>Medicine cabinets</p> |
| <p>15.39 Indicate bottom of all mirrors above accessible lavatories or countertops to be 40" max AFF to the bottom of the reflecting surface.</p> | <p>CBC 1115B.8.1.1</p> | <p>(Mirrors)</p> |
| <p>15.40 When mirrors are provided at locations other than above lavatories or countertops, indicate bottom of at least one to be 35" max AFF to the bottom of the reflecting surface.</p> | <p>CBC 1115B.8.1.2</p> | <p>(Mirrors)</p> |
| <p>15.41 Provide soap dispenser within reach range of clear 30" x 48" user space at accessible lavatory.</p> | <p>CBC 1115B.4.3 #3,
CBC Fig. 11B-5C &
CBC Fig. 11B-5D</p> | <p>Accessible lavatories
Forward reach
Side reach</p> |
| <p>15.42 Indicate size and location of waste bin in all floor plans; especially if waste bin is not in contract (N.I.C.) This provides owner with dimensional requirements for purchase or installation. Provide recessed space in case waste bin would protrude into any required clear floor space (consider doors, fixtures, accessories, circulation path, etc.).</p> | <p>CBSC Part 1
4-317(b)</p> | <p>Plans</p> |

15

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).


Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 15. SANITARY FACILITIES

LAVATORIES (LAVs)

- 15.43** At least 5% of lavatories, but not less than one lavatory, shall be accessible
- 15.44** Provide and indicate 18" min from any adjacent side wall or partition to centerline of LAV.
- 15.45** Provide enlarged side elevation indicating the following dimensions:
 1. Rim or counter edge no higher than 34" AFF.
 2. Apron to floor 29" min.
 3. 27" min knee clearance (measured 8" min from front edge).
 4. A maximum of 6" of the 48" clear floor space required at the fixture can extend into the minimum 9" high toe clearance.



LAVATORY CLEARANCES

- 15.46** Lavatory elevation must reflect actual fixture chosen. Specify fixture that is shown in plans.
- 15.47** Provide note on plan stating that all drainpipes and all hot water pipes accessible under lavatories must be insulated or otherwise covered.
- 15.48** Provide the following note on plan: "There shall be no sharp or abrasive surfaces under lavatories".
- 15.49** Paper towel dispenser/electrical dryer cannot protrude into the required 30" x 48" clear floor space.

CBC 1115B.4.3
 CBC 1115B.4.3 #2
 CBC 1115B.4.3 #2, CBC Fig. 11B-1D & ADA Stds 4.19.2
 ADA Stds Fig 31 & CBC Fig. 11B-1D

Accessible lavatories
 Accessible lavatories
 Accessible lavatories
 Knee clearance
 Height and clearances
 Lavatory clearances
 Knee clearance
NOTE:
 DSA may consider some lavatories protruding objects if they are located in the direct path of travel, or if a blind person would not expect them at this location.

CBSC Part 1 4-317(b)
 CBC 1115B.4.3 #4
 CBC 1115B.4.3 #4
 CBC 1133B.8.6.1
 CBC Fig 11B-7D

Plans
 Accessible lavatories
 Accessible lavatories
 Protruding objects – General Protection Around Wall-Mounted Objects

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 15. SANITARY FACILITIES

URINALS

15.50 Where one or more wall-hung urinals are provided, provide at least one wall-hung accessible urinal and indicate the following:

1. Rim to be 17" max AFF.
2. Rim to project 14" to 17" from back wall.
3. Flush control at 44" max AFF.

CBC 1115B.4.2 #1

Accessible urinals

15.51 Indicate 30" min clearance between walls or partitions that project 24" or less from the front edge of the 30" x 48" clear space.

CBC 1115B.4.2 #2

Accessible urinals

CBC 1115B.4.2 #3
CBC 1118B.4

Accessible urinals
Clear floor or ground space for wheelchairs


CBC Fig 11B-5A(a)

15.52 Indicate 36" min clearance between walls or partitions that project more than 24" from the front edge of the 30" x 48" clear space (alcove situation).

CBC 1115B.4.2 #3
CBC 1118B.4

Accessible urinals
Clear floor or ground space for wheelchairs
Additional maneuvering clearance for alcoves

CBC Fig 11B-5A(b)



SHOWERS

15.53 Provide at least one accessible shower for each 100 (or fraction thereof) of total showers.

CBC 1115B.2 & ADA Stds 4.23.8

Bathing and shower facilities
Bathing and shower facilities

15.54 Indicate size of shower stall to be either:

CBC 1115B.4.4.1

Sizes and clearances

1. Roll-in shower – 60" min width between wall surfaces and 30" min depth with a full opening width on the long side.
2. Alternate roll-in shower – 60" min width between wall surfaces and 36" min depth with an entrance opening width of 36" min.
3. Alternate roll-in shower with optional enclosure – 60" min width between wall surfaces and 36" min depth as long as the entrance opening width is a minimum 36".

CBC Fig 11B-2A

Shower Stalls

CBC Fig 11B-2B

Shower Stalls

CBC Fig 11B-2C

Shower Stalls

15.55 Provide the following shower accessories and indicate location and dimensions:

15

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 15. SANITARY FACILITIES

1. Single-lever faucet control.	CBC 1115B.4.4.4	Water controls
2. Hand-held sprayer with hose	CBC 1115B.4.4.5	Hand-held sprayer unit
3. Folding seat.	CBC 1115B.4.4.8 #1	Shower accessories
4. Grab bars.	CBC 1115B.4.4.8 #2	Shower accessories
5. Soap dish.	CBC 1115B.4.4.9	Soap dish
15.56 Indicate floor slope to be 2% max in any direction.	CBC 1115B.4.4.7	Floor slope
15.57 Thresholds in roll-in type showers shall be 1/2 inch high maximum and comply with 1124B.2.	CBC 1115B.4.4.2	Thresholds
BATHTUBS		
15.58 Provide one accessible bathtub for each 100 (or fraction thereof) of total bathtubs.	CBC 1115B.2 & ADA Stds 4.23.8	Bathing and shower facilities Bathing and shower facilities
15.59 Indicate size of clear floor space in front of bathtub (in relation to long dimension of tub):	CBC 1115B.4.5 #1	Accessible bathtubs - Floor space
1. 48" x 60" for perpendicular approach at bathtub with seat in tub.	CBC Fig. 11B-8(a)	Clear floor space at bathtubs
2. 30" x 60" for parallel approach at bathtub with seat in tub.	CBC Fig. 11B-8(b)	Clear floor space at bathtubs
3. 30" x 75" for parallel approach at bathtub with seat at head of tub.	CBC Fig. 11B-8(c)	Clear floor space at bathtubs
15.60 Provide the following bathtub accessories and indicate location and dimensions:	CBC 1115B.4.5	Accessible bathtubs
1. Single-lever faucet control.	CBC 1115B.4.5 #4	Accessible bathtubs - Controls
2. Hand-held sprayer with hose.	CBC 1115B.4.5 #5	Accessible bathtubs - Shower unit
3. Seat.	CBC 1115B.4.5 #2 & CBC Fig. 11B-8	Accessible bathtubs - Seat Clear floor space at bathtubs
4. Grab bars.	CBC 1115B.4.5 #3 & CBC Fig. 11B-9	Accessible bathtubs - Grab bars Grab bars at bathtubs
LOCKER ROOMS IN BATHING FACILITIES		
15.61 1% of all lockers (but not less than 1) shall be made accessible.	CBC 1115B.8.5 ADA Stds 4.1.3(12)(a)	Lockers Storage, shelving and display units
15.62 The accessible route of travel to accessible lockers shall be no less than 36" in clear width.	CBC 1115B.8.5	Lockers
15.63 Provide elevation and indicate heights of locks (at 48" max) and shelves (between 15" and 48").	CBC 1118B.5	Forward reach
15.64 Provide and indicate a bench or section of bench close to the accessible locker, measuring 24" deep, 48" wide, and 17" to 19" AFF, fixed to a wall along the longer dimension.	CBC 1117B.8 ADA Stds 4.35.4	Fitting and dressing rooms Dressing, fitting, and locker rooms - Bench

15

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 15. SANITARY FACILITIES

15.65 Provide and indicate a 60" square min clear space in front of the accessible bench section, located in such a manner to allow a person using a wheelchair to make a parallel transfer onto the bench.

CBC 1117B.8
ADA Stds 4.35.2

Fitting and dressing rooms
Dressing, fitting, and locker rooms
- Clear floor space

CHILDREN

15.66 Design and construction of toilet and bathing facilities solely used by children may be adjusted to meet their accessibility needs. See Figure 15-A at the end of this Checklist for an updated table of suggested dimensions.

CBC 1115B.1.2 &
CBC Table 1115B-1

Where used by children
Suggested dimensions for
children's use

A = Adult dimensions (age 12 and over)
 E = Elementary school dimensions
 K = Kindergarten and pre-school dimensions
 FED = ADA Standards dimensions for children's use, shown for reference only – consult the federal ADA Standards for age specific dimensions where ranges are presented.

ALTERNATIVE DIMENSIONS IN INCHES		A (Inches)	E (Inches)	K (Inches)	FED Children
a	Toilet centering from wall	18	15	12	12-18
b	Toilet seat height/dimensions to top of seat	17-19	15	11-12**	11-17
c	Grab bar height (centerline)	33	27	20-22	18-27
d	Toilet paper above floor (centerline)	19 min	-	-	14-19
e	Toilet paper in front of toilet	12 max	6 max	6 max	-
f	Napkin disposal in front of toilet	12 max	12 max	N/A	-
g	Dispenser height	40 max	36 max	32 max	-
h	Mirror height (to bottom of glass)	40 max	36 max	32 max	-
l	Lavatory/sink top height	34 max	29 max	24 max	31 max
j	Lavatory apron clearance	29 min	-	-	24 min*
k	Lavatory/sink knee clearance	27 min	24 min	19 min	24 min*
l	Urinal lip height	17 max	15 max	13 min	-
m	Urinal, toilet flush handle height	44 max	37 max	32 max	36-44 max
n	Drinking fountain bubbler height	36 max	30 max**	30 max	30 max
o	Drinking fountain knee clearance	27 min	24 min	22 min	-
p	Ramp/stair handrail height	34-38	27***	22***	28 max***
q	Fixed or built-in seating, table top height	28-34	-	-	26-30*
r	Fixed or built-in seating and table knee clearance	27 min	-	-	24 min*
s	Forward reach range (high)	48 max	-	-	36-44 max
t	Side reach range (high)	54 max	-	-	36-44 max
u	Forward reach range (low)	15 min	-	-	20-16 min
v	Side reach range (low)	9 min	-	-	20-16 min

- * No ADA Standards requirement if element is used primarily by children ages 5 and younger and if clear floor and parallel approach is provided.
- ** Change from CBC due to more restrictive federal standards (see GC 4450(b) and CBC §1.9.1).
- *** In addition to adult rail. Maintain 9" minimum vertical clearance between upper and lower handrails to help prevent entrapment.

Fig 15-A. Alternative Dimensions for Children's Use







Fig 15-B. Locker Rooms




(a) CLEARANCES AT WATER CLOSET




(b) CLEARANCES AT WATER CLOSET IN COMPARTMENT WITH OUT-SWINGING END-OPENING DOOR



(c) CLEARANCES AT WATER CLOSET IN COMPARTMENT WITH IN-SWINGING END-OPENING DOOR



(d) CLEARANCES AT WATER CLOSET IN COMPARTMENT WITH OUT-SWINGING SIDE-OPENING DOOR



(e) CLEARANCES AT WATER CLOSET IN COMPARTMENT WITH IN-SWINGING SIDE-OPENING DOOR

Fig 15-C. Clearances at Water Closets

16

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 16. ALARMS

16.1 For general scoping requirements and exceptions see also **DSA-AC Checklist 1**. To be reviewed in coordination with Fire/Life/Safety.

ALARMS / EMERGENCY WARNING SYSTEMS

16.2 If emergency warning systems are provided, then they shall include both audible alarms and visible alarms complying with Section 907.5.2.1 and 907.5.2.3, NFPA 72 as amended in Chapter 35 of Title 24, and the ADA Stds.

EXCEPTION:

Emergency warning systems in medical care facilities may be modified to suit standard health care alarm design practice.

16.3 When installation of an emergency warning system is required in a building, provide names or numbers, and function (relevant to the occupancy type and use) for all rooms and areas.

16.4 Provide visible alarm notification appliances (strobe lights) in all public and common use areas and indicate location and intensity on plans. Public and common use areas include (but are not limited to) the following areas:

1. Toilet and bathing facilities.
2. Classrooms and locker rooms.
3. Band and music practice rooms.
4. Gymnasiums and multipurpose rooms.
5. Occupational shops.
6. Occupied rooms where ambient noise impairs hearing of the fire alarm.
7. Corridors, hallways, and lobbies.
8. Cafeterias, meeting and conference rooms.
9. Any rooms frequently used by persons with hearing impairments (such as HIP or speech therapy classrooms).
10. Filing, photocopy, and employee break rooms.
11. Dressing, examination, treatment rooms, and similar spaces that are not used solely as employee work areas.
12. Any other areas for common use.

16.5 Strobe lights must provide 75 candela min intensity @ 50'

16.6 Provide note or indicate on plan installation height of strobe light to be between 80" and 96" AFF or be at least 6" below the ceiling, whichever is lower.

16.7 No place in common corridors shall be more than 50' from the strobe light.

CBC 1114B.2.2

CBC 907.5.2.1
CBC 907.5.2.3
ADA Stds 4.1.3(14)

CBC 907.5.2.1

CBSC Part 1
4-317(b)

CBC 907.5.2.3.1
CBC 1102B
ADA Stds 4.28.1

ADA Stds 4.28.3(4)

ATBCB Bulletin

ADA Stds 4.28.3(8)

Alarms/emergency warning systems/accessibility
Audible alarms
Visible alarms
Accessible buildings: New construction

Audible alarms

Plans

Public and common use areas
Definitions
Alarms – General
See ATBCB Technical Bulletin at <http://www.access-board.gov/adaag/about/bulletins/alarms.htm>

DEFINITIONS:
COMMON-USE AREAS are those interior and exterior rooms, spaces, or elements that are made available for the use of a restricted group of people (for example, occupants of a homeless shelter, the occupants of an office building, or the guests of such occupants).
PUBLIC-USE AREAS are those interior or exterior rooms or spaces of a building that are made available to the general public and does not include common use areas. Public use areas may be provided at a building that is privately or publicly owned.

NOTE:
ADAAG requirements for alarm systems may be more stringent than those in CBC Ch 9 or NFPA

Visual alarms

Technical bulletin: Visual alarms

Visual alarms

16

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 16. ALARMS

<p>16.8 In transient lodging facilities, when units and sleeping accommodations have visible alarms in place, the signal shall be visible in all areas of the unit or room.</p> <p>Visible alarm shall be connected to building emergency alarm system, or shall have a standard 110-volt electrical receptacle into which such an alarm can be connected and a means by which a signal from the building emergency alarm system can trigger such an auxiliary alarm.</p>	<p>CBC 907.5.2.3.3 CBC 1111B.4.5.1 ADA Stds 4.28.4 ATBCB Bulletin</p>	<p>Groups I-1 and R-1 Places of transient lodging - Visible alarms Auxiliary alarms Technical bulletin: #2</p>
<p>16.9 Provide note or indicate on plan installation height of manual fire alarm boxes to be at 42" minimum to 48" maximum AFF to the highest point of the activating handle or lever.</p> <p>EXCEPTION: Enforcement officials shall not retroactively require fire alarm initiating devices be relocated to a 42" minimum to 48" maximum height.</p>	<p>CBC 907.4.2.2</p>	<p>Height</p>
<p>16.10 All areas to be "strobed" shall have either a direct line of sight or its reflection from adjacent walls and ceiling must be of an intensity that will raise the overall light level sharply, but not so intense as to be unsafe for direct viewing at a specified mounting height.</p>	<p>ATBCB Bulletin</p>	<p>Technical bulletin: #2</p>
<p>16.11 Provide front and parallel approach at newly installed fire alarm initiating device.</p>	<p>CBC 1117B.6</p>	<p>Controls and operating mechanisms</p>
<p>16.12 Indicate accessible operating hardware at initiating device (i.e., not requiring tight grasping, pinching, or twisting of the wrist, and 5 lbf max force).</p>	<p>CBC 907.4.2.2 ADA Stds 4.27.4</p>	<p>Height Operation</p>
<p>16.13 Fire alarm initiating device must be located on an accessible route of travel.</p>	<p>CBC 1117B.6</p>	<p>Controls and operating mechanisms</p>
<p>16.14 Fire alarm initiating device cannot be located where a person using a wheelchair would be forced to reach over an obstruction greater than 10" deep.</p>	<p>CBC 1118B.6 CBC Fig 11B-5D(b)</p>	<p>Side reach High and low side reach limits</p>
<p>FIRE EXTINGUISHERS</p>		
<p>16.15 Provide clear floor space for forward or parallel approach at fire extinguishers and fire extinguisher cabinets.</p>	<p>CBC 1118B.4</p>	<p>Clear floor or ground space for wheelchairs</p>
<p>16.16 Height of fire extinguisher handle and fire extinguisher cabinet opening hardware to correspond with provided approach – 48" maximum for forward approach or 54" maximum for parallel approach.</p>	<p>CBC 1118B.5 CBC 1118B.6</p>	<p>Forward reach Side reach</p>
<p>16.17 Indicate accessible opening hardware at fire extinguisher cabinet (e.g., U-pull and 5 lbf max latch force).</p>	<p>CBC 1125B.4</p>	<p>Storage - Hardware</p>

17

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Comments / Notes / Examples

Check List 17. SIGNAGE

<p>17.1 For additional scoping requirements and exceptions see also applicable DSA-AC Checklist 1.</p>		<p>NOTE: See Section 1111B.4.5 and Checklist 22 for additional requirements in motels, hotels and other residential occupancies.</p>
<p>17.2 Provide details and specs for all signs applicable to this project and indicate the provision/installation on site plans, floor plans and elevations.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>17.3 Signs that are located on or at doors must be included in the door schedule, or provide a separate signage schedule which references the door mark for each sign.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>17.4 Reference signage details for each door and indicate message (e.g., "TO EXIT", "GIRLS", "124", etc).</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>17.5 Provide and indicate detail(s) for the following sign(s):</p>		
<p>1. "Tow-away" signs at parking lot entrance (or at stall).</p>	<p>CBC 1129B.4</p>	<p>Identification of parking spaces for off-street parking facilities</p>
<p>2. Accessible parking signs, including van signs.</p>	<p>CBC 1129B.4</p>	<p>Identification of parking spaces for off-street parking facilities</p>
<p>3. International Symbol of Accessibility (ISA) at accessible passenger loading zones. See CBC Figure 11B-6.</p>	<p>CBC 1131B.2 #1</p>	<p>Passenger loading zones</p>
<p>4. International Symbol of Accessibility at entrances to buildings and facilities that are accessible. See CBC Figure 11B-6.</p>	<p>CBC 1117B.5.8.1.2</p>	<p>Entrance signs</p>
<p>5. In existing buildings & facilities, directional signage at all inaccessible entrances, directing persons to the nearest accessible entrance.</p>	<p>CBC 1117B.5.8.1.2</p>	<p>Entrance signs</p>
<p>6. Assistive Listening System (ALS) sign indicating availability of ALS, posted in a prominent place. See CBC Figure 11B-14C.</p>	<p>CBC 1104B.2 #4</p>	<p>Assistive-listening systems in assembly areas - Signage</p>
<p>7. Raised letters, contracted (Grade 2) Braille EXIT signs at all exit doors (in addition to the overhead/low-level illuminated exit signs).</p>	<p>CBC 1011.3</p>	<p>Tactile exit signs</p>
<p>8. California restroom symbols (circle/triangle) on door leaf.</p>	<p>CBC 1115B.6</p>	<p>Bathing and toilet facilities - Identification symbols</p>
<p>9. Restroom identification sign on wall including raised letters, contracted (Grade 2) Braille, and if desired, a gender pictogram.</p>	<p>CBC 1117B.5.1 #1</p>	<p>Identification signs</p>
<p>10. International Symbol of Accessibility at accessible seating: aisle transfer seats, companion seats, and wheelchair spaces at bleachers are to each be identified by a sign or marker with the International Symbol of Accessibility. Signage notifying patrons of the availability of such seats shall be posted at the ticket office.</p>	<p>CBC 1104B.3.4 #1, CBC 1117B.5.1 #2&3 & DSA Policy 98-05</p>	<p>Auditoriums, assembly halls, theater and related facilities - Wheelchair spaces Signs & identification - General Accessible seating in folding bleacher units</p>

17

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Comments / Notes / Examples

Check List 17. SIGNAGE

<p>11. Area of refuge identification complying with 1117B.5.1 #2. Sign shall be illuminated when exit sign illumination is required. Additionally, tactile signage complying with 1117B.5.1 #1 shall be located at each door to an area of refuge. Include evacuation instructions in each area of refuge.</p>	<p>CBC 1007.9</p>	<p>Areas of refuge - Identification</p>
<p>12. Volume control sign at telephones. See CBC Figure 11B-14B.</p>	<p>CBC 1117B.2.8</p>	<p>Telephone equipment for hearing Impaired persons</p>
<p>13. TTY identification signage and/or TTY directional signage. See CBC Figure 11B-14A.</p>	<p>CBC 1117B.2.9.2 #3 CBC 1117B.2.9.3</p>	<p>Text telephones – General Signage</p>
<p>14. Building directory or lobby signage informing building users that specific sanitary facilities and/or elevators are provided for public use.</p>	<p>CBC 1117B.5.8.1.3</p>	<p>Symbols of accessibility - Information posted</p>
<p>15. Warning signs at inaccessible exits indicating the closest accessible exit and signage indicating the direction to areas of refuge.</p>	<p>CBC 1133B.1.1.1.1 - Exception 2 & ADA Stds 4.3.11.5</p>	<p>Entrances and exterior ground floor exit doors Accessible route - Identification</p>
<p>16. Enclosed stairway signage.</p>	<p>CBC 1022.8 & CBC 1133B.4.3</p>	<p>Floor identification signs Floor identification signs</p>
<p>17. Elevator and elevator lobby signage.</p>	<p>CBC 1116B.1.14</p>	<p>Elevators - Doorjamb marking</p>
<p>18. Platform lift restriction signage.</p>	<p>CBC 1116B.2.7</p>	<p>Restriction sign</p>
<p>19. Evacuation plans.</p>	<p>CCR Title 19, §3.09</p>	<p>Emergency planning and information</p>
<p>20. No Smoking & Cleaner Air signage.</p>	<p>CBC 1117B.5.1 #2 CBC 1117B.5.11</p>	<p>Informational signs Cleaner air symbol</p>
<p>17.6 Indicate and specify materials, colors, and type styles to be used for all accessible signage (visual and tactile), according to the following criteria:</p>	<p>CBC 1117B.5 & ADA Stds 4.30</p>	<p>Signs and identification Signage</p>
<p>1. Except for reflective parking and traffic signs, all identification, informational and directional signs must have non-glare backgrounds and characters.</p>	<p>CBC 1117B.5.2 & ADA Stds 4.30.5</p>	<p>Finish and contrast Finish and contrast</p>
<p>2. Characters on signs shall be selected from fonts that have a width-to-height ratio of between 3:5 (60%) and 1:1 (100%) measured by the width of the uppercase letter "O" and height of the uppercase letter "I", and a stroke width-to-height ratio of between 1:5 (20%) and 1:10 (10%) measured by the width and height of the uppercase letter "I".</p>	<p>CBC 1117B.5.3</p>	<p>Proportions</p>
<p>3. Characters on signs required to be accessible shall be sized according to the Visual Character Height Table in CBC Section 1117B.5.4. The minimum height is measured using an uppercase letter "I". Lowercase characters are permitted. Viewing distance is measured as the horizontal distance between the character and an obstruction preventing further approach towards the sign.</p>	<p>CBC 1117B.5.4</p>	<p>Character height</p>

17

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Comments / Notes / Examples

Check List 17. SIGNAGE

<p>4. Add specifications for visual characters as follows: Visual characters can be serif or sans serif and upper and lowercase characters may be used for visual characters.</p>	<p>CBC 1117B.5.4</p>	<p>Character height</p>
<p>5. On signs installed on poles or pylons, when the bottom edge of the sign is at less than 80 inches AFF, provide 0.125 inch radius corners and eased edges.</p>	<p>CBC 1133B.8.6.3</p>	<p>Protruding objects - Free-standing signs</p>
<p>17.7 Add specifications for tactile characters as follows: raised characters must use sans serif font, in all uppercase characters. Simple or heavy serif fonts of any kind are not allowed. Raised text characters must be accompanied by contracted (Grade 2) Braille.</p>	<p>CBC 1117B.5.5 #1</p>	<p>Character type</p>
<p>17.8 Characters and Braille shall be in a horizontal format with Braille placed 3/8" min and 1/2" max directly below the tactile characters; flush left or centered. When text is multi-lined, all Braille shall be placed together below all lines of tactile text.</p>	<p>CBC 1117B.5.5 #4</p>	<p>Character placement</p>
<p>17.9 Braille dots within cells must be 1/10" O.C. Cells must be 2/10" apart. Measure cell distance from the center of top dot location of column two of the first cell to the center of top dot location of column one of the next cell on right, within the same word. Dots must be 1/40" high at dot apex. Braille dots shall be domed or rounded.</p>	<p>CBC 1117B.5.6</p>	<p>Braille</p>
<p>17.10 Indicate material and color descriptions and sample tpestyles in plans as follows:</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>1. Include color and material specifications for sign message backgrounds and characters to demonstrate minimum contrast and non-glare characteristics.</p>	<p>CBC 1117B.5.2</p>	<p>Finish and contrast</p>
<p>2. Show 1" high examples of uppercase characters "I," "O," and "X", in chosen tpestyle(s), indicating whether style is for tactile characters, visual characters, or both.</p>		
<p>17.11 Provide character and symbol size for all signs as follows:</p>		
<p>1. On visual signs, size characters and symbols according to viewing distance. Signs mounted with bottom edge at or above 80" AFF must have 3" high min characters.</p>	<p>CBC 1117B.5.4</p>	<p>Character height</p>
<p>2. On tactile signs, raised characters must be 5/8" to 2" high.</p>	<p>CBC 1117B.5.5 #2</p>	<p>Character size</p>
<p>3. Pictorial symbols (pictograms) that identify rooms and spaces, such as gender pictograms for restrooms must be in a 6" min high field directly above accompanying raised text and contracted (Grade 2) Braille. No characters or Braille in field.</p>	<p>CBC 1117B.5.5 #3</p>	<p>Pictorial symbol signs (pictograms) <u>NOTE:</u> Pictograms and other symbols, such as ISAs, which are included on signs with raised characters and Braille are not required to be raised.</p>
<p>17.12 Where size is dictated by code, specify exact sizes and material thickness. For instance, geometric symbol signs are</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>

17

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Comments / Notes / Examples

Check List 17. SIGNAGE

1/4" thick, and have 12" measurements.

17.13 For exterior way-finding signs, determine all decision points on site, beginning at pedestrian entrances, bus stops, parking lots and drop off points, where accessible route of travel deviates from regular route. Specify and locate on plan directional or informational sign for each decision point so that steps do not have to be retraced. Sign must include ISA and appropriate arrow and/or text. Determine appropriate size by distance from which sign will be viewed and mounting height of sign.

CBSC Part 1
4-317(b),
CBC 1127B.3 &
ADA Stds 4.30.3

Plans
Exterior routes of travel - Signs
Character height

ISA must be white on Federal Blue background, with non-glare surface.

CBC 1117B.5.8.1.1

Color of symbol

17.14 Place the International Symbol of Accessibility (ISA) at each accessible building entrance. In existing buildings or facilities where all entrances are not accessible, place directional or informational sign so that steps do not need to be retraced, to direct from inaccessible to accessible entrances. Include ISA on sign along with appropriate arrow and/or text.

CBC 1117B.5.8.1.2

Entrance signs
NOTE:
The ISA, when included on a tactile sign, does not require any accompanying text, either visual or tactile.

EXCEPTIONS:

1. An ISA is not required at entrances to individual rooms, suites, offices, sales or rental establishments, or other such spaces when all entrances to the building or facility are accessible and persons entering the building or facility have passed through one or more entrances with compliant signage.
2. An ISA is not required at entrances to machinery spaces frequented only by service personnel for maintenance, repair or occasional monitoring of equipment; for example, elevator pits or elevator penthouses; mechanical, electrical or communications equipment rooms; piping or equipment catwalks; electric substations and transformer vaults; and highway and tunnel utility facilities.

17.15 When interior accessible route of travel diverges from regular route, and when one is not immediately visible from the other, (for instance, elevator is not adjacent to stair or lift to stage platform is behind door) or when all facilities such as restrooms, drinking fountains, telephone equipment and ground floor exits are not accessible, specify and locate on plan informational and/or directional signs, to include appropriate Symbol of Accessibility and text such as "Restroom", "Elevator" or "TTY" along with brief text and arrows to indicate location of accessible elements. Locate signs at decision points so that steps will not have to be retraced.

CBSC Part 1
4-317(b),
CBC 1117B.5.8.1.2 &
CBC 1117B.5.8.1.3

Plans
Entrance signs
Information posted

17.16 Provide sign schedule to show identification of all permanent rooms and spaces, including restrooms and exits, with raised characters accompanied by contracted (Grade 2) Braille, in compliance with standards for tactile character and Braille signs. Requirement applies to all such rooms and spaces whether entered from interior hallways, or by individual exterior

CBC 1117B.5.1 #1

Identification signs

17

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Comments / Notes / Examples

Check List 17. SIGNAGE

entrances. Indicate on schedule any accompanying visual text and symbols or pictograms.

- 17.17** Specify appropriate tactile exit sign for each exit door. Use terminology established by California State Fire Marshal for tactile exit signs. For ground floor doors that exit to exterior, use "EXIT." For door leading directly into an exit stairway or ramp, use "EXIT STAIR (or RAMP) DOWN (or UP)" as appropriate. Each exit door that leads directly to a grade-level exterior exit by means of an exit enclosure or an exit passageway and each exit access door from an interior room or area that is required to have a visual exit sign shall be identified by a tactile exit sign with the words, "EXIT ROUTE." For horizontal exit (very rare) use "TO EXIT."
- Show location of tactile exit signs and floor designation signs in stairways on plan - adjacent to appropriate door.
- 17.18** In buildings with more than one floor and with enclosed stairwells, include in sign schedule required tactile floor designation, accompanied by contracted (Grade 2) Braille.
- Show location of tactile exit signs and floor designation signs in stairways on plan - adjacent to appropriate door.
- 17.19** Provide drawings for identification signs as follows:
1. Show layout of typical sign indicating position of raised text in relationship to Braille and any other raised elements on sign, such as borders or frames. Indicate location of pictograms and symbols on tactile identification signs and geometric door signs as appropriate by providing scale drawings of each sign type.
 2. Geometric symbol door signs for restrooms must contrast with door (dark on light or light on dark). For unisex door signs, triangle must contrast with circle, which must contrast with door. Entire background color of geometric symbol sign must contrast with door. It is not allowed to have a thin contrasting border around symbol, with remainder of sign background in a non-contrasting color. ISA, contrasting with background, may be on sign.
 3. If a gender pictogram is desired on geometric symbol sign, it must be repeated above raised characters and Braille on tactile sign adjacent to door. ISA may be included on either tactile sign, next to gender pictogram, or may be only on geometric symbol sign, as desired. No raised text or Braille is to be included on geometric door sign.
 4. For stair level sign at ground level, tactile 5-pointed star shall be placed to the left of floor number. All star points shall be of equal length, and star shall be same height as floor number (Braille translation for star is "Main").

CBC 1011.3

Tactile exit signs

CBSC Part 1
4-317(b)

Plans

CBC 1022.8 &
CBC 1133B.4.3

Floor identification signs
Floor identification signs

CBSC Part 1
4-317(b)

Plans

CBSC Part 1
4-317(b) &
CBC 1117B.5

Plans
Signs and identification

CBC 1115B.6 &
CBC 1117B.5.8.1

Identification symbols
International symbol of
accessibility

CBC 1115B.6,
CBC 1117B.5.1 #1 &
CBC 1117B.5.5 #3

Identification symbols
Identification signs
Pictorial symbol signs

CBC 1133B.4.3

Tactile floor designation signs in
stairways

NOTE:

Do not confuse with 12" Fire Code sign required in all enclosed stairwells in buildings of four or more floors by Title 19. The 12" sign does not require raised characters or Braille, and shall not be located immediately adjacent to the door leading from stairwell into corridor.

17

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Comments / Notes / Examples

Check List 17. SIGNAGE

17.20 Provide additional required signs on schedule as appropriate:

1. Locate accessible phone equipment on plan and specify appropriate Symbols of Accessibility, the TTY Symbol for text telephones, and the Volume Control Symbol for volume control phones. If there are banks of phones with no accessible equipment, indicate placement of sign that directs from those phones to accessible phones.
2. Determine if an assistive-listening system is required and specify appropriate informational sign with symbol. Locate signs at box office, lobby, entrance, or at administration building, as appropriate. More than one sign may be provided.
3. When buildings provide specific accessible elements such as restrooms and elevators for public use, post sign at entrance or in lobby informing of available features. Provide directional signage at inaccessible sanitary facilities indicating location of accessible sanitary facilities.
4. In buildings with more than one floor that has interior corridors, elevators and/or enclosed stairwells, evacuation plans are required. Locate these plans inside each main building entry, each elevator lobby, and in close vicinity of each door leading to enclosed stairwell.
 - Evacuation plans are directional and informational and must conform to standards for visual signs. They must be non-glare, high contrast, and use readable text and symbols of appropriate size.
 - Hotels and lodging houses must include evacuation plans in each room, and must provide evacuation information usable by persons with vision impairments.

CBSC Part 1
4-317(b),
CBC 1117B.2.8 &
CBC 1117B.2.9.3

Plans

Telephone equipment for hearing impaired persons
Text telephones - Signage

CBC 1104B.2 #4

Assistive-listening systems in assembly areas - Signage

CBC 1117B.5.8.1.3

Symbols of accessibility - Information posted

CCR Title 19, §3.09

Emergency planning and information

CBC 1117B.5.1 #2

Directional and informational signs

CFC 408.8.1

Evacuation diagrams

17.21 Specify installation of signs and show location of signs on plan.

1. Informational and directional signs can be installed on walls, doors, posts, or in the interiors of buildings, projecting from walls or hanging from the ceiling in corridors, as long as the location will allow them to be easily found and read by persons with various disabilities.
 - Specify location of TTY Symbol or Volume Control Symbol high enough so that another person can see the sign even when the telephone is in use.
 - Specify location of International Symbol of Hearing Loss to indicate the availability of an assistive-listening system outside the entrance to the room where it can be used. In addition, place signage in

CBSC Part 1
4-317(b)

Plans

CBC 1104B.2 #4

Assistive listening systems in assembly areas - Signage

17

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Comments / Notes / Examples

Check List 17. SIGNAGE

lobbies, at ticket windows, or at entrances to offices that must be reserved for use by persons with hearing impairments.

2. Specify location of tactile signs as follows: Tactile signs must be installed adjacent to the specific door they identify, at 60" AFF to the centerline of the sign. Where permanent identification signs are provided for rooms and spaces, they shall be located on the approach side of the door as one enters the room or space. Signs that identify exits shall be located on the approach side of the door as one exits the room or space. Signs must not be installed behind obstructions, and the reader must be able to approach the sign within 3" without being hit by the swing of a door.
3. Specify locations of evacuation plans so that the lower edge of the information sign is no more than 48" AFF.

CBC 1117B.5.1 #1 &
CBC 1117B.5.7

Identification signs
Mounting location and height

CCR Title 19, §3.09

Emergency planning and
information




Fig 17-A. Tactile Restroom Signage and Contrasting Restroom Symbols for Unisex Restroom




Fig 17-B. Contrasting Restroom Symbols Centered on Door Leaf at 60" O.C. AFF




Fig 17-D. Tactile Exit Route and Exit Signs





Fig 17-C. Tactile Stair Identification Sign with Exit Discharge Level Star



18

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 18. ASSEMBLY USE AREAS

18.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

18.2 For the purpose of Access Compliance review only: Regardless of occupancy load or classification, the requirements of CBC 1104B are not limited to Group A classified facilities or portions of facilities but do also apply to any facility or portion of facility which is used, either full-time or part-time, or can be characterized as an assembly area.

CBC 1105B.2
ADA Stds 3.5

Group B Occupancies
Definitions

DEFINITION:
ASSEMBLY AREA: A room or space accommodating a group of individuals for recreational, educational, political, social, civic, or amusement purposes, or for the consumption of food and drink.

ASSISTIVE LISTENING SYSTEMS (ALS)

CBC 1104B.2

18.3 Provide and indicate an ALS in all assembly areas, conference rooms, and meeting areas that are affected by project scope, whether device is in this contract or provided by the owner.

CBC 1104B.2

Assistive-listening systems in
assembly areas

NOTE:
If ALS is N.I.C. or to be provided by owner, state so on the plan and provide specs for equipment.

18.4 Provide and indicate a permanently installed assistive-listening system in space/room if:

CBC 1104B.2 #6
ADA Stds 4.1.3(19)(b)

Permanent and portable systems
Assembly areas

1. The space/room accommodates at least 50 persons, or has an audio-amplification system, and
2. The space/room has fixed seating.

NOTE:
Portable ALS may serve more than one space/room.

18.5 If the ALS provided is limited to specific areas or seats, then such areas or seats shall be within a 50' viewing distance of the stage or playing area and shall have a complete view of the stage or playing area.


CBC 1104B.2 #3

Locations

18.6 Indicate location of ALS sign(s) on plan for each space/room required to be equipped with an ALS and indicate text. This requirement applies even if the system is N.I.C.

CBC 1104B.2 #4
CBSC Part 1
4-317(b)

Signage
Plans



18.7 Reference detail of ALS signage.

CBSC Part 1
4-317(b)

Plans

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 18. ASSEMBLY USE AREAS

18.8 Provide ratio table for each space/room, indicating total number of seats and number of personal receivers required (4% min but never less than 2 receivers).

CBSC Part 1
4-317(b)
CBC 1104B.2 #1

Plans
Number of personal receivers required

18.9 Specify type of ALS even if the system is N.I.C. (See <http://www.access-board.gov/adaag/about/bulletins/als-index.htm> for an explanation of the different types available.)

CBC 1104B.2 #2

Types of listening systems

AUDITORIUMS, ASSEMBLY HALLS, THEATERS AND RELATED FACILITIES

CBC 1104B.3

18.10 Provide a seating layout plan showing individual seats or dimensioned benches/bleachers.

CBSC Part 1
4-317(b)

Plans

18.11 Where fixed or semi-permanent seating is provided identify on seating layout plan the location of:

CBC 1104B.3.5

Placement of wheelchair locations

1. Wheelchair spaces (show 33" x 48" or 33" x 60")

CBC 1104B.3.4

Wheelchair spaces

2. Companion seats (e.g., mark seat with a "C")

CBC 1104B.3.5

Placement of wheelchair locations

3. Semi-ambulant seats (e.g., mark seat with an "S")

CBC 1104B.3.8

Seating for semi-ambulant individuals

4. Transfer or aisle seats (e.g., mark seat with a "T")

CBC 1104B.3.4

Wheelchair spaces

18.12 Indicate the total number of seats and number of wheelchair spaces, companion seats, semi-ambulant seats and transfer seats.

CBC 1104B.3.4
CBC 1104B.3.5
CBC 1104B.3.8

Wheelchair spaces
Placement of wheelchair locations
Seating for semi-ambulant individuals

Seating Capacity	W	C	S	T	ALS Receiver
4 to 26	1	1	2	1	2
27 to 50	2	2	2	1	2
51 to 100	4	4	2	1	4%
101 to 200	4	4	2	1%	4%
201 to 300	4	4	1%	1%	4%
301 to 500	6	6	1%	1%	4%
501+	6+1 per add'l 100 seats over 500	6+1 per add'l 100 seats over 500	1%	1%	4%

NOTE:
Companion seats cannot be included in the count for semi-ambulant seats.

18.13 Indicate slope at wheelchair space to be 2% max in any direction.

CBC 1104B.3.4 #3

Wheelchair spaces

18.14 Indicate size of wheelchair space to be:

CBC 1104B.3.6 &
CBC Fig. 11B-15

Size of wheelchair location
Location

1. 33" x 48" for front or rear access.

2. 33" x 60" for side access.

18

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 18. ASSEMBLY USE AREAS

18.15 Provide detail (1/4" scale) of area showing all relevant dimensions, including wheelchair maneuvering space, all adjacent slopes and level changes, required egress, and accessible routes of travel.

CBSC Part 1
4-317(b)

Plans

18.16 Provide additional space in front or behind designated wheelchair space to ensure safe and convenient access and egress for persons using wheelchairs and the general public.


CBC 1104B.3.6
CBC 1104B.3.9

Size of wheelchair location
Life safety

18.17 Semi-ambulant seating must provide 24" clear leg room from the front edge of the seat to the nearest obstruction.

CBC 1104B.3.8

Seating for semi-ambulant
individuals



18.18 In existing facilities where site constraints exist, provide a reasonable portion of transfer seats on or adjacent to a wheelchair accessible path of travel.

CBC 1104B.3.4 #1

Wheelchair spaces

18.19 Indicate 1% (but not less than one) of all fixed seats to be aisle seats with no armrests on the aisle side, or removable or folding armrest on the aisle side.

CBC 1104B.3.4 #1

Wheelchair spaces

1. Indicate an identifying sign or marker with the International Symbol of Accessibility to be installed at each seat.
2. Indicate signage to be provided at ticket office notifying patrons that such seating is available.

NOTE:
Transfer seats are intended to facilitate seating of wheelchair users who wish to transfer to existing seating during an event when fixed seating is provided. Many persons who use wheelchairs are able to transfer to fixed seating with this relatively minor modification.

18.20 Where total seating capacity exceeds 300, provide accessible wheelchair seating in more than one location.

CBC 1104B.3.5

Placement of wheelchair locations

18.21 Arrange seating layout to provide integral seating for persons using wheelchairs and their companions (shoulder to shoulder).

CBC 1104B.3.5

Placement of wheelchair locations

18.22 Arrange seating layout to provide choice of admission prices and lines-of-sight for people using wheelchairs and their companions.

CBC 1104B.3.3
ADA Stds. 4.33.3

Variety of locations
Placement of wheelchair locations

18.23 Provide elevation or section to indicate how lines-of-sight requirement is met.

CBSC Part 1
4-317(b) &
CBC 1104B.3.5

Plans
Placement of wheelchair locations

CBSC Part 1
4-317(b)

Plans

18

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 18. ASSEMBLY USE AREAS

<p>18.24 If removable seats are planned, indicate on plan assigned storage space for removable seats.</p>		<p>NOTE: Public entities must keep wheelchair spaces free from removable seats in all but the most unusual cases (e.g., if an event is sold out and there were no requests for wheelchair spaces, removable seats can be installed and sold to non-disabled patrons).</p>
<p>18.25 Provide and indicate accessible routes of travel from wheelchair seating locations to performing areas, including stages, arena floors, dressing rooms, locker rooms and other spaces used by performers, and public restrooms.</p>	<p>CBSC Part 1 4-317(b), CBC 1104B.3.10 & CBC 1104B.3.13</p>	<p>Plans Access to performing areas Miscellaneous areas</p>
<p>18.26 Stages, enclosed and unenclosed platforms, orchestra pits and preparation areas must be made accessible.</p> <p>EXCEPTION:</p> <p>a. When DSA finds that requiring compliance for an enclosed or unenclosed platform or depressed area not more than 24" above or below an adjacent accessible level, would create an unreasonable hardship, the enclosed and unenclosed platform or depressed area must be made accessible by a portable ramp with a slope not exceeding 8.3%.</p> <p>b. In existing buildings, when DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.</p>	<p>CBC 1104B.3.11</p>	<p>Stages, enclosed and unenclosed platforms, and orchestra pits</p>
<p>18.27 Employee and customer sides of all ticket booths and of refreshment and concession stands must be made accessible.</p>	<p>CBC 1104B.3.12</p>	<p>Ticket booths</p>
<p>18.28 Provide enlarged detail and elevations for ticket booth, and refreshment and concession stands.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>18.29 Provide signage at ticket office that notifies customers of the availability of the different types of accessible seating and assistive listening devices.</p>	<p>ADA Stds 4.1.3(19)(a), CBC 1104B.3.4 #1& CBC 1104B.2 #4</p>	<p>Assembly areas Wheelchair spaces Signage</p>
<p>18.30 In outdoor assembly use areas (e.g. amphitheater type seating on turf) provide and indicate required ratio of wheelchair and companion seat spaces, located on an accessible path.</p>	<p>CBC 1104B.3.4 & CBC 1104B.3.5</p>	<p>Wheelchair spaces Placement of wheelchair locations</p>
<p>18.31 In amphitheaters, provide warning curb or rails where abrupt changes in level between the accessible route of travel and adjacent seating areas exceed 4" in height.</p>	<p>CBC 1133B.8.1</p>	<p>Warning curbs</p>
<p>18.32 Provide guards, walls, or fences (42" min high) at all elevated seating areas that are more than 30" above the ground.</p> <p>Guards at the front of the front row of seats that are not located at the end of an aisle and where there is no cross aisle may</p>	<p>CBC 1013 CBC 1025.14 CBC 1024.14.2</p>	<p>Guards Assembly guards Sightline-constrained guard heights</p>

18

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 18. ASSEMBLY USE AREAS

have a minimum height of 26" where the fascia or railing would interfere with sightlines.

STADIUMS, GRANDSTANDS, BLEACHERS, ATHLETIC PAVILIONS, GYMNASIUMS AND MISCELLANEOUS SPORT-RELATED FACILITIES

18.33 Accessible seating for stadiums, grandstands, bleachers, athletic pavilions, gymnasiums and miscellaneous sport related facilities must comply with 1104B.3 and items **18.9 through 18.31** of this Checklist.

EXCEPTION:

At folding bleachers where wheelchair spaces are provided by a cut back in the first rows, and when DSA finds that integrated companion fixed seats cannot be obtained, the following design will be accepted:

- Provide a 24"x48" clear space for companion seating next to each 33"x48" wheelchair space, with identifying signage on the companion seat.
- Provide an ISA on the floor or on the front face of the lowest bleacher row in front of space to identify the wheelchair space.
- The number of wheelchair accessible seats must be dispersed equally for each side (home and visitors) and cannot be clustered into one location for each side.

18.34 Employee and customer sides of all ticket booths and of refreshment and concession stands must be made accessible.

18.35 Provide enlarged detail and elevations for ticket booth, and refreshment and concession stands.

18.36 Provide signage at ticket office that notifies customers of the availability of the different types of accessible seating and assistive listening devices.

18.37 Provide and indicate an accessible route of travel to all participation and activity areas, including the following:

1. Tennis, racquetball and handball courts.
2. Gymnasium floor areas and general exercise rooms.
3. Basketball, volleyball and badminton courts, and bowling lanes.
4. Swimming pool deck areas and swimming pools.
5. Athletic team rooms and facilities, playing fields and running tracks.
6. Club rooms (home and guest).
7. Sanitary and locker facilities (home and guest).

CBC 1104B.4

CBC 1104B.4.1

DSA Policy 98-05

CBC 1104B.3.12 &
28 CFR §35.149

CBSC Part 1
4-317(b)

CBC 1104B.3.4 #1&
CBC 1104B.2 #4

CBC 1104B.4.3

CBC 1104B.4.3 #1

CBC 1104B.4.3 #2

CBC 1104B.4.3 #3

CBC 1104B.4.3 #4

CBC 1104B.4.3 #5

CBC 1104B.4.4

CBC 1104B.4.5

Spectator seating

Accessible seating in folding
bleacher units

Ticket booths
Program accessibility:
Discrimination prohibited

Plans

Wheelchair spaces
Signage

Participation areas

Participation areas

Participation areas

Participation areas

Participation areas

Participation areas

Clubroom

Sanitary and locker facilities

18

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 18. ASSEMBLY USE AREAS

<p>8. Baseball/softball player dugout.</p>	<p>CBC 1104B.4.3</p>	<p>Participation areas</p>
<p>18.38 Provide pool lift with rigid seat and arm rests or ramp to assist persons with disabilities to access and egress the swimming pool independently.</p>	<p>CBC 1104B.4.3 #4</p>	<p>Participation areas</p>
<p>18.39 Where spectator and/or participant sanitary and/or locker facilities are provided, they shall conform with the requirements in 1115B.</p>	<p>CBC 1104B.4.5</p>	<p>Sanitary and locker facilities</p>
<p>18.40 Provide vertical access to press boxes, announcer booths and similar facilities.</p>	<p>CBC 1114B.1.2 ADA Stds 4.1.3(1)</p>	<p>Accessible route of travel Accessible buildings</p>
<p>18.41 Provide guards, walls, or fences (42" min high) at all elevated seating areas that are more than 30" above the ground.</p> <p>Guards at the front of the front row of seats that are not located at the end of an aisle and where there is no cross aisle may have a minimum height of 26" where the fascia or railing would interfere with sightlines.</p>	<p>CBC 1013 CBC 1025.14 CBC 1024.14.2</p>	<p>Guards Assembly guards Sightline-constrained guard heights</p>
<p>DINING, BANQUET AND BAR FACILITIES</p>	<p>CBC 1104B.5</p>	
<p>18.42 All areas where each type of functional activity occurs must be made accessible.</p> <p>EXCEPTIONS:</p> <p>a. In alteration projects, where DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.</p> <p>b. In alteration projects, when legal or physical constraints would not allow compliance with these regulations or equivalent facilitation without creating an unreasonable hardship.</p>	<p>CBC 1104B.5 #1 ADA Stds 5.1</p>	<p>General General</p> <p>NOTE: Jurisdictional findings and determinations for exception (b) are subject to an internal DSA appeals process.</p>
<p>18.43 All floors, levels, and mezzanines of dining areas must be made accessible.</p> <p>EXCEPTION:</p> <p>In alteration projects, where DSA determines that compliance would create an unreasonable hardship, an exception is granted provided that:</p> <ul style="list-style-type: none"> ▪ A minimum of 75% of the dining, banquet and bar area is on a common level or connected by ramps, passenger elevators or platform lifts, <u>and</u> ▪ The same services and decor are provided in an accessible space usable by the general public and are not restricted to use by persons with disabilities. 	<p>CBC 1104B.5 #3 CBC 1120B.1 CBC 1120B.2</p>	<p>Raised or sunken areas Floors within each story Floor surface</p>
<p>18.44 Provide and indicate one 30" x 48" clear wheelchair seating space for each 20 seats per functional area.</p>	<p>CBC 1104B.5 #4</p>	<p>Seating</p>
	<p>CBSC Part 1 4-317(b) &</p>	<p>Plans</p>

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 18. ASSEMBLY USE AREAS

18.45 Provide enlarged detail and elevations of accessible section of fixed tables and counters. Indicate

1. Surface top to be 28" min and 34" max AFF.

CBC 1122B

Fixed or built-in seating, tables and counters

2. Knee clearance at bars, counters, and tables must be at least 27" high x 30" wide x 19" deep.

CBC 1122B

Fixed or built-in seating, tables and counters

3. The accessible portion of the counter must be 60" min in length when food or drink is served at counters exceeding 34" in height for consumption by customers sitting on stools or standing.

CBC 1104B.5 #4

Seating

18.46 Provide and indicate adequate maneuvering and passing space behind each wheelchair seating space.

CBSC Part 1
4-317(b)
CBC Fig 11B-13

Plans

Minimum clearances for seating and table

18.47 Wheelchair space must be integrated with general seating.

CBC 1104B.5 #4

Seating

18.48 Provide 36" clear width accessible route of travel to wheelchair seating space.

CBC 1104B.5 #4

Seating

18.49 Provide and indicate 36" min wide (42" preferred) food service aisles.

CBC 1104B.5 #5

Food service aisles

18.50 At food service aisles, provide and indicate all tray slides to be 34" max AFF.

CBC 1104B.5 #5
CBC Fig. 11B-16

Food service aisles
Food service lines

18.51 Provide and indicate at least 50% of each type self-service shelves to be within reach ranges.

CBC 1104B.5 #5
CBC Fig. 11B-5C
CBC Fig. 11B-5D

Food service aisles
Forward reach
Side reach

18.52 Indicate reach range dimensions for self-service tableware, dishware, condiments, food and beverage display shelves, and dispensing devices.

CBC 1104B.5 #6
CBC Fig. 11B-17

Tableware areas
Tableware areas

18.53 Provide and indicate accessible doors to all food preparation areas.

CBC 1104B.5 #8

Food preparation areas

18.54 All toilets, locker and powder rooms, including those serving employees, must be made accessible.

CBC 1104B.5 #7

Restrooms

RELIGIOUS FACILITIES

18.55 Provide and indicate access to sanctuaries, assembly areas, platforms, choir rooms, performing areas, and sanitary facilities.

CBC 1104B.6
CBC 1104B.6.1 &
CBC 1104B.6.2

General
Sanctuary

EXCEPTION:

In alteration projects, where DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.

CBC 1104B.6.2.2

Sanctuary – wheelchair access

18

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 18. ASSEMBLY USE AREAS

18.56 Provide and indicate access to raised platforms, choir rooms, choir lofts, performing areas, and other similar areas.

EXCEPTION:

In alteration projects, where DSA determines that compliance would create an unreasonable hardship, an exception may be granted.

18.57 Provide and indicate accessible doors to all classrooms and offices.

CBC 1104B.6.4

Classrooms and offices

19

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 19. BUSINESS AND MERCANTILE USE AREAS

19.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklist 1**.

19.2 For the purpose of Access Compliance review only: Regardless of occupancy load or classification, the requirements of CBC 1105B and 1110B are not limited to Group B and M facilities or portions of facilities but do also apply to any facility or portion of facility which is used, either full-time or part-time, or can be characterized as a business or mercantile area.

OFFICE BUILDINGS, PERSONAL AND PUBLIC SERVICE FACILITIES

19.3 The following areas in business and professional office facilities must be accessible:

1. Client, visitor, office areas and related toilet facilities.
2. Conference rooms, counseling rooms or cubicles and similar areas.
3. Employee work areas must have 36" clear width access.
4. Professional medical and dental offices (see also **Checklist 21** for additional requirements.)

CBC 1105B.3.2

Business & professional offices

CBC 1105B.3.2 #1

Business & professional offices

CBC 1105B.3.2 #2

Business & professional offices

CBC 1105B.3.2 #3

Business & professional offices

CBC 1105B.3.2 #4

Business & professional offices

19.4 The following areas in personal and public service facilities areas must be accessible:

1. Client, visitor, office areas, and related toilet facilities.
2. Employee work areas must have 36" clear width access.
3. Automated teller machines used by a financial institution and its customers for the primary purposes of executing financial transactions.

CBC 1105B.3.3

Personal and public service facilities

CBC 1105B.3.3 #1

Personal and public service facilities

CBC 1105B.3.3 #2

Personal and public service facilities

CBC 1105B.3.3 #3

Personal and public service facilities

19.5 The following areas in public utility facilities must be accessible:

1. Office areas, meeting rooms and similar areas, and related toilet rooms.
2. Public tour areas, to the extent that such public tours are conducted through or about a facility, or where the public is permitted to walk in such areas.

CBC 1105B.3.4

Public utility facilities

CBC 1105B.3.4 #1

Public utility facilities

CBC 1105B.3.4 #2

Public utility facilities - public tour areas

EXCEPTIONS:

- a. Facilities located in operational areas which would not have any reasonable availability to or usage by persons who use wheelchairs for mobility are not subject to the wheelchair accessibility requirements.
- b. When DSA determines that compliance would create an unreasonable hardship, an exception may be

19

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 19. BUSINESS AND MERCANTILE USE AREAS

granted when equivalent facilitation is provided.

3. Visitors overlook facilities, orientation areas and similar public use areas, and any sanitary facilities that serve these facilities.

CBC 1105B.3.4 #3

Public utility facilities

4. Where public parking is provided, parking spaces shall be provided for persons with disabilities.

CBC 1105B.3.4 #4

Public utility facilities

19.6 The following areas in police department, law enforcement, fire department facilities and courtrooms must be accessible:

CBC 1105B.3.5

Police department, law enforcement, fire department facilities and courtrooms

1. Office areas, conference rooms, classrooms, dormitories, dispatch rooms and similar areas, along with related sanitary facilities.

CBC 1105B.3.5 #1

2. Detention area visitor rooms.

CBC 1105B.3.5 #2

3. At least one detention cell facility (with supporting sanitary facilities).

CBC 1105B.3.5 #3

4. Courtroom areas, including the judge's chambers and bench, counsel tables, jury box, witness stand and public seating area.

CBC 1105B.3.5 #4

SALES ESTABLISHMENTS

19.7 General sales, display, and office areas, along with related sanitary facilities must be accessible.

CBC 1110B.1.1

General areas

19.8 Provide wheelchair access to sales employee work stations and customer sides of sales or checkout stations.

CBC 1110B.1.2

Work areas

19.9 When not all check stands are accessible, accessible check stands shall be identified by a sign clearly visible to a person in a wheelchair displaying the ISA. The sign shall be a minimum 4" x 4". When check stands are open for customer use, a minimum of one accessible check stand shall always be available. As check stands are opened and closed based on fluctuating customer levels, the number of accessible check stands available shall comply with Table 11B-2.

CBC 1110B.1.3

Check stands

19.10 Provide and indicate the top of required accessible sales and service counters, teller windows, and information counters to be 28" min and 34" max AFF for a length of 36" min on the customer side.

CBC 1122B.5

Sales and service counters, teller windows and information counters

EXCEPTIONS:

- a. Where seated service is provided, for example in banks, insurance offices, travel agencies, etc, counters and fixed tables must provide knee and toe clearances.
- b. At check stands (see CBC 1110B.1.3 for requirements).

19

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 19. BUSINESS AND MERCANTILE USE AREAS

<p>19.11 Theft-prevention barriers and any device used to prevent the removal of shopping carts from store premises cannot limit access or egress to people in wheelchairs. Provide accessible entry that is equally convenient to that provided for the general public.</p>	<p>CBC 1110B.1.6</p>	<p>Theft-prevention barriers</p>
<p>19.12 Provide and indicate 5% but never less than one accessible fitting or dressing room for each type of use in each cluster of dressing rooms.</p>	<p>CBC 1117B.8</p>	<p>Fitting and dressing rooms</p>
<p>19.13 Identify type of use of each dressing room on floor plan (e.g., customer, staff, male, female, family, etc).</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>19.14 Provide enlarged plan and elevations for accessible dressing rooms and indicate the following:</p> <ol style="list-style-type: none"> 1. Accessible door or curtain. 2. Full-length mirror, 18" min wide x 54" min high, bottom at 20" max AFF, and positioned to afford a view to a person on the bench as well as to a person standing. 3. Clothing hook at 48" max AFF. 4. Bench or section of bench measuring 24" deep, 48" wide, and 17" to 19" high, and fixed to a wall along the longer dimension. 5. 60" x 60" clear space in front of the accessible bench section, located in such a manner to allow a person using a wheelchair to make a parallel transfer onto the bench. (Door cannot swing into this clear space.) 6. Provide ISA on outside of door to accessible dressing room. 	<p>CBSC Part 1 4-317(b) & CBC 1117B.8</p>	<p>Plans Fitting and dressing rooms</p>
<p>19.15 Provide and indicate the following minimum circulation aisle and pedestrian way widths at all areas with fixed displays:</p> <ol style="list-style-type: none"> 1. 36" min if displays and similar fixtures or equipment are placed on only one side of the aisle. 2. 44" min if displays and similar fixtures or equipment are placed on both sides of the aisle. 	<p>CBC 1017.2, CBC 1105B.3.6 #1, CBC 1110B.2.1 & CBC 1133B.6.2</p>	<p>Aisles in Groups B and M Miscellaneous general standards Circulation Width</p>
<p>19.16 Provide and indicate the following minimum circulation aisle and pedestrian way widths at all areas with non-fixed displays or displays that are N.I.C. to inform the owner of aisle width requirements at displays:</p> <ol style="list-style-type: none"> 1. 36" min if displays and similar fixtures or equipment are placed on only one side of the aisle. 2. 44" min if displays and similar fixtures or equipment are placed on both sides of the aisle. 	<p>CBC 1017.2, CBC 1105B.3.6 #1, CBC 1110B.2.1 & CBC 1133B.6.2</p>	<p>Aisles in Groups B and M Miscellaneous general standards Circulation Width</p>
<p>19.17 Provide and indicate 32" min clear door opening at all storage areas.</p>	<p>CBC 1105B.3.6 #2 & CBC 1110B.2.2</p>	<p>Storage areas Storage areas</p>

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 20. EDUCATIONAL USE AREAS

<p>20.1 For additional scoping requirements and exceptions see also applicable DSA-AC Checklist 1.</p>		
<p>20.2 For the purpose of Access Compliance review only: Regardless of occupancy load or classification, the requirements of CBC 1106B are not limited to Group E facilities or portions of facilities but do also apply to any facility or portion of facility which is used, either full-time or part-time, or can be characterized as an educational use area.</p>		
<p>20.3 All laboratories, prep rooms, dark rooms, computer rooms, equipment rooms, teaching facility cubicles, study carrels, libraries, and similar areas must be made accessible.</p> <p>EXCEPTIONS:</p> <p>a. In existing buildings where DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided.</p> <p>b. In existing buildings where DSA determines that, due to legal or physical constraints, compliance with building standards requirements or equivalent facilitation would create an unreasonable hardship.</p>	<p>CBC 1106B.1</p>	<p>Group E Occupancies - General</p> <p><u>NOTE:</u> Jurisdictional findings and determinations for exception (b) are subject to an internal DSA appeals process.</p>
<p>LABORATORIES (Labs)</p>		
<p>20.4 Provide and indicate 5%, but never less than one accessible workstation of each type of use in labs, science, home economics and other similar specialized classrooms.</p>	<p>CBC 1106B.2 ADA Stds. 4.1.3(18)</p>	<p>Laboratory rooms</p>
<p>20.5 Provide and indicate 5%, but never less than one accessible workstation of each type of use in laboratory preparation rooms, supply rooms, dry rooms, cold rooms, walk-in freezers, sterile rooms, small research laboratories, and areas containing specialized equipment.</p> <p>EXCEPTION: Where DSA determines that compliance would create an unreasonable hardship, such facilities need not be made fully accessible, except that a clear accessible path of travel must be maintained into such rooms.</p>	<p>CBC 1106B.3</p>	<p>Teaching facility cubicles, study carrels, etc.</p>
<p>20.6 Provide and indicate at least one of each type of sink and other specialized equipment such as fume hoods, microscopes, emergency eyewash and showers, etc, associated with the special use activity to be accessible.</p>	<p>CBC 1106B.3</p>	<p>Teaching facility cubicles, study carrels, etc.</p>
<p>20.7 Provide and indicate at least one teaching or demonstration station of each type to be accessible.</p>	<p>CBC 1106B.3</p>	<p>Teaching facility cubicles, study carrels, etc.</p>
<p>20.8 Provide floor plan and indicate:</p> <ol style="list-style-type: none"> 1. All workstations and equipment. 2. 30" x 48" clear space at each accessible workstation and at accessible equipment. 	<p>CBSC Part 1 4-317(b)</p> <p>CBC 1106B.2</p>	<p>Plans</p> <p>Laboratory rooms</p>

20

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 20. EDUCATIONAL USE AREAS

<p>3. Aisle width, maneuvering and turning clearances from room entry to all accessible elements.</p>	<p>CBC 1114B.1.1 CBC 1106B</p>	<p>Facility accessibility – General Accessibility for Group E Occupancies</p>
<p>20.9 Provide and indicate knee clearance at workstation or equipment: 27" high, 30" wide, and 19" deep min.</p>	<p>CBC 1122B.3</p>	<p>Knee clearance</p>
<p>20.10 Provide and indicate height of accessible work surface depending on the type of use between 28" and 34" AFF.</p>	<p>CBC 1122B.4 ADA Stds. 4.32.4</p>	<p>Height of work surfaces Height of tables or counters</p>
<p>20.11 Provide elevation or manufacturer's cut sheet for accessible fume hood indicating knee clearance and height of operable parts and controls to be 48" max AFF.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>20.12 Provide elevation or manufacturer's cut sheet for accessible emergency shower indicating height of operable parts and controls (e.g., pull-handle) to be 48" max AFF.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>20.13 Provide elevation or manufacturer's cut sheet for accessible emergency eyewash indicating centerline of bubbler to be 36" max AFF.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>20.14 Indicate 48" min aisle width for sink back-up space.</p>	<p>CBC 1118B.4 #1</p>	<p>Clear floor or ground space for wheelchairs - Size and approach</p>
<p>20.15 Provide and indicate reach range dimensions for gas/air/water outlets over an obstruction.</p>	<p>CBC Fig 11B-13</p>	<p>Minimum clearances for seating and table</p>
<p>20.16 Provide and indicate lever-action faucets at gas/air/water outlets.</p>	<p>CBC 1118B.5 CBC Fig 11B-5C(b) ADA Stds Fig. 5b</p>	<p>Forward reach Maximum forward reach Maximum forward reach</p>
<p>20.17 Provide and indicate lever-action faucets at gas/air/water outlets.</p>	<p>CBC 1117B.6 #4</p>	<p>Controls and operating mechanisms</p>
<p>TEACHING FACILITY CUBICLES, STUDY CARRELS, COMPUTER CLASSROOMS, AND DARKROOMS</p>		
<p>20.17 Provide and indicate 5%, but never less than one accessible workstation of each type of use at the following teaching facilities:</p> <ol style="list-style-type: none"> 1. Cubicles and study carrels. 2. Computer stations. 3. Language. 4. Medical and dental stations. 5. Audio-visual. 6. Typing, painting, sculpting, and ceramics studios. 7. Vocational, wood, and metal shops, including spray booth. 8. Darkrooms. 	<p>CBC 1106B.3</p>	<p>Teaching facility cubicles, study carrels, etc.</p>
<p>20.18 Provide and indicate at least one teaching or demonstration station to be accessible.</p>	<p>CBC 1106B.3</p>	<p>Teaching facility cubicles, study carrels, etc.</p>

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 20. EDUCATIONAL USE AREAS

- 20.19** Provide floor plan and indicate:
1. All workstations and equipment.
 2. 30" x 48" clear space at each accessible workstation and at accessible equipment.
 3. Knee clearance and reach ranges, if applicable.
 4. Aisle width, maneuvering and turning clearances from room entry to all accessible elements.

CBSC Part 1 4-317(b)

Plans

- 20.20** Provide accessible door at darkroom.

CBC 1118B.4

Clear floor or ground space for wheelchairs

CBC 1122B.3, CBC 1118B


Knee clearance
Space allowance & reach ranges

CBC 1133B.6.2, CBC 1118B

Aisles - width
Space allowance & reach ranges

CBC 1133B.2

Doors



Compliant Darkroom

60" turning radius, 30" x 48" clear space and knee clearance at each different type of equipment, door opening 32", inner diameter of door 57" clear provided

LIBRARIES

- 20.21** Provide floor plan and indicate:
1. Service, information, and checkout counters.
 2. Book drop.
 3. Book stacks, shelves, display tables and cabinets, card files, etc.
 4. Aisle widths, maneuvering and turning clearances throughout the public area.
 5. All workstations and equipment, including copying machines.

CBSC Part 1 4-317(b)

Plans

- 20.22** Provide and indicate 5%, but never less than one accessible library workstation of each type of use in each area, including:
1. Cubicles, reading and study carrels, and similar areas.
 2. Computer or similar workstations.

CBC 1106B.4 #5

Reading and study areas

- 20.23** Indicate height of counter/table top to be 28" min to 34" max AFF.

CBC 1122B.4

Height of work surfaces

- 20.24** At least one lane at each check-out area must be on an accessible route and have a portion of the counter which is at least 36" in length with a maximum height of 34" AFF with a 36" wide aisle on the customer side.

CBC 1106B.4 #6

Check-out areas

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 20. EDUCATIONAL USE AREAS

20.25 Bookshelves must be 54" AFF or less.

EXCEPTION: When an attendant is available at all times to assist persons with disabilities to retrieve books, shelves may be located higher than 54" AFF.

CBC 1106B.4 #3

Height of book shelves

CBC 1106B.4 #3

Height of book shelves

20.26 Card catalogs and magazine displays must be 48" max AFF for front reach and 54" max AFF for side reach.

CBC 1106B.4 #4

Card catalogs

20.27 Indicate 44" min width for all main aisles.

CBC 1106B.4 #2

Open book stacks

20.28 Indicate 36" min width for all side, range, and end aisles.

CBC 1106B.4 #2

Open book stacks

NOTE
Depending on the occupancy load, Chapter 10 may require wider aisles.

20.29 Provide and indicate the following dimensions when turning around bookshelves:

CBSC Part 1 4-317(b)

Plans


1. 90 degree turns can be made from a 36" wide aisle into another 36" aisle if the depth of the bookshelf is 48" or greater on the inside dimensions of the turn.
2. U-turns around bookshelves less than 48" wide can be made if the aisle width is 42" min and the base of the U-turn space is 48" min. wide.

CBC Fig. 11B-5E

Width of accessible route

CBC Fig. 11B-5E

Width of accessible route



20

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 20. EDUCATIONAL USE AREAS

PLAYGROUNDS

<p>20.30 Provide and indicate accessible route of travel to playground.</p>	<p>CBC 1106B.1</p>	<p>General</p>
<p>20.31 Provide and indicate accessible route of travel from playground area to play equipment.</p>	<p>CBC 1114B</p>	<p>Facility accessibility</p>
<p>20.32 Provide and indicate accessible playground equipment. See federal guidelines for acceptable solutions: (see http://www.access-board.gov/play/finalrule.htm).</p>	<p>36 CFR Part 1191</p>	<p>Accessibility guidelines for buildings and facilities</p>
<p>20.33 Provide and indicate destination material around playground equipment, to comply with the following standard, referenced by the federal guidelines:</p> <ol style="list-style-type: none"> 1. ASTM F 1487-98 Standard Consumer Safety Performance Specification for Playground Equipment for Public Use. 2. ASTM F 1951-99 Standard Specification for Determination of Accessibility of Surface Systems Under and Around Playground Equipment. 3. ASTM F 1292-99 Standard Specification for Impact Attenuation of Surface Systems Under and Around Playground Equipment. 	<p>36 CFR Part 1191 ADAAG Chapter 15 PRC 5410-5411 H&SC 115725</p>	
<p>20.34 Indicate play components to comply with ADA Guidelines for Play Areas.</p>	<p>PRC 5410-5411</p>	





Fig 20-A - Emergency Eyewash and Shower

Fig 20-B - Accessible Fume Hood



21

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 21. INSTITUTIONAL USE AREAS

<p>21.1 For additional scoping requirements and exceptions see also applicable DSA-AC Checklist 1.</p>		
<p>21.2 For the purpose of Access Compliance review only: Regardless of occupant load or classification, the requirements of CBC 1109B are not limited to Group I facilities or portions of facilities but do also apply to any facility or portion of a facility which is used, either full-time or part-time, or can be characterized as an institutional use area.</p>		
<p>21.3 All skilled nursing, long-term care, intermediate care, bed and care, nursing homes, hospitals, clinics, trauma centers, psychiatric, detoxification, rehabilitation, and similar facilities must be made accessible.</p>	<p>CBC 1109B.1 & ADA Stds 6.1</p>	<p>Group I occupancies - General Medical care facilities - General</p>
<p>EXCEPTION: In existing buildings where DSA determines that compliance would create an unreasonable hardship, an exception may be granted when equivalent facilitation is provided. Equivalent facilitation in alterations or additions must provide for either of the following:</p>	<p>CBC 1109B.1</p>	<p>Group I occupancies - General</p>
<p>a. When patient bedrooms are being added or altered as part of a planned renovation of an entire wing, a department, or other discrete area of an existing medical facility, a percentage of the patient bedrooms that are being added or altered must be made accessible. The percentage of accessible rooms provided must be consistent with the percentage of rooms required to be accessible by the applicable requirements of CBC 1109B.3 until the number of accessible patient bedrooms in the facility equals the overall number that would be required if the facility were newly constructed. Where toilet/bathrooms are part of patient bedrooms that are added or altered and required to be accessible, each such patient toilet/bathroom must be made accessible.</p>	<p>CBC 1109B.3</p>	<p>Patient bedrooms and toilet rooms</p>
<p>b. When patient bedrooms are being added or altered individually, and not as part of an alteration of the entire area, the altered patient bedrooms must be made accessible unless either a) the number of accessible rooms provided in the department or area containing the altered patient bedroom equals the number of accessible patient bedrooms that would be required if the percentage requirements of 1109B.3 were applied to that department or area, or b) the number of accessible patient bedrooms in the facility equals the overall number that would be required if the facility were newly constructed. Where toilet/bathrooms are part of patient bedrooms that are added or altered and required to be accessible, each such toilet/bathroom must be made accessible.</p>	<p>CBC 1109B.3</p>	<p>Patient bedrooms and toilet rooms</p>
<p>21.4 At outpatient units or facilities providing medical care or services to persons with mobility impairments 10% of the total number of parking spaces must be accessible.</p>	<p>CBC 1129B.2 #1</p>	<p>Accessible parking required – Medical care outpatient facilities - Outpatient units and facilities</p>

21

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 21. INSTITUTIONAL USE AREAS

<p>21.5 At facilities that specialize in the treatment of persons with mobility impairments 20% of the total number of parking spaces must be accessible.</p>	<p>CBC 1129B.2 #2</p>	<p>Units and facilities that specialize in treatment or services for persons with mobility impairments</p>
<p>21.6 One in every eight accessible parking spaces must be van-accessible.</p>	<p>CBC 1129B.3 #2</p>	<p>Parking space size - Van space(s)</p>
<p>21.7 At medical care facilities in which people receive physical or medical treatment or care <u>and</u> where persons may need assistance in responding to an emergency <u>and</u> where the period of stay may exceed 24 hours, provide and indicate at least one accessible entrance that is protected from the weather by a canopy or roof, and which incorporates an accessible passenger loading zone.</p> <p>EXCEPTION: Clinics and other medical facilities that are not intended for patient stays of 24 hours or more and that are located above the first floor.</p>	<p>CBC 1109B.2</p>	<p>Entrance</p>
<p>21.8 Provide enlarged plan in 1/4" scale representing the actual layout of the accessible passenger loading zone, including associated entrances, sidewalks and curb ramps. Provide and indicate:</p> <ol style="list-style-type: none"> 1. 5' x 20' access aisle adjacent and parallel to the vehicle pull-up space. 2. Access aisle and vehicle pull-up space must be level (2% max. slope in any direction). 3. A curb ramp, if there is a curb between the access aisle and the vehicle pull-up space, or if there is a curb between the access aisle and the accessible route of travel. 4. Vertical clearance of 114" min at passenger loading zones and one vehicle access route to such zones (from site entrances and exits). 5. Design of identifying signage (including ISA). 6. Indicate outline of canopy or roof on plan. 7. Bus stop pads and shelters (as applicable). 	<p>CBSC Part 1 4-317(b)</p> <p>CBC 1131B.2 #1</p> <p>CBC 1131B.2 #1</p> <p>CBC 1131B.2.1 #1</p> <p>CBC 1131B.2 #2</p> <p>CBC 1131B.2 #1</p> <p>CBSC Part 1 4-317(b)</p> <p>CBC 1121B.2</p>	<p>Plans</p> <p>Passenger loading zone - General</p> <p>Passenger loading zone - General</p> <p>Passenger loading zone - General</p> <p>Vertical clearance</p> <p>Passenger loading zone - General</p> <p>Plans</p> <p>Bus stops and terminals</p>
<p>21.9 All exterior and interior public use and common use areas, such as TV lounges, waiting rooms, offices, conference rooms, etc., must be made accessible.</p>	<p>CBC 1109B.1</p>	<p>Accessibility for group I Occupancies – General</p>
<p>21.10 In long-term care facilities (including skilled nursing, intermediate care, bed & care, and nursing homes) provide and indicate a minimum of 50% of patient bedrooms and toilet facilities to be accessible.</p>	<p>CBC 1109B.3 #1</p>	<p>Patient bedrooms and toilet rooms</p>
<p>21.11 In general-purpose hospitals, psychiatric and detoxification facilities provide and indicate a minimum of 10% of patient bedrooms and toilet facilities to be accessible.</p>	<p>CBC 1109B.3 #2</p>	<p>Patient bedrooms and toilet rooms</p>

21

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 21. INSTITUTIONAL USE AREAS

21.12 In hospitals and rehabilitation facilities that specialize in treating conditions that affect mobility, or units within either that specialize in treating conditions that affect mobility, provide and indicate that all patient bedrooms and toilet facilities shall be accessible.

CBC 1109B.3 #3

Patient bedrooms and toilet rooms

21.13 In buildings that house offices and suites of physicians, dentists, etc., all such offices or suites, and their sanitary facilities, must be made accessible.

CBC 1109B.8

Offices and suites

22

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes /
& Examples

Check List 22. RESIDENTIAL USE AREAS

22.1	Buildings and complexes containing publicly funded dwelling units shall be accessible as required by Chapter 11A, Housing Accessibility.	CBC 1111B.5.1	Buildings and complexes containing publicly funded dwelling units - General
22.2	Covered multifamily dwellings include one or more publicly funded dwelling units.	CBC 1111B.5.1	General
22.3	Alterations to publicly funded dwelling units must comply with Division IV of Chapter 11B, including the path of travel requirements.	CBC 1111B.5.1 CBC 1134B	General Accessibility for existing buildings
22.4	In covered multifamily dwelling units with fuel-burning appliances and/or attached garages as described in CBC 420.4.1, all required carbon monoxide alarms shall be provided with the capability to support visible alarm notification appliances.	CBC 420.4.4	Visible alarms

23

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 23. MISCELLANEOUS AND OTHER USE AREAS

23.1 For additional scoping requirements and exceptions see also applicable **DSA-AC Checklists 1 through 24.**

FACTORY AND WAREHOUSE USE AREAS

23.2 For the purpose of Access Compliance review only: Regardless of occupancy load or classification, the requirements of CBC 1107B are not limited to Group F facilities or portions of facilities but do also apply to any facility or portion of facility which is used, either full-time or part time, or can be characterized as factory or warehouse use area.

CBC 1107B

Factories and warehouses

23.3 All levels of multi-story factories and warehouses must be made accessible.

CBC 1107B &
CBC 1103B.1

Factories and warehouses
Building accessibility - General

EXCEPTIONS:

- a. Alterations when DSA determines that compliance would create an unreasonable hardship, and when equivalent facilitation is provided.
- b. Non-occupiable spaces accessed only by ladders, catwalks, crawl spaces, very narrow passageways, or freight (non-passenger) elevators, and frequented only by service personnel for maintenance, repair, or occasional monitoring of equipment, including, but not limited to, elevator pits, elevator penthouses, piping or equipment catwalks, and machinery rooms.
- c. Levels in private facilities that are less than three stories or that have less than 3000 square feet per story.

CBC 1103B.1 Exc 1

Building accessibility – General

CBC 1103B.1 -
Exception 2.1

Building accessibility – General

23.4 Factories must be made accessible as follows:

- 1. All major or principal floor areas must be made accessible.
- 2. All office areas must be made accessible.
- 3. All sanitary facilities serving these areas must be made accessible.

CBC 1107B.1 #1

Factories

CBC 1107B.1 #2

Factories

CBC 1107B.1 #3

Factories

23.5 Warehouses must be made accessible as follows:

- 1. All warehousing areas which are located on the floor nearest grade and those areas on other floors that are otherwise provided with access by level entry, ramp or elevator must be made accessible.
- 2. All office areas must be made accessible.
- 3. All sanitary facilities serving these areas must be made accessible.

CBC 1107B.2 #1

Warehouses

CBC 1107B.2 #2

Warehouses

CBC 1107B.2 #3

Warehouses

23

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 23. MISCELLANEOUS AND OTHER USE AREAS

HAZARDOUS USE AREAS

23.6 For the purpose of Access Compliance review only: Regardless of occupancy load or classification, the requirements of CBC 1108B are not limited to Group H facilities or portions of facilities but do also apply to any facility or portion of facility which is used, either full-time or part time, or can be characterized as hazardous use area.

CBC 1108B
CBC 1108B.1

Accessibility for Group H Occupancies
General

23.7 Hazardous use areas that are used by the public, as customers, clients, or visitors, or are potential places of employment, must be made accessible.

CBC 1108B.6

Accessible facilities

EXCEPTIONS:

- a. In alterations when DSA determines that compliance would create an unreasonable hardship, and when equivalent facilitation is provided.
- b. In existing buildings where DSA determines that, due to legal or physical constraints, compliance with accessibility standards or equivalent facilitation would create an unreasonable hardship.

NOTE:
Jurisdictional findings and determinations for exception (b) are subject to an internal DSA appeals process.

23.8 Provide and indicate accessible toilet and bathing facilities.

CBC 1108B.2

Accessible sanitation facilities

23.9 Provide and indicate an accessible route of travel, including entrances, stairs, ramps, doors, turnstiles, corridors, walks, and sidewalks.

CBC 1108B.3

Accessible routes

23.10 All floor and levels must be made accessible.

CBC 1108B.4

Accessible floors and levels

23.11 Provide and indicate a 36" min wide accessible route of travel and doors with 32" min clearance to all employee work areas.

CBC 1108B.5

Employee work areas

STORAGE AND UTILITY USE AREAS

23.12 Storage and utility use areas that are used by the public as customers, clients, visitors or which are potential places of employment must be made accessible.

CBC 1114B &
CBC 1.9.1.2

Facility accessibility
Division of the State Architect -
Access Compliance - Application

EXCEPTION:

In alterations when DSA determines that compliance would create an unreasonable hardship, and when equivalent facilitation is provided.

23

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 23. MISCELLANEOUS AND OTHER USE AREAS

<p>23.13 Provide and indicate at least one of each type of storage facility to be accessible.</p>	<p>CBC 1125B.1</p>	<p>Storage - General</p>
<p>23.14 Provide and indicate accessible route of travel to accessible storage units.</p>	<p>CBC 1114B.1.2</p>	<p>Accessible route of travel</p>
<p>23.15 Provide and indicate accessible opening hardware at accessible storage units.</p>	<p>CBC 1125B.4</p>	<p>Storage - Hardware</p>
<p>23.16 Provide and indicate accessible toilet and bathing facilities.</p>	<p>CBC 1115B.1</p>	<p>Bathing and toilet facilities – General</p>
<p>23.17 Provide and indicate a 36" min wide accessible route of travel and doors with 32" min clearance to all employee work areas.</p>	<p>CBC 1123B.2</p>	<p>Work stations</p>
<p>23.18 Public tour areas, to the extent that such public tours are conducted through or about a utility facility, or where the public is permitted to walk in such areas, must provide accessibility in those portions of the facility and grounds where this occurs.</p>	<p>CBC 1105B.3.4 #2</p>	<p>Public utility facilities</p>
<p>OUTDOOR USE AREAS</p>		
<p>23.19 For the purpose of Access Compliance review only: Regardless of occupancy load or classification, the requirements of CBC 1132B are not limited to outdoor use areas or facilities but do also apply to any area, facility, or portion of facility which is used, either full-time or part time, or can be characterized as outdoor use area.</p>	<p>CBC 1132B</p>	<p>Outdoor occupancies</p>
<p>23.20 Outdoor use areas, including naturally occurring public accommodations, must be made accessible.</p>	<p>CBC 1132B.1</p>	<p>General</p>
<p>23.21 Parks and recreational areas and facilities must be made accessible.</p> <p>EXCEPTIONS:</p> <ol style="list-style-type: none"> a. In alterations when DSA determines that compliance would create an unreasonable hardship, and when equivalent facilitation is provided. b. Where DSA finds that, in specific areas, the natural environment would be physically damaged by compliance; such areas shall be subject to these regulations only to the extent that such material damage would not occur. c. Automobile access shall not be provided or routes of travel shall not be made accessible when DSA determines that compliance with these regulations would create an unreasonable hardship. 	<p>CBC 1132B.1</p>	<p>General</p>
<p>23.22 Provide and indicate a minimum of 3% but never less than two (2) accessible campsites.</p>	<p>CBC 1132B.2</p>	<p>Parks and recreational areas</p>
<p>23.23 Accessible campsite must be level and provide a firm and stable surface.</p>	<p>CBC 1132B.2 #1</p>	<p>Campsites</p>
	<p>CBC 1124B.1</p>	<p>Ground and floor surfaces - General</p>

23

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 23. MISCELLANEOUS AND OTHER USE AREAS

<p>23.24 Provide and indicate accessible route of travel from accessible campsites to sanitary facilities.</p>	<p>CBC 1132B.2 #1</p>	<p>Campsites</p>
<p>23.25 If permanent sanitary facilities are provided on the site, these must be made accessible to persons using wheelchair.</p>	<p>CBC 1132B.2 #1 & 3</p>	<p>Campsites & Sanitary facilities</p>
<p>23.26 All beaches, picnic areas, day use areas, vista points and similar areas must be made accessible.</p>	<p>CBC 1132B.2 #2</p>	<p>Beaches, picnic areas</p>
<p>23.27 Boat docks, fishing piers, etc. must be made accessible.</p>	<p>CBC 1132B.2 #4</p>	<p>Boat docks</p>
<p>23.28 Trails, paths and nature walk areas, or portions of these, shall permit at least partial use by wheelchair occupants. Hard surface paths or walks shall be provided to serve all buildings and other functional areas.</p>	<p>CBC 1132B.2 #6</p>	<p>Trails and paths</p>
<p>23.29 Provide and indicate running slopes or elevation points and cross slopes.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>23.30 Indicate and specify accessible trail surface material.</p>	<p>CBSC Part 1 4-317(b)</p>	<p>Plans</p>
<p>23.31 Nature trails and other similar educational or informational areas must be accessible to the blind with rope guidelines, raised Arabic numerals and symbols, informational signs and related guide and/or assistance devices.</p>	<p>CBC 1132B.2 #7</p>	<p>Nature trails <u>NOTE:</u> For museums, orientation buildings, visitor centers, office buildings, retail stores, restaurants, etc., and sanitary facilities serving these uses, see Sections 1104B through 1111B, 1115B, and sections listed in Section 1114B.1.1.</p>
<p>23.32 Highway rest areas and similar facilities must be made accessible, including:</p>	<p>CBC 1132B.3</p>	<p>Highway rest areas</p>
<p>1. An accessible sanitary facility for each sex.</p>	<p>CBC 1132B.3.1 #1</p>	<p>Permanent facilities</p>
<p>2. At least one accessible picnic table and one additional table for each 20 tables, or fraction thereof provided.</p>	<p>CBC 1132B.3.1 #2</p>	<p>Permanent facilities</p>
<p>3. Accessible information and display areas.</p>	<p>CBC 1132B.3.1 #3</p>	<p>Permanent facilities</p>
<p>4. Hi-low drinking fountains.</p>	<p>CBC 1132B.3.1 #4</p>	<p>Permanent facilities</p>
<p>5. At least one van-accessible parking space.</p>	<p>CBC 1132B.3.1 #5</p>	<p>Permanent facilities</p>
<p>6. Curb ramps conforming to CBC 1127B.5 must be provided at pedestrian ways where appropriate.</p>	<p>CBC 1132B.3.1 #6</p>	<p>Permanent facilities</p>

23

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 23. MISCELLANEOUS AND OTHER USE AREAS

SWIMMING POOLS

<p>23.33 Swimming pool deck areas shall be accessible.</p>	<p>CBC 1104B.4.3 #4</p>	<p>Participation areas – Swimming pool deck areas</p>
<p>23.34 Swimming pools shall provide a mechanism to assist persons with disabilities in gaining entry into the pool and in exiting from the pool.</p>	<p>CBC 1104B.4.3 #4</p>	<p>Participation areas – Swimming pools</p>
<p>23.35 Provide and indicate swimming pool lift that complies with the following requirements:</p>	<p>CBC 1104B.4.3 #4</p>	<p>Participation areas – Swimming pool deck areas</p>
<p>1. Seat shall be rigid.</p>	<p>CBC 1104B.4.3 #4.1.1</p>	<p>Swimming pool deck areas</p>
<p>2. Seat shall be between 17” and 19” above the deck of the pool, including any cushioned surface.</p>	<p>CBC 1104B.4.3 #4.1.2</p>	<p>Swimming pool deck areas</p>
<p>3. Seat shall have two armrests. The armrest on the side of the seat by which access is gained must be removable or fold clear of the seat.</p>	<p>CBC 1104B.4.3 #4.1.3</p>	<p>Swimming pool deck areas</p>
<p>4. Seat shall have a back support that is at least 12” tall.</p>	<p>CBC 1104B.4.3 #4.1.4</p>	<p>Swimming pool deck areas</p>
<p>5. Seat shall have an occupant restraint for use by the occupant of the seat. Restraint must meet the standards for operable controls per CBC Section 1117B.6 #4 – be operable with one hand and not require tight grasping, pinching, or twisting of the wrist; and not require a force greater than 5 lbf (22.2 N) to activate the controls.</p>	<p>CBC 1104B.4.3 #4.1.5</p>	<p>Swimming pool deck areas</p>
<p>6. Lift shall be capable of unassisted operation from both the deck and water levels.</p>	<p>CBC 1104B.4.3 #4.2</p>	<p>Swimming pool deck areas</p>
<p>7. Lift shall be stable and not permit unintended movement when a person is getting into or out of the seat.</p>	<p>CBC 1104B.4.3 #4.3</p>	<p>Swimming pool deck areas</p>
<p>8. Lift shall be designed to have a live-load capacity of not less than 300 lbs.</p>	<p>CBC 1104B.4.3 #4.4</p>	<p>Swimming pool deck areas</p>
<p>9. Lift shall be noted to be positioned so that if the pool has water of different depths, it will place the operator into water that is at least three feet deep.</p>	<p>CBC 1104B.4.3 #4.5</p>	<p>Swimming pool deck areas</p>
<p>10. Lift shall be able to lower the operator at least 18” below the surface of the water.</p>	<p>CBC 1104B.4.3 #4.6</p>	<p>Swimming pool deck areas</p>

24

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 24. QUALIFIED HISTORICAL BUILDINGS

24.1	Provide documentation that verifies the project is a qualified historical building or property and submit along with plans for review.	CHBC 8-602.2 #2	Alternative provisions
24.2	This checklist applies to every qualified historical building, or property, that is required to provide access to people with disabilities.	CHBC, Chapter 8-6	Accessibility
24.3	Design and construction must preserve the integrity of qualified historical buildings and properties, while providing access to, and use by people with disabilities. Every function or accommodation available to the general public must be accessible either directly or by alternatives as indicated below.	CHBC 8-602	Intent
24.4	Regular code for access for persons with disabilities shall be applied to qualified historical buildings or properties, unless strict compliance with the regular code will threaten or destroy the historical significance, or character-defining features of the building or property.	CHBC 8-602.1 CHBC, Chapter 8-2	Regular code Definitions – Regular code <u>DEFINITION:</u> REGULAR CODE: The adopted regulations that govern the design and construction or alteration of non-historical buildings and properties within the jurisdiction of the enforcing agency.
24.5	If the historical significance or character-defining features are threatened, alternative provisions for access may be applied pursuant to this Checklist, provided the following conditions are met:	CHBC 8-602.2	Alternative provisions
1.	These alternative provisions shall be applied only on an item-by-item or a case-by-case basis.	CHBC 8-602.2 #1	Alternative provisions
2.	Documentation is provided, including meeting minutes or letters, stating the reasons for the application of the alternative provisions. Such documentation shall be retained in the permanent file of the enforcing agency.	CHBC 8-602.2 #2	Alternative provisions
3.	A signature of approval from the applicable enforcement agency shall accompany any alternatives, equal facilitation designs, or exceptions agreed upon.	CHBC 8-602.2 #2	Alternative provisions

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification / Reference or Code Citation

Headings / Comments / Notes & Examples

Check List 24. QUALIFIED HISTORICAL BUILDINGS

24.6 The alternative minimum standards are listed below. All other related standards of regular code are not affected nor exempted.

1. Entry

The entrance alternatives below do not allow exceptions for the requirement of level landings in front of doors, except as provided in Section 8-603.4 (Item 3 below).

- A. Access to any entrance used by the general public and no further than 200' from the primary entrance.
- B. Access at any entrance not used by the general public, but open and unlocked with directional signs at the primary entrance and as close as possible to, but no further than 200' from, the primary entrance.
- C. Accessible entrance shall have a notification system. Where security is a problem, remote monitoring may be used.

2. Doors

Alternatives for doors listed in order of priority are:

- A. Single-leaf door that provides a 30" min clear opening.
- B. Single-leaf door which provides a 29-1/2" min clear opening.
- C. Double door, one leaf of which provides a 29-1/2" min clear opening.
- D. Double doors operable with a power-assist device to provide a 29-1/2" min clear opening when both doors are in the open position.

Exception: Door alternatives do not apply to alteration of commercial facilities and places of public accommodation (Title III entities).

3. Power-assisted Doors

A power-assisted door or doors may be considered an equivalent alternative to level landings, strike side clearance, and door-opening forces required by the regular code.

4. Toilet Rooms

In lieu of separate-gender toilet facilities as required in the regular code, an accessible unisex toilet facility may be designated.

5. Exterior and Interior Ramps and Lifts

Alternatives for ramps and lifts, listed in order of priority, are:

- A. A lift or a ramp of greater than standard slope, but no greater than 1:10, for horizontal distances not to exceed 5 feet. Signs shall be posted at upper and lower levels to indicate steepness of the slope.
- B. Access by ramps of 1:6 slope for horizontal distance not to exceed 13". Signs shall be posted at upper and lower levels to indicate steepness of the slope.

CHBC 8-603

Alternatives

CHBC 8-603.2

Alternatives – Entry

CHBC 8-603.3

Alternatives – Doors

CHBC 8-603.3 #1

Alternatives – Doors

CHBC 8-603.3 #2

Alternatives – Doors

CHBC 8-603.3 #3

Alternatives – Doors

CHBC 8-603.3 #4

Alternatives – Doors

CHBC 8-603.4

Alternatives – Power-assisted doors

CHBC 8-603.5

Alternatives – Toilet rooms

CHBC 8-603.6

Alternatives – Exterior and interior ramps and lifts

CHBC 8-603.6 #1

Alternatives – Exterior and interior ramps and lifts

CHBC 8-603.6 #2

Alternatives – Exterior and interior ramps and lifts

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 24. QUALIFIED HISTORICAL BUILDINGS

6. Equivalent Facilitation

Use of other designs and technologies, or deviation from particular technical and scoping requirements, are permitted if the application of the alternative provisions contained in Section 8-603 would threaten or destroy the historical significance or character-defining features of the qualified historical building or property.

- A. Such alternatives shall be applied only on an item-by-item or a case-by-case basis.
- B. Access provided by experiences, services, functions, materials and resources through methods including, but not limited to, maps, plans, videos, virtual reality, and related equipment, at accessible levels. The alternative design and/or technologies used will provide substantially equivalent or greater accessibility to, and usability of, the facility.
- C. The official charged with the enforcement of the standards shall document the reasons for the application of the design and/or technologies and their effect on the historical significance or character-defining features. Such documentation shall be in accordance with Section 8-602.2, Item 2, and shall include the opinion and comments of state or local accessibility officials, and the opinion and comments of representative local groups of people with disabilities. Such documentation shall be retained in the permanent file of the enforcing agency. Copies of the required documentation should be available at the facility upon request.

Note: For commercial facilities and places of public accommodation (Title III entities).

Equivalent facilitation for an element of a building or property when applied as a waiver of an ADA accessibility requirement will not be entitled to the USDOJ certification of the code as rebuttable evidence of compliance for that element.

CHBC 8-604

Equivalent facilitation

CHBC 8-604 #1

Equivalent facilitation

CHBC 8-604 #2

Equivalent facilitation

CHBC 8-604 #3

Equivalent facilitation

25

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 25. SPECIFICATIONS

25.1 For additional scoping requirements see also applicable **DSA-AC Checklists 1 through 24.**

DIVISION 2, SITE WORK

25.2 Specify concrete paving and concrete finishes along accessible routes of travel to be at least as slip-resistant as that described as a medium salted finish for slopes of less than 6%, and slip-resistant at slopes of 6% or greater

CBC 1133B.7.1

Continuous surface

25.3 Specify all gates, including ticket gates, to meet all applicable specifications for doors. Coordinate and specify height and type of hardware with door requirements.

CBC 1133B.1.1.1.4

Gates

25.4 Specify bottom 10" of gates to have a smooth uninterrupted surface.

CBC 1133B.2.6

Smooth surface

DIVISION 8, DOORS & STOREFRONTS

25.5 Specify thresholds in the accessible route of travel.

CBC 1133B.2.4.1

Thresholds

25.6 Specify closer-effort to be 5 lbf at exterior doors and interior doors.

CBC 1133B.2.5

Door opening force

EXCEPTION: When, at a single location, one of every 8 exterior door leafs, or fraction of 8, is a powered door, other exterior doors at the same location, serving the same interior space, may have a maximum opening force of 8.5 lbf. The powered leaf(s) shall be located closest to the accessible route.

CBC 1133B.2.5, Ex 2

Door opening force

25.7 Delete note that states that fire doors or rated doors can have up to 15 lbs operating effort, or provide the following note: "The Authority having Jurisdiction, may increase the maximum effort to operate fire doors to achieve positive latching, but not to exceed 15 lbs max."

CBC 1133B.2.5

Door opening force

25.8 Specify door closer and closer delay time.

CBC 1133B.2.5.1

Door closer

25.9 Where flush bolts occur in the accessible route of travel, specify accessible flush bolt (automatic).

CBC 1133B.2.5.2

Door hardware

25.10 Specify hand-activated hardware between 30" to 44" AFF; lever-type hardware, panic bars, push-pull activating or U-shaped handles; lever handle for thumb turn dead bolt.

CBC 1133B.2.5.2

Door hardware

25.11 Provide cut sheets for all door operating hardware at back check appointment.

--

25.12 Provide cut sheets for darkroom doors.

--

25

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 25. SPECIFICATIONS

DIVISION 9, FINISHES

25.13 Specify tile flooring to be slip-resistant.

CBC 1124B.1

Ground & floor surfaces –

25.14 Specify resilient flooring to be slip-resistant.

CBC 1124B.1

Ground & floor surfaces

25.15 Specify carpet to be securely attached to floor, firm or no pad, 1/2" max pile height, and level loop or cut pile.

CBC 1124B.3

Carpet

25.16 Specify anchorage at recessed doormats.

CBC 1133B.1.1.1.3

Recessed doormats

DIVISION 10, SPECIALTIES

25.17 Specify signage to be in compliance with 1114B, 1115B.5 and 1117B.5. Also see Checklist 17.

--

25.18 Specify signage font, size, color and color of background.

CBC 1117B.5

Signs & identification

25.19 Specify toilet compartment doors to have automatic-closing device, U-shaped handles below latch, and flip-over or sliding latch.

CBC 1115B.3.1 #4.5

Compartment doors

25.20 Specify coat hook to be installed at 48" max AFF.

CBC 1118B.5

Forward reach

25.21 Specify toilet tissue dispensers to be continuous flow type.

CBC 1115B.8.4

Toilet tissue dispensers

25.22 Specify grab bar length and diameter.

CBC 1115B.7

Grab bars, tub and shower seats

25.23 Provide cut sheets of all toilet room accessories at back check appointment.

--

DIVISION 11, EQUIPMENT

25.24 Specify accessible fume hood, eyewash, deluge shower, other specialized equipment, etc.

--

25.25 Provide cut sheets for specialized equipment used at back check appointment.

--

25.26 Specify clear knee space at specialized equipment and/or accessible reach ranges.

CBC 1118B.4,
CBC 1118B.5 &
CBC 1118B.6

Clear floor or ground space
Forward reach
Side reach

25.27 Specify food service aisle to be 36" min wide and tray slides to be mounted at 34" max AFF.

CBC 1104B.5 #5

Food service aisles

25.28 Specify walk-in coolers and freezers to have accessible entry and exit door hardware, and level maneuvering clearances at the exterior side.

CBC 1133B.2.4.2
CBC 1133B.2.5.2

Maneuvering clearances at doors
Hand-activated door opening hardware

DIVISION 12, FURNISHINGS

25.29 Specify U-pulls at cabinets/casework for accessible storage.

CBC 1125B.4

Hardware

25

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 25. SPECIFICATIONS

25.30	Specify access signage at bleachers.	CBC 1104B.3.4 #1	Wheelchair spaces
25.31	Provide code references for accessible seating for persons using wheelchairs and companion.	--	
25.32	Specify 1% or at least one accessible locker, including shelf and coat-hook height and signage.	CBC 1115B.8.5	Lockers
DIVISION 14, CONVEYING SYSTEMS			
25.33	Refer to Section 1116B.1 for elevators.	CBC 1116B.1	Elevators
25.34	Refer to Section 1116B.2 for platform (wheelchair) lifts.	CBC 1116B.2	Platform (wheelchair) lifts
25.35	Specify lift platform safety sensors to prevent downward travel if obstruction is encountered.	CCR Title 8	
25.36	Specify back-up battery when lift used for platform is without direct accessible means of egress.	CBC 1116B.2.5	Platform (wheelchair) lifts
25.37	Specify all elevator/lift signage.	CBC 1117B.5	Signs & identification
DIVISION 15, MECHANICAL/PLUMBING			
25.38	Coordinate height of accessible fixtures with those indicated in construction drawings	--	
25.39	Provide cut sheets for water closet, urinal, lavatories, drinking fountain, showers, etc	--	
25.40	Specify lever-operated faucets. Push-type and electronically controlled mechanisms are acceptable (controls to be operable with one hand; no tight grasping, pinching or twisting of the wrist).	CBC 1115B.4.3 #1	Accessible lavatories
25.41	Specify force to activate controls to be no greater than 5 lbf.	CBC 1115B.4.3 #1	Accessible lavatories
25.42	Specify faucet to remain open for at least 10 seconds when self-closing valves are used.	CBC 1115B.4.3 #1	Accessible lavatories
25.43	Specify insulation or cover for hot water and drainpipes under accessible lavatories and sinks.	CBC 1115B.4.3 #4 CBC 1117B.9 #2	Accessible lavatories Accessible sinks
25.44	Specify accessible sinks to be 6 1/2" max deep.	CBC 1117B.9 #2	Accessible sinks
DIVISION 16, ELECTRICAL			
25.45	Specify permanently installed assistive listening system for assembly use areas with fixed seating.	CBC 1104B.2 #6	ALS – Permanent and portable systems
25.46	Specify portable assistive listening system for assembly use areas with non-fixed seating.	CBC 1104B.2 #6 CBC 1104B.2 #2	ALS – Permanent and portable systems ALS – Types

25

Project designer (PD) shall address the following marked or circled items, and any additional plan review comments on drawings and specifications before scheduling a back check appointment for access compliance (AC). Any questions or points of disagreement must be resolved prior to back check by fax to plan reviewer (PR).

Justification /
Reference
or Code Citation

Headings / Comments / Notes
& Examples

Check List 25. SPECIFICATIONS

25.47 Specify type of assistive listening system.

25.48 Specify number of receivers and number of signs.

25.49 Specify electrical controls and switches intended to be used by the occupant of the room or area to be located no more than 48" measured from the top of the outlet box and no less than 15" measured from the bottom of the outlet box to the level of the finish floor or working platform.

25.50 Specify electrical receptacle outlets on branch circuits of 30 amperes or less and communication system receptacles to be located no more than 48" measured from the top of the receptacle outlet box or receptacle housing and no less than 15" measured from the bottom of the receptacle outlet box or receptacle housing to the level of the finish floor or working platform.

CBC 1104B.2 #2

CBC 1117B.6 #5.1

CBC 1117B.6 #5.2

ALS – Types

Electrical switches

Electrical receptacle outlets

DSA Access Compliance Code Appeals

DSA — 2011 CALIFORNIA ACCESS COMPLIANCE REFERENCE MANUAL CODE APPEALS

Introduction

Section 6 – Code Appeals: When accessibility code interpretation or code application disagreements occur in DSA's regional offices, a Code Appeal Process (CAP) is available. CAP (formerly RIP) is a formal method to resolve project-specific disputes by the issuance of official interpretations by DSA. This section contains selected DSA code appeal determinations.

DSA Access Compliance Code Appeals

When accessibility code interpretation or code application disagreements occur in DSA's regional offices, a Code Appeal Process (CAP) is available. CAP (formerly RIP or Rapid Interpretation Process) is a formal method to resolve project-specific disputes by the issuance of official interpretations by DSA. This section contains selected DSA code appeal determinations.

Interpretation/ CAP Number	Subject	Issue Date
6-06 DSA/AC	Multistory Fitness Center	10-13-06
7-06 DSA/AC	New High School Press Box	10-23-06
8-06 DSA/AC	Sanitary Facilities in Alterations Projects	11-01-06
1-07 DSA/AC	Alterations: Hardwood Floor & Concrete Walkways	02-05-07
2-07 DSA/AC	School Modernization: Children's Heights	02-08-07
6-07 DSA/AC	Alterations: Removal of Roof Lights & Replacement of Skylights	05-06-07
8-07 DSA/AC	Student Housing Facility: Door Signal	06-01-07
4-08 DSA/AC	Middle School Tables & Counters: Knee Clearance	04-18-08
5-08 DSA/AC	Ramp Handrails at 45-Degree Angle to Ramp Run	05-06-08
HQ 01-2010AC04-01 HQ 02-2010AC04-02	Suggested Heights for Children	02-17-10



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 6-06 DSA/AC
Subject: Multistory Fitness Center
DSA Application Number:
Code Edition: 2001 CBC
Issue Date: 10-13-2006

QUESTION:

Does the installation of the exterior elevator, as shown in this design, comply with provisions of CBC 1114B.1.2 which indicate that the accessible route shall, to the maximum extent feasible, coincide with the route for the general public?

RESPONSE:

For the newly constructed multistory fitness center (Building 24), the installation of the exterior elevator, as shown in this design, does not comply with the provisions of CBC 1114B.1.2.

The accessible route does not coincide with the route for the general public, to the maximum extent feasible. If an interior route for the general public is provided, then an interior route accessible to persons with disabilities shall also be provided.

BACKGROUND:

DSA application numbers 01-106990 & 01-106898 are for two projects at the XXXXX College located in XXXXX, California. The first project (XX-XXXXXX) is the construction of a new 2 story fitness center (identified as Building 24), containing less than 10,000 square feet per floor. The second project (XX-XXXXXX) is the construction of a track and field, bleachers, softball field, field lighting, portables, a concession building, modernization of a two story gymnasium, and an exterior elevator. The combined construction costs for both projects total approximately 7.5 million dollars. The DSA regional office previously approved both projects, and is now questioning whether the XX-XXXXXX project (Building 24 fitness center) complies with the

California Building Code. The new two story fitness center (Building 24) contains an interior stair located approximately in the center of the building connecting the first and second stories.

An accessible route is provided to both stories via a new freestanding exterior elevator located in a courtyard adjacent to the existing gymnasium (identified as Building 22), utilizing a series of exterior walks and exterior elevated walkways to connect to the fitness center. The elevator appears to provide an accessible route connecting both stories of the gymnasium, serves to provide an accessible route to the new athletic fields which are approximately at the same level as the second story of both buildings, and also provides an accessible route connecting both stories of the fitness center (Building 24).

Upon the DSA regional office's determination that the design of the accessible routes for Building 24 did not meet the minimum building code requirement, the college retained the services of XXXXX XXXXX XXXXX, Inc. to complete an independent review of the disputed accessibility issues. XXXXX XXXXX XXXXX, Inc. provides compliance services for businesses and public entities to enhance or achieve compliance with the Americans with Disabilities Act and related legislation.

The DSA regional office asserts non-compliance with CBC Section 1114B.1.2, which requires the accessible route to coincide with the route for the general public, to the maximum extent feasible. The basis for this determination is that the new two story fitness center (Building 24) contains an interior circulation stair connecting both stories; however, the accessible route requires the occupant to leave the building, travel to a separate outside structure, take an elevator, travel back to the building, and then re-enter it. The route the general public can take at the centrally located interior stairs, to travel from one story to the other, is approximately 25 feet. The accessible route to travel to these same points utilizes exterior walks, the exterior elevator, and exterior elevated walkways appear to exceed 300 feet.

The applicant relies on an independent opinion issued by XXXXX XXXXX XXXXX, Inc. dated September 5, 2006 to support their position that this design is compliant. The opinion indicates several points as follows:

- (1) The use of the exterior elevator provides greater accessibility for the physical education programs, when viewed in their entirety,
- (2) The elevator will provide the most direct route.
- (3) Stairs are not to be considered in a discussion of comparability.
- (4) The route for the general public does coincide with the route of the exterior elevator, in that the exterior elevator is the route for the general public, both with and without disabilities.
- (5) The exterior elevator provides the most direct route between adjacent buildings and programs.
- (6) The floor area of the fitness center (Building 24) is less than 10,000 square feet, and therefore does not have to comply with the maximum distance of 200 feet from circulation stairs to an accessible elevator (CBC 1003B.1).

ANALYSIS:

CBC Section 1114B.1.2 indicates the accessible route shall, to the maximum extent feasible, coincide with the route for the general public. The ordinary dictionary meaning of *coincide* is *to*

occupy the same place in space; to occur at the same time or occupy the same period of time; to be identical or correspond in nature, character or function.

Regarding XXXXX XXXXX XXXXX, Inc. point (1), DSA agrees that the installation of the exterior elevator provides greater accessibility for certain physical education programs; however, there is no challenge or assertion of non-compliance related to the installation of this elevator.

Regarding XXXXX XXXXX XXXXX, Inc. point (2), DSA agrees that the elevator will provide the most direct route for some areas, but disagrees that it provides the most direct route for Building 24 (the newly constructed two story fitness center).

Regarding XXXXX XXXXX XXXXX, Inc. point (3), DSA disagrees that the interior circulation route (stairs) are not to be considered in an examination of comparability when assessing whether the accessible route, to the maximum extent feasible, coincides with the route for the general public.

Regarding XXXXX XXXXX XXXXX, Inc. point (4), DSA disagrees that the exterior elevator is the route for the general public for Building 24 when establishing coincidence for accessible routes. The accessible route of the exterior elevator does not coincide with the interior circulation stairs connecting stories for the general public, to the maximum extent feasible.

Regarding XXXXX XXXXX XXXXX, Inc. point (5), DSA disagrees that the exterior elevator provides the most direct route between adjacent buildings and program(s) insofar as the new construction of the multistory fitness center (Building 24), and the program(s) contained within it, when considering the coinciding standard for routing.

Regarding XXXXX XXXXX XXXXX, Inc. point (6) DSA would like to point out the intent of CBC 1003B.1 with regard to elevator or ramp placement. CBC 1003B.1 contains a provision limiting the travel distance from each stair to each elevator (or ramp) to 200 feet maximum for buildings having floors with over 10,000 square feet. Although it can certainly be applied to buildings that have only one stair, the primary reason for this code change that appeared in the 2001 CBC is to address *larger* buildings that have multiple interior stairs that are used for general circulation, and to specifically address when more than one accessible elevator shall be installed by indicating a maximum distance relationship of elevator locations to stair locations in these larger buildings. The effect of this code change does not necessarily trump the requirement that accessible routes shall, to the maximum extent feasible, coincide with the route for the general public in buildings that are 10,000 square feet or less. In fact, one could easily assert that since a 200 foot limit is for buildings of over 10,000 square feet per floor, then something actually less than 200 feet would be appropriate in smaller buildings. In other words, it could simply be considered more feasible for the distance between routes to coincide *more* closely in small buildings, than in large buildings, however the code provides no specificity in this regard.

Nevertheless, the point to be made here is that the concept of the accessible route *coinciding with the route for the general public* does not necessarily mean the *distance* to be traveled is the only consideration. As the definition cited above indicates, *coincide* also means to *correspond in nature, character or function*. Therefore, it could be said that distance, character, and function either considered together or separately is what generally establishes coincidence, and the further that the two routes begin to depart from one another, insofar as these three basic meanings, the more difficult it is to concur that this performance standard has been met.

In this particular case, the general public merely walks up a centrally located open 25 foot long interior stair. However, persons with disabilities actually have to leave the building, travel to a separate outside structure, take an elevator, travel back to the building, and then re-enter it. This point forms the basis for our conclusion.

It is already established that elements such as ramps and elevators or other circulation devices shall be placed to minimize the distance which wheelchair users and other persons who cannot negotiate steps or stairs may have to travel compared to the general public. In lending further support to this decision we look to the United States of America v. Penn's Landing Partners and Brennan Beer Gorman¹ in the United States District Court for the Eastern District of Pennsylvania. In Civil Action 02-7463, within the Consent Order and Final Judgment, it is clear that the route for the general public is, in fact, considered the non-accessible route. When non-accessible routes exist (such as stairs), that is the route used in establishing whether the accessible route coincides with the route for the general public. In the Exhibit 1 Violations List the following items are noted (emphasis added):

Access to the Terrace from the Restaurant.

11. [(a)] *The restaurant has **direct access to the terrace (with dining tables) via a flight of interior stairs. The accessible route does not coincide with the route for the general public. Individuals who are unable to negotiate the stairs must leave the restaurant to access the terrace** via an exterior ramp at the front of the hotel. Standard section 4.1.3(1), in conjunction with standard Sections 4.3.1 and 4.3, requires that "the accessible route shall, to the maximum extent feasible; coincide with the route for the general public." The restaurant cannot have sunken seating sections without an accessible route to them. (Standard 5.4)*

(b) *Boardwalk to Main Hotel and Restaurant Front Entries on Dock St. - **The accessible route from the public sidewalk (Boardwalk) to the Restaurant entry does not coincide with the more direct stair route the general public can take** from the Boardwalk. The accessible route requires wheelchair users arriving from the northern approach to the Boardwalk to use a lengthy route of Boardwalk, switchback ramp and walkway that is far longer than the direct route via stairs that the public can use. The general public can use the stairs to the north of the switchback ramp to the main entry level. (Standard 4.3.2)*

(c) *Boardwalk to Restaurant Terrace - **There is no accessible route via ramp or elevator between the Terrace and the Boardwalk. The obvious route for the general public between the Terrace and Boardwalk (5'-8" level change) is the stairs** located in the middle of the length of the Terrace. The route does not coincide to the maximum extent possible with the route the general public can take from the Boardwalk. (Standard 4.3.2)*

(d) *Boardwalk from the Garage - **The route does not coincide to the maximum extent feasible with the route the general public can take from the Garage to the Boardwalk. (Standard 4.3.2) The general public using the garage can exit the garage directly to the Boardwalk as pedestrians from either the first floor or basement floor via one flight of stairs** down or up respectively. Additionally, there are no accessible exits from the Garage nor an accessible route to an exit. (Standard 4.1.3(8)(ii) and 4.6.3) Accessible pairs of parking stalls are located adjacent to the elevators on the Basement floor and floors 2-5. The*

first floor accessible stalls are located adjacent to the opposite (north) end vehicular entry to the garage (Walnut St.) Disabled customers going to the Boardwalk from accessible stalls would have to traverse the full length of the sloped garage, and exit via the sloped vehicular exit lane. A vehicular lane is not an accessible route, except at a crosswalk.

*(e) Access from public transportation - Columbus St. sidewalk to Dock St Front Entry - **The accessible route from the sidewalk and public transportation to the entry does not coincide to the maximum extent feasible with the route the general public can take. (Standard 4.3.2) The accessible route shown from the sidewalk on Columbus St. requires wheelchair users to go around the south, east, and half the north sides of the courtyard driveway, rather than the more direct route from the sidewalk on the north side of the courtyard. The north side from the sidewalk appears to be a non-compliant ramp slope (but not designed as a ramp with handrails), and the walk lacks curb ramps enabling a wheelchair user to cross the valet driveway opening.***

In citing this case within *Enforcing the ADA: A Status Report from the Department of Justice*², July–September 2002, the Department of Justice indicated that the U.S. Attorney for the Eastern District of Pennsylvania negotiated a consent decree with Penn's Landing Partners, the owner and developer of the Hyatt Regency Hotel at Penn's Landing in Philadelphia, and the architectural firm of Brennan Beer Gorman that resolves violations of the ADA's requirements for new construction. Similar to the circumstances being considered for this interpretation, the violations were identified in a compliance review while the hotel was under construction. Among the design changes agreed to by the parties were, among others, the following:

- The accessible route from the terrace to the restaurant **would approximate in length and convenience the route provided by steps to the general public;**
- To the extent feasible, accessible routes between various elements of the hotel and the adjacent public ways, including the promenade along the river, would coincide with those for the general public, and there would be improved accessibility in employee work areas;

In addition, the developer paid a civil penalty of \$15,000 and Brennan Beer Gorman, the architectural firm, paid a civil penalty of \$25,000. Further, Brennan has agreed to provide additional ADA training to its architects specializing in hotel design.

¹<http://www.usdoj.gov/crt/ada/pennland.htm>

²<http://www.usdoj.gov/crt/ada/julsep02.htm>

Approved for distribution 10-13-06

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca.gov



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 7-06 DSA/AC

Subject: New High School Press Box

DSA Application Number:

Code Edition: 2001 CBC

Issue Date: 10-23-2006

QUESTION:

Is an accessible route required to a one story elevated press box that is less than 500 square feet in size?

RESPONSE:

Yes, an accessible route is required to a one story elevated press box that is less than 500 square feet in size.

BACKGROUND:

DSA application number XX-XXXXXX is for a new high school in XXXXX, California that includes bleachers with an elevated press box at a football/soccer field. The applicant wishes to utilize an exception contained in the *updated* ADA Accessibility Guidelines for Buildings and Facilities (ADAAG, 2004) which provides specific exception to the accessible route requirement for certain press boxes located in bleachers.

ANALYSIS:

In July 2004, the US Access Board completed a comprehensive *update* of ADAAG, along with an update of its guidelines for federally funded facilities covered by the Architectural Barriers Act (ABA). These new guidelines will *eventually* serve as the basis for updated standards that will be used to enforce the design requirements of the ADA and the ABA once they are adopted. However, they have not yet been adopted and until they are, the original ADA standards remain in effect.

Even when the updated ADAAG standards are adopted, any provisions providing exception to accessibility requirements would also have to be adopted by the California Building Standards Commission in order for them to be effective in California.

Currently, the CBC exceptions for accessibility are contained in CBC 1103B.1 & 1123B.2. These two sections provide accessibility exceptions for floors or portions of floors not customarily occupied, including, but not limited to, non-occupiable or employee spaces accessed only by ladders, catwalks, crawl spaces, very narrow passageways or freight (non-passenger) elevators, and frequented only by service personnel for repair or maintenance purposes; such spaces as elevator pits and elevator penthouses, piping and equipment catwalks, machinery rooms, in addition to observation galleries used primarily for security purposes. A school press box serving an athletic field for a public school does not qualify for any of the exceptions stated above. CBC 1133B.1.1.1.1 indicates that all entrances to buildings and facilities shall be made accessible to persons with disabilities. The CBC does not provide a waiver for this requirement in new construction.

Since this facility is not a multistory building, an elevator or ramp is not necessarily required, however an accessible route is. As indicated in CBC 1116B.2.3, a platform wheelchair lift may be provided as part of an accessible route to provide access to incidental occupiable spaces and rooms which are not open to the general public and which house no more than five persons. A press box of less than 250 square feet could be considered incidentally occupied, that is, it is generally only occupied during sporting events, and that due to its small size, it could be considered to house no more than 5 persons. Therefore, a ramp, elevator, platform wheelchair lift, or any combination thereof, could be utilized to provide an accessible route. Further, since the project may qualify for the use of a platform wheelchair lift, it would be possible to consider a *limited use elevator* as an alternative to a platform wheelchair lift.

Further, under Title II of the ADA, public entities must ensure that all newly constructed buildings and facilities are free of architectural and communication barriers that restrict access or use by individuals with disabilities. Public entities may choose between two technical standards for accessible design: The current Uniform Federal Accessibility Standard (UFAS), established under the Architectural Barriers Act, or the current Americans with Disability Act Accessibility Guidelines, adopted by the Department of Justice for places of public accommodation and commercial facilities covered by title III of the ADA. However, it should be acknowledged that the elevator exemption allowed for small multistory buildings under the current ADAAG, does not apply to public entities covered by Title II.

In lending further support to this decision, we look to a letter¹ sent to a member of the United States House of Representatives from the United States Department of Justice, Civil Rights Division. The letter directly discusses the construction of a press box constructed for a public high school, and in relation to compliance with the ADA, indicates the following: "...we infer that his school has chosen to design a traditional press box that is located above the viewing stands with an entrance well-above ground level. This design choice is permitted by the ADA, but it is not compelled by it." If the "school wants to comply with the ADA, but to avoid the cost of an elevator, the school should explore alternative press box designs." The letter is repeated below.

¹<http://www.usdoj.gov/crt/foia/tal769.htm>

August 5, 1998

The Honorable Gil Gutknecht
Member, U.S. House of Representatives
1530 Greenview Drive, SW
Suite 108
Rochester, Minnesota 55902

Dear Congressman Gutknecht:

I am responding to your inquiry on behalf of your constituent, xxxxxx, who wrote to you concerning the accessibility requirements applicable to a high school stadium press box.

The Federal law that applies to this situation is the Americans with Disabilities Act of 1990 (ADA), which prohibits discrimination on the basis of disability by public entities, including public school systems. The Federal regulations implementing the ADA, which took effect on January 26, 1992, require all new construction to be readily accessible to, and usable by, people with disabilities. A public school system may meet this requirement by complying with either the ADA Standards for Accessible Design, 28 C.F.R. pt. 36, App. A, or the Uniform Federal Accessibility Standards, 41 C.F.R. pt. 101-19.6. In addition to this Federal requirement, most State building codes now contain accessibility requirements that are similar to those implemented by the ADA. Because Mr. xxxxxx letter specifically mentions a law that became effective in January 1996, we infer that the action affecting him was initiated under the State building code.

The ADA does not contain provisions that specifically address the construction of "press boxes." The ADA merely requires that all new construction by covered entities must comply with the applicable requirements of the regulations. In general, these requirements would include an accessible route to an accessible facility and an accessible entrance. In a multi-story facility, an accessible means of vertical access must be provided to connect all levels. Although an elevator is the most common means of providing vertical access, ramps and (in certain-limited circumstances) platform lifts may also be used. See, § 4.1.3.(5), Exception 4, of the enclosed ADA Standards. If the press box is not part of a multi-story facility, a ramp may be used to provide access to the entrance. The ADA does not provide for a waiver of these new construction requirements.

Mr. xxxxxx did not describe the press box in his letter to you, but, because he specifically complained that he is being required to install an elevator to provide access, we infer that his school has chosen to design a traditional press box that is located above the viewing stands with an entrance well-above ground level. **This design choice is permitted by the ADA, but it is not compelled by it. Therefore, if Mr. xxxxxx school wants to comply with the ADA, but to avoid the cost of an elevator, the school should explore alternative press box designs.**

Mr. xxxxxx should also note that the ADA does not preempt the authority of the State of Minnesota to impose more stringent requirements on construction through its building code process. The interpretation and application of the State's accessibility code is a matter that Mr. xxxxxx must resolve with State code officials.

For your information, we note that the ADA Standards are based on the ADA Accessibility Guidelines (ADAAG) developed by the United States Architectural and Transportation Barriers Compliance Board (Access Board). The Access Board is now engaged in a total review of these accessibility guidelines. The Access Board anticipates that the revised guidelines should be published as a proposed rule before the end of this year.

If Mr. xxxxxx wants to address this issue with the Access Board, he may write to:

Thurman M. Davis, Chair
U.S. Architectural and Transportation
Barriers Compliance Board
1331 F Street, N.W.
Washington, DC 20004-1111

Copies of the Department's regulations implementing title II and title III of the ADA are enclosed for your reference. The ADA Standards for Accessible Design are published as Appendix A to the title III regulation.

I hope that this information is helpful to you in responding to your constituent.

Sincerely,

Bill Lann Lee
Acting Assistant Attorney General
Civil Rights Division

Approved for distribution 10-23-2006

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca.gov



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 8-06 DSA/AC

Subject: Sanitary Facilities in Alterations Projects

DSA Application Number:

Code Edition: 2001 CBC

Issue Date: 11-1-2006

QUESTION :

1. When evaluating an alteration to an existing site that may have several accessible and non-accessible sanitary facilities, what is considered to be a reasonable distance per CBC 1115B, Exception, Item 1?
2. Does DSA have the authority to make this determination?

RESPONSE 1:

1. The building code does not provide a specific distance in determining what is or is not a reasonable distance. Therefore it is an interpretational issue to be determined by DSA on a case-by-case basis, depending on the various circumstances related to the project.
2. Yes, DSA has the authority to make this determination.

BACKGROUND:

DSA application number XX-XXXXXX & XX-XXXXXX is for the placement of new relocatable buildings at two existing high schools. The applicant objects to DSA's determination that the accessible sanitary facilities are not within a reasonable distance of the non-accessible sanitary facilities.

Further, the applicant contends several points as follows:

- (1) The regional office's determination is not consistent with CBC Section 1115B.2
- (2) The language in the code does not specifically specify a standard for *close proximity*, and therefore the distance should be consistent with other sections of the building code.
- (3) The potential cost mitigation to comply with an arbitrary standard is prohibitive.
- (4) Proximity should be appropriate to the site itself.

ANALYSIS:**Regarding the applicant's point (1), DSA believes that the determination is not relevant to CBC Section 1115B.2.**

CBC 1115B.2 indicates that where separate facilities are provided for persons without disabilities of each sex, separate facilities shall be provided for persons with disabilities of each sex also. Where unisex facilities are provided for persons without disabilities, at least one unisex facility shall be provided for persons with disabilities within close proximity to the non-accessible facility.

The first part of CBC 1115B.2 is addressing where separate facilities for each sex are provided, and extends this same for provision for persons with disabilities. This is generally intended to prevent the construction of non-accessible gender separated restrooms with an accessible unisex restroom. It is not to be construed to allow the construction of non-accessible sanitary facilities. The second part of 1115B.2 is addressing where unisex restrooms are provided, and extends this same for provision, in close proximity, for persons with disabilities.

In simple terms, this section is indicating that when you provide separate facilities, provide separate accessible facilities; and when you provide unisex facilities, provide accessible unisex facilities in close proximity.

DSA does not believe that 1115B.2 is relevant to the question. For the issue under consideration, it is more appropriate to look toward CBC 1115B.1 rather than reviewing this under 1115B.2, which is a section that mainly provides the standard for equitable separated and equitable unisex sanitary facilities, when they are provided. Since this issue does not concern gender separation or unisex provisions, for the purposes of this interpretation, the applicable standard for review will be CBC 1115B.1, and employ the use of the term reasonable distance.

CBC 1115B.1 indicates that sanitary facilities that serve buildings, facilities or portions of buildings or facilities that are required by the standards to be accessible to persons with disabilities, shall conform to certain requirements. The exception to this section indicates that in existing buildings or facilities, when the *enforcing agency* determines that compliance with any building standard under this section would create an unreasonable hardship, an exception to such standard shall be granted when equivalent facilitation is provided.

When equivalent facilitation is used, *all sanitary facilities are not required to comply with the building standards when the enforcing agency determines that sanitary facilities are accessible to and usable by persons with disabilities within a reasonable distance of accessible areas.*

Section 1115B.1 directly relates to the issue under consideration, in that it establishes a clear performance obligation in order to ensure that reasonable distances to sanitary facilities are provided. In this case, this section contemplates conditions where multiple existing sanitary facility locations are contained within an existing building or facility, and under a determination of an unreasonable hardship, allows an exception to the requirement of upgrading all the (multiple) sanitary facilities, provided the reasonable distance standard is maintained.

When taken in concert with CBC Section 1114B.1.2, which requires accessible routes of travel to coincide with the routes provided for the general public, the obligation becomes easier to understand, and therefore easier to interpret.

Regarding the applicant's point (2), DSA agrees that the language in the code does not specifically specify a standard for *reasonable distance*. DSA agrees that it is the school district that is legally responsible for accessibility compliance. DSA disagrees that the interpretation of the term *reasonable distance* solely rests with the school district merely because a specific distance is not indicated. DSA disagrees that the *reasonable distance* should be consistent with (compared to) other sections of the code, such as half the distance of the school property (similar to exit separation in CBC Chapter 10).

Pursuant to Government Code 4453(a), DSA is the entity that has enforcement authority over this project to ensure compliance with the regulations contained in Title 24, California Code of Regulations.

Pursuant to Education Code 17308(d), DSA has the authority to render interpretations of the regulations it is charged to enforce, for those projects under its jurisdictional authority as indicated in Government Code Section 4454(a), typically California public schools and any project utilizing state funding.

Pursuant to Government Code 4454(a), DSA must issue written approval stating that the plans and specifications for the project comply with the applicable regulations, and contained within those regulations is the performance standard for *reasonable distance* for persons with disabilities. The fact that a performance standard is not necessarily prescriptive is no reason to shift the determination of compliance with that performance standard away from the entity that has the legal authority to make such a determination. In this case, a determination by the DSA regional office has been made that this performance standard has not been met.

Regarding the assertion that *reasonable distance* could be considered half the distance between opposite corners of the school property, DSA believes that concept to be arbitrary, unrelated, and in a majority of cases would actually result in a violation of the building code, especially at larger school sites. The more appropriate measure of what a *reasonable distance* is would be to incorporate into the analysis guidance which is already contained in the accessibility standards in the state building code, and additionally, under similar standards contained in federal law.

That guidance is the routing standard taken from current federal regulation and subsequently incorporated into CBC Section 1114B.2.1. This routing standard serves to form a substantial basis for equal opportunity and equal benefit, two of the fundamentals concepts in designing buildings and facilities for persons with disabilities.

CBC Section 1114B.1.2 indicates the accessible route shall, to the maximum extent feasible, coincide with the route for the general public. The ordinary dictionary meaning of *coincide* is *to*

occupy the same place in space; to occur at the same time or occupy the same period of time; to be identical or correspond in nature, character or function.

Therefore interpreting *reasonable distance* must incorporate a comparison between the route provided for the general public, and the route provided for persons with disabilities. If these two routes are one in the same, a comparison is not needed. However, the point to be made here is that the concept of the accessible route *coinciding with the route for the general public* means the *distance* to be traveled is only one of the considerations. As the definition cited above indicates, *coincide* also means to *correspond in nature, character or function*. Therefore, it could be said that distance, character, and function either considered together or separately is what generally establishes the level of coincidence; the further that the two routes begin to depart from one another, insofar as these three basic criteria, the more difficult it is to concur that this performance standard has been met.

Regarding the applicant's point (3), DSA disagrees that the potential cost mitigation to comply with an arbitrary standard is prohibitive.

First, DSA does not consider *reasonable distance* to be an arbitrary standard. As previously indicated, it is considered to be a performance standard to be applied on a case-by-case basis depending on the particular circumstances related to the project. This same standard is also enforced under federal law by the United States Department of Justice.

Second, in these two cases, both projects are well under the disproportionate cost level of CBC 1134B.2.1 Exception 1. Therefore, any expenditure for accessibility would be limited to 20% maximum of the project's cost excluding the accessible upgrades. In these cases, since each project has a construction budget of \$50,000, the maximum required expenditure for accessibility, if needed, would be \$10,000 for each.

Regarding the applicant's point (4), DSA disagrees that the reasonable distance should be appropriate to the site itself. The distance a high school student can travel verses a first grade student is significantly different.

Reasonable distance is not contingent on only site specific issues, or is particular age ranges a sole consideration. Although once a reasonable distance is attained, it would be at the designer's discretion to provide a *more* reasonable distance based on the perceived needs of a particular age group. In other words, when the use of school facilities is analyzed, it is students, teachers, parents and grandparents that will typically use the facilities.

While many considerations could be taken into account, DSA would certainly review any documentation submitted which supports a reasonable distance determination.

In conclusion, for alterations to an existing school site where multiple sanitary facilities are located, when choosing which sanitary facilities to upgrade for accessibility, the main considerations to be taken into account are:

1. Which sanitary facilities serve the area(s) of alteration?
2. Does the route(s) for the general public to sanitary facilities coincide with the route(s) for persons with disabilities?
3. Considering the items above, is the distance reasonable?

For the specific projects under consideration, if the general public can access sanitary facilities, however persons with disabilities must travel 700 feet farther (round trip) to obtain the same accommodation, the questions to be asked are:

1. Is it proper to consider those sanitary facilities as serving the area of alteration (CBC 1134B.2)? In other words, would the general public tend to travel the 700 foot extra distance or would they choose the facilities that are 700 feet (round trip) closer? Keeping in mind that it's the sanitary facilities that serve the area of alteration which are the ones that are required to be upgraded.
2. Does the route for the general public coincide with the route for persons with disabilities (CBC 1114B.1)?
3. In making the decision to choose which sanitary facilities to upgrade for accessibility, is the distance to accessible sanitary facilities considered reasonable (CBC 1115B.1)?

In this case, and in consideration of the 3 questions above, our decision is to let the determination made by the DSA regional office stand.

Approved for distribution.

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 1-07 DSA/AC

Subject: Alterations: Hardwood Floor & Concrete Walkways

DSA Application Number:

Code Edition: 2001 CBC

Issue Date: 2-05-2007

QUESTION :

1. Is the removal and replacement of the entire existing hardwood floor in a multi-purpose assembly occupancy considered to be an alteration for the purposes of applying California Building Code (CBC) 1134B.2? Is such work considered to be cosmetic for the purposes of applying CBC 1134B.2.1, Exception 4?

2. Is the removal and replacement of exterior concrete walkways considered to be an alteration for the purposes of applying CBC 1134B.2? Is such work considered to be cosmetic for the purposes of applying CBC 1134B.2.1, Exception 4?

RESPONSE:

1. Yes, the removal and replacement of the entire existing hardwood floor in a multi-purpose assembly occupancy is considered an alteration for the purposes of applying CBC 1134B.2.1. Such work is not considered to be cosmetic for the purposes of applying CBC 1134B.2.1, Exception 4.

2. Yes, the removal and replacement of exterior concrete walkways is considered to be an alteration for the purposes of applying CBC 1134B.2.1. Such work is not considered to be cosmetic for the purposes of applying CBC 1134B.2.1, Exception 4.

BACKGROUND:

DSA application number XX-XXXXXX is for the removal and replacement of the entire existing hardwood floor (approximately 2,600 S.F.) in a multi-purpose assembly occupancy, exclusive of the stage. Additionally, the removal and replacement of over 4,000 S.F. of exterior concrete walkways is proposed.

The applicant indicates that the project is cosmetic work that is exempt from triggering accessibility upgrades based on CBC 1134B.2.1 Exception 4. Further, the project just replaces a rain damaged floor and corrects inadequate drainage at the exterior walkways.

ANALYSIS:CBC Section 202 Alterations

CBC Section 202 indicates that an alteration is *any change, addition or modification in construction...*

CBC Sections 1134B.2 & 1134B.2.1, Exception 4

CBC Section 1134B.2 applies to renovation, structural repair, alteration and additions to existing buildings and facilities. It identifies the minimum standards for removing architectural barriers and providing and maintaining accessibility to existing buildings and their related facilities. CBC Section 1134B.2.1 requires that all existing buildings and facilities, when alterations, structural repairs or additions are made to such buildings or facilities, shall comply with all the provisions for new buildings except that these requirements shall apply only to the area of specific alteration, structural repair or addition. In addition, a primary entrance to the building or facility, the primary path of travel to the specific area of alteration, sanitary facilities, drinking fountains, signs and public telephones serving the area must also comply with all the provisions for new buildings.

CBC Section 1134B.2.1, Exception 4 provides an exception to the above requirements. In order to qualify for the exception, projects must consist of heating, ventilation, air conditioning, re-roofing, electrical work not involving placement of switches and receptacles, cosmetic work that does not affect items regulated by the code, such as painting, equipment not considered to be a part of the architecture of the building or area, such as computer terminals, office equipment, etc. In general, the code does not consider this type of work to be alterations for the purposes of applying the accessibility requirements of CBC 1134B.2.1. Therefore, projects qualifying for the exception can proceed without activating new building compliance for the primary entrance to the building or facility, the primary path of travel to the specific area of alteration, sanitary facilities, drinking fountains, signs and public telephones serving the area.

The removal and replacement of existing hardwood floor:

The ordinary dictionary meaning of *cosmetic* is decorative rather than functional, ornamental, beautifying, done for the sake of appearance, and serving an aesthetic rather than a useful purpose.

A hardwood floor in a multi-purpose facility is a functional and constructed floor that is a horizontal interior component of the architecture of the building. Since the cosmetic element of a hardwood floor is its finish, a recoating (or refinishing) could be considered cosmetic work,

however its entire removal and replacement is not. This would be much more comparable to the example of *cosmetic* indicated in the code at CBC 1134B.2.1 Exception 4, which is *painting*.

In a quite similar but vertical scenario, utilizing the code example of *painting* as to what is considered *cosmetic*, the removal and replacement of wallboard is not considered to be cosmetic work, however the painting of it is. Since a similar example could be applied to floors, quite similar conclusions can be derived.

Therefore, the removal and replacement of a hardwood floor is a change in construction as defined in CBC Section 202 Alteration, and such replacement is not considered to be cosmetic work per CBC 1134B.2.1 Exception 4.

The removal and replacement of exterior concrete walkways:

For very similar reasons given above, exterior concrete walkways are a functional and constructed component of the architecture of the site. Exterior concrete walkways are not decorative rather than functional, and do not serve only an aesthetic rather than a useful purpose.

Therefore, the removal and replacement of exterior concrete walkways are a change in construction as defined in Section CBC 202 Alteration, and such replacement is not considered to be cosmetic work per CBC 1134B.2.1 Exception 4.

In conclusion, it should be noted that the regulations for alterations to existing buildings do not focus on why the alterations are occurring, but rather whether they are occurring or not. The presumption appears to be that since existing constructed elements are simply being removed and replaced with new materials under the pretext of maintenance or repair, that they are then exempt from triggering accessibility upgrades. However, such reasoning is not supported by what is defined in regulation as an alteration, which is *any change or modification in construction*.

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 2-07 DSA/AC

Subject: School Modernization: Children's Heights

DSA Application Number:

Code Edition: 1998 CBC

Issue Date: 2-08-2007

QUESTION:

1. In a kindergarten toilet room renovation, is the installation of a new 12" high toilet centered 18" from the wall a violation of the 1998 California Building Code?

RESPONSE:

No. In a kindergarten toilet room renovation, the installation of a new 12" high toilet centered 18" from the wall is not a violation of the 1998 California Building Code.

BACKGROUND:

DSA application number XX-XXXXXX includes kindergarten toilet room renovations which are now complete. The issue under consideration is the utilization of *suggested* alternate heights for children. In this case, a 12" high toilet seat was installed based on the fact that the primary users are small children (standard seat height is 17" to 19"); however the distance from the wall to the centerline of the toilet utilizes the standard dimension of 18" instead of the suggested 12" for children.

ANALYSIS:

1998 CBC Table 1115B-1

1998 CBC Table 1115B-1 contains alternate dimensions suggested for children. For kindergarten, the code suggests 12" for the toilet seat height, and 12" for toilet centering from the wall. It is important to note that the code required a determination of *unreasonable hardship*

in order to allow the 12" centering from the wall, however no determination of unreasonable hardship was required for a 12" seat height.

Here we have a design where the architect chose to provide a reduced toilet seat height based on the reduced stature of kindergarten children clearly allowed by code, and chose not to request a determination of *unreasonable hardship* for the toilet centering from the wall.

Standard dimensions could have been selected for these kindergarten toilet rooms at the architect's discretion, and standard dimensions would have complied with the building code. The 1998 CBC requirement for an *unreasonable hardship* request and determination for the toilet's 12" centering is persuasive, in that it lends reason why a design professional would have elected to not pursue such a request. This is coupled with the fact that the code doesn't indicate that all suggested dimensions for a particular fixture must be used in a consistent manner. The use of the word *suggested* in CBC Table 1115B-1 and 1115B.3 indicates something that is desirable, rather than mandatory.

The decision to reduce the seat height for children did not then cause the standard toilet centering from the wall of 18" to become a building code violation under the 1998 CBC.

While this project was approved under the 1998 CBC, it should be noted that the unreasonable hardship requirement was removed for the 2001 CBC as it pertained to toilet centering in the alternate dimensions suggested for children indicated at CBC Table 1115B-1.

While not an explicit mandatory code requirement, good design practice would certainly dictate that we remain consistent as we select the various alternate dimensions that apply to children. In other words, it is highly recommended that (1) the specifications chosen correspond to the age group of the primary user group and that (2) all the specifications of one age group should be applied consistently in the design and installation of water closets and other related elements to which alternate children's dimensions apply.

Since under the current 2001 CBC, unreasonable hardships are no longer required for any alternate dimensions suggested for children, in new construction, designers *should* provide this consistency since an opportunity to provide such consistency in design is quite easily achieved, though it is not necessarily required by the building code.

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca.gov



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 6-07 DSA/AC

Subject: Alterations: Removal of Roof Lights & Replacement of Skylights

DSA Application Number:

Code Edition: 2001 CBC

Issue Date: 5-03-2007

QUESTION :

Does the removal of monitor-type roof lights and the installation of new translucent skylight panels in their place, along with associated roofing and structural elements in the MP Building constitute an alteration per CBC 1134B.2.1?

RESPONSE:

The removal of monitor-type roof lights (structure and windows) and the installation of new translucent roof panels in their place, with associated structural work constitutes an alteration per CBC 1134B.2.1.

Reroofing is not considered to be an alteration per CBC 1134B.2.1, Exception 4.

ANALYSIS:

CBC Section 1134B.1 indicates the provisions apply to renovation, structural repair, alteration and additions to existing buildings.

CBC Sections 1134B.2 and 1134B.2.1 indicate that all existing buildings and facilities, when alterations, structural repairs or additions are made to such buildings or facilities, shall comply with all provisions of Division I, New Buildings, except as modified by this division. These requirements shall apply only to the area of specific alteration, structural repair or addition and shall include a primary entrance to the building or facility and the primary path of travel to the

specific area of alteration, structural repair or addition, and sanitary facilities, drinking fountains, signs and public telephones serving the area.

CBC Section 202 defines *alteration* as any change, addition or modification in construction or occupancy or structural repair or change in primary function to an existing structure other than repair or addition.

The code specifically indicates what work to existing buildings is exempt from 1134B application. CBC Section 1134B.2.1 Exception 4 indicates that projects which consist only of heating, ventilation, air conditioning, reroofing, electrical work not involving placement of switches and receptacles, cosmetic work that does not affect items regulated by this code, such as painting, equipment not considered to be a part of the architecture of the building or area, such as computer terminals, office equipment, etc., are not considered alteration projects for the purposes of accessibility for persons with disabilities and shall not be subject to this code.

In this project, the existing roof monitors are being removed and replaced with new translucent roof panels (skylights). Such work is a material change to the architecture of the building (an alteration) and is not considered to be reroofing.

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca.gov



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 8-07 DSA/AC

Subject: Student Housing Facility: Door Signal

DSA Application Number:

Code Edition: 2001 CBC

Issue Date: 6-01-2007

QUESTION:

Is it acceptable to have a wireless door signal device at the primary entrance in covered multifamily dwelling units subject to CBC Chapter 11A?

RESPONSE:

No, CBC Section 1106A.1 requires the door signal device be connected to permanent wiring.

ANALYSIS:

2001 CBC Section 1106A.1 (slightly revised in CBC 1132A.10 per the October 12, 2006 Supplement) indicates:

Every primary entrance to a dwelling unit in buildings containing three or more dwelling units shall be provided with a door buzzer, bell, chime or equivalent installation, mounted a maximum of 48 inches (1219 mm) above the floor, connected to permanent wiring.

The location of the term *equivalent installation* contained within this section is relevant, in that it strictly relates only to the type of audible device used. The intent of this term is that a bell, chime, buzzer, or some other equivalent form of audible device could be installed as an *equivalent installation*. In other words, it merely acknowledges that audible devices other than those listed could be considered, such as a horn or speaker.

The requirement for new construction is that the door signal device must be connected to permanent wiring. Such installations, as opposed to wireless installations, are typically maintenance free (never need batteries).

The use of a wireless installation as an alternative method to comply with a wired installation would have the effect of rendering the above mentioned code section useless and meaningless.

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca.gov



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 4-08 DSA/AC

Subject: Middle School Tables & Counters: Knee Clearance

DSA Application Number:

Code Edition: 2001 CBC

Issue Date: 4-18-2008

QUESTION 1:

Are alternate dimensions for children, specifically knee clearances, acceptable at all computer tables and counters used by students only, in a middle school with grades six through eight?

RESPONSE 1:

Alternate dimensions for children apply to facilities or portions of a facility used primarily by children 12 and younger. Generally, middle school students in grades six through eight can vary in age from 11 to 14. Taken as a whole, a middle school is not a facility used primarily by children 12 and younger. However, it is possible that there may be *portions* of a middle school used primarily by children 12 and younger. Alternate dimensions for children can be solely utilized only if it can be demonstrated that the specific portion of the facility is used primarily by children 12 and younger. See analysis.

QUESTION 2:

Are adult dimensions, specifically knee clearances, required for all computer tables and counters used by students only, in a middle school with grades six through eight?

RESPONSE 2:

In facilities or portions of a facility where it is not demonstrated that they are used primarily by children 12 and younger, adult dimensions are mandatory for at least five percent but never less than one. Additional tables and counters utilizing the alternate dimensions for children can be

used at the discretion of the school. Generally, middle school students in grades six through eight can vary in age from 11 to 14. See analysis.

ANALYSIS:

In 1986 the federal Access Board issued "*Recommendations for Accessibility Guidelines to Serve Physically Handicapped Children in Elementary Schools.*" The report included recommended modifications or additions based on children's sizes to certain sections of an earlier accessibility rule, the Uniform Federal Accessibility Standards. The recommendations were developed to assist states in designing and constructing accessible *elementary schools*. Many states and localities have applied these recommendations to newly constructed schools serving *grades one through six*.

The federal Access Board then issued final guidelines¹ to provide additional guidance to the Department of Justice and the Department of Transportation in establishing alternate specifications for building elements designed for use by children. These specifications are based on children's dimensions and anthropometrics and apply to building elements designed specifically for use by children *ages 12 and younger*. It ensures that newly constructed and altered facilities covered by titles II and III of the Americans with Disabilities Act of 1990 are readily accessible to and usable by children with disabilities. The guidelines provide alternate specifications based on children's dimensions as *exceptions* to specifications based on adult dimensions. Therefore as exceptions, the use of children's specifications is considered discretionary, not mandatory.

The ADA Accessibility Guidelines (as amended through 2002) Section 4.32.5 allows knee spaces at least 24 inches high at fixed or built-in seating or tables used primarily by *children ages 12 and younger*.

The CBC contains "*suggested*" dimensions for children's use in Table 1115B-1 and indicates a knee clearance of 24" for lavatories intended for elementary school aged children (children younger than 12). CBC Table 1115B-1 does not specifically address seating or tables for children's use.

In this case, the middle school in question contains grades six through eight. Sixth grade students are usually 11-12 years old, seventh grade students are usually 12-13 years old, eighth grade students are usually 13-14 years old. Taken as whole, middle schools with grades six through eight are not used primarily by children ages 12 and younger. However, there could certainly be portions of a middle school that are used primarily by children ages 12 and younger. For instance, tables and counters used only by students in a sixth grade classroom could be considered used primarily by children 12 and younger.

It is acknowledged that facilities containing multiple age groups of school aged children can present a challenge to designers in order to achieve compliance with the prescriptive standards. An analysis of how the school operates, the uses of particular rooms or spaces, and more importantly the ages of the students can all play a role in determining appropriate design decisions. There is indeed concern that designing facilities to solely serve one particular age group could have the effect of excluding those who are clearly entitled to the prescriptive standards for another.

¹ <http://www.access-board.gov/adaag/kids/final.htm#2>

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca.gov



DSA INTERPRETATION

The Rapid Interpretation Process (RIP) provides technical support to the Division of the State Architect's (DSA) four regional offices by processing official interpretations for the California Building Code (CBC) or other applicable standards, laws, or regulations. The process is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific interpretation committee, and the interpretations rendered by the committee represent the official position of DSA.

Interpretation Number: 5-08 DSA/AC

Subject: Ramp Handrails at 45-Degree Angle to Ramp Run

DSA Application Number:

Code Edition: 2001 CBC

Issue Date: 5-06-2008

QUESTION:

For a ramp with a slope of 1:12, can a handrail be installed at a 45 degree angle to the direction of the ramp run in order to avoid an exterior wall offset?

RESPONSE:

No, for a ramp with a slope of 1:12, a handrail is not acceptable at a 45 degree angle to the direction of the ramp run.

ANALYSIS:

Many persons with disabilities rely heavily upon handrails to pull themselves, maintain balance, and prevent serious falls. Ramps that do not have level landings at changes in direction can create cross slopes that will not meet the requirements for accessible routes of travel.

2001 CBC Section 1133B.7.1.3 indicates that surface cross slopes shall not exceed 1/4 inch per foot. In the example submitted, the 45 degree handrail compels the user to traverse the ramp in a diagonal fashion. At a 1:12 slope, such diagonal travel results in a cross slope that is not in compliance with the standards.

Coordinated for committee by:

Aaron Noble
Senior Architect
Division of the State Architect Headquarters
Architecture Code and Building Standards Development
1102 Q Street
Suite 5100
Sacramento, CA 95811
Phone: 916-445-4310
Fax: 916-445-7658
Email: aaron.noble@dgs.ca.gov



DSA CAP INTERPRETATION

The Code Appeal Process (CAP) provides technical support to the Division of the State Architect's (DSA) four regional offices, and is intended to provide accurate, effective, and timely dispute resolution assistance by issuing project-specific interpretations of regulations enforced by the DSA. Interpretations are developed utilizing a discipline specific Statewide Team, and the approved CAP interpretations represent the official position of DSA.

CAP Number: HQ 01-2010AC04-01
HQ 02-2010AC04-02

Subject: Suggested Heights for Children

DSA Application Number: 04-109974

Code Edition: 2007 CBC

Issue Date: February 17, 2010

QUESTION:

(1) For facilities used solely by children under 12, CBC Table 1115B-1 "*Suggested Dimensions for Children's Use*" indicates an accessible toilet seat height of 15" for elementary school children. Can other dimensions be used, such as 14" minimum to 16" maximum for an accessible toilet seat height?

(2) For facilities used solely by children under 12, CBC Table 1115B-1 "*Suggested Dimensions for Children's Use*" indicates an accessible lavatory height of 29" maximum with minimum knee clearance of 24" for elementary school children. Can other lavatory height dimensions be used, such as 31" maximum for an accessible lavatory height, while maintaining 24" minimum knee clearance?

RESPONSE:

(1) Dimensions of 14" minimum to 16" maximum for an accessible toilet seat height can be used for elementary school facilities, where such toilets are used solely by children age 12 and under.

(2) Dimensions of 31" maximum to the rim or counter surface at an accessible lavatory, while maintaining a 24" minimum for apron and knee clearance, can be used for accessible lavatories

at elementary school facilities, where such lavatories are used solely by children age 12 and under.

DISCUSSION:

The Americans with Disabilities Act Accessibility Guidelines (ADAAG)

In 1986 the Access Board issued "Recommendations for Accessibility Guidelines to Serve Physically Handicapped Children in Elementary Schools." The report included recommended modifications or additions, based on children's sizes, to certain sections of an earlier accessibility rule, the Uniform Federal Accessibility Standards (UFAS). The recommendations were developed to assist states in designing and constructing accessible elementary schools.

Americans with Disabilities Act Accessibility Guidelines (ADAAG) as published in 1991 did not provide requirements based on children's dimensions. ADAAG as originally published only contained requirements based on adult dimensions. However, ADAAG included a provision (2.2 Equivalent Facilitation) which permits departures from ADAAG requirements that provide equal or greater access. While this provision may have served as the basis for departures from ADAAG in designing for access according to children's dimensions, designers and others sought more specific guidance and technical criteria in this area.

In 1992, new recommendations were developed through a research project sponsored by the Access Board. The project studied accessibility requirements for children with disabilities at a variety of facilities. The Center for Accessible Housing at North Carolina State University conducted this study which included a review of codes, standards, and guidelines, ergonomic studies and evaluation literature, and post-occupancy evaluations of children's facilities. This study focused on facilities serving pre-kindergarten and elementary school-aged children and, to a lesser extent, facilities serving infants and toddlers. The recommended guidelines developed from this study are known as "Recommendations for Accessibility Standards for Children's Environments".

In 1998, the Access Board amended ADAAG by adding guidelines for children's facilities. These guidelines add alternatives to the existing adult dimensions that can be used when designing building elements for children. The guideline provides alternate specifications based on children's dimensions as *exceptions* to specifications based on adult dimensions. As exceptions, these specifications are discretionary, not mandatory.

The California Building Code (CBC) and ADAAG

CBC Section 1115B.1.2 indicates where facilities are to be used solely by children, the specific heights and clearances may be adjusted to meet their accessibility needs. Table 1115B-1 contains *Suggested* Dimensions for Children's Use. In Table 1115B-1, DSA Access Compliance *recommends* dimensions as adequately serving the needs of children, and that those recommendations are based on the federal "Recommendations for Accessibility for Children in Elementary School" (reference similarly titled 1986 document above).

DSA acknowledges the further study performed by the Access Board subsequent to the recommendations it issued in 1986 and the ADAAG addition of specific guidelines for children's facilities in 1998. Since CBC Section 202 defines "*Recommend*" as not requiring mandatory acceptance, but identifies only a *suggested* action, dimensions other than those shown in CBC Table 1115B-1 can be accepted.

Dimensions of 14" minimum to 16" maximum for an accessible toilet seat height can be used for elementary school facilities, where such toilets are used solely by children age 12 and under. For water closets, once a specific age group is utilized for design, the specifications of that age group are to be applied consistently, including related elements such as water closet centerline, toilet seat height, and grab bar height.

A dimension of 31" maximum for an accessible lavatory height, while maintaining a 24" minimum for knee clearance, can be used for accessible lavatories at elementary school facilities where such lavatories are used solely by children age 12 and under.

In the two questions contained in the appeals, the alternate dimensions for children proposed by the applicant fall at or within the dimensions indicated or referenced in ADAAG (as amended through 2002) 4.16.1 Exception 1 and 4.19.2 Exception 1, even though they depart from suggested recommendations contained in CBC Table 1115B-1.

The alternate specifications based on children's dimensions have been incorporated into ADAAG as exceptions to technical requirements so that the alternate specifications function as permitted departures from requirements based on adult dimensions. The decision to utilize these exceptions will likely be determined by the designer, when based on the use of the facility the use of the exceptions is warranted.

Even though the decision to use the exceptions for children's dimensions in ADAAG is optional, if an exception is used, the technical specifications it contains or references must then be followed.

Interpretation coordinated by:

Aaron Noble
Senior Architect
Division of the State Architect, Headquarters Office
Department of General Services
1102 Q Street, Suite 5100
Sacramento, CA 95811
(916) 445-4310 (Tel.)
(916) 445-7658 (Fax)
Aaron.Noble@dgs.ca.gov

